

H:\2016\60801\02 - Eaton_SRTS\0909\Design\Roadway\Sheets\0909\GG001.dgn Sheet 12/1/2020 3:10:33 PM Kcollins

SHEET NUM.												PART.	ITEM	ITEM	GRAND	UNIT	DESCRIPTION	SEE SHEET NO.
5	6	7	9	16	22							01/SAF/OT	EXT	TOTAL				
												LS	201	11000	LS			
			110									57	202	23000	110	SY	ROADWAY CLEARING AND GRUBBING PAVEMENT REMOVED	
			1,039 205									1,039 205	202 202	30000 32000	1,039 205	SF FT	WALK REMOVED CURB REMOVED	
				73 2								73 2	203 203	10000 20000	73 2	CY CY	EXCAVATION EMBANKMENT	
			50									50	204	10000	50	SY	SUBGRADE COMPACTION	
			1,912 239 756									1,912 239 756	608 608 608	10000 13020 52000	1,912 239 756	SF SF SF	4" CONCRETE WALK 7" CONCRETE WALK CURB RAMP	
																	EROSION CONTROL	
2												2	659	00100	2	EACH	SOIL ANALYSIS TEST	
45												45	659	00300	45	CY	TOPSOIL	
410												410	659	00500	410	SY	SEEDING AND MULCHING, CLASS 1	
21												21	659	14000	21	SY	REPAIR SEEDING AND MULCHING	
0.06												0.06	659	20000	0.06	TON	COMMERCIAL FERTILIZER	
0.09												0.09	659	31000	0.09	ACRE	LIME	
2												2	659	35000	2	MGAL	WATER	
												3,000	832	30000	3,000	EACH	EROSION CONTROL	
																	PAVEMENT	
			15									15	253	02001	15	CY	PAVEMENT REPAIR, AS PER PLAN	
			260									260	254	01000	260	SY	PAVEMENT PLANING, ASPHALT CONCRETE, 3"	
			32									32	407	20000	32	GAL	NON-TRACKING TACK COAT	
			22									22	441	50000	22	CY	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448), PG64-22	
			50									50	452	10010	50	SY	6" NON-REINFORCED CONCRETE PAVEMENT, CLASS QC 1P	
			148									148	609	12000	148	FT	COMBINATION CURB AND GUTTER, TYPE 2	
																	WATER WORK	
			3									3	638	10800	3	EACH	VALVE BOX ADJUSTED TO GRADE	
																	TRAFFIC CONTROL	
												2	625	32000	2	EACH	GROUND ROD	
												42	630	03100	42	FT	GROUND MOUNTED SUPPORT, NO. 3 POST	
												33	630	80100	33	SF	SIGN, FLAT SHEET	
												1	630	85100	1	EACH	REMOVAL OF GROUND MOUNTED SIGN AND REERECTION	
												1	630	86002	1	EACH	REMOVAL OF GROUND MOUNTED POST SUPPORT AND DISPOSAL	
												2	630	97700	2	EACH	SIGNING, MISC.:SOLAR POWERED RETANGULAR RAPID FLASHING BEACON (RRFB) SIGN ASSEMBLY	
												2	632	64020	2	EACH	PEDESTAL FOUNDATION	
												0.05	644	00100	0.05	MILE	EDGE LINE, 4"	
												0.01	644	00300	0.01	MILE	CENTER LINE	
												82	644	00500	82	FT	STOP LINE	
												1,090	644	00600	1,090	FT	CROSSWALK LINE, 12"	
												720	644	00601	720	FT	CROSSWALK LINE, AS PER PLAN, 24"	
												192	642	00800	192	FT	CURB MARKING, TYPE 1	
												960	644	30000	960	FT	REMOVAL OF PAVEMENT MARKING	
																	MAINTENANCE OF TRAFFIC	
	0.01											0.01	614	21100	0.01	MILE	WORK ZONE CENTER LINE, CLASS I, 642 PAINT	
																	INCIDENTALS	
												LS	614	11000	LS		MAINTAINING TRAFFIC	
												LS	623	10000	LS		CONSTRUCTION LAYOUT STAKES AND SURVEYING	
												LS	624	10000	LS		MOBILIZATION	

GENERAL SUMMARY

PRE-EATON-SRTS

CALCULATED
KJC
CHECKED
SAM

8
27