

H:\2016\160801\02 - Eaton SRTS\0909\Design\Roadway\Sheets\0909\GG001.dgn Sheet 12/1/2020 3:10:33 PM Kcollins

SHEET NUM.													PART.	ITEM	ITEM	GRAND	UNIT	DESCRIPTION	SEE SHEET NO.
5	6	7	9	16	22							01/SAF/OT	EXT	TOTAL					
													LS	201	11000	LS		ROADWAY	
													57	202	23000	110	SY	CLEARING AND GRUBBING	
			110															PAVEMENT REMOVED	
			1,039										1,039	202	30000	1,039	SF	WALK REMOVED	
			205										205	202	32000	205	FT	CURB REMOVED	
				73									73	203	10000	73	CY	EXCAVATION	
				2									2	203	20000	2	CY	EMBANKMENT	
				50									50	204	10000	50	SY	SUBGRADE COMPACTION	
				1,912									1,912	608	10000	1,912	SF	4" CONCRETE WALK	
				239									239	608	13020	239	SF	7" CONCRETE WALK	
				756									756	608	52000	756	SF	CURB RAMP	
																		EROSION CONTROL	
2													2	659	00100	2	EACH	SOIL ANALYSIS TEST	
45													45	659	00300	45	CY	TOPSOIL	
410													410	659	00500	410	SY	SEEDING AND MULCHING, CLASS 1	
21													21	659	14000	21	SY	REPAIR SEEDING AND MULCHING	
0.06													0.06	659	20000	0.06	TON	COMMERCIAL FERTILIZER	
													0.09	659	31000	0.09	ACRE	LIME	
													2	659	35000	2	MGAL	WATER	
													3,000	832	30000	3,000	EACH	EROSION CONTROL	
																		PAVEMENT	
			15										15	253	02001	15	CY	PAVEMENT REPAIR, AS PER PLAN	
			260										260	254	01000	260	SY	PAVEMENT PLANING, ASPHALT CONCRETE, 3"	
			32										32	407	20000	32	GAL	NON-TRACKING TACK COAT	
			22										22	441	50000	22	CY	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448), PG64-22	
			50										50	452	10010	50	SY	6" NON-REINFORCED CONCRETE PAVEMENT, CLASS QC 1P	
			148										148	609	12000	148	FT	COMBINATION CURB AND GUTTER, TYPE 2	
																		WATER WORK	
				3									3	638	10800	3	EACH	VALVE BOX ADJUSTED TO GRADE	
																		TRAFFIC CONTROL	
			2										2	625	32000	2	EACH	GROUND ROD	
					42								42	630	03100	42	FT	GROUND MOUNTED SUPPORT, NO. 3 POST	
					33								33	630	80100	33	SF	SIGN, FLAT SHEET	
					1								1	630	85100	1	EACH	REMOVAL OF GROUND MOUNTED SIGN AND REERECTION	
					1								1	630	86002	1	EACH	REMOVAL OF GROUND MOUNTED POST SUPPORT AND DISPOSAL	
					2								2	630	97700	2	EACH	SIGNING, MISC.:SOLAR POWERED RETANGULAR RAPID FLASHING BEACON (RRFB) SIGN ASSEMBLY	
			2										2	632	64020	2	EACH	PEDESTAL FOUNDATION	
					0.05								0.05	644	00100	0.05	MILE	EDGE LINE, 4"	
					0.01								0.01	644	00300	0.01	MILE	CENTER LINE	
					82								82	644	00500	82	FT	STOP LINE	
					1,090								1,090	644	00600	1,090	FT	CROSSWALK LINE, 12"	
					720								720	644	00601	720	FT	CROSSWALK LINE, AS PER PLAN, 24"	
					192								192	642	00800	192	FT	CURB MARKING, TYPE 1	
					960								960	644	30000	960	FT	REMOVAL OF PAVEMENT MARKING	
																		MAINTENANCE OF TRAFFIC	
	0.01												0.01	614	21100	0.01	MILE	WORK ZONE CENTER LINE, CLASS I, 642 PAINT	
																		INCIDENTALS	
													LS	614	11000	LS		MAINTAINING TRAFFIC	
													LS	623	10000	LS		CONSTRUCTION LAYOUT STAKES AND SURVEYING	
													LS	624	10000	LS		MOBILIZATION	

GENERAL SUMMARY

PRE-EATON-SRTS