

V:\1736\octive\173620094\engineer\ng\_96654\ProjAdmin\PlanReviews\Tracings\Tracings- Revised Addendum 3\_3\_6\_2020\96654\_gg001.dgn 3/7/2020 10:26:45 AM pdurham

SHEET NUM.								PART.				ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.	
16	17	19	20	35	36A	48		01/IMS/PV	02/IMS/BR	03/IMS/PV	05/STR/PV							
	LS							LS					201	11000	LS		ROADWAY	
					3,688					3,688			202	23000	3,688	SY	CLEARING AND GRUBBING	
				8,799	3,882			8,799		3,882			202	23010	12,681	SY	PAVEMENT REMOVED	
					472					472			202	32000	472	FT	PAVEMENT REMOVED, ASPHALT	
					76					76			202	35100	76	FT	CURB REMOVED	
				19,109				19,109					202	38000	19,109	FT	PIPE REMOVED, 24" AND UNDER	
				46				46					202	42010	46	EACH	GUARDRAIL REMOVED	
				14				14					202	42040	14	EACH	ANCHOR ASSEMBLY REMOVED, TYPE E	
				12				12					202	42050	12	EACH	ANCHOR ASSEMBLY REMOVED, TYPE T	
				63				63					202	47000	63	EACH	ANCHOR ASSEMBLY REMOVED, TYPE B	
					1					1			202	58100	1	EACH	BRIDGE TERMINAL ASSEMBLY REMOVED	
					2					2			202	58200	2	EACH	CATCH BASIN REMOVED	
					1					1			202	58400	1	EACH	INLET REMOVED	
		824			95			824		95			203	10000	919	CY	INLET ABANDONED	
		44						44					203	20000	44	CY	EXCAVATION	
1,992								1,992					204	10000	1,992	SY	EMBANKMENT	
		666						666					204	13000	666	CY	SUBGRADE COMPACTION	
		666						666					204	30020	666	CY	EXCAVATION OF SUBGRADE	
1								1					204	45000	1	hour	GRANULAR MATERIAL, TYPE C	
		1,992						1,992					204	50000	1,992	SY	PROOF ROLLING	
				227				227					209	15000	227	STA	GEOTEXTILE FABRIC	
				734				734					209	70000	734	CY	RESHAPING UNDER GUARDRAIL	
				15,250				15,250					606	15050	15,250	FT	BORROW	
				4,213				4,213					606	15100	4,213	FT	GUARDRAIL, TYPE MGS	
				12				12					606	26050	12	EACH	GUARDRAIL, TYPE MGS WITH LONG POSTS	
				46				46					606	26150	46	EACH	ANCHOR ASSEMBLY, MGS TYPE B	
				14				14					606	26550	14	EACH	ANCHOR ASSEMBLY, MGS TYPE E, (MASH 2016)	
				59				59					606	35002	59	EACH	ANCHOR ASSEMBLY, MGS TYPE T	
				4				4					606	35102	4	EACH	MGS BRIDGE TERMINAL ASSEMBLY, TYPE 1	
				5				5					SPECIAL	69050100	5	EACH	MGS BRIDGE TERMINAL ASSEMBLY, TYPE 2	18
			LS					LS					SPECIAL	69098400	LS		MAILBOX SUPPORT SYSTEM, SINGLE	20
																	CONSULTANT FOR CONCRETE QUALITY CONTROL/INCLUDING TESTING AND INSPECTION	
																	EROSION CONTROL	
		12,084		12,629	1,261			24,713		1,261			659	00300	1,261	CY	TOPSOIL	
		1,236			11,355			1,236		11,355			659	10000	36,068	SY	SEEDING AND MULCHING	
		3.34			1.54			3.34		1.54			659	14000	1,236	SY	REPAIR SEEDING AND MULCHING	
		5.11			2.35			5.11		2.35			659	20000	4.88	TON	COMMERCIAL FERTILIZER	
					62			134		62			659	35000	196	MGAL	LIME	
		134			4,861			4,861		4,861			670	00500	4,861	SY	WATER	
		5,000			10,000			5,000		10,000			832	30000	15,000	EACH	SLOPE EROSION PROTECTION	
					LS			LS		LS			832	15000	LS		EROSION CONTROL	
					LS			LS		LS			832	15002	LS		STORM WATER POLLUTION PREVENTION PLAN	
					LS			LS		LS			832	15010	LS		STORM WATER POLLUTION PREVENTION INSPECTIONS	
																	STORM WATER POLLUTION PREVENTION INSPECTION SOFTWARE	
																	PAVEMENT	
		5,000						5,000					253	01000	5,000	SY	PAVEMENT REPAIR	
2,811								2,811					253	02000	2,811	CY	PAVEMENT REPAIR	
888,996								888,678			4,318		254	01000	888,996	SY	PAVEMENT PLANING, ASPHALT CONCRETE, 3 1/4"	
8,890								8,847			43		254	01600	8,890	SY	PATCHING PLANED SURFACE	
						566				566			255	10160	566	SY	FULL DEPTH PAVEMENT REMOVAL AND RIGID REPLACEMENT, CLASS QC MS	
						852				852			255	20000	852	FT	FULL DEPTH PAVEMENT SAWING	
						2,452				2,452			256	10000	2,452	SF	BONDED PATCHING OF PORTLAND CEMENT CONCRETE PAVEMENT, TYPE A	
						1,270				1,270			258	10000	1,270	EACH	RETROFIT DOWEL BAR	
374								374					301	46000	374	CY	ASPHALT CONCRETE BASE, PG64-22	
354								354					304	20000	354	CY	AGGREGATE BASE	
242								242					407	10000	242	GAL	TACK COAT	
124,460								123,855			605		407	20000	124,460	GAL	NON-TRACKING TACK COAT	
51								51					441	50000	51	CY	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448), PG64-22	

GENERAL SUMMARY

PRE-70-0.00

