


SHEET NUM.											PART.	ITEM	ITEM	GRAND	UNIT	DESCRIPTION	SEE SHEET NO.
4	5	6	10	11	RW.3				01/S<2/04	EXT	TOTAL						
				LS				LS		202	11001	LS			STRUCTURE 20 FOOT SPAN AND UNDER (RIC-314-2.75)		
	LS							LS		503	11100	LS			STRUCTURE REMOVED, AS PER PLAN		5
								LS		503	21300	LS			COFFERDAMS AND EXCAVATION BRACING		
								LS		2,498	509	10000	2,498		UNCLASSIFIED EXCAVATION		
								4.5		4.5	511	46010	4.5		EPOXY COATED STEEL REINFORCEMENT		
															CLASS QC1 CONCRETE, RETAINING/WINGWALL NOT INCLUDING FOOTING		
								15		15	511	46510	15		CLASS QC1 CONCRETE, FOOTING		
								2		2	511	46610	2		CLASS QC1 CONCRETE, HEADWALL		
								21		21	512	10100	21		SEALING OF CONCRETE SURFACES (EPOXY-URETHANE)		
								116		116	512	33000	116		TYPE 2 WATERPROOFING		
								LS		LS	518	21230	LS		POROUS BACKFILL WITH GEOTEXTILE FABRIC		
															MAINTENANCE OF TRAFFIC		
								LS		LS	614	12420	LS		DETOUR SIGNING		
			2					2		2	614	18601	2	SNMT	PORTABLE CHANGEABLE MESSAGE SIGN, AS PER PLAN		6
															INCIDENTALS		
								LS		LS	614	11000	LS		MAINTAINING TRAFFIC		
								2		2	619	16000	2	MNTH	FIELD OFFICE, TYPE A		
								LS		LS	623	10000	LS		CONSTRUCTION LAYOUT STAKES AND SURVEYING		
								LS		LS	624	10000	LS		MOBILIZATION		

GENERAL SUMMARY

DESIGN AGENCY	DISTRICT 3
	
ENGINEERING TEAM FOUR	
DESIGNER	JLB
REVIEWER	NRF 09-25-24
PROJECT ID	115032
SHEET TOTAL	P.9 25