

SHEET NUM.											PART.	ITEM	ITEM	GRAND	UNIT	DESCRIPTION	SEE SHEET NO.
3	7	10	16	17							01/STR/OT	EXT	TOTAL				
ROADWAY																	
LS											LS	201	11000	LS	CLEARING AND GRUBBING		
	1,118										1,118	202	23000	1,118	SY	PAVEMENT REMOVED	
	115										115	202	35100	115	FT	PIPE REMOVED, 24" AND UNDER	
	225										225	202	38000	225	FT	GUARDRAIL REMOVED	
	1										1	202	42010	1	EACH	ANCHOR ASSEMBLY REMOVED, TYPE E	
	1										1	202	58100	1	EACH	CATCH BASIN REMOVED	
25											25	202	98100	25	EACH	REMOVAL MISC.: PILING REMOVED	14
			51								51	203	10000	51	CY	EXCAVATION	
			34								34	203	20000	34	CY	EMBANKMENT	
	1,255										1,255	204	10000	1,255	SY	SUBGRADE COMPACTION	
	213										213	606	15050	213	FT	GUARDRAIL, TYPE MGS	
	1										1	606	26150	1	EACH	ANCHOR ASSEMBLY, MGS TYPE E, NCHRP 350/MASH 2016	
EROSION CONTROL																	
		1									1	601	21050	1	SY	TIED CONCRETE BLOCK MAT WITH TYPE 1 UNDERLAYMENT	
		3									3	601	32104	3	CY	ROCK CHANNEL PROTECTION, TYPE B WITH GEOTEXTILE FABRIC	
218											218	659	00500	218	SY	SEEDING AND MULCHING, CLASS 1	
11											11	659	14000	11	SY	REPAIR SEEDING AND MULCHING	
0.03											0.03	659	20000	0.03	TON	COMMERCIAL FERTILIZER	
											0.05	659	31000	0.05	ACRE	LIME	
											1	659	35000	1	MGAL	WATER	
											5,000	832	30000	5,000	EACH	EROSION CONTROL	
DRAINAGE																	
		1									1	602	20000	1	CY	CONCRETE MASONRY	
	736										736	605	14000	736	FT	6" BASE PIPE UNDERDRAINS	
	75										75	611	00510	75	FT	6" CONDUIT, TYPE F FOR UNDERDRAIN OUTLETS	
	73										73	611	07400	73	FT	18" CONDUIT, TYPE B, 706.02, 707.12 ALUMINUM COATED, 707.13, (0.109) GALVANIZED, 707.33	
	27										27	611	10400	27	FT	24" CONDUIT, TYPE B, 707.33	
											1	611	98510	1	EACH	CATCH BASIN, NO. 2-3	
		1									1	611	99710	1	EACH	PRECAST REINFORCED CONCRETE OUTLET	
PAVEMENT																	
		52									52	252	01500	52	FT	FULL DEPTH PAVEMENT SAWING	
		176									176	301	56000	176	CY	ASPHALT CONCRETE BASE, PG64-22, (449)	
		214									214	304	20000	214	CY	AGGREGATE BASE	
		236									236	407	10000	236	GAL	TACK COAT	
		90									90	441	70000	90	CY	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (449), PG64-22	
TRAFFIC CONTROL																	
							9				9	621	00100	9	EACH	RPM	
							9				9	621	54000	9	EACH	RAISED PAVEMENT MARKER REMOVED	
							7				7	626	00112	7	EACH	BARRIER REFLECTOR, TYPE 3 BIDIRECTIONAL	
							18				18	630	03100	18	FT	GROUND MOUNTED SUPPORT, NO. 3 POST	
							2				2	630	85100	2	EACH	REMOVAL OF GROUND MOUNTED SIGN AND REERECTION	
								1			1	630	08600	1	EACH	SIGN POST REFLECTOR	
								1			1	630	86002	1	EACH	REMOVAL OF GROUND MOUNTED POST SUPPORT AND DISPOSAL	
								0.14			0.14	642	00104	0.14	MILE	EDGE LINE, 6", TYPE 1	
								0.07			0.07	642	00300	0.07	MILE	CENTER LINE, TYPE 1	
RETAINING WALLS																	
											2,182	507	00400	2,182	FT	STEEL PILES, MISC.: TYPE 1 STEEL BEAM, FURNISHED	14
											1,499	524	94603	1,499	FT	DRILLED SHAFTS, 30" DIAMETER, ABOVE BEDROCK, AS PER PLAN	14
											720	524	94605	720	FT	DRILLED SHAFTS, 30" DIAMETER INTO BEDROCK, AS PER PLAN	14
											1,328	524	95000	1,328	FT	DRILLED SHAFTS, MISC.: PLUG PILE, 30" DIAMETER, UNREINFORCED	14
											15	524	95000	15	FT	DRILLED SHAFTS, MISC.: PLUG PILE, 36" DIAMETER, UNREINFORCED	14
INCIDENTALS																	
											LS	614	11000	LS		MAINTAINING TRAFFIC	
											LS	623	10000	LS		CONSTRUCTION LAYOUT STAKES AND SURVEYING	
											LS	624	10000	LS		MOBILIZATION	

GENERAL SUMMARY

DESIGN AGENCY



DESIGNER

SDC

REVIEWER

SCS 03/01/22

PROJECT ID

115231

SHEET TOTAL

P.06 17