

I:\ProjectData\SCI\00496_SCI_52_3\24\Design\Roadway\Sheets\00496_GG001.dgn Sheet 2/24/2020 9:39:56 AM ccoffrei

SHEET NUM.											PART.			ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
3	5	6	7	16	19	20	21	23	26	01/NHS/PV	02/NHS/BR	03/NHS/CV							
ROADWAY																			
LS										LS			201	11000	LS		CLEARING AND GRUBBING		
					169						169		202	23000	169	SY	PAVEMENT REMOVED		
					337.5						337.5		202	38000	337.5	FT	GUARDRAIL REMOVED		
					125						125		202	38300	125	FT	GUARDRAIL REMOVED, BARRIER DESIGN		
					2						2		202	42010	2	EACH	ANCHOR ASSEMBLY REMOVED, TYPE E		
					8						8		202	47000	8	EACH	BRIDGE TERMINAL ASSEMBLY REMOVED		
					2						2		202	47800	2	EACH	IMPACT ATTENUATOR REMOVED		
					10.3					10.3			209	60500	10.3	MILE	LINEAR GRADING		
					10						10		209	70000	10	CY	BORROW		
					8						8		209	72001	8	STA	PREPARING SUBGRADE FOR SHOULDER PAVING, AS PER PLAN	4	
					600						600		606	15050	600	FT	GUARDRAIL, TYPE MGS		
					2						2		606	26050	2	EACH	ANCHOR ASSEMBLY, MGS TYPE B		
					2						2		606	26100	2	EACH	ANCHOR ASSEMBLY, TYPE E		
					4						4		606	35002	4	EACH	MGS BRIDGE TERMINAL ASSEMBLY, TYPE I		
EROSION CONTROL																			
								12				12	601	32100	12	CY	ROCK CHANNEL PROTECTION, TYPE B WITH FILTER		
1,000											900	100	659	10000	1,000	SY	SEEDING AND MULCHING		
50											45	5	659	14000	50	SY	REPAIR SEEDING AND MULCHING		
0.14											0.13	0.01	659	20000	0.14	TON	COMMERCIAL FERTILIZER		
0.21											0.19	0.02	659	31000	0.21	ACRE	LIME		
5											4	1	659	35000	5	MGAL	WATER		
											700	200	100	832	30000	1,000	EACH	EROSION CONTROL	
DRAINAGE																			
								240					240	SPECIAL	20270130	240	FT	PIPE CLEANOUT OVER 48"	3
								LS					LS	503	11100	LS		COFFERDAMS AND EXCAVATION BRACING	
								240					240	837	10000	240	FT	LINER PIPE 48", (707.12, 748.06, SS938, 707.75)	
								240					240	837	21000	240	FT	BACKFILL FOR LINER PIPE	
PAVEMENT																			
					1,768						1,768		254	01001	1,768	SY	PAVEMENT PLANING, ASPHALT CONCRETE, AS PER PLAN 1.25" (RUMBLE STRIPS REMOVED)	16	
500											500		255	10011	500	SY	FULL DEPTH PAVEMENT REMOVAL AND RIGID REPLACEMENT, CLASS QC1, AS PER PLAN	3	
					152	9,574					9,574	152	407	10000	9,726	GAL	TACK COAT		
						3,129					3,129		424	12000	3,129	CY	FINE GRADED POLYMER ASPHALT CONCRETE, TYPE B		
						5					5		441	50701	5	CY	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 1, (448), (UNDER GUARDRAIL), AS PER PLAN	4	
					62						62		442	10000	62	CY	ASPHALT CONCRETE SURFACE COURSE, 12.5 MM, TYPE A (446)		
						335					335		617	10100	335	CY	COMPACTED AGGREGATE		
					10.3						10.3		618	40600	10.3	MILE	RUMBLE STRIPS, SHOULDER (ASPHALT CONCRETE)		
					112,635						112,635		897	01010	112,635	SY	PAVEMENT PLANING, ASPHALT CONCRETE, CLASS A, 0.75"		
2,718											2,718		897	02000	2,718	SY	PATCHING PLANED SURFACE		
TRAFFIC CONTROL																			
								346			346		621	00100	346	EACH	RPM		
								346			346		621	54000	346	EACH	RAISED PAVEMENT MARKER REMOVED		
					4						4		626	00102	4	EACH	BARRIER REFLECTOR, TYPE 1 (ONE-WAY)		
					9						9		626	00112	9	EACH	BARRIER REFLECTOR, TYPE 3(ONE WAY)		
					10.35						10.35		644	00104	10.35	MILE	EDGE LINE, 6"		
					5.14						5.14		644	00204	5.14	MILE	LANE LINE, 6"		
					1,305						1,305		644	00404	1,305	FT	CHANNELIZING LINE, 12"		
					1,175						1,175		644	01510	1,175	FT	DOTTED LINE, 6"		
					0.04						0.04		646	10010	0.04	MILE	EDGE LINE, 6"		
					0.02						0.02		646	10110	0.02	MILE	LANE LINE, 6"		

GENERAL SUMMARY

SCI-52-31.24

