

SHEET NUM.											PART.	ITEM	ITEM	GRAND	UNIT	DESCRIPTION	SEE SHEET NO.	
										6	26	01/STR/BR	EXT	TOTAL				
STRUCTURE OVER 20 FOOT SPAN (SCI-00239-00.980) CONTINUED																		
											128,576	128,576	513	10261	128,576	LB	STRUCTURAL STEEL MEMBERS, LEVEL 3, AS PER PLAN	24
											4,260	4,260	513	20000	4,260	EACH	WELDED STUD SHEAR CONNECTORS	
											63	63	516	13900	63	SF	2" PREFORMED EXPANSION JOINT FILLER	
											130	130	516	14020	130	FT	SEMI-INTEGRAL ABUTMENT EXPANSION JOINT SEAL	
											12	12	516	44100	12	EACH	ELASTOMERIC BEARING WITH INTERNAL LAMINATES AND LOAD PLATE (NEOPRENE) (8" x 11" x 2")	
											12	12	516	44100	12	EACH	ELASTOMERIC BEARING WITH INTERNAL LAMINATES AND LOAD PLATE (NEOPRENE)(10" x 14" x 2")	
											322.33	322.33	517	70000	322.33	FT	RAILING (TWIN STEEL TUBE)	
											57	57	518	21200	57	CY	POROUS BACKFILL WITH GEOTEXTILE FABRIC	
											376	376	SPECIAL	51822300	376	FT	STEEL DRIP STRIP	23
											153	153	518	40000	153	FT	6" PERFORATED CORRUGATED PLASTIC PIPE	
											40	40	518	40010	40	FT	6" NON-PERFORATED CORRUGATED PLASTIC PIPE, INCLUDING SPECIALS	
											1	1	523	20000	1	EACH	DYNAMIC LOAD TESTING	
											211	211	526	25010	211	SY	REINFORCED CONCRETE APPROACH SLABS WITH QC/QA (T=15")	
											99.21	99.21	526	90010	99.21	FT	TYPE A INSTALLATION	
											9	9	843	50000	9	SF	PATCHING CONCRETE STRUCTURES WITH TROWELABLE MORTAR	
											41	41	846	00110	41	CF	POLYMER MODIFIED ASPHALT EXPANSION JOINT SYSTEM	
MAINTENANCE OF TRAFFIC																		
											88	88	253	02000	88	CY	PAVEMENT REPAIR	
											35	35	407	20000	35	GAL	NON-TRACKING TACK COAT	
											18	18	441	50000	18	CY	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448), PG64-22	
											40	40	614	11110	40	HOUR	LAW ENFORCEMENT OFFICER WITH PATROL CAR FOR ASSISTANCE	
											6	6	614	18601	6	SNMT	PORTABLE CHANGEABLE MESSAGE SIGN, AS PER PLAN	6
											0.16	0.16	614	21100	0.16	MILE	WORK ZONE CENTER LINE, CLASS I, 642 PAINT	
											1	1	616	10000	1	MGAL	WATER	
INCIDENTALS																		
													LS	614		LS	MAINTAINING TRAFFIC	
													5	619		MNTH	FIELD OFFICE, TYPE B	
													LS	623		LS	CONSTRUCTION LAYOUT STAKES AND SURVEYING	
													LS	624		LS	MOBILIZATION	

GENERAL SUMMARY

DESIGN AGENCY
KORDA
 KORDA / NEMETH
 ENGINEERING, INC
 1650 Watermark Drive,
 Suite 200,
 Columbus, OH 43215

DESIGNER
 ATD

REVIEWER
 CLP 07/22/21

PROJECT ID
 105100

SHEET TOTAL
 10 44

SHEET NO.	REF NO.	LOCATION	STATION		SIDE	CODE	SIZE (INCHES)	621	621	630	630	630	630	642	642	626				
			FROM	TO				RPM	RAISED PAVEMENT MARKER REMOVED	GROUND MOUNTED SUPPORT, NO. 3 POST	SIGN POST REFLECTOR	REMOVAL OF GROUND MOUNTED SIGN AND REERECTION	REMOVAL OF GROUND MOUNTED POST SUPPORT AND DISPOSAL	EDGE LINE, 6" TYPE 1 (WHITE)	CENTER LINE, TYPE 1: DOUBLE SOLID	BARRIER REFLECTOR, TYPE 3, BIDIRECTIONAL				
								EACH	EACH	FT	EACH	EACH	EACH	MILE	MILE	EACH				
12	R-1	☺ SR 239	42+94		RT							1	1							
12	R-2	☺ SR 239	44+39		LT							1	1							
13	R-3	☺ SR 239	44+71		LT							1	1							
13	R-4	☺ SR 239	45+17		RT							1	1							
13	R-5	☺ SR 239	45+24		RT							1	1							
12	S-1	☺ SR 239	43+00		RT					10.5										
13	S-2	☺ SR 239	44+40		LT					10.5										
13	S-3	☺ SR 239	44+70		LT					11.0	1.0									
13	S-4	☺ SR 239	44+15		RT					12.5										
13	S-5	☺ SR 239	44+20		RT					11.5										
12	EL-1	☺ SR 239	41+55	44+75	LT									0.06						
13	EL-2	☺ SR 239	41+55	45+89	RT									0.08						
13	EL-3	☺ SR 239	45+22	45+89	LT									0.01						
12	CL-1	☺ SR 239	41+55	44+75	☺			3	3						0.06					
13	CL-2	☺ SR 239	45+40	45+89	☺			1	1						0.01					
12	BR-1	☺ SR 239	40+51	43+58	LT											4				
12	BR-2	☺ SR 239	42+74	45+85	RT											4				
TOTALS CARRIED TO GENERAL SUMMARY								4	4	56.0	1	5	5	0.15	0.07	8				

SIGNING AND PAVEMENT MARKING SUBSUMMARY

DESIGN AGENCY
KORDA
 KORDA / NEMETH
 ENGINEERING, INC
 1650 Watermark Drive,
 Suite 200,
 Columbus, OH 43215

DESIGNER
 CLP

REVIEWER
 ATD 07/22/21

PROJECT ID
 105100

SHEET TOTAL
 20 44