ITEM 614, MAINTAINING TRAFFIC

A MINIMUM OF 1 LANE OF TRAFFIC IN EACH
DIRECTION SHALL BE MAINTAINED AT ALL TIMES BY USE
OF THE EXISTING PAVEMENT AND THE COMPLETED PAVEMENT.
FOLLOWING A PERIOD OF 60 CONSECUTIVE CALENDAR DAYS
COMMENCING WITH THE FIRST LANE CLOSURE, NO TRAFFIC
RESTRICTIONS OR LANE CLOSURES SHALL BE IN PLACE.
A DISINCENTIVE SHALL BE ASSESSED IN THE AMOUNT OF \$1,500
PER DAY FOR EACH CALENDAR DAY TRAFFIC IS BEING MAINTAINED
BEYOND THE SPECIFIED LIMIT.

BEFORE THE WORK BEGINS, THE CONTRACTOR SHALL SUBMIT TO THE ENGINEER THE NAME(S) AND TELEPHONE NUMBER(S) OF A PERSON OR PERSONS WHO CAN BE CONTACTED TWENTY-FOUR (24) HOURS PER DAY BY THE OHIO DEPARTMENT OF TRANSPORTATION AND ALL INTERESTED POLICE AGENCIES. THIS PERSON OR PERSONS SHALL BE RESPONSIBLE FOR PLACING OR REPLACING NECESSARY TRAFFIC CONTROL DEVICES IN ACCORDANCE WITH THE OHIO MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES.

THE CONTRACTOR WILL ADVISE THE DISTRICT PUBLIC INFORMATION OFFICER AT (740) 774-8834, OR EMAIL D09.PIO@DOT.OHIO.GOV FOURTEEN (14) DAYS PRIOR TO THE START OF CONSTRUCTION ACTIVITIES. THE PROJECT ENGINEER WILL PROVIDE ASSISTANCE/CLARIFICATION FOR ANY QUESTIONS.

THE CONTRACTOR SHALL ARRANGE FOR ALL MAINTENANCE OF TRAFFIC OPERATIONS SUCH THAT THERE WILL BE NO OBSTRUCTIONS TO THE CONTINUOUS FLOW OF TRAFFIC. ALL INTERSECTIONS AND DRIVEWAYS SHALL BE OPEN TO TRAFFIC AT ALL TIMES UNLESS OTHERWISE SHOWN IN THE PLAN.

NO WORK SHALL BE PERFORMED AND ALL EXISTING LANES SHALL BE OPEN TO TRAFFIC DURING THE FOLLOWING DESIGNATED HOLIDAYS OR SPECIAL EVENTS:

NEW YEAR'S (OBSERVED)	GENERAL/REGULAR ELECTION DAY (NOV)
MEMORIAL DAY	THANKSGIVING
FOURTH OF JULY (OBSERVED)	CHRISTMAS (OBSERVED)
LABOR DAY	(OTHER HOLIDAY OR SPECIAL EVENT)

THE PERIOD OF TIME THAT THE LANES ARE TO BE OPEN DEPENDS ON THE DAY OF THE WEEK ON WHICH THE HOLIDAY OR SPECIAL EVENT FALLS. THE FOLLOWING SCHEDULE SHALL BE USED TO DETERMINE THIS PERIOD:

DAY OF HOLIDAY OR SPECIAL EVENT	TIME ALL LANES MUST BE OPEN TO TRAFFIC
SUNDAY	12:00N FRIDAY THROUGH 6:00 AM MONDAY
MONDAY	12:00N FRIDAY THROUGH 6:00 AM TUESDAY
TUESDAY	12:00N MONDAY THROUGH 6:00 AM WEDNESDAY
TUESDAY (GEN./REG. ELECTION)	5:00 AM TUESDAY THROUGH 12:00 AM WEDNESDAY
WEDNESDAY	12:00N TUESDAY THROUGH 6:00 AM THURSDAY
THURSDAY	12:00N WEDNESDAY THROUGH 6:00 AM FRIDAY
THURSDAY (THANKSGIVING ONLY)	6:00 AM WEDNESDAY THROUGH 6:00 AM MONDAY
FRIDAY	12:00N THURSDAY THROUGH 6:00 AM MONDAY
SATURDAY	12:00N THURSDAY THROUGH 6:00 AM MONDAY

ITEM 614, MAINTAINING TRAFFIC, CONT'D

DURING THE SAME PERIODS, MAINTAIN PEDESTRAIN ACCESS IF PEDESTRIAN ACCESS WAS PRESENT PRIOR TO CONSTRUCTION.

SHOULD THE CONTRACTOR FAIL TO MEET ANY OF THESE REQUIREMENTS, THE CONTRACTOR SHALL BE ASSESSED A DISINCENTIVE PER THE LANE VALUE CONTRACT (PN 127).

LANE VALUE CONTRACT TABLE

DESCRIPTION OF CRITICAL LANE	TIME UNIT	DISINCENTIVE \$ PER TIME UNIT
ALL LANES OF EB & WB SCI-52 FROM SLM 0.00-10.07	EACH MINUTE	\$15.00

LENGTH AND DURATION OF LANE CLOSURES AND RESTRICTIONS SHALL BE AT THE APPROVAL OF THE ENGINEER. IT IS THE INTENT TO MINIMIZE THE IMPACT TO THE TRAVELING PUBLIC. LANE CLOSURES OR RESTRICTIONS OVER SEGMENTS OF THE PROJECT IN WHICH NO WORK IS ANTICIPATED WITHIN A REASONABLE TIME FRAME, AS DETERMINED BY THE ENGINEER, SHALL NOT BE PERMITTED. THE LEVEL OF UTILIZATION OF MAINTENANCE OF TRAFFIC DEVICES SHALL BE COMMENSURATE WITH THE WORK IN PROGRESS.

ALL WORK AND TRAFFIC CONTROL DEVICES SHALL BE IN
ACCORDANCE WITH C&MS 614 AND OTHER APPLICABLE PORTIONS
OF THE SPECIFICATIONS, AS WELL AS THE OHIO MANUAL OF
UNIFORM TRAFFIC CONTROL DEVICES. PAYMENT FOR ALL
LABOR, EQUIPMENT AND MATERIALS SHALL BE INCLUDED IN
THE LUMP SUM CONTRACT PRICE FOR ITEM 614, MAINTAINING
TRAFFIC, UNLESS SEPARATELY ITEMIZED IN THE PLAN.

NOTIFICATION OF TRAFFIC RESTRICTIONS

THROUGHOUT THE DURATION OF THE PROJECT, THE CONTRACTOR SHALL NOTIFY THE PROJECT ENGINEER IN WRITING OF ALL TRAFFIC RESTRICTIONS AND UPCOMING MAINTENANCE OF TRAFFIC CHANGES. THE CONTRACTOR SHALL ENSURE THE WRITTEN NOTIFICATION IS SUBMITTED IN A TIMELY MANNER TO ALLOW THE PROJECT ENGINEER TO MEET THE REQUIRED TIME FRAMES SET FORTH IN THE TABLE BELOW TO INFORM THE SPECIAL HAULING PERMITS SECTION (HAULING.PERMITS@DOT.OHIO.GOV) AND THE DISTRICT PUBLIC INFORMATION OFFICE (PIO). THIS NOTIFICATION SHALL BE RECEIVED BY THE PROJECT ENGINEER PRIOR TO THE PHYSICAL SETUP OF ANY APPLICABLE SIGNS OR MESSAGE BOARDS.

INFORMATION SHOULD INCLUDE, BUT IS NOT LIMITED TO, ALL CONSTRUCTION ACTIVITIES THAT IMPACT OR INTERFERE WITH TRAFFIC AND SHALL LIST THE SPECIFIC LOCATION, TYPE OF WORK, ROAD STATUS, DATE AND TIME OF RESTRICTION, DURATION OF RESTRICTION, NUMBER OF LANES MAINTAINED, NUMBER OF LANES CLOSED, MINIMUM VERTICAL CLEARANCE, MINIMUM WIDTH OF DRIVABLE PAVEMENT, DETOUR ROUTES, IF APPLICABLE, AND ANY OTHER INFORMATION REQUESTED BY THE PROJECT ENGINEER.

ITEM	DURATION OF CLOSURE	NOTICE DUE TO PERMITS & PIO
RAMP & ROAD	>= 2 WEEKS	21 CALENDAR DAYS PRIOR TO CLOSURE
CLOSURES	> 12 HOURS & < 2 WEEKS	14 CALENDAR DAYS PRIOR TO CLOUSRE
	<= 12 HOURS	4 CALENDAR DAYS PRIOR TO CLOSURE
LANE CLOSURES &	>2 WEEKS	14 CALENDAR DAYS PRIOR TO CLOSURE
RESTRICTIONS	< 2 WEEKS	5 CALENDAR DAYS PRIOR TO CLOSURE
START OF CONST. & TRAFFIC PATTERN CHANGES	N/A	14 CALENDAR DAYS PRIOR TO CLOSURE

ANY UNFORESEEN CONDITIONS NOT SPECIFIED IN THE PLANS REQUIRING TRAFFIC RESTRICTIONS SHALL ALSO BE REPORTED TO THE PROJECT ENGINEER USING THE NOTIFICATION TIME TABLE.

WORK ZONE MARKINGS AND SIGNS

THE FOLLOWING ESTIMATED QUANTITIES HAVE BEEN CARRIED
TO THE GENERAL SUMMARY FOR USE AT LOCATIONS IDENTIFIED
BY THE ENGINEER FOR WORK ZONE PAVEMENT MARKINGS AND
SIGNS PER THE REQUIREMENTS OF C&MS 614.04 AND 614.11.

ITEM 614, WORK ZONE MARKING SIGN

47 EACH

ITEM 614, WORK ZONE CENTER LINE, CLASS III, 642 PAINT 30.09 MILE
ITEM 614, WORK ZONE EDGE LINE, CLASS III, 642 PAINT

60.18 MILE

DESIGN AGEN



DESIGNER
ZDR

REVIEWER
EMB 3-17-25

PROJECT ID
121325

SHEET TOTAL
P.4 8

DESIGN AGENCY

0

Z

ERAL

EN

9

FFIC

0

 \Box

AINTENAN

EET	SEE SHEET	DECCDIDITION			GRAND	ITEM	ITE	PART.					3ER	SHEET NUME			
	NO.	DESCRIPTION		UNIT	TOTAL	EXT	ITEM		01/NHS	8	8	7		6	4	3	
		PAVEMENT															
	P.3	MENT REPAIR (ASPHALT CONCRETE BASE), AS PER PLAN		SY	500	01041	251		500							500	
			AGGREGATE, SINGLE CH	SY GAL	143,287 53,016	11000 25000	422 422		143,287			141,497 52,354		1,790 662			
			EMULSION, CHIP SEAL COMPACTED AGGREGA	CY	204	10100	617		53,016 204			32,334		002		204	
		,, (1 E	FOG SEAL	GAL	21,494	11000	886		21,494			21,225		269		201	
		TRAFFIC CONTROL															
		TRAFFIC CONTROL	RPM	EACH	618	00100	621		618	18	618						
			RAISED PAVEMENT MAI	EACH	618	54000	621		618		618						
			EDGE LINE, 6", TYPE 1	MILE	20.06	00104	642		20.06		20.06						
			CENTER LINE, TYPE 1 REMOVAL OF PAVEMEN	MILE MILE	10.03 30.09	00300 30030	642 644		10.03 30.09		10.03 30.09						
							0.11										
			EDGE LINE, 6"	MILE	0.08	10010	646		0.08		0.08						
-			CENTER LINE	MILE	0.04	10200	646		0.04	J4	0.04						
		MAINTENANCE OF TRAFFIC				10.100											
		G SIGN LINE, CLASS III, 642 PAINT	WORK ZONE MARKING	EACH MILE	30.09	21550	614	~~~	30.09						47 30.09		
		NE, CLASS III, 6", 642 PAINT			60.18	22360	614		60.18						60.18		
					uuu	uuu	mmmm	·····	uuu								
		INCIDENTALS			ıc	11000	C14		ıc								
		UT STAKES AND SURVEYING	MAINTAINING TRAFFIC		LS LS	11000 10000	614 623		LS LS								
			MOBILIZATION		LS	10000	624		LS								
																	
											<u> </u>		-				
\dashv																	
DESIGN																	
																	
_																	
DESIGN											 		1				
R EMB																	
PROJEC																	
1																	
			-			-				_		<u> </u>	•	<u> </u>		<u> </u>	