

COMMENCEMENT AND PROCEDURE

ALL ITEMS TO BE DEMOLISHED OR REMOVED UNDER THIS CONTRACT WILL NOT ALL BE RELEASED TO THE CONTRACTOR FOR DEMOLITION OR REMOVAL AT ONE TIME, BUT WILL BE RELEASED INDIVIDUALLY OR IN GROUPS AS RIGHT-OF-WAY NEGOTIATIONS ARE COMPLETED, AND BUILDINGS ARE VACATED. THE CONTRACTOR WILL BE NOTIFIED BY THE PROJECT ENGINEER WHEN ITEMS STATED ABOVE ARE AVAILABLE FOR DEMOLITION OR REMOVAL. SEVEN (7) WORKING DAYS AFTER THE DATE OF NOTIFICATION (TO INCLUDE THE EPA WAITING PERIOD. SEE "NOTIFICATION OF EPA" SECTION) WILL CONSTITUTE THE STARTING DATE FOR THE REMOVAL PERIOD AS CALCULATED UNDER THE "COMPLETION DATE SCHEDULE" OUTLINED IN THE NOTE.

FAILURE TO MEET THE LISTED TIME CONSTRAINTS WITHIN THE PLAN WILL RESULT IN THE CONTRACTOR BEING ASSESSED LIQUIDATED DAMAGES IN THE AMOUNT OF \$2000.00 PER CALENDAR DAY BEYOND THE INDICATED TIME PERIOD.

NO ITEM WILL BE BURNED UNLESS THE CONTRACTOR TEST AND/OR ABATES ANY ASBESTOS MATERIAL NOT REQUIRED TO BE REMOVED FOR DEMOLITION. THE CONTRACTOR MUST OBTAIN THE APPLICABLE PERMITS FROM THE LOCAL GOVERNING AGENCIES.

STORM WATER POLLUTION PREVENTION PLAN (SWPPP)

A STORM WATER POLLUTION PREVENTION PLAN (SWPPP) WILL BE DEVELOPED AND MUST BE ADHERED TO IN ORDER TO PREVENT SEDIMENT AND/OR RUNOFF ASSOCIATED WITH CONSTRUCTION ACTIVITIES FROM ENTERING THE CANTON CITY WATER WELL FIELD LOCATED EAST OF THE PROJECT. THE CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATING ALL PROJECT ACTIVITIES WITH THE CANTON CITY WATER DEPARTMENT FOR THEIR APPROVAL, ALONG WITH THE DEVELOPMENT OF A SWPPP, BEFORE CONSTRUCTION ACTIVITY CAN TAKE PLACE. WATER QUALITY PRACTICES SHALL BE INCORPORATED INTO THE PROJECT SWPPP PLAN TO PREVENT UNTREATED STORM WATER TO BE DISCHARGED IN THE WATER WELL FIELD. THE PROJECT SWPPP PLAN SHALL BE SUBMITTED TO THE CANTON CITY WATER DEPARTMENT FOR REVIEW AND COMMENT BEFORE CONSTRUCTION ACTIVITY CAN TAKE PLACE.

BEST MANAGEMENT PRACTICES FOR TEMPORARY AND PERMANENT SOIL EROSION/SEDIMENT CONTROL AND WATER POLLUTION CONTROLS SHALL BE IMPLEMENTED THROUGHOUT CONSTRUCTION ACTIVITIES IN ACCORDANCE WITH ODOT'S CONSTRUCTION MATERIAL SPECIFICATIONS (CMS), THE SWPPP, AND ALL OTHER APPLICABLE SUPPLEMENTAL SPECIFICATIONS. ALL SOIL EROSION AND SEDIMENT MEASURES SPECIFIED IN THE SWPPP SHALL BE IN PLACE PRIOR TO ANY CLEARING AND GRUBBING, EXCAVATING, GRADING OR FILLING OPERATIONS AND INSTALLATION OF PROPOSED STRUCTURES OR UTILITIES, AND SHALL REMAIN IN PLACE UNTIL CONSTRUCTION IS COMPLETE AND THE AREA IS STABILIZED AS ACCEPTED BY THE ENGINEER.

THE CONTRACTOR SHALL ENSURE THAT ALL APPLICABLE STATE AND LOCAL PERMITS AND AUTHORIZATIONS ARE OBTAINED BEFORE CONSTRUCTION ACTIVITY CAN TAKE PLACE.

COMPLETION DATE SCHEDULE

UPON WRITTEN NOTIFICATION BY THE ENGINEER THAT AN ITEM IS RELEASED FOR DEMOLITION OR REMOVAL, THE CONTRACTOR SHALL COMMENCE WORK ON SUCH ITEMS NO LATER THAN SEVEN (7) WORKING DAYS THEREFROM. THE TIME ALLOTTED FOR COMPLETION OF THE DEMOLITION OR REMOVAL OF SUCH ITEMS WILL BE BASED ON THE TOTAL OF THE LUMP SUM BID FOR THE BUILDING OR GROUP OF BUILDINGS.

THEREFORE: 7 WORKING DAYS PLUS

BID:	WORKING DAYS:
\$0.00 - \$10,000.00	1 WORKING DAY
\$10,000.00 - \$20,000.00	2 WORKING DAYS
\$20,000.00 - \$30,000.00	3 WORKING DAYS
\$30,000.00 - \$40,000.00	4 WORKING DAYS
\$40,000.00 - \$50,000.00	5 WORKING DAYS
\$50,000.00 - \$60,000.00	6 WORKING DAYS
\$60,000.00 - \$70,000.00	7 WORKING DAYS

THE SCHEDULE FOR DAYS ALLOTTED CONTINUES, BASED ON ONE WORKING DAY FOR EACH ADDITIONAL INCREMENT OF \$10,000.00 OR PART THEREOF UP TO A MAXIMUM OF 50 DAYS, BID FOR THE ITEMS RELEASED EACH DATE ESTABLISHED FOR THE COMPLETION OF WORK BASED ON THE ABOVE PROCEDURE SHALL BE CONSIDERED AS "DATE OF COMPLETION" OR "CONTRACT DATE" FOR THE PURPOSE OF ADMINISTERING THE PROVISIONS OF SECTION 108.07 OF THE SPECIFICATIONS. THE BID AMOUNT OF THE ITEMS RELEASED WILL BE CONSIDERED TO BE THE "ORIGINAL CONTRACT AMOUNT" IN DETERMINING THE AMOUNT OF LIQUIDATED DAMAGES TO BE DEDUCTED FOR EACH CALENDAR DAY OVERRUN BEYOND THE DATE ESTABLISHED FOR THE COMPLETION OF WORK FOR THAT ITEM.

IF, WHEN EACH ADDITIONAL ITEM IS RELEASED FOR DEMOLITION OR REMOVAL, THE WORK TIME OF ANY PREVIOUSLY RELEASED ITEM HAS NOT EXPIRED, THE COMPLETION FOR EACH ADDITIONAL ITEM WILL BE COMPUTED COMMENCING IMMEDIATELY AFTER THE COMPLETION TIME FOR PREVIOUSLY RELEASED ITEM, EXCEPT THAT THE SEVEN (7) DAYS TO COMMENCE WORK WILL NOT APPLY.

HOWEVER, IF AN ADDITIONAL ITEM IS RELEASED FOR DEMOLITION OR REMOVAL PRIOR TO THE SCHEDULED COMPLETION TIME OF PREVIOUSLY RELEASED ITEM, AND THE CONTRACTOR HAS FINISHED THE DEMOLITION OR REMOVAL OF SUCH PREVIOUSLY RELEASED ITEM AND MOVED OFF THE SITE, THE SEVEN (7) WORKING DAYS TO COMMENCE WORK WILL APPLY.

PARAGRAPH REMOVED

PROJECT PRE-CONSTRUCTION AND CONSTRUCTION SCHEDULE NOTIFICATIONS

THE CITY OF CANTON ENGINEERING DEPARTMENT, WATER DEPARTMENT, CANTON PARKS AND RECREATION DEPARTMENT AND PLAIN TOWNSHIP SHALL BE INVITED TO ATTEND THE PROJECT PRE-CONSTRUCTION MEETING. THE CONTRACTOR SHALL COORDINATE THE PROJECT SCHEDULE WITH THE CITY OF CANTON ENGINEERING DEPARTMENT, WATER DEPARTMENT, CANTON PARKS AND RECREATION DEPARTMENT AND PLAIN TOWNSHIP.

DRINKING WATER RESOURCES - PUBLIC DRINKING WATER SUPPLY PROTECTION

THIS PROJECT IS LOCATED IN OR NEAR THE SOURCE OF A PUBLIC DRINKING WATER SUPPLY. DO NOT PERFORM EQUIPMENT FUELING WITHIN THE LOCATIONS IDENTIFIED IN THE IN THE TABLE BELOW. IF REFUELING OF IMMOBILE EQUIPMENT IS NECESSARY WITHIN THESE LIMITS, PROVIDE SECONDARY CONTAINMENT WITH ENOUGH CAPACITY TO COMPLETELY CONTAIN AND COLLECT ALL POTENTIAL LIQUID WASTES IN THE EVENT OF A SPILL. DO NOT PERFORM MAINTENANCE ACTIVITIES ASSOCIATED WITH ANY VISCOUS MATERIAL THAT HAS POTENTIAL TO CONTAMINATE THE GROUNDWATER. ALL EQUIPMENT OR LIQUID CONTAINERS SHALL BE REGULARLY CHECKED FOR LEAKS PRIOR TO ENTERING THE RESTRICTED AREAS. IDENTIFY ALL AREAS OF FUEL STORAGE, EQUIPMENT MAINTENANCE AND SPILL KITS ON THE STORMWATER POLLUTION PREVENTION PLAN. ALL AREAS UTILIZED BY THE CONTRACTOR NOT INCLUDED WITHIN THE TABLE BELOW AND NOT IN THE PROJECT LIMITS SHALL BE ASSESSED FOR POTENTIAL GROUNDWATER CONTAMINATION AND BE INDICATED ON THE STORMWATER POLLUTION PREVENTION PLAN OR SPILL PREVENTION CONTROL AND COUNTERMEASURES PLAN. THE CONTRACTOR SHALL IMMEDIATELY TAKE STEPS TO MITIGATE ANY EVENT, SUCH AS A SPILL OF FUELS, OILS, OR CHEMICALS. ANY SUCH SPILL OR EVENT SHALL BE REPORTED IMMEDIATELY TO THE EMERGENCY CONTACT LISTED BELOW FOR EACH DRINKING WATER SOURCE. IF THE SPILL IS A REPORTABLE AMOUNT, THE CONTRACTOR SHOULD CONTACT THE STARK COUNTY EMERGENCY MANAGEMENT AGENCY (330-451-3900) AND OHIO EPA ENVIRONMENTAL RESPONSE AND REVITALIZATION (800-282-9378) FOR CLEANUP OF THE SPILL.

DRINKING WATER SOURCE RESTRICTED REFUELING AND MAINTENANCE AREA: US ROUTE 62 FROM APPROXIMATELY STA. 1199+00 TO STA. 1219+00 (PROJECT END)

CITY OF CANTON DRINKING WATER CONTACT: TYLER CONVERSE AT 330-489-3308

ITEM 690, MISC.: ABATEMENT OF REGULATED UNIVERSAL HAZARDOUS WASTE

THIS ITEM IS A FIXED AMOUNT IN THE PROPOSAL TO PROVIDE COMPENSATION FOR THE REMOVAL AND DISPOSAL OF THE REGULATED UNIVERSAL AND HAZARDOUS WASTE NOT ANTICIPATED BY THE PLAN FOR THE PARCELS LISTED BELOW THAT ASBESTOS REPORTS ARE NOT AVAILABLE IDENTIFIED FOR REMOVAL. THE FIXED AMOUNT SHOWN IN THE PROPOSAL IS INCLUDED (AS ANY OTHER BID ITEMS) IN THE TOTAL BID AMOUNT. THIS FIXED AMOUNT IS THE DEPARTMENT'S ESTIMATE OF THE TOTAL COST OF THE REMOVAL AND DISPOSAL OF THE REGULATED UNIVERSAL AND HAZARDOUS WASTE. PAYMENT FOR THIS ITEM WILL BE ADJUSTED AS PER SECTION 109.05 OF THE 2013 CONSTRUCTION AND MATERIALS SPECIFICATIONS (CM&S) AND WILL BE BASED ON THE FIELD CONDITIONS ENCOUNTERED DURING CONSTRUCTION. C&M'S TABLE 104.02-2 DO NOT APPLY TO REDUCTIONS OR INCREASES IN THIS CONTRACT ITEM. THE FOLLOWING QUANTITY HAS BEEN CARRIED TO THE GENERAL SUMMARY.

PARCEL 10, PARCEL 14, PARCEL 15, PARCEL 19, PARCEL 25, PARCEL 29, PARCEL 39, PARCEL 46, PARCEL 50, PARCEL 88, PARCEL 93, PARCEL 94 AND PARCEL 100

690, MISC.: ABATEMENT OF REGULATED UNIVERSAL AND HAZARDOUS WASTE 97,500 EACH

INTERIM START DATE

NO WORK ASSOCIATED WITH THE PARCELS LISTED BELOW SHALL BEGIN PRIOR NOVEMBER 2, 2020.

PARCEL 14, PARCEL 19, PARCEL 25, PARCEL 29, PARCEL 39, PARCEL 50, PARCEL 88, PARCEL 93, PARCEL 94, PARCEL 100

I:\Project+Data\STA\109358-62-24\05DEW0\Design\Roadway\Sheets\109358_GN001.dgn Sheet2 4/2/2020 8:08:17 AM rbaughna

revised

SHEET NUM.

PART.

ITEM

ITEM

GRAND

UNIT

DESCRIPTION

SEE SHEET NO.

CALCULATED RCB CHECKED MAC

6

01/S>2/O
T

EXT

TOTAL

BUILDING DEMOLITION

MISC: NOTIFICATION AND COORDINATION: 1517 30th St NE 4

MISC: NOTIFICATION AND COORDINATION: 1523 30th St NE 4

MISC: NOTIFICATION AND COORDINATION: 1527 30th St NE 4

MISC: NOTIFICATION AND COORDINATION: 1601 30th St NE 4

MISC: NOTIFICATION AND COORDINATION: 1611 30th St NE 4

MISC: NOTIFICATION AND COORDINATION: 1617 30th St NE 4

MISC: NOTIFICATION AND COORDINATION: 1631 30th St NE 4

MISC: NOTIFICATION AND COORDINATION: 1635 30th St NE 4

MISC: NOTIFICATION AND COORDINATION: 1640 30th St NE 4

MISC: NOTIFICATION AND COORDINATION: 1642 30th St NE 4

MISC: NOTIFICATION AND COORDINATION: 2985 Maple Ave NE 4

MISC: NOTIFICATION AND COORDINATION: 3009 Rowland Ave NE 4

MISC: NOTIFICATION AND COORDINATION: 30th St NE (garage) 4

INCIDENTALS

MAINTAINING TRAFFIC

FIELD OFFICE, TYPE B

CONSTRUCTION LAYOUT STAKES AND SURVEYING

MOBILIZATION

I:\Projects\STA 109358_62-24.05\EMO\Design\Roadway\Sheets\09358_6200.dgn Sheet3 1/2/2020 8:09:21 AM Pdaughma

GENERAL SUMMARY

**STA -62-24.05
DEMO**

8
19

