


SHEET NUM.											PART.						ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
3	4	5	6	9	10	14	15	16	19		01/NHS/05/CUYF	02/NHS/05/CUYF	03/NHS/05	04/NHS/06/SLAK	05/NHS/05/STOW	06/MPO/05/STOW						
			200								25		50		125		614	11110	200	HOUR	MAINTENANCE OF TRAFFIC	
		20									6		4		10		614	12460	20	EACH	WORK ZONE MARKING SIGN	
		20									7		6		7		614	13000	20	CY	ASPHALT CONCRETE FOR MAINTAINING TRAFFIC	6
			6								2		2		2		614	18601	6	SNMT	PORTABLE CHANGEABLE MESSAGE SIGN, AS PER PLAN	
		18.86									1.9	0.1	4.42		12.44		614	20000	18.86	MILE	WORK ZONE LANE LINE, CLASS I, 4"	
		9.43									0.95	0.05	2.21		6.22		614	20550	9.43	MILE	WORK ZONE LANE LINE, CLASS III, 4", 642 PAINT	
		9.72									0.96	0.34	2.2		6.22		614	21000	9.72	MILE	WORK ZONE CENTER LINE, CLASS I	
		4.86									0.48	0.17	1.1		3.11		614	21550	4.86	MILE	WORK ZONE CENTER LINE, CLASS III, 642 PAINT	
		1,940									600		80		1,260		614	26000	1,940	FT	WORK ZONE STOP LINE, CLASS I	
		970									300		40		630		614	26610	970	FT	WORK ZONE STOP LINE, CLASS III, 642 PAINT	
													LS				614	11000	LS		INCIDENTALS	
													12				619	16010	12	MNTH	MAINTAINING TRAFFIC	
													LS				623	10000	LS		FIELD OFFICE, TYPE B	
													LS				624	10000	LS		CONSTRUCTION LAYOUT STAKES AND SURVEYING	
																					MOBILIZATION	

GENERAL SUMMARY

DESIGN AGENCY



DESIGNER  
MRS

REVIEWER  
MAC 05-12-23

PROJECT ID  
110743

SHEET TOTAL  
P.8 | 20