STATION FROM	STATION TO	SIDE	LENGTH (L)	AVERAGE WIDTH (W)	CADD AREA	AREA FOR 4"BASE EXTENSION	AREA FOR 10" BASE EXTENSION	AREA FOR 16" BASE EXTENSION					202 PAVEMENT REMOVED, ASPHALT		204 SUBGRADE COMPACTION	204 PROOF ROLLING (1 HOUR/2000 SQ YD)			302 9" ASPHALT CONCRETE BASE, PG64-22	304 6" AGGREGATE BASE, AS PER PLAN		407 NON-TRACKING TACK COAT (0.055 GAL/SY - 2 APPLICATIONS)			441 1 3/4" ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 2 (446)	441 1 1/2" ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (446), PG 64-22, AS PER PLAN		618 RUMBLE STRIPS, SHOULDER (ASPHALT CONCRETE)											
			FEET	FEET	SQ FT	SF	SF	SF					SY		SY	HOUR			CY	CY		GAL			CY	CY		FT												
RAMP B																																								
FULL DEPTH LANES																																								
2+97.50	4+74.84	LT	177.34	29.50	5550.07										616.67	0.308			154.17	102.78		67.83			29.98	25.69														
4+74.84	6+99.84	LT	225.00	26.75	6197.80										688.64	0.344			172.16	114.77		75.75			33.48	28.69														
2+97.50	6+99.84	LT/RT	402.34		17361.37								1930																											
FULL DEPTH SHOULDERS																																								
2+97.50	3+70.00	RT	72.50	2.00	144.41	23.95	59.80	95.53							26.66	0.013			5.17	4.44		1.76			0.78	0.67														
3+70.00	5+70.00	RT	200.00	6.00	1627.37	64.73	161.69	258.41							209.53	0.105			48.35	34.93		19.89			8.79	7.53														
5+70.00	6+99.84	RT	129.84	10.00	1290.60	42.75	106.85	170.86							162.38	0.081			37.92	27.06		15.77			6.97	5.97														
2+97.50	5+27.98	LT	230.48	2.00	518.44	86.78	217.14	347.74							96.24	0.048			18.63	16.04		6.34			2.80	2.40														
5+27.98	6+99.84	LT	171.86	VAR.	2032.70										225.86	0.113			56.46	37.64		24.84			10.98	9.41		178												
TOTALS CARRIED TO PAVEMENT SUBSUMMARY													1930		2026	2			493	338		213			94	81		178												

CALCULATED KRM

CHECKED MRG

PAVEMENT CALCULATIONS

SUM-76-6.40