

STATE OF OHIO
DEPARTMENT OF TRANSPORTATION

TRU-193-0.00

LIBERTY AND VIENNA TOWNSHIP
TRUMBULL COUNTY

PROJECT DESCRIPTION


IMPROVEMENT OF 6.78 MILES OF SR 193 BY PLANING AND RESURFACING INCLUDING PARTIAL DEPTH, FULL DEPTH REPAIRS, AND CURB INLET REPAIRS, AS WELL AS VARIOUS STRUCTURE WORK AT TRU-193-0491 AND TRU-193-0618.

PROJECT EARTH DISTURBED AREA: 3.78 ACRES
ESTIMATED CONTRACTOR EARTH DISTURBED AREA: 0.25 ACRES
NOTICE OF INTENT EDA: N/A (MAINTENANCE PROJECT)

2016 SPECIFICATIONS

THE STANDARD SPECIFICATIONS OF THE STATE OF OHIO, DEPARTMENT OF TRANSPORTATION, INCLUDING CHANGES LISTED IN THE PROPOSAL SHALL GOVERN THIS IMPROVEMENT.


I HEREBY APPROVE THESE PLANS AND DECLARE THAT THE MAKING OF THIS IMPROVEMENT WILL NOT REQUIRE THE CLOSING TO TRAFFIC OF THE HIGHWAY AND THAT PROVISIONS FOR THE MAINTENANCE AND SAFETY OF TRAFFIC WILL BE AS SET FORTH ON THE PLANS AND ESTIMATES.



LOCATION MAP

LATITUDE: 41°08'02" LONGITUDE: 80°39'56"

SCALE IN MILES



| | |
|-------------------------|-------|
| PORTION TO BE IMPROVED | ----- |
| INTERSTATE HIGHWAY | ----- |
| FEDERAL ROUTES | ----- |
| STATE ROUTES | ----- |
| COUNTY & TOWNSHIP ROADS | ----- |
| OTHER ROADS | ----- |

DESIGN DESIGNATION

DESIGN FUNCTIONAL CLASSIFICATION:
RURAL MAJOR COLLECTOR
NHS PROJECT ----- NO

DESIGN EXCEPTIONS

NONE

INDEX OF SHEETS:

| | |
|-----------------------------------|-------|
| TITLE SHEET | 1 |
| TYPICAL SECTIONS | 2-4 |
| GENERAL NOTES | 5-8 |
| MAINTENANCE OF TRAFFIC | 9-10 |
| GENERAL SUMMARY | 11-12 |
| PAYMENT CALCULATIONS | 13-14 |
| CURB RAMP SUB SUMMARY | 15-17 |
| PAYMENT MARKING SUB SUMMARY | 18 |
| RAISED PAYMENT MARKER SUB SUMMARY | 19 |
| STRUCTURES | 20-22 |


UNDERGROUND UTILITIES
CONTACT BOTH SERVICES TWO WORKING DAYS BEFORE YOU DIG.

Call Before You Dig
1-800-362-2764

(Non-members must be called directly)
OIL & GAS PRODUCERS
UNDERGROUND PROTECTION SERVICE
1-800-925-0988

PLAN PREPARED BY:
ODOT-- DISTRICT 4 PLANNING AND ENGINEERING
2008 S ARLINGTON RD
AKRON, OH 44306

ENGINEERS SEAL:



SIGNED: *Thomas Powell*
DATE: 01/31/17

| STANDARD CONSTRUCTION DRAWINGS | | | | SUPPLEMENTAL SPECIFICATIONS | SPECIAL PROVISIONS |
|--------------------------------|---------|----------|----------|-----------------------------|--------------------|
| BP-3.1 | 7/18/14 | TC-41.20 | 10/18/13 | 800-2016 4/21/17 | |
| BP-5.1 | 7/19/13 | TC-42.10 | 10/18/13 | 821 4/20/12 | |
| BP-7.1 | 7/18/14 | TC-42.20 | 10/18/13 | 832 1/17/14 | |
| | | TC-52.10 | 10/18/13 | 897 1/16/15 | |
| CB-2.1 | 1/15/16 | TC-52.20 | 7/15/16 | 921 4/20/12 | |
| | | TC-61.30 | 1/20/17 | | |
| DM-1.1 | 1/15/16 | TC-65.10 | 1/17/14 | | |
| DM-4.3 | 1/15/16 | TC-65.11 | 7/15/16 | | |
| DM-4.4 | 1/15/16 | TC-71.10 | 1/20/17 | | |
| | | TC-82.10 | 7/17/15 | | |
| MT-95.31 | 1/20/17 | | | | |
| MT-95.32 | 1/20/17 | | | | |
| MT-99.20 | 7/19/13 | | | | |
| MT-101.90 | 7/17/15 | | | | |
| MT-105.10 | 7/19/13 | | | | |

APPROVED: *[Signature]*
DATE: 1-31-17 DISTRICT DEPUTY DIRECTOR

APPROVED: *[Signature]*
DATE: 1-31-17 DIRECTOR, DEPARTMENT OF TRANSPORTATION

TRU - SR 193-00.00
170407 PID - 88916
Dist 4 6/8/2017

Contract Proposal Available @
www.contracts.dot.state.oh.us/home

FEDERAL PROJECT NO.
E130(865)


PID NO.
88916

CONSTRUCTION PROJECT NO.


RAILROAD INVOLVEMENT
NONE

TRU-193-0.00


I:\ProjectData\TRU\88916_193_0.00\Design\Roadway\Sheets\88916_GY001.dgn_Sheet 1/31/2017 8:38:17 AM ccobelan



| TYPICAL SECTION 1 | | | |
|-------------------|------|---------|----------------|
| SLM | | PW (FT) | LENGTH (MILES) |
| FROM | TO | | |
| 0.00 | 0.87 | 56.00 | 0.87 |
| 0.87 | 0.92 | 69.00 | 0.05 |
| 0.92 | 0.97 | 56.00 | 0.05 |
| 0.97 | 1.03 | 69.00 | 0.06 |
| 1.03 | 1.36 | 56.00 | 0.33 |
| 1.73 | 1.78 | 56.00 | 0.05 |
| 1.78 | 1.90 | 68.00 | 0.12 |
| 1.90 | 1.97 | 80.00 | 0.07 |



| TYPICAL SECTION 2 | | | | |
|-------------------|------|-----------|------------|----------------|
| SLM | | PW NB(FT) | PW SB (FT) | LENGTH (MILES) |
| FROM | TO | | | |
| 1.36 | 1.56 | 24.00 | 32.00 | 0.20 |
| 1.56 | 1.68 | 50.00 | 29.00 | 0.12 |
| 1.68 | 1.73 | 22.00 | 33.00 | 0.05 |




| TYPICAL SECTION 3 | | | |
|-------------------|------|---------|----------------|
| SLM | | PW (FT) | LENGTH (MILES) |
| FROM | TO | | |
| 1.97 | 2.05 | 71.00 | 0.08 |
| 2.05 | 3.39 | 65.00 | 1.34 |

LEGEND


- ① ITEM 254, PAVEMENT PLANING, ASPHALT CONCRETE, AS PER PLAN (T=3")
- ② ITEM 407, NON-TRACKING TACK COAT @ 0.08 GAL/SY
- ③ ITEM 407, NON-TRACKING TACK COAT @ 0.05 GAL/SY
- ④ ITEM 441, ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 2, (446) (T 1 3/4")
- ⑤ ITEM 441, ASPHALT CONCRETE SURFACE COURSE, TYPE 1 (446), AS PER PLAN (PG70-22M) (T= 1 1/4")
- ⑥ ITEM 897, PAVEMENT PLANING, ASPHALT CONCRETE, CLASS A (T= 1 1/4")
- ⑦ ITEM 424, FINE GRADED POLYMER ASPHALT CONCRETE, TYPE B, AS PER PLAN (T = 1 1/4")
- ⑧ 617, COMPACTED AGGREGATE, AS PER PLAN (T = 2")
- ⑨ SAFETY EDGE, REFER TO SAFETY EDGE DETAIL SHEET 4
- ⑩ PRIME COAT, AS PER PLAN @ 0.4 GAL/SY

- (A) EXISTING ASPHALT
- (B) EXISTING CONCRETE BASE
- (C) EXISTING CONCRETE BASE (SLM 0.00 TO SLM 1.77)
- (D) EXISTING ASPHALT BASE (SLM 1.77 TO SLM 1.97)
- (E) EXISTING CONCRETE GUTTER
- (F) EXISTING CONCRETE ISLAND

I:\ProjectData\TRU\88916_193_0_00\Design\Roadway\Sheets\88916_GY001.dgn_Sheet2 1/31/2017 8:38:18 AM ccopelan




| TYPICAL SECTION 4 | | | |
|-------------------|------|---------|----------------|
| SLM | | PW (FT) | LENGTH (MILES) |
| FROM | TO | | |
| 3.39 | 3.50 | 67.00 | 0.11 |
| 3.50 | 3.96 | 54.00 | 0.46 |
| 3.96 | 4.05 | 65.00 | 0.09 |
| 4.05 | 5.13 | 54.00 | 1.08 |
| 5.38 | 6.56 | 54.00 | 1.18 |
| 6.56 | 6.60 | 64.00 | 0.04 |
| 6.7 | 6.78 | 64.00 | 0.08 |



| TYPICAL SECTION 5 | | | |
|-------------------|------|---------|----------------|
| SLM | | PW (FT) | LENGTH (MILES) |
| FROM | TO | | |
| 5.13 | 5.18 | 54.00 | 0.05 |
| 5.18 | 5.38 | 54.00 | 0.20 |

* NO RIGHT GUTTER SLM 5.13 TO SLM 5.18
PLACE COMPACTED AGGREGATE AND SAFETY
EDGE AS SHOWN IN TYPICAL 3



| TYPICAL SECTION 6 | | | |
|-------------------|------|---------|----------------|
| SLM | | PW (FT) | LENGTH (MILES) |
| FROM | TO | | |
| 6.60 | 6.70 | 29.00 | 0.10 |

SAFETY EDGE (ASPHALT CONCRETE)

IN ADDITION TO THE REQUIREMENTS OF 401.12, ATTACH A DEVICE TO THE SCREED OF THE PAVER THAT CONFINES THE MATERIAL AT THE END GATE AND EXTRUDES THE ASPHALT MATERIAL IN SUCH A WAY THAT RESULTS IN A COMPACTED WEDGE SHAPE PAVEMENT EDGE OF APPROXIMATELY 30 DEGREES (NOT STEEPER THAN 40 DEGREES). ENSURE THE DEVICE MAINTAINS CONTACT WITH THE EXISTING SURFACE, AND ALLOW FOR AUTOMATIC TRANSITION TO CROSS ROADS, DRIVEWAYS AND OBSTRUCTIONS. DO NOT USE CONVENTIONAL SINGLE PLATE STRIKE OFF.

CONSTRUCTION OF SAFETY EDGE CAN BE OMITTED AT LOCATIONS WHERE EXISTING WIDTH OF GRADED SHOULDER OR BERM IS LESS THAN 12". PROJECTS WITH VARYING CONDITIONS SHOULD USE SAFETY EDGE WHERE POSSIBLE. PLAN PREPARATION HAS MADE EVERY REASONABLE ATTEMPT TO IDENTIFY POSSIBLE SAFETY EDGE LOCATIONS.

USE THE TRANSTECH SHOULDER WEDGE MAKER, THE CARLSON SAFETY EDGE END GATE, THE ADVANT-EDGER, THE TROXLER SAFETY SLOPE OR A SIMILAR APPROVED-EQUAL DEVICE THAT PRODUCES THE SAME WEDGE CONSOLIDATION RESULTS. CONTACT INFORMATION FOR THESE WEDGE SHAPE COMPACTION DEVICES IS THE FOLLOWING:

TRANSTECH SYSTEMS, INC.
1594 STATE STREET
SCHENECTADY, NY 12304
1-800-724-6306
WWW.TRANSTECHSYS.COM

ADVANT-EDGE PAVING EQUIPMENT LLC
P.O. BOX 9163
NISKAYUNA, NY 12309-0163
518-280-6090
WWW.ADVANTAEDGEPAVING.COM

CARLSON SAFETY EDGE END GATE
18425 50TH AVENUE EAST
TACOMA, WA 98446
253-875-8000

TROXLER ELECTRONIC LABORATORIES, INC.
3008 E. CORNWALLIS RD.
RESEARCH TRIANGLE PARK, NC 27709
1-877-TROXLER
WWW.TROXLERLABS.COM

IF ELECTING TO USE A SIMILAR DEVICE, PROVIDE PROOF THAT THE DEVICE HAS BEEN USED ON PREVIOUS PROJECTS WITH ACCEPTABLE RESULTS OR CONSTRUCT A TEST SECTION PRIOR TO THE BEGINNING OF WORK AND DEMONSTRATE WEDGE COMPACTION TO THE SATISFACTION OF THE ENGINEER. SHORT SECTIONS OF HANDWORK WILL BE ALLOWED WHEN NECESSARY FOR TRANSITIONS AND TURNOUTS OR OTHERWISE AUTHORIZED BY THE ENGINEER.

IN ADDITION TO THE REQUIREMENTS OF 401.16, MAKE THE FIRST ROLLER PASS 8 TO 12 INCHES AWAY FROM TAPERED EDGE. DO NOT ROLL THE TAPER.

ITEM 209, PREPARING SUBGRADE FOR SHOULDER PAVING, AS PER PLAN.

PREPARE THE SHOULDER FOR PAVING A CONSISTENT SAFETY EDGE IN BOTH THICKNESS AND WIDTH.

PRIOR TO PAVING THE SAFETY EDGE, GRADE AN AREA 10 INCHES WIDE, BEGINNING AT THE EDGE OF THE PAVED ROADWAY, TO PROVIDE A LEVEL SURFACE FREE OF VEGETATION FOR CONSTRUCTION OF THE SAFETY EDGE. IF NECESSARY, EXCAVATE THE GRADED AREA TO THE DEPTH NECESSARY TO CONSTRUCT THE SAFETY EDGE. THE MATERIAL REMOVED DURING THIS PROCESS SHOULD BE REMOVED IMMEDIATELY. COMPACT THE GRADED SHOULDER ACCORDING TO 617.05, OR AS DIRECTED BY THE ENGINEER.

NOTES:

1.) SAFETY EDGES ARE REQUIRED AT THE OUTSIDE EDGES OF THE PAVED ROADWAY (EDGE OF TRAVEL LANE OR EDGE OF PAVED SHOULDER).


2.) CONSTRUCT THE SAFETY EDGE THE FULL ASPHALT CONCRETE OVERLAY THICKNESS OR 2.5" WHICHEVER IS GREATER, NOT TO EXCEED THE MAXIMUM SAFETY EDGE THICKNESS OF 6". CONSTRUCT A NEAR-VERTICAL FACE BELOW THE SAFETY EDGE FOR THICKNESS GREATER THAN 6".

3.) BLADE AND SHAPE EXISTING SHOULDER MATERIAL TO FORM A UNIFORM SURFACE UNDER THE SAFETY EDGE PRIOR TO PLACEMENT OF THE ASPHALT CONCRETE OVERLAY.

* 40° MAX

ESTIMATED QUANTITIES

| ROUTE | SAFETY EDGE THICKNESS (IN.) | S.L.M TO S.L.M. | | SIDE | 209 | 424 | 441 | |
|-----------------------------------|-----------------------------|-----------------|----|------|---|--|---|----|
| | | STA | TO | | PREPARING SUBGRADE FOR SHOULDER PAVING, AS PER PLAN | FINE GRADED POLYMER ASPHALT CONCRETE, TYPE B | ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (446), AS PER PLAN, PG70-22M | |
| 193 | 2.5 | 1.97 | TO | 3.39 | L/R | 150.0 | 14.44 | |
| 193 | 3 | 3.39 | TO | 5.13 | L/R | 183.7 | 25.18 | |
| 193 | 3 | 5.13 | TO | 5.18 | R | 2.6 | 0.36 | |
| 193 | 3 | 5.38 | TO | 6.60 | L/R | 128.8 | 17.65 | |
| 193NB | 3 | 6.60 | TO | 6.70 | L/R | 10.6 | 1.45 | |
| 193SB | 3 | 6.60 | TO | 6.70 | L/R | 10.6 | 1.45 | |
| 193 | 3 | 6.70 | TO | 6.78 | L/R | 8.4 | 1.16 | |
| TOTALS CARRIED TO GENERAL SUMMARY | | | | | | 495 | 15 | 48 |



SAFETY EDGE DETAIL FOR 1 COURSE OVERLAY

I:\ProjectData\TRU\88916_193_0.00\Design\Roadway\Sheets\88916_GY001.dgn_Sheet3 1/31/2017 8:38:19 AM ccopelan

UTILITIES

THE CONTRACTOR SHALL USE THE FOLLOWING PROCEDURE AT EACH LOCATION WHERE WORK IS PERFORMED, IN ACCORDANCE WITH SECTIONS 105.07 AND 107.16 IN THE CONSTRUCTION AND MATERIALS SPECIFICATIONS.

THE CONTRACTOR SHALL NOTIFY THE PROJECT ENGINEER, THE OHIO UTILITIES PROTECTION SERVICE (OUPS), THE OHIO & GAS PROCEDURES UNDERGROUND PROTECTION SERVICE (OGPUPS), THE OHIO DEPARTMENT OF TRANSPORTATION DISTRICT 4 HEAD-QUARTERS AND ALL NON REGISTERED UTILITY OWNERS AT LEAST TWO (2) WORKING DAYS PRIOR TO COMMENCING CONSTRUCTION IN ALL AREAS.

OUPS 1-800-362-2764 (CONTACT LIMITED BASIS PARTICIPANTS DIRECTLY)
 OGPUPS 1-800-925-0988
 ODOT 330-786-3145 KEN GREENE

THE LOCATION OF EXISTING UNDERGROUND UTILITIES ARE NOT SHOWN ON THE PLANS, BUT CAN BE OBTAINED FROM THE OWNERS OF THE UTILITIES. THE CONTRACTOR IS RESPONSIBLE FOR ANY DAMAGE TO UTILITIES.

PAVEMENT MARKING DETAILS

THE PAVEMENT MARKING DETAIL SHEETS WILL BE SUPPLIED TO THE CONTRACTOR AT THE PRE-CONSTRUCTION MEETING.

PROFILE AND ALIGNMENT

PLACE THE PROPOSED PAVEMENT TO FOLLOW THE ALIGNMENT AND PROFILE OF THE EXISTING PAVEMENT. PLACE THE PROPOSED ASPHALT CONCRETE OVERLAY AS SHOWN ON THE TYPICAL SECTIONS.

WORK LIMITS

THE WORK LIMITS SHOWN ON THESE PLANS ARE FOR PHYSICAL CONSTRUCTION ONLY. PROVIDE THE INSTALLATION AND OPERATION OF ALL WORK ZONE TRAFFIC CONTROL AND WORK ZONE TRAFFIC CONTROL DEVICES REQUIRED BY THESE PLANS WHETHER INSIDE OR OUTSIDE THESE WORK LIMITS.

INTERSECTIONS

INTERSECTIONS WILL BE RESURFACED 25 FT. BEYOND THE EDGE LINE, UNLESS OTHERWISE DIRECTED BY THE ENGINEER OR INDICATED IN THE PLAN. INTERSECTIONS SHALL BE PAVED AFTER COMPLETION OF THE SURFACE COURSE. A BUTT JOINT, AS PER STANDARD CONSTRUCTION DRAWING BP-3.1, SHALL BE USED TO PROVIDE A SMOOTH TRANSITION TO THE EXISTING PAVEMENT. USE THE SAME ASPHALT CONCRETE AS THE MAINLINE PAVEMENT UNLESS SHOWN OTHERWISE ON THE ASPHALT CONCRETE CALCULATIONS SHEET. ANY GRADING OR PRIME NECESSARY TO ACCOMPLISH THIS WORK SHALL BE INCLUDED IN THE COST OF THE PERTINENT BID ITEM.

CURB RAMPS / DETECTABLE WARNINGS


UNLESS OTHERWISE DIRECTED BY THE ENGINEER, INSTALLATION OF THE CURB RAMPS / DETECTABLE WARNINGS WILL BE PERFORMED PRIOR TO MAINLINE RESURFACING.

PEDESTRIAN CURB CUTS

THE CONTRACTOR WILL PROVIDE CURB CUTS, AS DETAILED BELOW WHERE CURB CURRENTLY EXISTS. THE FOLLOWING ITEMS WILL BE USED TO REMOVE THE EXISTING CURB AND INSTALL NEW PEDESTRIAN CURB CUTS (ALL ITEMS MAY NOT BE USED AT ALL LOCATIONS):

- ITEM 202, CURB REMOVED
- ITEM 203, EXCAVATION
- ITEM 203, EMBANKMENT
- ITEM 609, COMBINATION CURB AND GUTTER, TYPE 2
- ITEM 609, CURB, TYPE 6
- ITEM 659, SEEDING AND MULCHING


REFER TO THE CURB RAMP SUB-SUMMARY FOR LOCATIONS AND QUANTITIES.



ITEM 251 - PARTIAL DEPTH PAVEMENT REPAIR (441)

A QUANTITY OF THIS ITEM SHALL BE PROVIDED FOR USE AS DIRECTED BY THE ENGINEER. THE ITEM SHALL CONSIST OF REPAIRING EXISTING LOCATIONS EXHIBITING SURFACE DETERIORATION AND PLACING ITEM 441 ASPHALT CONCRETE, TYPE 2. THE ASPHALT CONCRETE SHALL BE COMPACTED WITH A TYPE I PNEUMATIC TIRE ROLLER AND A STEEL WHEEL ROLLER AS PER 401.13. IT IS NOT THE INTENT TO REPAIR EVERY DETERIORATED AREA WITHIN THE PROJECT. THE ENGINEER SHALL DETERMINE WHICH AREAS ARE TO BE REPAIRED. UNLESS OTHERWISE DIRECTED BY THE ENGINEER, THIS ITEM SHALL BE PERFORMED AFTER THE COMPLETION OF MAINLINE PAVEMENT PLANING. ALSO, THIS ITEM SHALL COMMENCE WITHIN 7 DAYS OF THE COMPLETION OF MAINLINE PAVEMENT PLANING. PAYMENT SHALL BE BASED ON THE ACTUAL NUMBER OF SQUARE YARDS OF PAVEMENT REPAIR. THE FOLLOWING ESTIMATED QUANTITY HAS BEEN CARRIED TO THE GENERAL SUMMARY:

- SLM 0.00 TO SLM 1.97
251, PARTIAL DEPTH PAVEMENT REPAIR (441), 600 SQ. YD.
- SLM 1.97 TO SLM 3.39
251, PARTIAL DEPTH PAVEMENT REPAIR (441), 200 SQ YD
- SLM 3.39 TO SLM 5.37
251, PARTIAL DEPTH PAVEMENT REPAIR (441), 300 SQ YD
- SLM 5.37 TO SLM 6.78
251, PARTIAL DEPTH PAVEMENT REPAIR (441), 200 SQ YD



ITEM 203 - EXCAVATION (FOR PAVEMENT REPAIR)

THIS ITEM OF WORK SHALL CONSIST OF REMOVING AND DISPOSING OF ALL UNSUITABLE MATERIAL BY EXCAVATING THE EXISTING SUBGRADE AND SUBBASE TO AN AVERAGE DEPTH OF 6 INCHES OR AS DIRECTED BY THE ENGINEER. EXACT LIMITS OF REMOVAL SHALL BE DETERMINED BY THE ENGINEER. ALL EQUIPMENT, LABOR, TOOLS, AND INCIDENTALS NECESSARY TO COMPLETE THIS ITEM SHALL BE INCLUDED IN THE UNIT PRICE BID FOR ITEM 203 EXCAVATION (FOR PAVEMENT REPAIR). THE FOLLOWING ESTIMATED QUANTITY HAS BEEN CARRIED TO THE GENERAL SUMMARY:

- SLM 0.00 TO SLM 1.97
203, EXCAVATION (FOR PAVEMENT REPAIR) 200 CU YD
- SLM 3.39 TO SLM 5.37
203, EXCAVATION (FOR PAVEMENT REPAIR) 8 CU YD
- SLM 5.37 TO SLM 6.78
203, EXCAVATION (FOR PAVEMENT REPAIR) 8 CU YD

ITEM 304 - AGGREGATE BASE (FOR PAVEMENT REPAIR)


THE FOLLOWING ESTIMATED QUANTITY HAS BEEN PROVIDED AND SHALL BE USED AS DIRECTED BY THE ENGINEER TO BACKFILL AREAS WHICH WERE EXCAVATED UNDER ITEM 203 EXCAVATION (FOR PAVEMENT REPAIR). THE FOLLOWING ESTIMATED QUANTITY HAS BEEN CARRIED TO THE GENERAL SUMMARY:

- SLM 0.00 TO SLM 1.97
304, AGGREGATE BASE (FOR PAVEMENT REPAIR), 200 CU YD
- SLM 3.39 TO SLM 5.37
304, AGGREGATE BASE (FOR PAVEMENT REPAIR), 8 CU YD
- SLM 5.37 TO SLM 6.78
304, AGGREGATE BASE (FOR PAVEMENT REPAIR), 8 CU YD

ITEM 255- FULL DEPTH PAVEMENT REMOVAL AND RIGID REPLACEMENT, CLASS OC MS (SLM 0.00 TO SLM 1.97)

A QUANTITY OF THIS ITEM SHALL BE PROVIDED FOR USE AS DIRECTED BY THE ENGINEER. THIS ITEM SHALL CONSIST OF CUTTING AND REMOVING DETERIORATED PAVEMENT FULL DEPTH AND PLACING 9" CONCRETE, CLASS OC MS. UNLESS OTHERWISE DIRECTED BY THE ENGINEER, THIS ITEM SHALL BE PERFORMED AFTER THE COMPLETION OF MAINLINE PAVEMENT PLANING. IT IS NOT THE INTENT TO REPAIR EVERY DETERIORATED AREA WITHIN THE PROJECT. THE ENGINEER SHALL DETERMINE WHICH AREAS ARE TO BE REPAIRED. PAYMENT SHALL BE BASED ON THE ACTUAL NUMBER OF SQUARE YARDS OF PAVEMENT REMOVED AND REPLACED TO THE LIMITS DESIGNATED BY THE ENGINEER. THE FOLLOWING ESTIMATED QUANTITY HAS BEEN CARRIED TO THE GENERAL SUMMARY:

- SLM 0.00 TO SLM 1.97
255, FULL DEPTH PAVEMENT REMOVAL AND REPLACEMENT, CLASS OC MS, 1200 SQ YD
255, FULL DEPTH PAVEMENT SAWING, 5400 FT



ITEM 254 - PAVEMENT PLANING, ASPHALT CONCRETE, AS PER PLAN

THIS ITEM OF WORK SHALL BE PERFORMED IN CONFORMANCE WITH ITEM 254 IN THE CMS EXCEPT THE DEPTH SHALL VARY FROM 3" TO THE TOP OF THE CONCRETE WHICHEVER IS FIRST. THIS WORK SHALL BE PERFORMED SO THAT THE CONCRETE BASE IS NOT DISTURBED. ALL EQUIPMENT, LABOR, TOOLS, AND OTHER INCIDENTALS REQUIRED TO PERFORM THIS WORK SHALL BE INCLUDED IN THE UNIT BID PRICE FOR ITEM 254 PAVEMENT PLANING, ASPHALT CONCRETE, AS PER PLAN.

CALCULATED
CNC
CHECKED
MAC

GENERAL NOTES

TRU-193-0.00


I:\Project+Data\TRU\88916_193_0.00\Design\Roadway\Sheets\88916_GN001.dgn Sheet 1/31/2017 8:38:21 AM ccopejan

ITEM 253 - PAVEMENT REPAIR

A QUANTITY OF THIS ITEM SHALL BE PROVIDED FOR USE AS DIRECTED BY THE ENGINEER. THIS ITEM SHALL CONSIST OF CUTTING AND REMOVING DETERIORATED PAVEMENT FULL DEPTH AND PLACING 9"± 301 ASPHALT CONCRETE BASE, PG64-22. THE MAXIMUM COMPACTED DEPTH OF ANY ONE LAYER SHALL BE 6 INCHES. UNLESS OTHERWISE DIRECTED BY THE ENGINEER, THIS ITEM SHALL BE PERFORMED AFTER THE COMPLETION OF MAINLINE PAVEMENT PLANING. ALSO, THIS ITEM SHALL COMMENCE WITHIN 7 DAYS OF THE COMPLETION OF MAINLINE PAVEMENT PLANING. IT IS NOT THE INTENT TO REPAIR EVERY DETERIORATED AREA WITHIN THE PROJECT. THE ENGINEER SHALL DETERMINE WHICH AREAS ARE TO BE REPAIRED. PAYMENT SHALL BE BASED ON THE ACTUAL NUMBER OF SQUARE YARDS OF PAVEMENT REMOVED AND REPLACED TO THE LIMITS DESIGNATED BY THE ENGINEER. THE FOLLOWING ESTIMATED QUANTITY HAS BEEN CARRIED TO THE GENERAL SUMMARY:

SLM 3.39 TO SLM 5.37
 253, PAVEMENT REPAIR, 50 SQ YD
 255, FULL DEPTH PAVEMENT SAWING, 225 FT

SLM 5.37 TO SLM 6.78
 253, PAVEMENT REPAIR, 50 SQ YD
 255, FULL DEPTH PAVEMENT SAWING, 225 FT



ITEM 441 - ASPHALT CONCRETE SURFACE COURSE, TYPE 1, AS PER PLAN (PG70-22M)

ITEM 424- FINE GRADED POLYMER ASPHALT CONCRETE, TYPE B, AS PER PLAN

703.05 DO NOT USE FINE AGGREGATE FROM A SOURCE DESIGNATED 'SR' OR 'SRH' ACCORDING TO THE OFFICE OF MATERIALS MANAGEMENT (OMM) IN ANY JOB MIX FORMULA (JMF) FOR THIS ITEM.

ITEM 408 - PRIME COAT, AS PER PLAN

APPLY "MC-70" AT A RATE OF 0.4 GALLONS PER SQUARE YARD, OR AS DETERMINED BY THE ENGINEER, TO THE COMPLETED COMPACTED AGGREGATE SHOULDER.

ITEM 617 - COMPACTED AGGREGATE, AS PER PLAN

IN LOW SHOULDER AREAS EXCEEDING 1", AND ADJACENT TO THE SAFETY EDGE, OR AS DIRECTED BY THE ENGINEER, RECYCLED ASPHALT PAVEMENT (RAP) SHALL BE USED IN AREAS ADJACENT TO THE PAVED BERM. THE RAP SHALL HAVE A MINIMUM PG CONTENT OF 4.5% AND MEET THE FOLLOWING GRADATION. ONCE THE STOCKPILE MEETS THE GRADATION, THE PG CONTENT OF THE RAP SHALL BE DETERMINED PER 441.03. THE RAP ANALYSIS MUST BE SUBMITTED TO THE ENGINEER FOR APPROVAL 2 WEEKS PRIOR TO USE. METHOD OF MEASUREMENT SHALL BE AS PER 617.06. PLACEMENT AND COMPACTION SHALL MEET THE REQUIREMENTS OF ITEM 617. ALL MATERIALS, LABOR, EQUIPMENT, TOOLS AND INCIDENTALS NECESSARY TO COMPLETE THE WORK SHALL BE INCLUDED IN THE UNIT PRICE BID FOR ITEM 617 COMPACTED AGGREGATE, AS PER PLAN.

MODIFIED GRADATION SHALL APPLY:

| SIEVE | TOTAL PERCENT PASSING |
|---------|-----------------------|
| 1-1/2" | 100 |
| 3/4" | 50-100 |
| NO. 4 | 35-70 |
| NO. 30 | 9-33 |
| NO. 200 | 0-13 |

ROADWAY, MISC.: VERTICAL CLEARANCE

AFTER ALL CONSTRUCTION HAS BEEN COMPLETED, A REGISTERED SURVEYOR WILL TAKE VERTICAL CLEARANCE MEASUREMENTS AT LOCATIONS INDICATED ON THE APPROVED ODOT FORM (AVAILABLE IN THE DISTRICT 4 STRUCTURES AND PAVEMENT OFFICE). THE FINAL MEASUREMENTS SHALL BE RECORDED ON THE FORM AND SUBMITTED TO THE PROJECT ENGINEER AND THE DISTRICT 4 STRUCTURES AND PAVEMENT ENGINEER. THE RECORD SHALL BEAR THE SEAL OF THE LICENSED SURVEYOR WHO HAS TAKEN THE MEASUREMENTS. THIS WORK SHALL BE PERFORMED AT THE FOLLOWING STRUCTURES:

TRU-80-0420L/R
 TRU-82-2212L/R

THE FOLLOWING QUANTITY HAS BEEN CARRIED TO THE GENERAL SUMMARY:

ROADWAY, MISC.: VERTICAL CLEARANCE, 4 EACH

LINEAR GRADING

SHOULDER WIDTH BEYOND THE LIMITS OF THE COMPACTED AGGREGATE WILL BE GRADED TO PROVIDE POSITIVE DRAINAGE AND WILL BE PERFORMED ONLY IN THE AREAS NECESSARY. THIS WORK WILL NOT BE PERFORMED ON THE ENTIRE PROJECT. THE AREAS FOR THE WORK WILL BE MARKED BY THE PROJECT ENGINEER. UNDER NO CIRCUMSTANCES WILL THIS WORK BE PERFORMED CONCURRENTLY WITH ANY OTHER OPERATION.

GRADING WILL BE ACCOMPLISHED BY THE REMOVAL OF, OR ADDITION OF MATERIAL TO PROVIDE A 0.08 POSITIVE SLOPE. EXCESS MATERIAL WILL BE WINDROWED ON THE SHOULDER. THE GRADED AREAS WILL BE COMPACTED TO A SUFFICIENT DENSITY TO PREVENT EROSION UNTIL SEEDING AND MULCHING IS PERFORMED. ALL EXCESS MATERIAL WILL BE REMOVED FROM THE BERMS AND WILL BE DISPOSED OF OFF THE PROJECT BY THE CONTRACTOR.

SEEDING AND MUCHING, FERTILIZER AND LIME WILL BE PERFORMED WITHIN A PERIOD NOT TO EXCEED 10 DAYS AFTER THE LINEAR GRADING.

THE QUANTITY OF ITEM 209 IS NOT PERMITTED TO BE INCREASED. REDUCTIONS IN QUANTITIES ARE PERMITTED AS DETERMINED BY THE PROJECT ENGINEER.

ALL MATERIALS, LABOR, EQUIPMENT, TOOLS, AND INCIDENTALS NECESSARY TO COMPLETE THIS WORK WILL BE INCLUDED IN THE UNIT PRICE FOR THE PERTINENT BID ITEM. THE FOLLOWING QUANTITIES HAVE BEEN CARRIED TO THE GENERAL SUMMARY:

SLM 0.00 TO SLM 5.37
 209, LINEAR GRADING, 180 STA.
 659, SEEDING AND MULCHING, 10,000 SQ YD
 659, COMMERCIAL FERTILIZER, 1.35 TON
 659, LIME, 2.07 ACRES
 659, WATER, 54 M. GAL.

SLM 5.37 TO SLM 6.78
 209, LINEAR GRADING, 149 STA.
 659, SEEDING AND MULCHING, 8,278 SQ YD
 659, COMMERCIAL FERTILIZER, 1.37 TON
 659, LIME, 1.71 ACRES
 659, WATER, 45 M. GAL.

I:\ProjectData\TRU\88916_193_0.00\Design\Roadway\Sheets\88916_GN001.dgn_Sheet 2 1/31/2017 8:38:21 AM ccopelan

CALCULATED
 CNC
 CHECKED
 MAC

GENERAL NOTES

TRU-193-0.00

ITEM SPECIAL - MISCELLANEOUS METAL

EXISTING CASTINGS MAY PROVE TO BE UNSUITABLE FOR REUSE, AS DETERMINED BY THE ENGINEER. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO PROVIDE THE CASTINGS OF THE REQUIRED TYPE, SIZE AND STRENGTH (HEAVY OR LIGHT DUTY) FOR THE PARTICULAR STRUCTURE IN QUESTION. ALL MATERIAL SHALL MEET ITEM 611 OF THE SPECIFICATIONS AND SHALL HAVE THE PRIOR APPROVAL OF THE ENGINEER.

THE FOLLOWING ESTIMATED QUANTITY HAS BEEN CARRIED TO THE GENERAL SUMMARY FOR USE AS DIRECTED BY THE ENGINEER.

SPECIAL, MISCELLANEOUS METAL 40,000 POUNDS

THE CONTRACTOR IS CAUTIONED TO USE EXTREME CARE IN THE REMOVAL, STORAGE AND REPLACEMENT OF ALL EXISTING CASTINGS. CASTINGS DAMAGED BY THE NEGLIGENCE OF THE CONTRACTOR, AS DETERMINED BY THE ENGINEER, SHALL BE REPLACED WITH THE PROPER NEW CASTINGS AT THE EXPENSE OF THE CONTRACTOR.

ITEMS ADJUSTED TO GRADE

THE FOLLOWING QUANTITIES HAVE BEEN PROVIDED FOR USE AS DIRECTED BY THE ENGINEER TO ADJUST EXISTING CATCH BASINS AND MANHOLES TO GRADE.

611, MANHOLE ADJUSTED TO GRADE, 28 EACH
623, MONUMENT BOX ADJUSTED TO GRADE, 19 EACH

ITEM 611 -CATCH BASIN RECONSTRUCTED TO GRADE

THIS ITEM SHALL CONSIST OF RECONSTRUCTING 9 EXISTING CATCH BASINS. THE FOLLOWING QUANTITY HAS BEEN CARRIED TO THE GENERAL SUMMARY FOR USE AS DIRECTED BY THE ENGINEER.

611, CATCH BASIN RECONSTRUCTED TO GRADE, 9 EACH

ITEM 611- INLET RECONSTRUCTED TO GRADE, AS PER PLAN

THIS ITEM SHALL CONSIST OF RECONSTRUCTING 50 EXISTING CURB INLETS TO GRADE AS DIRECTED BY THE ENGINEER. THE CONTRACTOR SHALL REFER TO STANDARD CONSTRUCTION DRAWING C.B-2.1 OR THE "RAISED CUERB INLET DETAIL" SHOW ON SHEET 8 FOR EACH CURB INLET REPAIR.

WHEN A CURB INLET AS SHOWN ON SHEET 8 IS TO BE RECONSTRUCTED TO GRADE, A NEW CONCRETE TOP SHALL ALSO BE PROVIDED.

PAYMENT FOR THE ABOVE WORK SHALL BE MADE AT THE UNIT BID PRICE FOR ITEM 611, INLET RECONSTRUCTED TO GRADE AND SHALL INCLUDE ALL SAW CUTTING, LABOR, TOOLS, EQUIPMENT, AND MATERIALS NECESSARY TO RECONSTRUCT A COMPLETE AND FUCTIONAL PAVEMENT INLET.

EACH INLET RECONSTRUCTION LOCATION SHALL RECONSTRUCT A TOTAL OF 10FT OF CURB SURROUNDING THE INLET.

ITEM 202, CURB REMOVED, 670FT
ITEM 609, CURB TYPE 6, 670FT
ITEM 611, INLET RECONSTRUCTED TO GRADE, AS PER PLAN 67 EACH
ITEM 611, 12" CONDUIT, TYPE B, 130FT
ITEM 611, 15" CONDUIT, TYPE B, 50FT
ITEM 611, 21" CONDUIT, TYPE B, 30FT
ITEM 611, 24" CONDUIT, TYPE B, 20FT
ITEM 611, 27" CONDUIT, TYPE B, 10 FT

CURB REPAIR

THIS ITEM SHALL BE USED TO REPLACE MISSING OR DAMAGED CURB ALONG SR 193 FROM SLM 0.00 TO SLM 1.97. IT IS NOT THE INTENT TO REPAIR EVERY DETERIORATED SECTION WITHIN THE PROJECT. THE ENGINEER SHALL DETERMINE WHICH AREAS ARE TO BE REPAIRED. PAVEMENT SHALL BE BASED UPON THE ACTUAL NUMBER OF FEET OF CURB REPLACED. ANY SAW CUTTING NECESSARY TO REMOVE THE EXISTING CURB SHALL BE INCIDENTAL TO THE UNIT BID PRICE FOR ITEM 202, CURB REMOVED.

ITEM 202, CURB REMOVED, 8,000FT
ITEM 609, CURB TYPE 6, 8,000FT

BEST MANAGEMENT PRACTICES/SOIL EROSION AND SEDIMENTATION CONTROL

WATER COLUMN AND SEDIMENTATION IMPACTS SHALL BE KEPT TO A MINIMUM THROUGH THE USE OF BEST MANAGEMENT PRACTICES FOR SOIL EROSION AND SEDIMENTATION CONTROL. ALL SOIL EROSION CONTROL MEASURES SHALL BE IN PLACE PRIOR TO ANY EXCAVATION, GRADING OR FILLING OPERATIONS AND INSTALLATION OF PROPOSED STRUCTURES OR UTILITIES. THEY SHALL REMAIN IN PLACE UNTIL CONSTRUCTION IS COMPLETED AND THE AREA IS STABILIZED AS ACCEPTED BY THE ENGINEER. THESE SHALL COMPLY WITH ODOT'S HANDBOOK FOR SEDIMENT AND ROSION CONTROL, WHICH MAY BE FOUND AT: [HTTP://WWW.DOT.STATE.OH.US/DRRC/](http://www.dot.state.oh.us/drrc/).

COMMUNITY NOTIFICATION

THE CONTRACTOR WILL ADVISE THE ODOT PROJECT ENGINEER A MINIMUM OF TWENTY-ONE (21) DAYS PRIOR TO THE START OF CONSTRUCTION ACTIVITIES. THE CONTRACTOR MUST ALSO PROVIDE NOTIFICATION TO THE ODOT PROJECT ENGINEER A MINIMUM OF TWENTY-ONE (21) DAYS PRIOR TO ANY LANE RESTRICTIONS. THE ODOT PROJECT ENGINEER WILL FORWARD THE INFORMATION TO THE ODOT, DISTRICT 4 OFFICE OF PUBLIC INFORMATION FOR USE TO NOTIFY EMERGENCY SERVICES, SCHOOL SYSTEMS AND COMMUNITIES A MINIMUM OF FOURTEEN (14) DAYS PRIOR TO THE START OF PROJECT CONSTRUCTION. INCLUDED IN THIS NOTIFICATION WILL BE THE PROJECTED DATES OF ANY LANE RESTRICTIONS, ROADWAY CLOSURES AND DETOUR ROUTES REQUIRED BY THE PROJECT.

STRUCTURE PAINTING/CONCRETE SEALING OPERATIONS

THE CONTRACTOR SHALL TAKE ALL PRECAUTIONS NECESSARY TO PREVENT EPOXY-URETHANE SEALER, PAINT OR OTHER MATERIALS USED TO REPAIR, CLEAN, PAINT, SEAL OR TREAT ANY STRUCTURE FROM ENTERING ANY STREAMS, WETLANDS OR OTHER WATERS OF THE UNITED STATES AND TAKE THE APPROPRIATE ACTIONS IN THE EVENT OF A RELEASE.

STREAM AVOIDANCE

NO EXCAVATION, GRADING OR FILLING OPERATIONS SHALL BE PERFORMED IN THE STREAMS LOCATED AT TRU-193-4.91 AND TRU-193-6.18. UNDER NO CIRCUMSTANCES SHALL THE CONTRACTOR STORE CONSTRUCTION EQUIPMENT AND/OR MATERIALS IN THIS STREAM. ODOT CONSTRUCTION AND MATERIALS SPECIFICATIONS SECTION 107.10 (PROTECTION AND RESTORATION OF PROPERTY) PROHIBIT THE CONTRACTOR FROM CREATING STAGING AREAS NEAR STREAMS AND/OR WETLANDS.

I:\Project+Data\TRU\88916_193_0_00\Design\Roadway\Sheets\88916_GN001.dgn_Sheet 3 1/31/2017 8:38:21 AM ccapelan

CALCULATED
CNC
CHECKED
MAC

GENERAL NOTES

TRU-193-0.00

7
22

MAINTENANCE OF TRAFFIC

THIS ITEM SHALL CONSIST OF MAINTENANCE OF TRAFFIC ON EXISTING ROADWAYS AND RAMPS IN ACCORDANCE WITH THE OHIO MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES FOR STREETS AND HIGHWAYS, CURRENT EDITION, LATEST REVISION, THE SPECIFICATIONS AND THE FOLLOWING:

1. A MINIMUM OF ONE TEN FOOT LANE IN EACH DIRECTION SHALL BE MAINTAINED ON THE EXISTING PAVEMENT AND COMPLETED PAVEMENT DURING CONSTRUCTION OF THE WORK.

2. THE CONTRACTOR SHALL INFORM THE DISTRICT OFFICE (330) 786-2208, EIGHTEEN (18) DAYS PRIOR TO THE BEGINNING OF WORK.

3. ALL FULL DEPTH PAVEMENT REMOVAL AND REPLACEMENT OPERATIONS SHALL BE COMPLETED THE SAME DAY THE EXCAVATION IS MADE. IF THE CONTRACTOR CANNOT COMPLETE THE WORK, THE EXCAVATION SHALL BE BACKFILLED OR PROTECTED AS PER STANDARD CONSTRUCTION DRAWING MT-101.90.

4. UNDER NO CIRCUMSTANCES SHALL THE CONTRACTOR BE PERMITTED TO HAVE SUCCESSIVE WORK ZONES UNLESS THE DISTANCE BETWEEN THE DRUMS, BARRICADES OR CONES EXCEEDS TWO (2) MILES.

5. ONLY DURING OFF-PEAK PERIODS (ie ANY PERIOD OTHER THAN 6-8AM AND 3-6PM) SHALL THE CONTRACTOR INSTALL AND SUBSEQUENTLY RESET ALL TRAFFIC CONTROL NECESSARY FOR THE WORK ZONE FOR EACH CONSTRUCTION PHASE.

6. IN ADDITION TO THE REQUIREMENTS OF 614.11 WORK ZONE PAVEMENT MARKINGS, AT THE END OF EACH DAY OF WORK, THE CONTRACTOR SHALL REPLACE (WITH WORK ZONE MARKINGS) ALL LANE, CENTER, STOP OR CHANNELIZING LINES THAT WERE REMOVED OR COVERED DURING THE PAVEMENT REMOVAL OR PLACEMENT OPERATIONS. QUANTITIES FOR SUCH PLACEMENT ARE CARRIED AS PART OF THE ITEMS LISTED UNDER 614 WORK ZONE PAVEMENT MARKINGS.

7. PRIOR TO OPENING TO TRAFFIC EACH LANE SHALL BE IN A SAFE, PASSABLE CONDITION. ALL TRANSVERSE JOINTS SHALL EXTEND ACROSS THE FULL LANE AND SHOULDER WIDTH AND EACH LANE SHALL BE FREE FROM UNEVEN LONGITUDINAL JOINTS. THE CONTRACTOR SHALL PROVIDE ASPHALT WEDGES FOR TRANSVERSE JOINTS WHEREVER THERE ARE PAVEMENT ELEVATION DIFFERENCES.

8. THE CONTRACTOR SHALL PLACE THE SIGNS: W8-1 [BUMP] PER OMUTCD 2C.28; W8-11 [UNEVEN LANES] PER OMUTCD 6F.45; AND W6-3 [TWO-WAY TRAFFIC] PER OMUTCD 6F.32. PAYMENT FOR THESE SIGNS SHALL BE INCIDENTAL TO THE LUMP SUM ITEM 614-MAINTAINING TRAFFIC. A QUANTITY OF ITEM 614 WORK ZONE MARKING SIGNS HAS BEEN INCLUDED IN THE PLANS PER CMS 614.04.

THE FOLLOWING QUANTITIES SHALL BE USED FOR THE MAINTENANCE OF TRAFFIC ON THIS PROJECT:

PHASE I- PLANED SURFACE (SLM 0.00 TO SLM 5.37)
ITEM 614, WORK ZONE CENTER LINE, CLASS I, 6.73 MILE
ITEM 614, WORK ZONE LANE LINE, CLASS I, 5.37 MILE
ITEM 614, WORK ZONE MARKING SIGNS
(ALL PHASES, SLM 0.00 TO SLM 5.37), 24 EACH

PHASE I- PLANED SURFACE (SLM 5.37 TO SLM 6.78)
ITEM 614, WORK ZONE CENTER LINE, CLASS I, 2.01 MILE
ITEM 614, WORK ZONE LANE LINE, CLASS I, 2.82 MILE
ITEM 614, WORK ZONE MARKING SIGNS
(ALL PHASES, SLM 5.37 TO 6.78), 5 EACH

PHASE II- INTERMEDIATE COURSE
SLM 0.00 TO SLM 1.97, SLM 3.39 TO SLM 5.37)
ITEM 614, WORK ZONE CENTER LINE, CLASS I, 4.84 MILE
ITEM 614, WORK ZONE LANE LINE, CLASS I, 3.95 MILE

PHASE II- INTERMEDIATE COURSE (SLM 5.37 TO SLM 6.78)
ITEM 614, WORK ZONE CENTER LINE, CLASS I, 2.01 MILE
ITEM 614, WORK ZONE LANE LINE, CLASS I, 2.82 MILE

PHASE III- SURFACE COURSE (SLM 0.00 TO SLM 5.37)
ITEM 614, WORK ZONE CENTER LINE, CLASS III,
642 PAINT, 6.73 MILE
ITEM 614, WORK ZONE LANE LINE, CLASS III,
642 PAINT, 5.37 MILE

PHASE III- SURFACE COURSE (SLM 5.37 TO SLM 6.78)
ITEM 614, WORK ZONE CENTER LINE, CLASS III,
642 PAINT, 2.01 MILE
ITEM 614, WORK ZONE LANE LINE, CLASS III, 642 PAINT, 2.82 MILE

TO BE USED AS DIRECTED BY THE ENGINEER:
SLM 1.98 TO SLM 5.37
ITEM 614, WORK ZONE EDGE LINE, CLASS III, 642 PAINT, 6.78 MILE
SLM 5.37 TO 6.74
ITEM 614, WORK ZONE EDGE LINE, CLASS III, 642 PAINT, 3.10 MILE

ITEM 614, MAINTAINING TRAFFIC (WINTER TIME LIMITATIONS)

ALL EXISTING LANES, INCLUDING RAMPS, SHALL BE OPEN AND AVAILABLE TO TRAFFIC IN THE ORIGINAL OR PROPOSED FINAL ALIGNMENT BETWEEN OCTOBER 31 AND APRIL 1. SHOULD THE CONTRACTOR FAIL TO MEET THESE REQUIREMENTS, A DISINCENTIVE SHALL BE ASSESSED IN THE AMOUNT OF \$3000 PER CALENDAR DAY.

ITEM 614, MAINTAINING TRAFFIC (ESTIMATED QUANTITIES)

THE FOLLOWING ESTIMATED QUANTITIES HAVE BEEN INCLUDED IN THE GENERAL SUMMARY FOR USE AS DETERMINED BY THE ENGINEER FOR THE MAINTENANCE OF TRAFFIC.

ITEM 614, ASPHALT CONCRETE FOR MAINTAINING TRAFFIC 200 CU. YD.

TIME LIMITATION, TRAFFIC ON A MILLED SURFACE

THE MAXIMUM ALLOWABLE TIME FOR TRAFFIC TO BE PLACED ON A MILLED SURFACE SHALL BE 7 CONSECUTIVE CALENDAR DAYS. SHOULD THE CONTRACTOR FAIL TO MEET THIS REQUIREMENT, THE CONTRACTOR SHALL BE ASSESSED A DISINCENTIVE IN THE AMOUNT OF \$3000 PER DAY THAT THE TRAFFIC IS PLACED ON A MILLED SURFACE BEYOND THE SPECIFIED LIMIT.

ADVANCED NOTICE TO PAVE

THE CONTRACTOR SHALL SUBMIT FOR APPROVAL TO THE DISTRICT CONSTRUCTION ENGINEER A DETAILED SCHEDULE 15 DAYS PRIOR TO THE PLACEMENT OF THE OVERLAY COURSES, ON HOW THEY PROPOSE TO PROSECUTE THE PAVING OPERATIONS. THE DETAILS SHALL SHOW THE ORDER OF PERFORMANCE OF EACH STAGE (START TO FINISH) OF THE WORK INCLUDING THE MAINTENANCE OF TRAFFIC THAT WILL BE USED.

LANE CLOSURE RESTRICTIONS DURING PAVING OPERATIONS (SLM 0.00 TO SLM 1.97)

DURING PAVING OPERATIONS FROM SLM 0.00 TO SLM 1.97, ALL LANES SHALL BE OPEN TO TRAFFIC FROM 6AM TO 7PM DAILY. SHOULD THE CONTRACTOR FAIL TO MEET THE ABOVE REQUIREMENT, THE CONTRACTOR SHALL BE ASSESSED A DISINCENTIVE IN THE AMOUNT OF \$3000 FOR EACH HOUR THAT ABOVE LANE RESTRICTION IS VIOLATED.

TRAFFIC CONTROL INSPECTOR

THE CONTRACTOR SHALL DESIGNATE AN INDIVIDUAL OTHER THAN THE SUPERINTENDENT AND SUBJECT TO THE APPROVAL OF THE ENGINEER, TO CONTINUOUSLY INSPECT ALL TRAFFIC CONTROL DEVICES WHENEVER CONSTRUCTION WORK IS BEING PERFORMED WITHIN THE WORK LIMITS OF THE PROJECT. THE DESIGNATED INDIVIDUAL SHALL ALSO INSPECT ALL TRAFFIC DEVICES AT THE BEGINNING AND AT THE END OF EACH WORK DAY. THE DESIGNATED INDIVIDUAL OR A QUALIFIED REPRESENTATIVE SHALL ALSO BE AVAILABLE ON AN AROUND THE CLOCK BASIS TO REPAIR AND/OR REPLACE DAMAGED OR MISSING TRAFFIC CONTROL DEVICES. THESE INDIVIDUALS SHALL BE EQUIPPED WITH CELLULAR PHONES AND THEIR NAMES AND PHONE NUMBERS SHALL BE GIVEN TO THE PROJECT ENGINEER AT THE PRE-CONSTRUCTION MEETING. THE DESIGNATED INDIVIDUAL MAY HAVE OTHER CONSTRUCTION RELATED DUTIES AS LONG AS IMMEDIATE ATTENTION IS GIVEN TO TRAFFIC CONTROL. PAYMENT FOR THE SERVICES OF THE TRAFFIC CONTROL INSPECTOR SHALL BE INCLUDED IN THE LUMP SUM PRICE BID FOR ITEM 614 MAINTAINING TRAFFIC.

INLET REPAIRS

INLET REPAIRS ON SR 193 FROM SLM 0.00 TO SLM 1.97 SHALL NOT BE PERFORMED ON NORTH AND SOUTHBOUND SIMULTANEOUSLY.

ITEM 614, MAINTAINING TRAFFIC (LANES OPEN DURING HOLIDAYS OR SPECIAL EVENTS)

NO WORK SHALL BE PERFORMED AND ALL EXISTING LANES SHALL BE OPEN TO TRAFFIC DURING THE FOLLOWING DESIGNATED HOLIDAYS OR EVENTS:

| | |
|--------------|----------------|
| CHRISTMAS | FOURTH OF JULY |
| NEW YEARS | LABOR DAY |
| MEMORIAL DAY | THANKSGIVING |

THE PERIOD OF TIME THAT THE LANES ARE TO BE OPEN DEPENDS ON THE DAY OF THE WEEK ON WHICH THE HOLIDAY OR EVENT FALLS. THE FOLLOWING SCHEDULE SHALL BE USED TO DETERMINE THIS PERIOD:

| DAY OF HOLIDAY OR EVENT | TIME ALL LANES MUST BE OPEN TO TRAFFIC |
|------------------------------|--|
| SUNDAY | 12:00N FRIDAY THROUGH 6:00 AM MONDAY |
| MONDAY | 12:00N FRIDAY THROUGH 6:00 AM TUESDAY |
| TUESDAY | 12:00N MONDAY THROUGH 6:00 AM WEDNESDAY |
| WEDNESDAY | 12:00N TUESDAY THROUGH 6:00 AM THURSDAY |
| THURSDAY | 12:00N WEDNESDAY THROUGH 6:00 AM FRIDAY |
| THURSDAY (THANKSGIVING ONLY) | 6:00 AM WEDNESDAY THROUGH 6:00 AM MONDAY |
| FRIDAY | 12:00N THURSDAY THROUGH 6:00 AM MONDAY |
| SATURDAY | 12:00N FRIDAY THROUGH 6:00 AM MONDAY |

SHOULD THE CONTRACTOR FAIL TO MEET ANY OF THESE REQUIREMENTS, THE CONTRACTOR SHALL BE ASSESSED A DISINCENTIVE IN THE AMOUNT OF \$3000 FOR EACH HOUR THE ABOVE DESCRIBED LANE CLOSURE RESTRICTIONS ARE VIOLATED.

INTERIM COMPLETION DATE (SLM 0.00 TO SLM 1.97)

ALL WORK ON TRU- SR 193 FROM SLM 0.00 (GYSPY LANE) TO SLM 1.97 (SR 304) SHALL BE COMPLETED BY OCTOBER 31, 2017. ALL WORK SHALL INCLUDE BUT NOT LIMITED TO INLET RECONSTRUCTION, CURB AND CURB RAMP INSTALLATION, AND ALL RESURFACING WORK. SHOULD THE CONTRACTOR FAIL TO MEET ANY OF THESE REQUIREMENTS, A DISINCENTIVE SHALL BE ASSESSED IN THE AMOUNT OF \$3000 PER CALENDAR DAY.

INTERIM START DATE (SLM 1.97 TO SLM 6.78)

NO WORK ON SR 193 FROM SLM 1.97 (SR 304) TO SLM 6.78 (END OF PROJECT) SHALL BEGIN PRIOR TO APRIL 1, 2018 WITHOUT WRITTEN APPROVAL FROM THE DISTRICT CONSTRUCTION ENGINEER.

I:\ProjectData\TRU\88916_193_0.00\Design\Roadway\Sheet\88916_MN001.dgn Sheet 1/31/2017 8:38:22 AM ccapelan

CALCULATED
CNC
CHECKED
LAB

MAINTENANCE OF TRAFFIC GENERAL NOTES

TRU-193-0.00

ITEM 632 - DETECTOR LOOP, AS PER PLAN

THE CONTRACTOR SHALL CONTACT THE DISTRICT OFFICE (330-786-3146) THREE WORKING DAYS PRIOR TO ANY PLANING OR TRENCHING AT THE FOLLOWING INTERSECTIONS WITH SR 193:

- GYPSY LANE
- COLONIAL DR
- TRUMBULL AVE
- GOLDIE RD
- LIBERTY PLAZA
- LIBERTY ST
- RAMP FROM I-80
- CHURCHILL RD
- TIBBITS WICK RD

LOOP DETECTORS DISTURBED BY PAVEMENT PLANING OR TRENCHING SHALL BE ABANDONED IN PLACE. THE LOOP DETECTOR WIRE WILL BE CUT INTO THE PAVEMENT AFTER THE PROPOSED SURFACE COURSE HAS BEEN PLACED. ALL STOP LINE INDUCTANCE DETECTOR LOOPS SHALL BE THE POWERHEAD CONFIGURATION SHOWN ON TC-82.10. THE WIDTH SHALL BE AS SPECIFIED BELOW. THE LOCATION OF THESE LOOPS SHALL BE SUCH THAT THE POWERHEAD IS LOCATED AT THE STOP LINE, NOT PAST IT. ALL DILEMMA ZONE INDUCTANCE DETECTOR LOOPS CALLED FOR IN THE PLANS SHALL BE THE ANGULAR DESIGN DETECTION (ADD) LOOP AS SHOWN ON TC-82.10. DIMENSIONS SHALL BE AS SPECIFIED ON TC-82.10 AND THE LOOP SHALL BE PLACED AT THE SAME LOCATION AS THE EXISTING LOOPS.

THE QUANTITIES LISTED BELOW HAVE BEEN CARRIED TO THE GENERAL SUMMARY. THE NEW LOOP DETECTOR WIRES SHALL BE RUN INTO THE EXISTING CONTROL BOX OR THE EXISTING PULLBOX. INCLUDED IN THIS ITEM IS THE POURED EPOXY TYPE CABLE SPLICE KIT (CONFORMING TO T25.15E) THAT MUST BE USED IN MAKING THESE CONNECTIONS. ALL NECESSARY MATERIAL, LABOR, SPLICE KITS AND EQUIPMENT SHALL BE INCIDENTAL TO PAYMENT OF THESE ITEMS.

632 DETECTOR LOOP, AS PER PLAN, 49 EACH

SR 193 AND GYPSY LANE
1- POWERHEAD (8' X 30') ON 193SB

SR 193 AND COLONIAL DR
1- POWERHEAD (8' X 30') ON COLONIAL DR
2 SYSTEM LOOPS ON SR 193 NB

SR 193 AND TRUMBULL AVE
1 POWERHEAD (6' X 25') ON SR 193NB
2 POWERHEAD (6' X 30') ON TRUMBULL AVE WEST

SR 193 AND GOLDIE RD
1 POWERHEAD (6' X 25') ON SR 193SB
1 POWERHEAD (8' X 30') ON GOLDIE WB
1 POWERHEAD (8' X 25') ON GOLDIE EB
1 POWERHEAD (6' X 25') ON GOLDIE EB

SR 193 AND LIBERTY PLAZA
1 POWERHEAD (6' X 25') ON SR 193 NB
1 POWERHEAD (6' X 25') ON SR 193SB
4 POWERHEADS (6' X 25) ON LIBERTY PLAZA (2 EACH SIDE)

SR 193 AND LIBERTY ST
1 POWERHEAD (6' X 25') ON SR 193 NB
1 POWERHEAD (6' X 25') ON SR 193 SB
2 SYSTEM LOOPS SR 193 ON SR 193 NB
2 SYSTEM LOOPS SR 193 ON SR 193 SB
1 POWERHEAD (6' X 25') ON LIBERTY E LT LANE
1 POWERHEAD (8' X 30') ON LIBERTY E RT LANE
1 POWERHEAD (8' X 30') ON LIBERTY W LT LANE
1 POWERHEAD (6' X 25') ON LIBERTY W RT LANE

SR 193 AND I-80WB OFF RAMP
1 POWERHEAD (6' X 25') ON SR 193 NB
1 POWERHEAD (6' X 25') ON SR 193 SB
2 SYSTEM LOOPS SR 193 ON SR 193 NB
2 SYSTEM LOOPS SR 193 ON SR 193 SB
1 POWERHEAD (8' X 30') I-80 OFF RAMP RT LANE
1 POWERHEAD (6' X 30') I-80 OFF RAMP LT LANE

SR 193 AND SR 304
1 POWERHEAD (6' X 25') ON SR 193 NB
1 POWERHEAD (6' X 25') ON SR 193 SB
2 POWERHEADS (6' X 30') ON SR 304 WEST
2 POWERHEADS (6' X 30') ON SR 304 EAST

SR 193 AND TIBBETSWICK
1 POWERHEAD (8' X 20') ON SR 193 NB
1 POWERHEAD (8' X 20') ON SR 193 SB
2 A.D.D ON SR 193 NB
2 A.D.D ON SR 193 SB
1 POWERHEAD (8' X 30') ON TIBBETSWICK EAST
1 POWERHEAD (8' X 30') ON TIBBETSWICK WEST

NOTIFICATION OF TRAFFIC RESTRICTIONS

THROUGHOUT THE DURATION OF THE PROJECT, THE CONTRACTOR SHALL NOTIFY THE PROJECT ENGINEER IN WRITING OF ALL TRAFFIC RESTRICTIONS AND UPCOMING MAINTENANCE OF TRAFFIC CHANGES. THE CONTRACTOR SHALL ENSURE THE WRITTEN NOTIFICATION IS SUBMITTED IN A TIMELY MANNER TO ALLOW THE PROJECT ENGINEER TO MEET THE REQUIRED TIME FRAMES SET FORTH IN THE TABLE BELOW TO INFORM THE OFFICE OF COMMUNICATIONS. THIS NOTIFICATION SHALL BE RECEIVED BY THE PROJECT ENGINEER PRIOR TO THE PHYSICAL SETUP OF ANY APPLICABLE SIGNS OR MESSAGE BOARDS.

INFORMATION SHOULD INCLUDE, BUT IS NOT LIMITED TO, ALL AND SHALL LIST THE SPECIFIC LOCATION, TYPE OF WORK, ROAD STATUS, DATE AND TIME OF RESTRICTION, DURATION OF RESTRICTION, NUMBER OF LANES MAINTAINED, NUMBER OF LANES CLOSED, DETOUR ROUTES, IF APPLICABLE, AND ANY OTHER INFORMATION REQUESTED BY THE PROJECT ENGINEER.

| NOTICE TO OFFICE OF COMMUNICATIONS TIME TABLE | | |
|--|------------------------|--|
| ITEM | DURATION OF CLOSURE | NOTICE DUE TO OFFICE OF COMMUNICATIONS |
| RAMP & RAMP CLOSURES | >= 2WEEKS | 21 CALENDAR DAYS PRIOR TO CLOSURE |
| | > 12 HOURS & < 2 WEEKS | 14 CALENDAR DAYS PRIOR TO CLOSURE |
| | <12 HOURS | 4 BUSINESS DAYS PRIOR TO CLOSURE |
| LANE CLOSURES & RESTRICTIONS | >=2 WEEKS | 14 CALENDAR DAYS PRIOR TO CLOSURE |
| | < 2 WEEKS | 2 BUSINESS DAYS PRIOR TO CLOSURE |
| START OF CONSTRUCTION & TRAFFIC PATTERNS CHANGES | N/A | 14 CALENDAR DAYS PRIOR TO IMPLEMENTATION |

ANY UNFORESEEN CONDITIONS NOT SPECIFIED IN THE PLANS REQUIRING TRAFFIC RESTRICTIONS SHALL ALSO BE REPORTED TO THE PROJECT ENGINEER USING THE NOTICE TO OFFICE OF COMMUNICATIONS TIME TABLE.

ITEM 614 - LAW ENFORCEMENT OFFICER (WITH PATROL CAR) FOR ASSISTANCE DURING CONSTRUCTION OPERATIONS

USE OF LAW ENFORCEMENT OFFICERS (LEOS) BY CONTRACTORS OTHER THAN THE USES SPECIFIED BELOW WILL NOT BE PERMITTED AT PROJECT COST. LEOS SHOULD NOT BE USED WHERE THE OMTCD INTENDS THAT FLAGGERS BE USED.

IN ADDITION TO THE REQUIREMENTS OF CMS 614 AND THE OMTCD, A UNIFORMED LEO WITH AN OFFICIAL PATROL CAR (CAR WITH TOP-MOUNTED EMERGENCY FLASHING LIGHTS AND COMPLETE MARKINGS OF THE APPROPRIATE LAW ENFORCEMENT AGENCY) SHALL BE PROVIDED FOR THE FOLLOWING TRAFFIC CONTROL TASKS:

DURING THE ENTIRE ADVANCE PREPARATION AND CLOSURE SEQUENCE WHERE COMPLETE BLOCKAGE OF TRAFFIC IS REQUIRED.

WHEN TRAFFIC NEEDS TO BE DIRECTED THROUGH AN ENERGIZED TRAFFIC SIGNAL CONTRARY TO THE SIGNAL DISPLAY (E.G., DIRECTING MOTORISTS THROUGH A RED LIGHT).

FOR LANE CLOSURES: DURING INITIAL SET-UP PERIODS, TEAR DOWN PERIODS, SUBSTANTIAL SHIFTS OF A CLOSURE POINT OR WHEN NEW LANE CLOSURE ARRANGEMENTS ARE INITIATED FOR LONG-TERM LANE CLOSURES/SHIFTS (FOR THE FIRST AND LAST DAY OF MAJOR CHANGES IN TRAFFIC CONTROL SETUP).

IN GENERAL, LEOS SHOULD BE POSITIONED AT THE POINT OF LANE RESTRICTION OR ROAD CLOSURE AND TO MANUALLY CONTROL TRAFFIC MOVEMENTS THROUGH INTERSECTIONS IN WORK ZONES.

LEOS SHOULD NOT FORGO THEIR TRAFFIC CONTROL RESPONSIBILITIES TO APPREHEND MOTORISTS FOR ROUTINE TRAFFIC VIOLATIONS. HOWEVER, IF A MOTORIST'S ACTIONS ARE CONSIDERED TO BE RECKLESS, THEN PURSUIT OF THE MOTORIST IS APPROPRIATE.

THE LEOS WORK AT THE DIRECTION OF THE ENGINEER. THE CONTRACTOR IS RESPONSIBLE FOR SECURING THE SERVICES OF THE LEOS WITH THE APPROPRIATE AGENCIES AND COMMUNICATING THE INTENTIONS OF THE PLANS WITH RESPECT TO DUTIES OF THE LEOS. THE ENGINEER SHALL HAVE FINAL CONTROL OVER THE LEOS' DUTIES AND PLACEMENT, AND WILL RESOLVE ANY ISSUES THAT MAY ARISE BETWEEN THE TWO PARTIES.

THE LEO SHALL REPORT IN TO THE CONTRACTOR PRIOR TO THE START OF THE SHIFT, IN ORDER TO RECEIVE INSTRUCTIONS REGARDING SPECIFIC WORK ASSIGNMENTS DURING HIS/HER SHIFT. THE LEO IS EXPECTED TO STAY AT THE PROJECT SITE FOR THE ENTIRE DURATION OF HIS/HER SHIFT. THE LEO SHALL REPORT TO THE CONTRACTOR AT THE END OF HIS/HER SHIFT. ONCE THE LEO HAS COMPLETED THE DUTIES DESCRIBED ABOVE AND STILL HAS TIME REMAINING ON HIS/HER SHIFT, THE LEO MAY BE ASKED TO PATROL THROUGH THE WORK ZONE (WITH FLASHING LIGHTS OFF) OR BE PLACED AT A LOCATION TO DETER MOTORISTS FROM SPEEDING. SHOULD IT BE NECESSARY TO LEAVE THE PROJECT SITE, THE LEO SHALL NOTIFY THE ENGINEER. THE CONTRACTOR SHALL PROVIDE THE LEO WITH A TWO-WAY COMMUNICATION DEVICE WHICH SHALL BE RETURNED TO THE CONTRACTOR AT THE END OF HIS/HER SHIFT.

LEOS (WITH PATROL CAR) REQUIRED BY THE TRAFFIC MAINTENANCE TASKS ABOVE SHALL BE PAID FOR ON A UNIT PRICE (HOURLY) BASIS UNDER ITEM 614, LAW ENFORCEMENT OFFICER (WITH PATROL CAR) FOR ASSISTANCE. THE FOLLOWING ESTIMATED QUANTITIES HAVE BEEN CARRIED TO THE GENERAL SUMMARY.

ITEM 614, LAW ENFORCEMENT OFFICER WITH PATROL CAR FOR ASSISTANCE 400 HOURS

THE HOURS PAID SHALL INCLUDE ANY MINIMUM SHOW-UP TIME REQUIRED BY THE LAW ENFORCEMENT AGENCY INVOLVED.

ANY ADDITIONAL COSTS (ADMINISTRATIVE OR OTHERWISE) INCURRED BY THE CONTRACTOR TO OBTAIN THE SERVICES OF AN LEO ARE INCLUDED WITH THE BID UNIT PRICE FOR ITEM 614, LAW ENFORCEMENT OFFICER WITH PATROL CAR FOR ASSISTANCE.

I:\ProjectData\TRU\88916_193_0.00\Design\Roadway\Sheet\88916_MN001.dgn Sheet 2 1/31/2017 8:38:23 AM ccopelan

CALCULATED
CNC
CHECKED
LAB

MAINTENANCE OF TRAFFIC GENERAL NOTES

TRU-193-0.00

I:\ProjectData\TRU\88916_193_0_00\Design\Roadway\Sheets\88916_GG001.dgn_Sheet 1/31/2017 8:38:24 AM ccopelan

| SHEET NUM. | | | | | | | | | | | | PART. | | ITEM | ITEM EXT | GRAND TOTAL | UNIT | DESCRIPTION | SEE SHEET NO. |
|------------|-----|---|-------|----|----|----|----|--------|-----|----|------------|------------|---------|----------|----------|-------------|---|-----------------|---------------|
| 4 | 5 | 6 | 7 | 10 | 13 | 14 | 15 | 16 | 18 | 19 | 01/S>2/P V | 02/STR/P V | | | | | | | |
| | | | | | | | | 1,302 | 816 | | 2,118 | | 202 | 30000 | 2,118 | SF | ROADWAY | | |
| | 216 | | 8,670 | | | | 91 | 131 | | | 8,892 | | 202 | 32000 | 8,892 | FT | WALK REMOVED | | |
| | | | | | | | 1 | 6 | | | 215 | 8 | 203 | 10000 | 223 | CY | CURB REMOVED | | |
| | | | | | | | | 6 | | | 6 | | 203 | 20000 | 6 | CY | EXCAVATION | | |
| | | | 4 | | | | | 6 | | | 2 | 2 | 203 | 98600 | 4 | EACH | EMBANKMENT | | |
| | | | | | | | | | | | | | | | | | ROADWAY, MISC.:VERTICAL CLEARANCE | 6 | |
| | | | | | | | | | | | 180 | 149 | 209 | 60200 | 329 | STA | LINEAR GRADING | | |
| 495 | | | 329 | | | | | | | | 337 | 158 | 209 | 72001 | 495 | STA | PREPARING SUBGRADE FOR SHOULDER PAVING, AS PER PLAN | 4 | |
| | | | | | | | | 160 | | | 160 | | 608 | 13000 | 160 | SF | 6" CONCRETE WALK | | |
| | | | | | | | | 1,336 | 821 | | 2,157 | | 608 | 52000 | 2,157 | SF | CURB RAMP | | |
| | | | | 19 | | | | | | | 19 | | 623 | 39500 | 19 | EACH | MONUMENT BOX ADJUSTED TO GRADE | | |
| | | | | | | | | 18,278 | | | 10,018 | 8,278 | 659 | 10000 | 18,296 | SY | EROSION CONTROL | | |
| | | | | | | | | | | | 1.35 | 1.37 | 659 | 20000 | 2.72 | TON | SEEDING AND MULCHING | | |
| | | | | | | | | | | | 2.07 | 1.71 | 659 | 31000 | 3.78 | ACRE | COMMERCIAL FERTILIZER | | |
| | | | | | | | | | | | 54 | 45 | 659 | 35000 | 99 | MGAL | LIME | | |
| | | | | | | | | | | | 800 | 200 | 832 | 30000 | 1,000 | EACH | WATER | | |
| | | | | | | | | | | | | | | | | | EROSION CONTROL | | |
| | | | | | | | | 130 | | | 130 | | 611 | 04400 | 130 | FT | DRAINAGE | | |
| | | | | | | | | | | | 50 | | 611 | 05900 | 50 | FT | 12" CONDUIT, TYPE B | | |
| | | | | | | | | | | | 30 | | 611 | 08900 | 30 | FT | 15" CONDUIT, TYPE B | | |
| | | | | | | | | | | | 20 | | 611 | 10400 | 20 | FT | 21" CONDUIT, TYPE B | | |
| | | | | | | | | | | | 10 | | 611 | 11900 | 10 | FT | 24" CONDUIT, TYPE B | | |
| | | | | | | | | | | | 9 | | 611 | 98634 | 9 | EACH | 27" CONDUIT, TYPE B | | |
| | | | | | | | | | | | 67 | | 611 | 99155 | 67 | EACH | CATCH BASIN RECONSTRUCTED TO GRADE | | |
| | | | | | | | | | | | 28 | | 611 | 99654 | 28 | EACH | INLET RECONSTRUCTED TO GRADE, AS PER PLAN | 7 | |
| | | | | | | | | | | | 40,000 | | | | | LB | MANHOLE ADJUSTED TO GRADE | | |
| | | | | | | | | | | | | | SPECIAL | 61199820 | 40,000 | | MISCELLANEOUS METAL | 7 | |
| | | | | | | | | 1,300 | | | 1,100 | 200 | 251 | 01000 | 1,300 | SY | PAVEMENT | | |
| | | | | | | | | | | | 50 | 50 | 253 | 01000 | 100 | SY | PARTIAL DEPTH PAVEMENT REPAIR (441) | | |
| | | | | | | | | | | | 68,981 | 114,760 | 254 | 01001 | 183,741 | SY | PAVEMENT REPAIR | | |
| | | | | | | | | | | | 1,200 | | 255 | 10160 | 1,200 | SY | PAVEMENT PLANING, ASPHALT CONCRETE, AS PER PLAN(T=3") | 5 | |
| | | | | | | | | | | | 5,400 | 450 | 255 | 20000 | 5,850 | FT | FULL DEPTH PAVEMENT REMOVAL AND RIGID REPLACEMENT, CLASS QC MS | | |
| | | | | | | | | | | | | | | | | | FULL DEPTH PAVEMENT SAWING | | |
| | | | | | | | | | | | 208 | 8 | 304 | 20000 | 216 | CY | AGGREGATE BASE | | |
| | | | | | | | | | | | 13,323 | 14,826 | 407 | 20000 | 28,149 | GAL | NON-TRACKING TACK COAT | | |
| | | | | | | | | | | | 1,333 | 3,065 | 408 | 10001 | 4,398 | GAL | PRIME COAT, AS PER PLAN | 6 | |
| 15 | | | | | | | | | | | 1,890 | 35 | 424 | 12001 | 1,940 | CY | FINE GRADED POLYMER ASPHALT CONCRETE, TYPE B, AS PER PLAN | 6 | |
| 48 | | | | | | | | | | | 2,396 | 3,985 | 441 | 10101 | 6,429 | CY | ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (446), AS PER PLAN(PG70-22M) | 6 | |
| | | | | | | | | | | | 3,354 | 5,579 | 441 | 10200 | 8,933 | CY | ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 2, (446) | | |
| | | | | | | | | | | | 8,670 | | 609 | 26000 | 8,905 | FT | CURB, TYPE 6 | | |
| | | | | | | | | | | | 186 | 426 | 617 | 10101 | 612 | CY | COMPACTED AGGREGATE, AS PER PLAN | 6 | |
| | | | | | | | | | | | 54,431 | 991 | 897 | 01010 | 55,422 | SY | PAVEMENT PLANING, ASPHALT CONCRETE, CLASS A(T= 1 1/4") | | |
| | | | | | | | | | | | 1,627 | 1,324 | 303 | 621 | 00100 | 1,627 | EACH | TRAFFIC CONTROL | |
| | | | | | | | | | | | | | | | | | RPM | | |
| | | | | | | | | | | | | | | | | | RAISED PAVEMENT MARKER REMOVED | | |
| | | | | | | | | | | | 9.88 | | 644 | 00104 | 9.88 | MILE | EDGE LINE, 6" | | |
| | | | | | | | | | | | 13.56 | | 644 | 00204 | 13.56 | MILE | LANE LINE, 6" | | |
| | | | | | | | | | | | 8.74 | | 644 | 00300 | 8.74 | MILE | CENTER LINE | | |
| | | | | | | | | | | | 4,128 | | 644 | 00400 | 4,128 | FT | CHANNELIZING LINE, 8" | | |
| | | | | | | | | | | | 651 | | 644 | 00500 | 651 | FT | STOP LINE | | |
| | | | | | | | | | | | 862 | | 644 | 00600 | 862 | FT | CROSSWALK LINE | | |
| | | | | | | | | | | | 329 | | 644 | 00700 | 329 | FT | TRANSVERSE/DIAGONAL LINE | | |
| | | | | | | | | | | | 91 | | 644 | 01300 | 91 | EACH | LANE ARROW | | |
| | | | | | | | | 49 | | | 49 | | 632 | 26501 | 49 | EACH | TRAFFIC SIGNALS | | |
| | | | | | | | | | | | | | | | | | DETECTOR LOOP, AS PER PLAN | 10 | |
| | | | | | | | | | | | | | | | | | STRUCTURE REPAIRS | | |
| | | | | | | | | | | | | | | | | | FOR TRU-193-0491 ESTIMATED QUANTITIES | 21 | |
| | | | | | | | | | | | | | | | | | FOR TRU-193-0618 ESTIMATED QUANTITIES | 21 | |

GENERAL SUMMARY

TRU-193-0.00

CALCULATED
CNC
CHECKED
MAC

11
22

I:\Project+Data\TRU\88916_193_0.00\Design\Roadway\Sheets\88916_GS002.dgn Sheet 1/3/2017 8:38:49 AM ccopelan

| MAIN ROUTE | INTERSECTING ROUTE | QUADRANT RL=REAR LT, RR=REAR RT FL=FWD LT, FR=FWD RT (LOOKING UPSTATION) | CURB RAMP TYPE (SCD BP-7.1, SHEET 2/3) | 202 | 202 | 202 | 203 | 608 | 608 | 608 | 609 | | 609 | 659 | COMMENTS | |
|--|----------------------------------|---|---|--------------------|--------------------|-------------------------------|--|------------------------|------------------------|-----------------|--|--------------------|----------------------------|------|---|--|
| | | | | WALK REMOVED SF | CURB REMOVED FT | CURB AND GUTTER REMOVED FT | EXCAVATION (FOR ROCK REMOVAL) CY | 4" CONCRETE WALK SF | 6" CONCRETE WALK SF | CURB RAMP SF | COMBINATION CURB AND GUTTER, TYPE 2 FT | CURB, TYPE 6 FT | SEEDING AND MULCHING SY | | | |
| SR 193 | GYSPY LANE | FL | | 32.00 | 6.00 | | | | | 32.00 | | | | | | |
| SR 193 | GYSPY LANE | FR | | 32.00 | 6.00 | | | | | 32.00 | | | | | | |
| SR 193 | GYSPY LANE | RR | | 20.00 | 6.00 | | | | | 20.00 | | | | | | |
| SR 193 | GYSPY LANE | RL | | 24.00 | 6.00 | | | | | 24.00 | | | | | | |
| SR 193 | BENCH STOP (SLM 0.04) | L | | 16.00 | | | | | 20.00 | | | 7.00 | | | REMOVE CURB RAMP, PLACE CURB AND NEW 5' WIDE WALK | |
| SR 193 | BENCH STOP (SLM 0.10) | R | | 72.00 | | | | | 60.00 | | | 7.00 | | | REMOVE CURB RAMP, PLACE CURB AND NEW 5' WIDE WALK | |
| SR 193 | CRUMRINE ST | FL | | 15.00 | | | | | | 15.00 | | | | | | |
| SR 193 | CRUMRINE ST | RL | | 20.00 | | | | | | 20.00 | | | | | | |
| SR 193 | BELGRADE AVE | FL | | 40.00 | | | | | | 40.00 | | | | | | |
| SR 193 | BELGRADE AVE | RL | | 20.00 | | | | | | 20.00 | | | | | | |
| SR 193 | FAIRLAWN AVE | FR | | 20.00 | | | | | | 20.00 | | | | | | |
| SR 193 | FAIRLAWN AVE | RR | | 20.00 | | | | | | 20.00 | | | | | | |
| SR 193 | COLONIAL DR | FR | | 44.00 | | | | | | 44.00 | | | | | | |
| SR 193 | COLONIAL DR | RR | | 55.00 | | | | | | 55.00 | | | | | | |
| SR 193 | COLONIAL DR | FL | | 35.00 | | | 1.00 | | 35.00 | 55.00 | | 18.00 | | | SEE DETAIL A ON SHEET 17 | |
| SR 193 | COLONIAL DR | RL | | 45.00 | | | | | | 45.00 | | | | | | |
| SR 193 | COLONIAL DR (CROSSING COLONIAL) | FR | | 32.00 | 6.00 | | | | | 32.00 | | 6.00 | | | | |
| SR 193 | COLONIAL DR (CROSSING COLONIAL) | RR | | 50.00 | 7.00 | | | | | 50.00 | | 7.00 | | | | |
| SR 193 | AMHERST ST | FL | | 32.00 | | | | | | 32.00 | | | | | | |
| SR 193 | AMHERST ST | RL | | 32.00 | | | | | | 32.00 | | | | | | |
| SR 193 | BENCH STOP (SLM 0.47) | R | | 16.00 | | | | | 20.00 | | | 7.00 | | | REMOVE CURB RAMP, PLACE CURB AND NEW 5' WIDE WALK | |
| SR 193 | BENCH STOP (SLM 0.54) | L | | 25.00 | | | | | 25.00 | | | 7.00 | | | REMOVE CURB RAMP, PLACE CURB AND NEW 5' WIDE WALK | |
| SR 193 | DARLINGTON AVE | FL | | 28.00 | | | | | | 28.00 | | | | | | |
| SR 193 | DARLINGTON AVE | RL | | 20.00 | | | | | | 20.00 | | | | | | |
| SR 193 | TRUMBULL AVE (CROSSING SR 193) | RL | | 12.00 | 11.00 | | | | | 35.00 | | 10.00 | | | RELOCATE CURB RAMP PER DETAIL B ON SHEET 17 | |
| SR 193 | TRUMBULL AVE (CROSSING TRUMBULL) | RL | | 60.00 | | | | | | 60.00 | | | | | SEE DETAIL B ON SHEET 17 | |
| SR 193 | TRUMBULL AVE | RR | | 28.00 | | | | | | 35.00 | | 24.00 | | | RELOCATE CURB RAMP PER DETAIL B ON SHEET 17 | |
| SR 193 | TRUMBULL AVE | FR | | 36.00 | | | | | | 36.00 | | | | | | |
| SR 193 | TRUMBULL (CROSSING SR 193) | FL | | 32.00 | 2.00 | | | | | 32.00 | | 2.00 | | | | |
| SR 193 | EUCLID BLVD | FR | | 20.00 | | | | | | 20.00 | | | | | | |
| SR 193 | EUCLID BLVD | RR | | 35.00 | | | | | | 35.00 | | | | | | |
| SR 193 | MANSELL DR | FR | | 44.00 | 10.00 | | | | | 44.00 | | | | | | |
| SR 193 | MANSELL DR | RR | | 44.00 | 10.00 | | | | | 44.00 | | | | | | |
| SR 193 | HAZELWOOD DR | FL | | 24.00 | | | | | | 24.00 | | | | | | |
| SR 193 | HAZELWOOD DR | RL | | | | | | | | 75.00 | | | | | | |
| SR 193 | BENCH STOP (SLM 1.04) | R | | 16.00 | | | | | | 20.00 | | 7.00 | | | REMOVE CURB RAMP, PLACE CURB AND NEW 5' WIDE WALK | |
| SR 193 | BENCH STOP (SLM 1.06) | L | | 16.00 | | | | | | 20.00 | | 7.00 | | | REMOVE CURB RAMP, PLACE CURB AND NEW 5' WIDE WALK | |
| SR 193 | BENCH STOP (SLM 1.33) | R | | 70.00 | 7.00 | | | | | 70.00 | | 7.00 | | | REMOVE CURB RAMP, PLACE CURB AND NEW 5' WIDE WALK | |
| SR 193 | BENCH STOP (SLM 1.61) | L | | 48.00 | 7.00 | | | | | 60.00 | | 7.00 | | | REMOVE CURB RAMP, PLACE CURB AND NEW 5' WIDE WALK | |
| SR 193 | BENCH STOP (SLM 1.74) | R | | 40.00 | 7.00 | | | | | 50.00 | | 7.00 | | | REMOVE CURB RAMP, PLACE CURB AND NEW 5' WIDE WALK | |
| SR 193 | BENCH STOP (SLM 1.80) | L | | 32.00 | | | | | | 40.00 | | 7.00 | | | REMOVE CURB RAMP, PLACE CURB AND NEW 5' WIDE WALK | |
| SUBTOTALS | | | | 1302.00 | 91.00 | 0.00 | 1.00 | 0.00 | 160.00 | 1336.00 | 0.00 | 0.00 | 137.00 | 0.00 | 0.00 | |
| TOTALS CARRIED TO GENERAL SUMMARY | | | | 1302 | 91 | 0 | 1 | 0 | 160 | 1336 | 0 | 0 | 137 | 0 | 0 | |



| | | | |
|-----------------------------|-----|---------|-----|
| CALCULATED | CNC | CHECKED | MAC |
| CURB RAMP SUBSUMMARY | | | |
| TRU-193-0.00 | | | |
| 15 22 | | | |

I:\Project+Data\TRU\88916_193_0.00\Design\Roadway\Sheets\88916_GS002.dgn Sheet2 1/31/2017 8:38:58 AM ccopeian

| MAIN ROUTE | INTERSECTING ROUTE | QUADRANT RL=REAR LT, RR=REAR RT FL=FWD LT, FR=FWD RT (LOOKING UPSTATION) | CURB RAMP TYPE (SCD BP-7.1, SHEET 2/3) | 202 | 202 | 202 | 203 | 203 | 608 | 608 | 609 | | 609 | 659 | COMMENTS | | | | |
|--|-----------------------------------|---|---|--------------|--------------|-------------------------|--|------------|------------------|-----------|--|--------------|----------------------|-------|----------|----|----|----|----|
| | | | | WALK REMOVED | CURB REMOVED | CURB AND GUTTER REMOVED | EXCAVATION(FOR WALK OR CURB RAMP INSTALLATION) | EMBANKMENT | 6" CONCRETE WALK | CURB RAMP | COMBINATION CURB AND GUTTER, TYPE 2 (FOR WALK OR CURB RAMP INSTALLATION) | CURB, TYPE 6 | SEEDING AND MULCHING | SF | | FT | FT | CY | CY |
| SR 193 | LIBERTY PLAZA | FR | | 20.00 | 2.00 | | | | | | | | 2.00 | | | | | | |
| SR 193 | LIBERTY PLAZA (CROSSING PLAZA) | FR | | 40.00 | | | | | | | | | | | | | | | |
| SR 193 | LIBERTY PLAZA (CROSSING PLAZA) | RR | | 75.00 | 2.00 | | | | | | | | 2.00 | | | | | | |
| SR 193 | LIBERTY PLAZA | FL | | 28.00 | 2.00 | | | | | | | | 2.00 | | | | | | |
| SR 193 | LIBERTY PLAZA | RL | | 44.00 | 2.00 | | | | | | | | 2.00 | | | | | | |
| SR 193 | LIBERTY PLAZA (CROSSING Mc. DON.) | FL | | 24.00 | 2.00 | | | | | | | | 2.00 | | | | | | |
| SR 193 | LIBERTY PLAZA (CROSSING Mc. DON.) | RL | | 28.00 | 2.00 | | | | | | | | 2.00 | | | | | | |
| SR 193 | LAUREL ST | FL | | 20.00 | | | | | | | | | 20.00 | | | | | | |
| SR 193 | LAUREL ST | RL | | 56.00 | | | | | | | | | 56.00 | | | | | | |
| SR 193 | MONTROSE ST | FL | | 25.00 | | | | | | | | | 25.00 | | | | | | |
| SR 193 | MONTROSE ST | RL | | 30.00 | | | | | | | | | 30.00 | | | | | | |
| SR 193 | MONTROSE ST | FR | | 35.00 | | | | | | | | | 35.00 | | | | | | |
| SR 193 | MONTROSE ST | RR | | 20.00 | | | | | | | | | 20.00 | | | | | | |
| SR 193 | CATHERINE ST | FL | | 20.00 | | | | | | | | | 20.00 | | | | | | |
| SR 193 | CATHERINE ST | RL | | 35.00 | | | | | | | | | 35.00 | | | | | | |
| SR 193 | LIBERTY | FL | CURBCUT | | 13.00 | | 1.00 | 1.00 | | | | | 13.00 | 3.00 | | | | | |
| SR 193 | LIBERTY | FR | | 65.00 | 16.00 | | | | | | | | | | | | | | |
| SR 193 | MONTOR INN DR | FR | | 40.00 | 10.00 | | | | | | | | 2.00 | | | | | | |
| SR 193 | MOTOR INN DR | RR | | 28.00 | | | | | | | | | 2.00 | | | | | | |
| SR 193 | SPEEDWAY DR AT I-80 | FR | | 55.00 | 2.00 | | | | | | | | 2.00 | | | | | | |
| SR 193 | SPEEDWAY DR AT I-80 | RR | | 58.00 | 2.00 | | | | | | | | 2.00 | | | | | | |
| SR 193 | GOLDIE (CROSSING GOLDIE) | FR | | 42.00 | 7.00 | | | | | | | | 42.00 | | | | | | |
| SR 193 | GOLDIE (CROSSING GOLDIE) | RR | | 28.00 | 4.00 | | | | | | | | 28.00 | | | | | | |
| SR 193 | GOLDIE (CROSSING SR 193) | RR | CURBCUT | | 13.00 | | 1.00 | 1.00 | | | | | 13.00 | 3.00 | | | | | |
| SR 193 | GOLDIE (CROSSING SR 193) | RL | CURBCUT | | 13.00 | | 1.00 | 1.00 | | | | | 13.00 | 3.00 | | | | | |
| SR 193 | GOLDIE (CROSSING GOLDIE) | RL | CURBCUT | | 13.00 | | 1.00 | 1.00 | | | | | 13.00 | 3.00 | | | | | |
| SR 193 | GOLDIE (CROSSING SR 193) | FL | CURBCUT | | 13.00 | | 1.00 | 1.00 | | | | | 13.00 | 3.00 | | | | | |
| SR 193 | GOLDIE (CROSSING GOLDIE) | FL | CURBCUT | | 13.00 | | 1.00 | 1.00 | | | | | 13.00 | 3.00 | | | | | |
| SUBTOTALS | | | | 816.00 | 131.00 | 0.00 | 6.00 | 6.00 | 0.00 | 821.00 | 0.00 | 0.00 | 98.00 | 18.00 | 0.00 | | | | |
| TOTALS CARRIED TO GENERAL SUMMARY | | | | 816 | 131 | 0 | 6 | 6 | 0 | 821 | 0 | 0 | 98 | 18 | 0 | | | | |

| | | | | | | |
|--|------------|-----|---------|-----|----------------------|--------------|
| <table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <td style="text-align: center;">CALCULATED</td> <td style="text-align: center;">CNC</td> </tr> <tr> <td style="text-align: center;">CHECKED</td> <td style="text-align: center;">XXX</td> </tr> </table> | CALCULATED | CNC | CHECKED | XXX | CURB RAMP SUBSUMMARY | TRU-193-0.00 |
| CALCULATED | CNC | | | | | |
| CHECKED | XXX | | | | | |
| 16 | 22 | | | | | |

I:\ProjectData\TRU\88916_193_0.00\Design\Roadway\Sheets\88916_GS002.dgn Sheet 3 1/31/2017 8:39:06 AM ccopelgn



| | |
|------------|---------|
| CALCULATED | CNC |
| | CHECKED |
| | XXX |

CURB RAMP DETAIL

TRU-193-0.00

EDGE LINE, 6"

GENERAL SPEC: 640
MATERIAL TYPE: 644

| CTY | ROUTE | TRUE LOG | FROM | TRUE LOG | TO | WHITE EDGE LINE | | | YELLOW EDGE LINE | | | COMMENTS |
|--------------|-------|----------|---------------------------------|----------|---------------------------------|-----------------|---------|------|------------------|---------|------|----------|
| | | | | | | TOTAL | HIGHWAY | RAMP | TOTAL | HIGHWAY | RAMP | |
| TRU | 193 | 1.98 | S.R. 304 | 5.37 | SMITH STEWART RD | 6.78 | | | | | | |
| TRU | 193 | 5.37 | SMITH STEWART RD | 6.60 | RAMP TO S.R. 82 EAST | 2.46 | | | | | | |
| TRU | 193 | 6.60 | RAMP TO S.R. 82 EAST | 6.74 | 0.02 MILES S OF SR 82 EXIT RAMP | 0.28 | 0.28 | | 0.28 | 0.28 | | |
| TRU | 193 | 6.74 | 0.02 MILES S OF SR 82 EXIT RAMP | 6.78 | PAVEMENT JOINT N OF SR 82 | 0.08 | | | | | | |
| TOTAL | | | | | | 9.60 | 0.28 | | 0.28 | 0.28 | | |

LANE LINE

| CTY | ROUTE | TRUE LOG | FROM | TRUE LOG | TO | TOTAL MILES | 6" LANE LINE | | COMMENTS |
|--------------|-------|----------|----------------------|----------|---------------------------|-------------|--------------|-------|----------|
| | | | | | | | DASHED | SOLID | |
| TRU | 193 | 0.00 | MAHONING COUNTY LINE | 5.37 | SMITH STEWART RD | 10.74 | | | |
| TRU | 193 | 5.37 | SMITH STEWART RD | 6.78 | PAVEMENT JOINT N OF SR 82 | 2.82 | | | |
| TOTAL | | | | | | 13.56 | | | |

CENTER LINE

| CTY | ROUTE | TRUE LOG | FROM | TRUE LOG | TO | TOTAL MILES | EQUIVALENT SOLID LINE | | COMMENTS |
|--------------|-------|----------|----------------------|----------|---------------------------|-------------|-----------------------|--|----------|
| | | | | | | | | | |
| TRU | 193 | 0.00 | MAHONING COUNTY LINE | 5.37 | SMITH STEWART RD | 6.73 | 14.58 | | |
| TRU | 193 | 5.37 | SMITH STEWART RD | 6.78 | PAVEMENT JOINT N OF SR 82 | 2.01 | 2.70 | | |
| TOTAL | | | | | | 8.74 | 17.27 | | |

AUXILIARY

| CTY | ROUTE LOCATION | TRUE LOG | CHANNEL LINE | STOP LINE | CROSS WALK LINES | TRANSVERSE DIAGONAL LINES | | ISLAND MARKING | SYMBOL MARKINGS | | | LANE ARROWS | | | COMMENTS | | |
|--------------|--------------------|----------|--------------|-----------|------------------|---------------------------|--------|----------------|-----------------|--------|----|-------------|------------|------|--|-------|-------|
| | | | | | | WHITE | YELLOW | | R x R | SCHOOL | | TURN LEFT | TURN RIGHT | THRU | | COMB. | MERGE |
| | | | | | | | | | | FT | FT | | | | | | |
| TRU | GYPSY LANE | 0 | 240 | 40 | 180 | | | | | | 5 | | | | | | |
| TRU | COLONIAL DR. | 0.23 | 140 | 66 | 212 | | | | | | 4 | | | | | | |
| TRU | TRUMBULL AVE. | 0.51 | 155 | 70 | 220 | | | | | | 5 | | | | RELOCATE S. CROSSWALK LINE TO PROPOSED CURB RAMP | | |
| TRU | GOLDIE RD. | 0.82 | 490 | 80 | | | | | | | 4 | 3 | | | | | |
| TRU | LIBERTY PLAZA | 1.03 | 445 | 85 | 250 | | | | | | 10 | 3 | | | | | |
| TRU | LIBERTY JONES | 1.25 | 460 | 75 | | | | | | | 6 | | | | | | |
| TRU | I.R. 80 EB RAMPS | 1.500 | 1000 | 70 | | | | | | | 9 | | | | | | |
| TRU | S.R. 304 (SOUTH) | 1.973 | 208 | 50 | | | | | | | 7 | 3 | | | | | |
| TRU | S.R. 304 (NORTH) | 1.973 | 265 | 50 | | | | | | | 5 | 2 | | | | | |
| TRU | GIANT EAGLE | 2.030 | 200 | | | | | | | | 4 | | | | | | |
| TRU | 2.03 - 3.45 | 2.040 | | | | | | | | | 14 | | | | | | |
| TRU | TIBBETTS-WICK ROAD | 3.420 | 285 | 65 | | | | | | | 4 | | | | | | |
| TRU | KLINES DRIVE | 4.050 | 240 | | | | | | | | 3 | | | | | | |
| TRU | SR 82 | 6.614 | | | | | | | | | | | | | 181 | | |
| TRU | SR 82 | 6.742 | | | | | | | | | | | | | 148 | | |
| TOTAL | | | 4128 | 651 | 862 | | 329 | | | | 80 | 11 | | | | | |

PAVEMENT MARKING SUB SUMMARY

TRU-193-0.00

I:\ProjectData\TRU\88916_193_0.00\Design\Roadway\Sheets\88916_GS001.dgn Sheet 1/31/2017 8:39:06 AM ccopelan

I:\ProjectData\TRU\88916_193_0_00\Design\Roadway\Sheets\88916_GC001.dgn Sheet 1/31/2017 8:39:15 AM ccobelan

| COUNTY | ROUTE | SECTION (S.L.M.) | | | | | 621 | 621 | 621 | 621 | | 621 | REMARKS | |
|-----------------------------------|-------|---------------------|-----------------|--|--|--|-------------|------------------|--------------------------------|------|--|------|------------------------------------|--|
| | | RPM (YELLOW/YELLOW) | RPM (WHITE/RED) | | | | RPM (WHITE) | RPM (YELLOW/RED) | RAISED PAVEMENT MARKER REMOVED | | | | | |
| | | FROM | TO | | | | EACH | EACH | EACH | EACH | | EACH | | |
| TRU | 193 | 0.00 | 0.51 | | | | 58 | 75 | | | | 107 | GYSKY LN TO TRUMBULL AVE | |
| TRU | 193 | 0.51 | 0.83 | | | | 39 | 47 | | | | 69 | GYSKY LN TO GOLDIE AVE | |
| TRU | 193 | 0.83 | 1.97 | | | | 91 | 196 | | | | 230 | GOLDIE AVE TO SR 304 | |
| TRU | 193 | 1.97 | 5.37 | | | | 305 | 465 | 48 | | | 655 | GOLDIE AVE TO SMITH STEWART RD | |
| TRU | 193 | 5.37 | 6.78 | | | | 115 | 188 | | | | 243 | SMITH STEWART RD TO PAVEMENT JOINT | |
| SUB TOTALS | | | | | | | 608 | 971 | 48 | | | 1304 | | |
| TOTALS CARRIED TO GENERAL SUMMARY | | | | | | | | 1627 | | | | | | |

| | |
|---|---------|
| CALCULATED | CNC |
| | CHECKED |
| MAC | |
| RAISED PAVEMENT MARKER SUB SUMMARY | |
| TRU-193-0.00 | |
| 19 | 22 |

I:\ProjectData\TRU\88916_193_0_00\Design\Structures\TRU193_0491C_Sheets\193_0491C_SND01.dgn_Sheet 1/31/2017 8:39:23 AM ccopele

DESIGN SPECIFICATIONS

THIS STRUCTURE CONFORMS TO "STANDARD SPECIFICATIONS FOR HIGHWAY BRIDGES" ADOPTED BY THE AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS, 17TH EDITION, INCLUDING THE 2002 INTERIM SPECIFICATIONS AND THE ODOT BRIDGE DESIGN MANUAL.

EXISTING STRUCTURE VERIFICATION

EXISTING STRUCTURE VERIFICATION: DETAILS AND DIMENSIONS SHOWN ON THESE PLANS PERTAINING TO THE EXISTING STRUCTURE HAVE BEEN OBTAINED FROM PLANS OF THE EXISTING STRUCTURE AND FROM FIELD OBSERVATIONS AND MEASUREMENTS. CONSEQUENTLY, THEY ARE INDICATIVE OF THE EXISTING STRUCTURE AND THE PROPOSED WORK BUT THEY SHALL BE CONSIDERED TENTATIVE AND APPROXIMATE. THE CONTRACTOR IS REFERRED TO CMS SECTIONS 102.05, 105.02 AND 513.04.

BASE CONTRACT BID PRICES UPON A RECOGNITION OF THE UNCERTAINTIES DESCRIBED ABOVE AND UPON A PREBID EXAMINATION OF THE EXISTING STRUCTURE. HOWEVER, THE DEPARTMENT WILL PAY FOR ALL PROJECT WORK BASED UPON ACTUAL DETAILS AND DIMENSIONS WHICH HAVE BEEN VERIFIED IN THE FIELD.

PROPOSED WORK

TRU-193-0491 (BRANCH SQUAW CREEK)
- SEAL CONCRETE HEADWALLS WITH EPOXY-URETHANE
- CLEARING AND GRUBBING WITHIN 15' OF STRUCTURE TO REMOVE ALL VEGETATION
- PROVIDE NEW CORRECT STRUCTURE IDENTIFICATION SIGNS

TRU-193-0618 (SQUAW CREEK)
- SEAL CONCRETE HEADWALLS WITH EPOXY-URETHANE
- CLEARING AND GRUBBING WITHIN 15' OF STRUCTURE TO REMOVE ALL VEGETATION
- PROVIDE NEW CORRECT STRUCTURE IDENTIFICATION SIGNS

CLEARING AND GRUBBING

ALTHOUGH THERE ARE NO TREES OR STUMPS SPECIFICALLY MARKED FOR REMOVAL WITHIN THE LIMITS OF THE PROJECT, A LUMP SUM QUANTITY IS INCLUDED IN THE GENERAL SUMMARY FOR ITEM 201, CLEARING AND GRUBBING. ALL PROVISIONS AS SET FORTH IN THE SPECIFICATIONS UNDER THIS ITEM ARE INCLUDED IN THE LUMP SUM PRICE BID FOR ITEM 201, CLEARING AND GRUBBING.

STRUCTURE/CULVERT IDENTIFICATION SIGNS

STRUCTURE IDENTIFICATION SIGNS (I-H25b) WILL BE PLACED ON EACH APPROACH OFF THE RIGHT SHOULDER, FACING TRAFFIC, AND BEHIND THE GUARDRAIL IF APPLICABLE. A QUANTITY OF ONE SIGN PER APPROACH WILL BE INSTALLED. THE SIGNS WILL HAVE A NON-REFLECTIVE WHITE SHEETING BACKGROUND.

THE SIGNS WILL BE MOUNTED ON NEW NO. 2 POSTS AND WILL BE INSTALLED AS PER STANDARD CONSTRUCTION DRAWING TC-41.20, MOST CURRENT REVISION. EACH POST WILL BE 7.5' IN LENGTH.

INSTALL SIGNS FOR THE FOLLOWING STRUCTURES:
TRU-193-0491 (2 APPROACHES)
TRU-193-0618 (2 APPROACHES)

THE FOLLOWING QUANTITIES HAVE BEEN INCLUDED FOR EACH APPROACH:

- ITEM 630 - SIGN, FLAT SHEET, 730.20, 1 SQ FT
- ITEM 630 - GROUND MOUNTED SUPPORT, NO. 2 POST, 7.5 FT
- ITEM 630 - REMOVAL OF GROUND MOUNTED SIGN AND DISPOSAL, 1 EACH
- ITEM 630 - REMOVAL OF GROUND MOUNTED POST SUPPORT AND DISPOSAL, 1 EACH

