



TYPICAL SECTION THRU NEW HANDICAP ITEM 608, CURB RAMPS  
NO SCALE

**NOTE:**

PAYMENT FOR SAWING-OUT THE EXISTING CURB SHALL BE INCLUDED IN THE PAYMENT FOR RAMPS AS PER CMS 608.09.

TOTAL FROM SHEET NO.								PART.	ITEM	ITEM EXT.	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.	
6	7	8	9	10	11	12	13	01/NFP/OT							
<b>ROADWAY</b>															
LUMP	LUMP	LUMP	LUMP	LUMP	LUMP	LUMP	LUMP	LUMP	201	11000	LUMP	LUMP	CLEARING AND GRUBBING		
1882	1814	1237	81					5014	202	30000	5014	S.F.	WALK REMOVED		
209	202	137	159	208	159	228	205	1507	204	10000	1507	S.Y.	SUBGRADE COMPACTION		
1726	1614	1142	1347	1705	1190	2084	1767	12,575	608	10001	12,575	S.F.	4" CONCRETE WALK AS PER PLAN	3	
104	182	67		80	40			473	608	13001	473	S.F.	6" CONCRETE WALK AS PER PLAN	3	
72	48	48	102	112	222		36	640	608	52000	640	S.F.	CURB RAMP		
24	16	16	32	32	56		8	184	608	53021	184	S.F.	DETECTABLE WARNING AS PER PLAN	3	
						10.5	7.3	17.8	651	10000	17.8	C.Y.	TOPSOIL STOCKPILED		
						10.5	7.3	17.8	652	10000	17.8	C.Y.	PLACING STOCKPILED TOPSOIL		
1.5	1.4	1.0	1.4	1.7	0.6			7.6	654	10000	7.6	M S.F.	RENOVATING EXISTING SOIL		
<b>EROSION CONTROL</b>															
.015	.014	.010	.014	.017	.006	.023	.016	0.12	659	20000	0.12	TON	COMMERCIAL FERTILIZER		
170	159	114	154	194	69	253	173	1286	659	10000	1286	S.Y.	SEEDING AND MULCHING		
								1000	832	30000	1000	EACH	EROSION CONTROL		
<b>PAVEMENT</b>															
23	23	16	18	23	18	26	22	169	304	20000	169	C.Y.	AGGREGATE BASE		
<b>SANITARY SEWER</b>															
				2				2	611	99655	2	EACH	MANHOLE ADJUSTED TO GRADE AS PER PLAN	10	
<b>INCIDENTALS</b>															
			LUMP	LUMP	LUMP	LUMP	LUMP	LUMP	614	11000	LUMP	LUMP	MAINTAINING TRAFFIC		
									LUMP	623	10001	LUMP	LUMP	CONSTRUCTION LAYOUT STAKES AND SURVEYING AS PER PLAN	3
									LUMP	624	10000	LUMP	LUMP	MOBILIZATION	