

ITEM 614 - MAINTAINING TRAFFIC, AS PER PLAN

THE CONTRACTOR SHALL MAINTAIN TRAFFIC AT ALL TIMES IN ACCORDANCE WITH THE REQUIREMENTS OF CMS ITEM 614, THESE MAINTENANCE OF TRAFFIC NOTES AND DETAILS, THE STANDARD CONSTRUCTION DRAWINGS, AND THE TRAFFIC CONTROL DETAILS DESCRIBED IN THESE PLANS.

THE MINIMUM LANE WIDTH FOR TRAFFIC CONTROL SHALL BE 11 FEET (EDGE LINE TO EDGE LINE) AT ALL TIMES. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO ORGANIZE HIS WORK IN SUCH A MANNER TO PROVIDE THE MOST SAFETY WITH THE LEAST INCONVENIENCE TO THE TRAVELING PUBLIC.

THE CONTRACTOR IS RESPONSIBLE FOR DESIGNING THE MAINTENANCE OF TRAFFIC SCHEME. THE CONTRACTOR SHALL SUBMIT, IN WRITING, THIS MAINTENANCE OF TRAFFIC SCHEME AND A SCHEDULE OF OPERATIONS TO THE ENGINEER AND RECEIVE APPROVAL BEFORE WORK IS STARTED ON THE PROJECT.

THE SHOULDERS SHALL HAVE THE EXISTING RUMBLE STRIPS REMOVED BEFORE TRAFFIC IS PERMITTED TO BE MAINTAINED ON THEM. SEE EXISTING RUMBLE STRIPS NOTE ON P.06 FOR ADDITIONAL INFORMATION.

THE PROPOSED MEDIAN SHOULDER PAVING SHALL BE COMPLETED BEFORE TRAFFIC IS PERMITTED TO BE MAINTAINED ON THEM.

ANY OPEN PAVEMENT TRENCH OR DROP-OFF SHALL BE ADEQUATELY MAINTAINED AND PROTECTED. THE PROTECTION USED SHALL MEET THE REQUIREMENTS OF STD DWG MT-101.90.

UNDER NO CIRCUMSTANCES SHALL THE CONTRACTOR BE PERMITTED TO HAVE WORK ZONES WHICH ALTERNATELY CLOSE BOTH THE PASSING AND TRAVEL LANE UNLESS THE DISTANCE BETWEEN THE LANE RESTRICTIONS EXCEEDS 2 MILES.

ALL RAMPS MUST BE BUILT PART WIDTH AND CANNOT BE SHUT DOWN AT ANY TIME.

THE CONTRACTOR SHALL BE RESPONSIBLE FOR SMOOTH AND ORDERLY FLOW OF TRAFFIC THROUGH THE PROJECT AREA 24 HOURS PER DAY FOR THE DURATION OF THE PROJECT. THIS CONSISTS OF NOTIFYING THE OHIO STATE PATROL AFTER ENCOUNTERING ANY ACCIDENTS OR DISABLED VEHICLES OR OBJECTS HINDERING THE FLOW OF TRAFFIC.

THE CONTRACTOR SHALL DESIGNATE TO THE ENGINEER A PERSON RESPONSIBLE FOR MAINTENANCE OF TRAFFIC CONTROL DURING NON-WORK HOURS WHO SHALL BE AVAILABLE WITHIN (30) MINUTES AFTER NOTIFICATION.

PAYMENT FOR PROVIDING WATCHMEN, FURNISHING, ERECTING, MAINTAINING AND REMOVING SIGNS, CONES, DRUMS, MARKERS, SPECIAL LIGHTING, FLOODLIGHTING, WORK ZONE PAVEMENT MARKINGS, WORK ZONE RAISED PAVEMENT MARKERS, ETC., SHALL BE INCLUDED IN THE LUMP SUM PRICE BID FOR ITEM 614 MAINTAINING TRAFFIC, AS PER PLAN.

THE CONTRACTOR SHALL FURNISH, INSTALL AND MAINTAIN ALL ADDITIONAL SIGNS OR OTHER TRAFFIC CONTROL DEVICES AS REQUIRED ABOVE. ALL COSTS INVOLVED IN FURNISHING, INSTALLING AND MAINTAINING THESE DEVICES SHALL BE INCLUDED IN THE LUMP SUM PRICE BID FOR ITEM 614, MAINTAINING TRAFFIC, AS PER PLAN.

UNLESS THE ENGINEER DEEMS IT PHYSICALLY IMPOSSIBLE, ALL CONSTRUCTION EQUIPMENT SHALL EXIT ALL WORK ZONES FROM THE DOWNSTREAM END OF THE WORK ZONE OR BY INTERCHANGE RAMPS. UNDER NO CIRCUMSTANCES SHALL THE CONTRACTOR BE PERMITTED TO DIRECTLY TRANSPORT OR OPERATE ANY EQUIPMENT ACROSS THE OPEN LANES OF THE ROADWAY.

ITEM 614 - MAINTAINING TRAFFIC, AS PER PLAN (CONTINUED...)

LENGTH AND DURATION OF LANE CLOSURES AND RESTRICTIONS SHALL BE AT THE APPROVAL OF THE ENGINEER. IT IS THE INTENT TO MINIMIZE THE IMPACT TO THE TRAVELING PUBLIC. LANE CLOSURES OR RESTRICTIONS OVER SEGMENTS OF THE PROJECT IN WHICH NO WORK IS ANTICIPATED WITHIN A REASONABLE TIME FRAME, AS DETERMINED BY THE ENGINEER, SHALL NOT BE PERMITTED. THE LEVEL OF UTILIZATION OF MAINTENANCE OF TRAFFIC DEVICES SHALL BE COMMENSURATE WITH THE WORK IN PROGRESS.

THE PLANING AND RESURFACING SHALL PROCEED CONTINUOUSLY DURING THE TIME FRAME SPECIFIED ABOVE, A MINIMUM OF FIVE (5) DAYS PER WEEK, WEATHER PERMITTING, EXCEPT DURING HOLIDAYS AND EVENTS LISTED BELOW.

NO WORK SHALL BE PERFORMED AND ALL EXISTING LANES SHALL BE OPEN TO TRAFFIC DURING THE FOLLOWING DESIGNATED HOLIDAYS OR EVENTS:

MEMORIAL DAY	FOURTH OF JULY
LABOR DAY	THANKSGIVING
ELECTION DAY	

THE PERIOD OF TIME THAT THE LANES ARE TO BE OPENED DEPENDS ON THE DAY OF THE WEEK ON WHICH THE HOLIDAY OR EVENT FALLS. THE FOLLOWING SCHEDULE SHALL BE USED TO DETERMINE THIS PERIOD:

DAY OF HOLIDAY OR SPECIAL EVENT	TIME ALL LANES MUST BE OPEN TO TRAFFIC
SUNDAY	12:00 N FRIDAY THROUGH 6:00 AM MONDAY
MONDAY	12:00 N FRIDAY THROUGH 6:00 AM TUESDAY
TUESDAY	12:00 N MONDAY THROUGH 6:00 AM WEDNESDAY
TUESDAY (ELECTION DAY)	5:00 AM TUESDAY THROUGH 12:00 AM WEDNESDAY
WEDNESDAY	12:00 N TUESDAY THROUGH 6:00 AM THURSDAY
THURSDAY	12:00 N WEDNESDAY THROUGH 6:00 AM FRIDAY
THANKSGIVING ONLY	6:00 AM WEDNESDAY THROUGH 6:00 AM MONDAY
FRIDAY	12:00 N THURSDAY THROUGH 6:00 AM SATURDAY

SHOULD THE CONTRACTOR FAIL TO MEET ANY OF THES REQUIREMENTS, THE CONTRACTOR SHALL BE ASSESSED A DISINCENTIVE PER THE LANE VALUE CONTRACT TABLE BELOW:

LANE VALUE CONTRACT			
DESCRIPTION OF CRITICAL LANE/RAMP TO BE MAINTAINED	RESTRICTED TIME PERIOD	TIME UNIT	DISINCENTIVE \$ PER TIME UNIT
ALL WORK ON I.R. 77 AND RAMPS	PER PLCS	EACH HOUR	\$8,800

ALL WORK AND TRAFFIC CONTROL DEVICES SHALL BE IN ACCORDANCE WITH CMS 614 AND OTHER APPLICABLE PORTIONS OF THE SPECIFICATIONS, AS WELL AS THE OHIO MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES. PAYMENT FOR ALL LABOR, EQUIPMENT AND MATERIALS SHALL BE INCLUDED IN THE LUMP SUM CONTRACT PRICE FOR ITEM 614, MAINTAINING TRAFFIC, AS PER PLAN UNLESS SEPARATELY ITEMIZED IN THE PLAN.

NOTIFICATION OF TRAFFIC RESTRICTIONS

THROUGHOUT THE DURATION OF THE PROJECT, THE CONTRACTOR SHALL NOTIFY THE PROJECT ENGINEER IN WRITING OF ALL TRAFFIC RESTRICTIONS AND UPCOMING MAINTENANCE OF TRAFFIC CHANGES. THE CONTRACTOR SHALL ENSURE THE WRITTEN NOTIFICATION IS SUBMITTED IN A TIMELY MANNER TO ALLOW THE PROJECT ENGINEER TO MEET THE REQUIRED TIME FRAMES SET FORTH IN THE TABLE BELOW TO INFORM THE SPECIAL HAULING PERMITS SECTION (HAULING.PERMITS@DOT.OHIO.GOV) AND THE DISTRICT PUBLIC INFORMATION OFFICE (PIO). THIS NOTIFICATION SHALL BE RECEIVED BY THE PROJECT ENGINEER PRIOR TO THE PHYSICAL SETUP OF ANY APPLICABLE SIGNS OR MESSAGE BOARDS.

INFORMATION SHOULD INCLUDE, BUT IS NOT LIMITED TO, ALL CONSTRUCTION ACTIVITIES THAT IMPACT OR INTERFERE WITH TRAFFIC AND SHALL LIST THE SPECIFIC LOCATION, TYPE OF WORK, ROAD STATUS, DATE AND TIME OF RESTRICTION, DURATION OF RESTRICTION, NUMBER OF LANES MAINTAINED, NUMBER OF LANES CLOSED, MINIMUM VERTICAL CLEARANCE, MINIMUM WIDTH OF DRIVABLE PAVEMENT, DETOUR ROUTES, IF APPLICABLE, AND ANY OTHER INFORMATION REQUESTED BY THE PROJECT ENGINEER.

NOTIFICATION TIME TABLE		
ITEM	DURATION OF CLOSURE	NOTICE DUE TO PERMITS & PIO
RAMP & ROAD CLOSURES	>= 2 WEEKS	21 CALENDAR DAYS PRIOR TO CLOSURE
	> 12 HOURS & < 2 WEEKS	14 CALENDAR DAYS PRIOR TO CLOSURE
	<= 12 HOURS	4 BUSINESS DAYS PRIOR TO CLOSURE
LANE CLOSURES AND RESTRICTIONS	>= 2 WEEKS	14 CALENDAR DAYS PRIOR TO CLOSURE
	< 2 WEEKS	5 BUSINESS DAYS PRIOR TO CLOSURE
START OF CONSTRUCTION & TRAFFIC PATTERN CHANGES	N/A	14 CALENDAR DAYS PRIOR TO IMPLEMENTATION

ANY UNFORESEEN CONDITIONS NOT SPECIFIED IN THE PLANS REQUIRING TRAFFIC RESTRICTIONS SHALL ALSO BE REPORTED TO THE PROJECT ENGINEER USING THE NOTIFICATION TIME TABLE.

DUST CONTROL

THE CONTRACTOR SHALL FURNISH AND APPLY WATER FOR DUST CONTROL AS DIRECTED BY THE ENGINEER. THE FOLLOWING ESTIMATED QUANTITIES HAVE BEEN INCLUDED FOR DUST CONTROL PURPOSES:

ITEM 616, WATER 5 M. GAL.

REMOVED FLOODLIGHTING NOTE

PERMITTED LANE CLOSURE SCHEDULE (PLCS)

LANE CLOSURE(S) SHALL CONFORM TO THE PLCS. PUBLISHED PLCS INFORMATION CAN BE FOUND ON THE ODOT WEBSITE AT: [HTTPS://WWW.TRANSPORTATION.OHIO.GOV/WPS/PORTAL/GOV/ODOT/WORKING/DATA-TOOLS/RESOURCES/PERMITTED-LANE-CLOSURE](https://www.transportation.ohio.gov/wps/portal/gov/odot/working/data-tools/resources/permited-lane-closure)

THE MONTHLY PUBLISHED SCHEDULES REQUIRED TO BE USED, FOR EACH PLCS SEGMENT WITHIN THE PROJECT AREA, ARE THOSE THAT COMPRISE THE CONSECUTIVE 12-MONTH PERIOD BEGINNING 15 MONTHS PRIOR TO THE MONTH AND YEAR OF SALE AND ENDING 4 MONTHS PRIOR TO THE MONTH AND YEAR OF SALE. THESE SAME 12 MONTHS APPLY FOR THE LIFE OF THE PROJECT AND SHALL BE APPLIED TO EACH RESPECTIVE MONTH OF CONSTRUCTION (MONTH OF LANE CLOSURE(S) SHALL MATCH MONTH OF PLCS USED). LANE CLOSURE(S) IN PLACE FOR MULTIPLE MONTHS SHALL ALWAYS COMPLY WITH THE CURRENT RESPECTIVE MONTH.

(FOR EXAMPLE: IF THE SALE DATE FOR THE PROJECT WAS MARCH OF 2021, THE MONTHLY PUBLISHED SCHEDULES FOR EACH APPLICABLE PLCS SEGMENT WOULD BE DECEMBER 2019 TO NOVEMBER 2020. IF THIS WAS A THREE-YEAR PROJECT, YEAR THREE WOULD STILL BE USING THE DECEMBER 2019 TO NOVEMBER 2020 MONTHLY SCHEDULES. IF THE PROJECT DESIRED TO CLOSE TWO LANES IN JUNE 2021, REFERENCE WOULD BE MADE TO THE JUNE 2020 SCHEDULE(S) FOR THE RESPECTIVE PLCS SEGMENT(S). IF THE SAME TWO LANES WERE DESIRED TO BE CLOSED AGAIN IN JULY 2021, REFERENCE WOULD BE MADE TO THE JULY 2020 SCHEDULE(S) FOR THE RESPECTIVE PLCS SEGMENT(S).)

MORE RESTRICTIVE CHANGES TO THE ALLOWABLE LANE CLOSURE HOURS ARE AT THE DISCRETION OF THE ENGINEER IN ORDER TO COMPLY WITH THE TRAFFIC MANAGEMENT IN WORK ZONES POLICY (21-008(P)) AND STANDARD PROCEDURE (123-001(SP)).

LESS RESTRICTIVE CHANGES TO THE ALLOWABLE LANE CLOSURE HOURS ARE SUBJECT TO THE TRAFFIC MANAGEMENT IN WORK ZONES POLICY (21-008(P)) AND STANDARD PROCEDURE (123-001(SP)) AND SHALL NOT BE IMPLEMENTED UNTIL, AND UNLESS, APPROVED BY THE PROPER ODOT AUTHORITY.

ALLOWABLE LANE CLOSURE HOURS FOR FACILITIES NOT COVERED BY THE PLCS, IF ANY, SHALL BE AS SPECIFIED ELSEWHERE IN THE PLANS.

MOVEMENT OF DRUMS

THE ROW OF DRUMS ALONG A CLOSED LANE SHALL BE MOVED OUT OF THE OPEN LANE ONTO THE NEW PAVEMENT AS SOON AS PAVING OPERATIONS PERMIT.

WINDOW CONTRACT TABLE

USE THE FOLLOWING TABLE AS REFERRED TO IN THE PROPOSAL:

DESCRIPTION OF CRITICAL WORK	CALENDAR DAYS TO COMPLETE	DISINCENTIVE \$ PER DAY	WORK WINDOW	
			START	END
ALL WORK ON I.R. 77 AND RAMPS	152 CALENDAR DAYS	\$5,000	CONTRACT EXECUTION DATE	10/31/27

