

SHEET NO.	STA. TO STA.		DISTANCE		AREA SQ YD	254	254	407	407	442		618	861	REMARKS
			FT	MILE		PAVEMENT PLANING, ASPHALT CONCRETE, 1.5"	PAVEMENT PLANING, ASPHALT CONCRETE, 3.0"	NON-TRACKING TACK COAT	NON-TRACKING TACK COAT (INTERMEDIATE)	ANTI-SEGREGATION EQUIPMENT	ASPHALT CONCRETE SURFACE COURSE, 12.5mm, TYPE A (447), 1.5"	RUMBLE STRIPS, SHOULDER (ASPHALT CONCRETE)	ASPHALT CONCRETE INTERMEDIATE COURSE, 12.5mm, TYPE A (446), 1.5"	
						SQ YD	SQ YD	GAL	GAL	CU YD	CU YD	MILE	CU YD	
50	889+09	917+00	2,791	0.53	22,330	22,330		1,900		724	930	2.11		
51	917+00	945+00	2,800	0.53	22,809	22,809		1,939		726	950	2.12		
52	945+00	973+00	2,800	0.53	22,400	22,400		1,904		726	933	2.12		
54	973+00	1001+00	2,800	0.53	25,699	25,699		2,185		863	1,071	2.12		
56	1001+00	1029+00	2,800	0.53	25,420	23,055	2,365	2,163	131	931	1,059	2.12	99	
57	1029+00	1057+00	2,800	0.53	22,829	17,337	5,492	1,943	616	904	951	2.12	229	
59	1057+00	1085+00	2,800	0.53	26,414	26,414		2,246		893	1,101	2.12		
61	1085+00	1113+00	2,800	0.53	26,632	26,632		2,265		902	1,110	2.12		
63	1113+00	1141+00	2,800	0.53	22,793	22,793		1,938		726	950	2.12		
65	1141+00	1169+00	2,800	0.53	22,400	22,400		1,904		726	933	2.12		
67	1169+00	1197+00	2,800	0.53	22,400	22,400		1,904		726	933	2.12		
69	1197+00	1225+00	2,800	0.53	22,400	22,400		1,904		726	933	2.12		
71	1225+00	1253+00	2,800	0.53	22,400	22,400		1,904		726	933	2.12		
73	1253+00	1281+00	2,800	0.53	22,876	22,876		1,945		730	953	2.12		
75	1281+00	1309+00	2,800	0.53	26,464	26,464		2,250		888	1,103	2.12		
77	1309+00	1337+00	2,800	0.53	26,745	24,866	1,879	2,275	160	960	1,114	2.12	78	
78	1337+00	1365+00	2,800	0.53	22,400	11,200	11,200	1,904	952	1,089	933	2.12	467	
79	1365+00	1393+00	2,800	0.53	22,400	14,024	8,376	1,905	712	998	933	2.12	349	
80	1393+00	1421+00	2,800	0.53	22,400	22,400		1,904		726	933	2.12		
81	1421+00	1449+00	2,800	0.53	22,400	22,400		1,904		726	933	2.12		
83	1449+00	1477+00	2,800	0.53	22,400	22,400		1,904		726	933	2.12		
85	1477+00	1506+00	2,900	0.55	23,200	23,200		1,972		752	967	2.20		
86	1506+00	1520+65	1,465	0.28	12,074	12,074		1,028		380	503	1.12		
87	RAMPS/REST AREA				30,952	30,952		2,638		1,290	1,290			
	DEDUCTION					-56,660	-2,746		-283					DEDUCTION FOR SHOULDER PAVEMENT REPAIRS (SEE TYPICAL SECTIONS FOR DETAILS)
	DEDUCTION									-24	-24	-0.05		STRUCTURE AT STA 23.55
QUANTITIES CARRIED TO GENERAL SUMMARY						475,265	26,566	47,728	2,288	19,539	23,362	47.80	1221	