

UNI-739-6.21

MODEL: 112878_GG001_PAPER SIZE: TX11 (in.) DATE: 2/9/2023 TIME: 10:56:01 AM USER: andlow1 pwc:\hoboc-pw-bentley.com\shhoboc-pw-02\Documents\01 Active Projects\Distict 06\Union\112878\40C-Engineering\Roadway\Sheets\112878_GG001.dgn

SHEET NUMBER													PARTICIPATION			ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
													01/STR/PV	02/STR/VCV	03/STR/BR						
P.13-P.17	P.18-P.20	P.29	P.30	P.31	P.32	P.33	P.34	P.84	P.90	P.91	P.92	P.93									
		725											725			202	23000	725	SY	ROADWAY PAVEMENT REMOVED	
			65										65			202	23001	65	SY	PAVEMENT REMOVED, AS PER PLAN	P.13
						23				25			23	25		202	35100	48	FT	PIPE REMOVED, 24" AND UNDER	
										40				40		202	35200	40	FT	PIPE REMOVED, OVER 24"	
						2500							2500			202	38001	2500.0	FT	GUARDRAIL REMOVED, AS PER PLAN	P.13
						75.0							75.0			202	38500	75.0	FT	BRIDGE RAILING REMOVED	
						29							29			202	42001	29	EACH	ANCHOR ASSEMBLY REMOVED, TYPE A, AS PER PLAN	P.13
						4							4			202	42011	4	EACH	ANCHOR ASSEMBLY REMOVED, TYPE E, AS PER PLAN	P.13
						4							4			202	42041	4	EACH	ANCHOR ASSEMBLY REMOVED, TYPE T, AS PER PLAN	P.13
						2							2			202	42051	2	EACH	ANCHOR ASSEMBLY REMOVED, TYPE B, AS PER PLAN	P.13
						14							14			202	47001	14	EACH	BRIDGE TERMINAL ASSEMBLY REMOVED, AS PER PLAN	P.13
										1				1		202	58100	1	EACH	CATCH BASIN REMOVED	
LS													LS			202	98000	LS		REMOVAL MISC.: ROCKS AT 28302 SR-739	P.13
4													4			202	98100	4	EACH	REMOVAL MISC.: ROCKS AT 24001 SR-739	P.13
										LS			LS			202	98000	LS		REMOVAL MISC.: SHRUB TRIMMING	P.13
		1377		368	14			27	208				1967		27	203	10000	1994	CY	EXCAVATION	
								88	88	30			118	30	88	203	20000	236	CY	EMBANKMENT	
						244							244			203	20001	244	CY	EMBANKMENT, AS PER PLAN	P.13
33													33			204	13000	33	CY	EXCAVATION OF SUBGRADE	
33										38			71			204	30020	71	CY	GRANULAR MATERIAL, TYPE C	
220										224			444			204	50000	444	SY	GEOTEXTILE FABRIC	
						2950							2950			606	15050	2950.0	FT	GUARDRAIL, TYPE MGS	
						825							825			606	15100	825.0	FT	GUARDRAIL, TYPE MGS WITH LONG POSTS	
						225.0							225.0			606	17360	225.0	FT	GUARDRAIL, TYPE MGS, LONG-SPAN	
						2							2			606	25550	2	EACH	ANCHOR ASSEMBLY, MGS TYPE A	
						1							1			606	26050	1	EACH	ANCHOR ASSEMBLY, MGS TYPE B	
						37							37			606	26151	37	EACH	ANCHOR ASSEMBLY, MGS TYPE E, AS PER PLAN (MASH 2016)	P.14
						8							8			606	26550	8	EACH	ANCHOR ASSEMBLY, MGS TYPE T	
						11							11			606	35141	11	EACH	BRIDGE TERMINAL ASSEMBLY, TYPE 4, AS PER PLAN	P.14
						1							1			606	35141	1	EACH	BRIDGE TERMINAL ASSEMBLY, TYPE 4, AS PER PLAN, RADIUS	P.14
150													150			606	98000	150	FT	GUARDRAIL, MISC.: ALTERNATIVE GUARDRAIL PLACEMENT	P.14
6													6			623	39600	6	EACH	MONUMENT ASSEMBLY RECONSTRUCTED TO GRADE	
													LS	LS	LS	878	25000	LS		INSPECTION AND COMPACTION TESTING OF UNBOUND MATERIALS	
						3							3			601	32200	3	CY	EROSION CONTROL ROCK CHANNEL PROTECTION, TYPE C WITH FILTER	
						467	65	44					511		65	659	00300	576	CY	TOPSOIL	
						4195	593	393	40				4588	40	593	659	10000	5221	SY	SEEDING AND MULCHING	
						209	30						209		30	659	14000	239	SY	REPAIR SEEDING AND MULCHING	
						209	30						209		30	659	15000	239	SY	INTER-SEEDING	
						0.59	0.09	0.05	0.01				0.64	0.01	0.09	659	20000	0.74	TON	COMMERCIAL FERTILIZER	
						0.88	0.11						0.88		0.11	659	31000	0.99	ACRE	LIME	
						23.0	3.1	2.1	0.2				25.1	0.2	3.1	659	35000	28.4	MGAL	WATER	
						12							12			670	00500		SY	SLOPE EROSION PROTECTION	
						4750	250	250					832			832	30000	5250	EACH	EROSION CONTROL	

GENERAL SUMMARY

DESIGN AGENCY



DESIGNER
AMH

REVIEWER
DP

PROJECT ID
112878

SHEET TOTAL
P.26 | P.107