SHEET NUM. 4	5	7	8									PART. 01/ENH/OT	ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
																	ROADWAY	
												LS	201	11000	LS		CLEARING AND GRUBBING	
		2,183										2,183	202	30000	2,183	SF	WALK REMOVED	
	LS											LS	202	98000	LS		REMOVAL MISC.: REMOVED	5
												600	203	10000	600	CY	EXCAVATION	
												106	203	20000	106	CY	EMBANKMENT	
		4,388										4,388	204	10000	4,388	SY	SUBGRADE COMPACTION	
	407											407	204	13000	407	CY	EXCAVATION OF SUBGRADE	
	407											407	204	30010	407	CY	GRANULAR MATERIAL, TYPE B	
	3											3	204	45000	3	HOUR	PROOF ROLLING	
	2,442											2,442	204	50000	2,442	SY	GEOTEXTILE FABRIC	
		3,451										3,451	SPECIAL	20961000	3,451	SY	SHAPING	5
		10,363										10,363	608	10001	10,363	SF	4" CONCRETE WALK, AS PER PLAN	5
		472										472	608	52001	472	SF	CURB RAMP, AS PER PLAN	5
		1										1	611	99654	1	EACH	MANHOLE ADJUSTED TO GRADE	
		1										1	SPECIAL	69050560	1	EACH	BICYCLE RACK	5
		2										2	SPECIAL	69050600	2	EACH	BOLLARD	5
		291										291	SPECIAL	69098700	291	CY	AGGREGATE BASE REMOVED	5
																	EROSION CONTROL	
608												608	659	00300	608	CY	TOPSOIL	
5,466												5,466	659	00500	5,466	SY	SEEDING AND MULCHING, CLASS 1	
275												275	659	14000	275	SY	REPAIR SEEDING AND MULCHING	
275												275	659	15000	275	SY	INTER-SEEDING	
0.5												0.5	659	20000	0.5	TON	COMMERCIAL FERTILIZER	
1.13												1.13	659	31000	1.13	ACRE	LIME	
0.03												0.03	659	35000	0.03	MGAL	WATER	
		1,079										1,079	670	00500	1,079	SY	SLOPE EROSION PROTECTION	
												LS	832	15000	LS		STORM WATER POLLUTION PREVENTION PLAN	
												LS	832	15002	LS		STORM WATER POLLUTION PREVENTION INSPECTIONS	
												LS	832	15010	LS		STORM WATER POLLUTION PREVENTION INSPECTION SOFTWARE	
												14,000	832	30000	14,000	EACH	EROSION CONTROL	
																	PAVEMENT	
		235										235	304	20001	235	CY	AGGREGATE BASE, AS PER PLAN	5
		393										393	407	20000	393	GAL	NON-TRACKING TACK COAT	
		316										316	411	10000	316	CY	STABILIZED CRUSHED AGGREGATE	
		251										251	441	50000	251	CY	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448), PG64-22	
		389										389	441	50300	389	CY	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 2, (448)	
		64										64	452	10011	64	SY	6" NON-REINFORCED CONCRETE PAVEMENT, CLASS QC 1P, AS PER PLAN	5
																	TRAFFIC CONTROL	
			196									196	630	03100	196	FT	GROUND MOUNTED SUPPORT, NO. 3 POST	
			62									62	630	80100	62	SF	SIGN, FLAT SHEET	
			5									5	630	85100	5	EACH	REMOVAL OF GROUND MOUNTED SIGN AND REERECTION	
			4									4	630	86002	4	EACH	REMOVAL OF GROUND MOUNTED POST SUPPORT AND DISPOSAL	
		43										43	642	00620	43	FT	CROSSWALK LINE, 12", TYPE 1	
																	INCIDENTALS	
												LS	614	11000	LS		MAINTAINING TRAFFIC	
												6	619	16010	6	MNTH	FIELD OFFICE, TYPE B	
												LS	623	10001	LS		CONSTRUCTION LAYOUT STAKES AND SURVEYING, AS PER PLAN	5
												LS	624	10000	LS		MOBILIZATION	

CALCULATED BMW
CHECKED MJH

GENERAL SUMMARY

VAN-ROTARY SOCCER PARK TRAIL