JOHN BROWN ROAD

Ex R/W — Ex R/W — Ex R/W — Ex R/W — Ex R/W — Ex R/W

END WORK
STA. 47+75.27

*NOTE: THE STAGING AND/OR STORAGE OF CONSTRUCTION EQUIPMENT OR MATERIALS SHALL NOT TAKE PLACE OUTSIDE PROPOSED CONSTRUCTION LIMITS THAT ARE WITHIN THE DEFINED BOUNDARIES OF THE 4(F) PROPERTY.

PATRICIA L. PUCKETT
8999 JOHN BROWN RD.

MATCH LINE STA. 75+00

Ex. GRAVEL PARKING LOT

CONSTRUCTION LIMITS

Ex. SIGN (DND)

P9

END PROJECT
STA. 46+42.13

47

76 — 77 — N00° 27' 15"E — 78 — 79 — 80

10'

PI STA. = 46+39.13

P8

END WORK
STA. 77+32.72

P10

S15

S14

NO PARKING IN GRASS WHEN WET
YOU WILL GET STUCK
YOU WILL BE RESPONSIBLE
THANK YOU

SPECIAL
18" x 24"
STA. 75+14

NO MOTOR VEHICLES

R5-3
24" x 24"
STA. 77+30

P7

PC STA. = 45+94.68

46

EX. GRAVEL PATH

DO NOT DISTURB CONCRETE BOLLARD

PT STA. = 45+62

FOR PAVEMENT LEGEND AND DETAILS SEE SHEET 3

FOR SIGN LEGEND & VEGETATIVE STRIP REQUIREMENTS SEE SHEET 10.

	75+00	76+00	77+00	78+00	79+00	80+00
PROPOSED CENTERLINE ELEVATIONS	777.95	777.88	777.81	777.73	777.66	777.58	777.51	777.42	777.30
EXISTING CENTERLINE ELEVATIONS	778.1	777.9	777.8	777.7	777.6	777.5	777.5	777.4	777.4	777.0	776.5

795 790 785 780 775 770 765

-0.30%

-0.49%

STA = 76+93.88
ELEV = 777.45

STA = 77+32.87
ELEV = 777.26

PROP. GRADE

Ex. GRADE

SCALE IN FEET
0 10 20 40

CALCULATED BMW
CHECKED MJH

PLAN AND PROFILE BIKE PATH EXTENSION STA. 75+00 TO STA. 80+00

VAN-ROTARY SOCCER PARK TRAIL

19
36