

STRUCTURE (OVER 20 FOOT SPAN) GENERAL SUMMARY										
PART. 01/ENH/28	ITEM	ITEM EXT.	TOTAL	UNIT	DESCRIPTION	ABUTMENT		PIER 1	PIER 2	SEE SHEET NO.
						REAR	FWD.			
LUMP	202	11200	LUMP		PORTIONS OF STRUCTURE REMOVED					
LUMP	503	11100	LUMP		COFFERDAMS AND EXCAVATION BRACING					
LUMP	503	21300	LUMP		UNCLASSIFIED EXCAVATION					
6052	509	10000	6052	POUND	EPOXY COATED STEEL REINFORCEMENT	1415	2449	1083	1105	
302	510	10000	302	EACH	DOWEL HOLES WITH NONSHRINK, NONMETALLIC GROUT	94	48	80	80	
29	511	43260	29	CUBIC YARD	CLASS QC2 CONCRETE, PIER CAP			14	15	
48	511	50210	48	CUBIC YARD	CLASS QC1 CONCRETE, SUBSTRUCTURE	12	36			
28	518	21200	28	CUBIC YARD	POROUS BACKFILL WITH GEOTEXTILE FABRIC	6	22			
49	518	40000	49	FOOT	6" PERFORATED CORRUGATED PLASTIC PIPE	20	29			
48	518	40012	48	FOOT	6" NON-PERFORATED CORRUGATED PLASTIC PIPE	24	24			
250	519	11100	250	SQUARE FEET	PATCHING CONCRETE STRUCTURE	50	50	75	75	
LUMP	SPECIAL	530E00200	LUMP		STRUCTURES: PRE-ENGINEERED SUPERSTRUCTURE					3
28	SPECIAL	530E00600	28	SQUARE FOOT	STRUCTURES: NON-SHRINK, NON-METALLIC GROUT	5	5	9	9	2

ESTIMATED QUANTITIES

BRIDGE NO. VIN-MRT-144/48
OVER RACCOON CREEK

VIN-MRT-144 / 48
PID No. 120373

4 / 10

STRUCTURE (OVER 20 FOOT SPAN) GENERAL SUMMARY										
PART. 01/ENH/28	ITEM	ITEM EXT.	TOTAL	UNIT	DESCRIPTION	ABUTMENT		PIER 1	PIER 2	SEE SHEET NO.
						REAR	FWD.			
LUMP	202	11200	LUMP		PORTIONS OF STRUCTURE REMOVED					
LUMP	503	11100	LUMP		COFFERDAMS AND EXCAVATION BRACING					
LUMP	503	21300	LUMP		UNCLASSIFIED EXCAVATION					
5472	509	10000	5472	POUND	EPOXY COATED STEEL REINFORCEMENT	1344	1350	1532	1246	
236	510	10000	236	EACH	DOWEL HOLES WITH NONSHRINK, NONMETALLIC GROUT	20	28	98	90	
37	511	43260	37	CUBIC YARD	CLASS QC2 CONCRETE, PIER CAP			22	15	
22	511	50210	22	CUBIC YARD	CLASS QC1 CONCRETE, SUBSTRUCTURE	11	11			
16	518	21200	16	CUBIC YARD	POROUS BACKFILL WITH GEOTEXTILE FABRIC	8	8			
38	518	40000	38	FOOT	6" PERFORATED CORRUGATED PLASTIC PIPE	19	19			
48	518	40012	48	FOOT	6" NON-PERFORATED CORRUGATED PLASTIC PIPE	24	24			
250	519	11100	250	SQUARE FEET	PATCHING CONCRETE STRUCTURE	50	50	75	75	2
LUMP	SPECIAL	530E00200	LUMP		STRUCTURES: PRE-ENGINEERED SUPERSTRUCTURE					3
28	SPECIAL	530E00600	28	SQUARE FOOT	STRUCTURES: NON-SHRINK, NON-METALLIC GROUT	5	5	9	9	2