

STATION	STATION	LENGTH	EXISTING WIDTH SURFACE (FEET AVERAGE)	PAVEMENT AREA SURFACE (S.Y. TOTAL)	254	254	407	441
		LIN. FT.			PATCH PLANED SURFACE (S.Y.)	PAVEMENT PLANING ASPHALT CONCRETE (S.Y.)	NON-TRACKING TACK COAT @ 0.075 GAL./S.Y. (GALS.)	ASPHALT CONCRETE SURFACE COURSE TYPE 1, (448), PG 64-22 (C.Y.)
10+00	15+50	550	50	3056	30.56	3056	229	170
15+50	21+00	550	57	3484	34.84	3484	261	194
21+00	26+50	550	45	2750	27.5	2750	206	153
26+50	32+00	550	50	3056	30.56	3056	229	170
32+00	37+50	550	54	3300	33	3300	248	184
37+50	43+00	550	45	2750	27.5	2750	206	153
43+00	48+50	550	44	2689	26.89	2689	202	150
48+50	54+00	550	44	2689	26.89	2689	202	150
54+00	59+50	550	42	1731	17.31	1731	130	97
59+50	65+00	550	39	2384	23.84	2384	179	133
65+00	70+50	550	37	2262	22.62	2262	170	126
70+50	76+00	550	37	2262	22.62	2262	170	126
76+00	81+50	550	45	2750	27.5	2750	206	153
81+50	87+00	550	43	2628	26.28	2628	197	146
87+00	92+50	550	40	2445	24.45	2445	183	136
92+50	98+00	550	37	2262	22.62	2262	170	126
98+00	103+50	550	40	2445	24.45	2445	183	136
103+50	103+68	18	61	122	1.22	122	9	7
TOTALS TO GEN SUM		9368		45065	451	45065	3380	2510

ITEM 441 ANTI-SEGREGATION EQUIPMENT

THIS PAY ITEM IS BASED ON THE PAVEMENT AREA TO RECEIVE SURFACE COURSE MINUS THE PAVED SHOULDER AREA TO RECEIVE SURFACE COURSE. THE BELOW ESTIMATED QUANTITY HAS BEEN CARRIED TO THE GENERAL SUMMARY.

ITEM 441 ANTI-SEGREGATION EQUIPMENT.....1870 CY

STATION	STATION	LENGTH	644	644	644	644	644	644	644	644	644	644	644	644	644	644	644
		LIN. FT.	CENTER LINE (MILES)	EDGE LINE, 6" (MILES)	CHANNELIZING LINE, 8" (FEET)	TRANSVERSE/DIAGONAL LINE (FEET)	SCHOOL SYMBOL MARKING, 96" (EACH)	LANE ARROW (EACH)	BIKE LANE SYMBOL MARKING (EACH)	SHARED LANE MARKING (EACH)	CROSS WALK LINE (FEET)	CROSS WALK LINE, AS PER PLAN (S.F.)	STOP LINE (FEET)	LANE ARROW (EACH)	PARKING LOT STALL MARKING (FEET)	WORD ON PAVEMENT, 72" (EACH)	ISLAND MARKINGS (S.F.)
10+00	15+50	550	0.19	0.21	116	410	1	2	1				2				
15+50	21+00	550	0.14	0.21	234	210		3	3	140		58	3		2		
21+00	26+50	550	0.10	0.21			1		5			21					
26+50	32+00	550	0.20	0.22	52	140	1		1								
32+00	37+50	550	0.20	0.24	190	60		2	4	108		66	2				30
37+50	43+00	550	0.11	0.22		10	1		4			26					
43+00	48+50	550	0.10	0.21													
48+50	54+00	550	0.10	0.21					4			18					
54+00	59+50	550	0.06	0.15					1								
59+50	65+00	550	0.14	0.21		100			2								
65+00	70+50	550	0.21	0.01		40	1	6		5			6				30
70+50	76+00	550	0.21					6		4	300	25	6				
76+00	81+50	550	0.20	0.07		245		2		4	100		2				
81+50	87+00	550	0.15	0.07		58	1	2		4		1440	72	2	96		
87+00	92+50	550	0.10	0.01		65				4		2376	64		340		
92+50	98+00	550	0.10	0.01		26				6		1680	32		320		
98+00	103+50	550	0.09	0.01						5		2216	36		372		
103+50	103+68	18										360	12				
TOTALS TO GEN SUM		9368	2.40	2.27	592	1364	6	23	25	32	648	8072	430	23	1128	2	60

CALCULATED
MSM
CHECKED
JAG

SUBSUMMARIES

WAR-SR741-13.82