SHEET NUM.									PART.					ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
5	6	7	14	15	16	17	18		01/NHS/PV	02/STR/PV	03/NHS/PV	04/STR/BR	05/NFP/OT						
																		ROADWAY	
						1,000				1,000				202	38000	1,000	FT	GUARDRAIL REMOVED	
						7				7				202	42001	7	EACH	ANCHOR ASSEMBLY REMOVED, TYPE A, AS PER PLAN	5
						5				5				202	42040	5	EACH	ANCHOR ASSEMBLY REMOVED, TYPE T	
						8				8				202	47000	8	EACH	BRIDGE TERMINAL ASSEMBLY REMOVED	
						888				888				606	15100	888	FT	GUARDRAIL, TYPE MGS WITH LONG POSTS	
						7				7				606	26150	7	EACH	ANCHOR ASSEMBLY, MGS TYPE E, MASH 2016	
						6				6				606	26550	6	EACH	ANCHOR ASSEMBLY, MGS TYPE T, MGS	
						8				8				606	35141	8	EACH	BRIDGE TERMINAL ASSEMBLY, TYPE 4, AS PER PLAN	5
																		PAVEMENT	
			12.92						1.36	6.74	4.82			209	72050	12.92	MILE	PREPARING SUBGRADE FOR SHOULDER PAVING	10
950									25	300	625			253	02000	950	CY	PAVEMENT REPAIR, (A)	5
2,500										2,500				253	02000	2,500	CY	PAVEMENT REPAIR, (B)	5
	304												304	253	02000	304	CY	PAVEMENT REPAIR, (C)	6, 20
	200												200	253	02000	200	CY	PAVEMENT REPAIR, (D)	6,21
			109,168						12,663	55,503	41,002			254	01000	109,168	SY	PAVEMENT PLANING, ASPHALT CONCRETE, 2.5"	
			3,258							3,258				254	01000	3,258	SY	PAVEMENT PLANING, ASPHALT CONCRETE, 1.25"	
			1,275							1,275				254	01000	1,275	SY	PAVEMENT PLANING, ASPHALT CONCRETE, 0.75"	
			1,143						127	605	411			254	01600	1,143	SY	PATCHING PLANED SURFACE	
			17,440						1,900	9,005	6,150		385	407	20000	17,440	GAL	NON-TRACKING TACK COAT	
			18,700										18,700	423	00204	18,700	SY	CRACK SEALING, TYPE II	
			4,197						454	2,156	1,475		112	441	50000	4,197	CY	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448), PG64-22	
			5,432						616	2,698	1,993		125	441	50300	5,432	CY	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 2, (448)	
			403						41	203	146		13	617	10100	403	CY	COMPACTED AGGREGATE	
			8.05						0.82	4.07	2.91		0.25	617	25000	8.05	MGAL	WATER	
																		TRAFFIC CONTROL	
					579				66	273	240			621	00100	579	EACH	RPM	
					579				66	273	240			621	54000	579	EACH	RAISED PAVEMENT MARKER REMOVED	
						19				19				626	00110	19	EACH	BARRIER REFLECTOR, TYPE 2, BI-DIRECTIONAL	
12				96							12		96	630	03100	108	FT	GROUND MOUNTED SUPPORT, NO. 3 POST	
				18									18	630	80100	18	SF	SIGN, FLAT SHEET	
				2									2	630	84900	2	EACH	REMOVAL OF GROUND MOUNTED SIGN AND DISPOSAL	
2										2				630	85100	2	EACH	REMOVAL OF GROUND MOUNTED SIGN AND REERECTION	
1				1						1			1	630	86002	2	EACH	REMOVAL OF GROUND MOUNTED POST SUPPORT AND DISPOSAL	
				200									200	642	00700	200	FT	TRANSVERSE/DIAGONAL LINE, TYPE 1, 10"	
				64,724									64,724	642	01200	64,724	FT	PARKING LOT STALL MARKING, TYPE 1	
				6									6	642	01300	6	EACH	LANE ARROW, TYPE 1	
				8									8	642	01702	8	EACH	HANDICAP SYMBOL MARKING, TYPE 1	
				13.84					1.36	7.5	4.98			644	00104	13.84	MILE	EDGE LINE, 6"	
				7.02					0.78	3.75	2.49			644	00300	7.02	MILE	CENTER LINE	
				1,700					600		1,100			644	00400	1,700	FT	CHANNELIZING LINE, 8"	
				60						48	12			644	00500	60	FT	STOP LINE	
				290							290			644	00700	290	FT	TRANSVERSE/DIAGONAL LINE, 24"	
				130					70		60			644	00900	130	SF	ISLAND MARKING	
				17					5		12			644	01300	17	EACH	LANE ARROW	
																		STRUCTURE OVER 20 FOOT SPAN (CLI-73-0458)	
						180						180		517	75600	180	FT	DEEP BEAM BRIDGE RETROFIT RAILING	
							37.58					37.58		846	00110	37.58	CF	POLYMER MODIFIED ASPHALT EXPANSION JOINT SYSTEM	
																		STRUCTURE OVER 20 FOOT SPAN (CLI-73-0581)	
						160						160		517	75601	160	FT	DEEP BEAM BRIDGE RETROFIT RAILING, AS PER PLAN	18
							41.76					41.76		846	00110	41.76	CF	POLYMER MODIFIED ASPHALT EXPANSION JOINT SYSTEM	

CALCULATED JED
CHECKED JDO

GENERAL SUMMARY

WAR/ CLI-SR 73
-20.05/ 0.00

i:\Project Data\WAR\98568_WAR_CLI-73-20.05_0.00\Design\Roadway\Sheets\98568_GC001.dgn Sheet 3/2/2020 3:08:36 PM Jdavis4