

OFFICE CALCS	SHEET NUM.											PART.		ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
	5	8	13	14	15	16	17	30	38	39	45	01/ ENH/OT	02/ SK2/OT						
		200	105	15	65	25	14					424		304	20000	424	CY	PAVEMENT	
			44		16		2					62		407	13900	62	GAL	TACK COAT, 702.13	
			24		8		2					34		441	50000	34	CY	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448), PG64-22	
			42	99	108	135	33					417		452	12010	417	SY	8" NON-REINFORCED CONCRETE PAVEMENT, CLASS QC 1P	
			544		191		11					746		452	13060	746	SY	9.5" NON-REINFORCED CONCRETE PAVEMENT, CLASS QC 1P	
																		WATER WORK	
				1	1	1						3		638	10400	3	EACH	FIRE HYDRANT ADJUSTED TO GRADE	
				5	3	2	3	3				16		638	10800	16	EACH	VALVE BOX ADJUSTED TO GRADE	
				2		1						3		638	98000	3	EACH	WATER WORK, MISC.:WATER METER ADJUSTED TO GRADE	5
																		OTHER UTILITIES	
					1	2	2					5		SPECIAL	61199700	5	EACH	GAS VALVE BOX ADJUSTED TO GRADE	5
																		TRAFFIC CONTROL	
												224.5		630	03100	224.5	FT	GROUND MOUNTED SUPPORT, NO. 3 POST	
												50.25		630	80100	50.25	SF	SIGN, FLAT SHEET	
												2		630	80500	2	EACH	SIGN, DOUBLE FACED, STREET NAME	
												24		630	84900	24	EACH	REMOVAL OF GROUND MOUNTED SIGN AND DISPOSAL	
												5		630	85100	5	EACH	REMOVAL OF GROUND MOUNTED SIGN AND REERECTION	
												20		630	86002	20	EACH	REMOVAL OF GROUND MOUNTED POST SUPPORT AND DISPOSAL	
												5		630	86010	5	EACH	REMOVAL OF GROUND MOUNTED POST SUPPORT AND REERECTION	
												0.05		642	00204	0.05	MILE	LANE LINE, 6", TYPE 1, WHITE	
												0.34		642	00300	0.34	MILE	CENTER LINE, TYPE 1, DOUBLE SOLID	
												53		642	00400	53	FT	CHANNELIZING LINE, 8", TYPE 1 WHITE	
												14		642	00500	14	FT	STOP LINE, TYPE 1, 24" WHITE	
												152		642	00600	152	FT	CROSSWALK LINE, TYPE 1, 12" WHITE	
												20		642	01200	20	FT	PARKING LOT STALL MARKING, TYPE 1, 4" BLUE HANDICAP	
												572		642	01200	572	FT	PARKING LOT STALL MARKING, TYPE 1, 4" WHITE	
												3		642	01300	3	EACH	LANE ARROW, TYPE 1	
												2		642	01400	2	EACH	WORD ON PAVEMENT, 72", TYPE 1, WHITE	
												2		642	01702	2	EACH	HANDICAP SYMBOL MARKING, TYPE 1, BLUE	
																		MAINTENANCE OF TRAFFIC	
			0.67									0.67		614	21000	0.67	MILE	WORK ZONE CENTER LINE, CLASS I (DOUBLE SOLID)	
			0.69									0.69		614	22000	0.69	MILE	WORK ZONE EDGE LINE, CLASS I, 4" WHITE	
	9											9		614	40051	9	EACH	BUSINESS ENTRANCE SIGN, AS PER PLAN	5
																		LIGHTING	
												14		202	75800	14	EACH	DISCONNECT EXISTING CIRCUIT	
												90		625	00470	90	EACH	CONNECTION, UNFUSED BOLTED	
												47		625	10481	47	EACH	LIGHT POLE, DECORATIVE, AS PER PLAN	50
												47		625	14000	47	EACH	LIGHT POLE FOUNDATION, 24" X 6' DEEP	
												7,324		625	23304	7,324	FT	NO. 8 AWG 600 VOLT DISTRIBUTION CABLE	
												5,289		625	23306	5,289	FT	NO. 10 AWG 600 VOLT DISTRIBUTION CABLE	
												1,880		625	23400	1,880	FT	NO. 10 AWG POLE AND BRACKET CABLE	
												7,921		625	25104	7,921	FT	CONDUIT, 1", 725.051, FOR POWER	
												1,531		625	25408	1,531	FT	CONDUIT, 2", 725.051, FOR FIBER OPTIC	
												726		625	25408	726	FT	CONDUIT, 2", 725.051, FOR POWER/COMMUNICATIONS	
												726		625	25504	726	FT	CONDUIT, 3", 725.051, FOR POWER	
												440		625	25902	440	FT	CONDUIT, JACKED OR DRILLED, 725.04, 3"	
												100		625	25906	100	FT	CONDUIT, JACKED OR DRILLED, 725.051, 1"	
												160		625	25906	160	FT	CONDUIT, JACKED OR DRILLED, 725.051, 3"	
												47		625	27403	47	EACH	LUMINAIRE, POST TOP, SOLID STATE (LED), AS PER PLAN	50
												4,114		625	29002	4,114	FT	TRENCH, 24" DEEP	
												5		625	30510	5	EACH	PULL BOX, 725.06, SIZE 4	
												3		625	30530	3	EACH	PULL BOX, 725.06, SIZE 18	
												47		625	32000	47	EACH	GROUND ROD	
												1		625	34001	1	EACH	POWER SERVICE, AS PER PLAN	50
												4,607		625	36010	4,607	FT	UNDERGROUND WARNING/MARKING TAPE	
												8		625	75401	8	EACH	LIGHT POLE REMOVED, AS PER PLAN	50
																		INCIDENTALS	
												LS		614	11000	LS		MAINTAINING TRAFFIC	
												LS		623	10000	LS		CONSTRUCTION LAYOUT STAKES AND SURVEYING	
												LS		624	10000	LS		MOBILIZATION	

GENERAL SUMMARY

WAS - START WESTWARD
PHASE 1

DRAWING: \\woopjeninc.local\Vol_Sharea\Shreea\Shreea\DE\Dayon\Clients\OH_City_of_Morrista\080441 WAS Starting Westward\108981 WAS Starting Westward\080441 Discipline\Roadway\Sheets\080441_00001.dwg
April 12, 2022, 2:15pm

