

TRAFFIC CONTROL SUB-SUMMARY

STRAIGHT LINE MILES (SLM IS ROUNDED TO THE NEAREST 0.01 MILES)		DISTANCE (D)	ITEM 632	ITEM 642	ITEM 644								NOTES
			DETECTOR LOOP	CROSSWALK LINE, 12", TYPE 1	CHANNELIZING LINE 4"	CENTER LINE	STOP LINE	CROSSWALK LINE	PARKING LOT STALL MARKINGS	LANE ARROW	WORD ON PAVEMENT, 72"	HANDICAP SYMBOL MARKING	
BEGIN	END	FT	EACH	FT	FT	MILE	FT	FT	FT	EACH	EACH	EACH	
WAS-FRONT-0.33													
0.33	0.55	1162	2		50	0.22	28	216	513	1	1	2	
0.55	0.70	792		80		0.15		232					ITEM 642 FOR USE ON BRICK SURFACE
0.70	0.74	211				0.04							
0.74	0.77	158		51		0.03		161					ITEM 642 FOR USE ON BRICK SURFACE
0.77	0.81	211				0.04							
0.81	1.00	1003		137		0.19		291					ITEM 642 FOR USE ON BRICK SURFACE
TOTALS CARRIED TO GENERAL SUMMARY			2	268	50	.67	28	900	513	1	1	2	

NOTE: IF CONTRACTOR PLACES CLASS III TEMPORARY PAVEMENT MARKINGS ON FINISHED SURFACE, THERMOPLASTIC MARKINGS MUST BE PLACED WITHIN 30 DAYS OF PLACEMENT OF TYPE III MARKINGS

NOTE: ITEM 632 - DETECTOR LOOP SHALL BE PLACED AT A DEPTH OF 4" BELOW ROADWAY SURFACE

NO:	REVISION:	BY:	DATE:
1	INSERTED ITEM 642, CROSSWALK LINE, 12", TYPE I AND QUANTITY ADJUSTED ITEM 644, CROSSWALK LINE, 12"	DHJ	01/19/23
DGN:	DRN:	CHK:	
CITY OF MARIETTA ENGINEERING DEPARTMENT 304 PUTNAM ST., MARIETTA, OH 45750 PHONE (740) 373-5495 FAX (740) 376-2006			
WAS-FRONT-0.33 PAVEMENT MARKING SUB-SUMMARY			
SCALE:	NTS		
DATE:	9-29-22		
<div style="border: 1px solid black; border-radius: 50%; width: 40px; height: 40px; display: flex; align-items: center; justify-content: center; margin: 0 auto;"> 5 24 </div>			

SHEET NUM.											PART.											
2	3	4	5	6	8	9	10	11	12	13	01/S<2/PV	Item	Item Ext.	Grand Total	Unit	Description	See Sheet Number					
																ROADWAY						
					706	682	251	660	957	1148		4404	202	30001	4404	SF	WALK REMOVED, AS PER PLAN	3				
					103	73	30	59	73	91		429	202	32000	429	FT	CURB REMOVED					
					264	114	96	286	634	468		1862	608	10000	1862	SF	4" CONCRETE WALK	3				
					444	495	155	374	323	680		2471	608	52001	2471	SF	CURB RAMP, AS PER PLAN	3				
					103	73	30	59	73	91		429	609	26000	429	FT	CURB, TYPE 6					
																EROSION CONTROL						
					32	28	14	16	36	45		171	659	00500	171	SY	SEEDING AND MULCHING, CLASS 1					
																PAVEMENT						
					13198							13198	254	01000	13198	SY	PAVEMENT PLANING, ASPHALT CONCRETE, 1.5"	2				
					846							846	407	20000	846	GAL	NON-TRACKING TACK COAT	2				
					572					2		574	441	50200	574	CY	1.50" ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448) PG 64-22	2				
																WATER WORK						
	8											8	638	10800	8	EACH	VALVE BOX ADJUSTED TO GRADE	3				
																SANITARY SEWER						
	4											4	611	99654	4	EACH	MANHOLE ADJUSTED TO GRADE	3				
	4											4	611	99900	4	EACH	DRAINAGE STRUCTURE, MISC: LAMPHOLE ADJUSTED TO GRADE	3				
																TRAFFIC CONTROL						
			2									2	632	26500	2	EACH	DETECTOR LOOP	3				
			268									268	642	00620	268	FT	CROSSWALK LINE, 12", TYPE 1	3				
			0.67									0.67	644	00300	0.67	MILE	CENTER LINE	3				
			50									50	644	00400	50	FT	CHANNELIZING LINE, 8"	3				
			28									28	644	00500	28	FT	STOP LINE	3				
			900									900	644	00620	900	FT	CROSSWALK LINE, 12"	3				
			513									513	644	01200	513	FT	PARKING LOT STALL MARKINGS	3				
			1									1	644	01300	1	EACH	LANE ARROW	3				
			1									1	644	01400	1	EACH	WORD ON PAVEMENT, 72" "ONLY"	3				
			2									2	644	01600	2	EACH	HANDICAP SYMBOL MARKING	3				
																MAINTENANCE OF TRAFFIC						
			0.67									0.67	614	21550	0.67	MILE	WORK ZONE CENTER LINE, CLASS III, 642 PAINT	3				
			50									50	614	23680	50	FT	WORK ZONE CHANNELIZING LINE, CLASS III, 8", 642 PAINT	3				
																INCIDENTALS						
	1											1	614	11000	1	LUMP	MAINTAINING TRAFFIC	3				
	1											1	623	10001	1	LUMP	CONSTRUCTION LAYOUT STAKES, AS PER PLAN	3				
	1											1	624	10000	1	LUMP	MOBILIZATION					

DATE:	01/19/23
BY:	DHJ
REVISION:	
NO:	1
JRT:	DHJ
DGN:	
DRN:	
CHK:	

CITY OF MARIETTA
ENGINEERING DEPARTMENT
304 PUTNAM ST. MARIETTA, OH 45750
PHONE (740) 373-5495 FAX (740) 376-2006

WAS-FRONT-0.33
GENERAL SUMMARY