

S:\WAS\12888_WAS_SR60_19_94\Design\Roadway\Sheets\12888_G0002.dgn Sheet 1/7/2021 10:20:22 AM James.Hamilton

SHEET NUM.											PART.	ITEM	ITEM	GRAND	UNIT	DESCRIPTION	SEE SHEET NO.
											01/SAF/O T		EXT	TOTAL			
								3	8	18							
										5	5	632	64020	5	EACH	TRAFFIC SIGNALS PEDESTAL FOUNDATION	
										564	564	632	65200	564	FT	LOOP DETECTOR LEAD-IN CABLE	
										145	145	632	68200	145	FT	POWER CABLE, 2 CONDUCTOR, NO. 6 AWG	
										1	1	632	70001	1	EACH	POWER SERVICE, AS PER PLAN	16
										1	1	632	70400	1	EACH	CONDUIT RISER, 2" DIAMETER	
										1	1	632	72100	1	EACH	SIGNAL SUPPORT, TYPE TC-81.22, DESIGN 2	
										1	1	632	72110	1	EACH	SIGNAL SUPPORT, TYPE TC-81.22, DESIGN 4	
										1	1	632	71380	1	EACH	SIGNAL SUPPORT, TYPE TC-12.31 DESIGN 10 POLE, WITH MAST ARMS TC-81.22 DESIGN 14 AND DESIGN 2	
										1	1	632	89700	1	EACH	PEDESTAL, 11'	
								1	1	1	2	632	90101	2	EACH	REMOVAL OF TRAFFIC SIGNAL INSTALLATION, AS PER PLAN	16
								1			1	632	90400	1	EACH	SIGNALIZATION, MISC.:SIGNAL UNDER STUDY FOR REMOVAL	3
										1	1	633	65510	1	EACH	CABINET, TYPE TS-2	
										1	1	633	67100	1	EACH	CABINET FOUNDATION	
										1	1	633	67200	1	EACH	CONTROLLER WORK PAD	
										1	1	809	69122	1	EACH	ATC V6.24 CONTROLLER	
											LS	614	11000	LS		INCIDENTALS MAINTAINING TRAFFIC	
											50	614	11110	50	HOUR	LAW ENFORCEMENT OFFICER WITH PATROL CAR FOR ASSISTANCE	5
											LS	623	10000	LS		CONSTRUCTION LAYOUT STAKES AND SURVEYING	
											LS	624	10000	LS		MOBILIZATION	

GENERAL SUMMARY

WAS-60-19.94

P:\PR58705\WAS\12888\Design\Signals\Sheets\12888_CS001.dgn_Sheet 7/27/2021 5:59:18 PM totman

ITEM	EXTENSION	TOTAL	UNIT	DESCRIPTION	SEE SHEET
625	25408	176	FT	CONDUIT, 2", 725.051	
625	25504	12	FT	CONDUIT, 3", 725.051	
625	25906	187	FT	CONDUIT, JACKED OR DRILLED, 725.051, 3"	
625	29000	188	FT	TRENCH	
625	30701	2	EACH	PULL BOX, 725.08, 18", AS PER PLAN	17
625	30707	5	EACH	PULL BOX, 725.08, 24", AS PER PLAN	17
625	32000	8	EACH	GROUND ROD	
630	79500	4	EACH	SIGN SUPPORT ASSEMBLY, POLE MOUNTED	
630	80500	4	EACH	SIGN, DOUBLE FACED, STREET NAME	
632	05007	8	EACH	VEHICULAR SIGNAL HEAD, (LED), 3-SECTION, 12" LENS, 1-WAY, POLYCARBONATE, AS PER PLAN	17
632	20731	8	EACH	PEDESTRIAN SIGNAL HEAD (LED), TYPE D2, COUNTDOWN, AS PER PLAN	17
632	25000	8	EACH	COVERING OF VEHICULAR SIGNAL HEAD	17
632	25010	8	EACH	COVERING OF PEDESTRIAN SIGNAL HEAD	
632	26000	8	EACH	PEDESTRIAN PUSHBUTTON	
632	26500	5	EACH	DETECTOR LOOP	
632	27004	3	EACH	LOOP DETECTOR UNIT	
632	40500	994	FT	SIGNAL CABLE, 5 CONDUCTOR, NO. 14 AWG	
632	40700	697	FT	SIGNAL CABLE, 7 CONDUCTOR, NO. 14 AWG	
632	64010	3	EACH	SIGNAL SUPPORT FOUNDATION	17
632	64020	5	EACH	PEDESTAL FOUNDATION	
632	65200	564	FT	LOOP DETECTOR LEAD-IN CABLE	
632	68200	145	FT	POWER CABLE, 2 CONDUCTOR, NO. 6 AWG	
632	70001	1	EACH	POWER SERVICE, AS PER PLAN	16
632	70400	1	EACH	CONDUIT RISER, 2" DIAMETER	
632	72100	1	EACH	SIGNAL SUPPORT, TYPE TC-81.22 DESIGN 2	
632	72110	1	EACH	SIGNAL SUPPORT, TYPE TC-81.22 DESIGN 4	
632	72380	1	EACH	SIGNAL SUPPORT, TYPE TC-12.31 DESIGN 10 POLE, WITH MAST ARMS TC-81.22 DESIGN 14 AND DESIGN 2	
632	89700	5	EACH	PEDESTAL, 11'	
632	90100	1	EACH	REMOVAL OF TRAFFIC SIGNAL INSTALLATION	3 / 16
633	65510	1	EACH	CABINET, TYPE TS-2	
633	67100	1	EACH	CABINET FOUNDATION	
633	67200	1	EACH	CONTROLLER WORK PAD	
809	69122	1	EACH	ATC V6.24 CONTROLLER	

CALCULATED
BPT
CHECKED
EMW

TRAFFIC SIGNAL SUBSUMMARY

WAS-60-19.94