

WAS MARIETTA SRTS FY2026

MODEL: Sheet PAPER:SIZE: 34x22 (in.) DATE: 9/4/2025 TIME: 8:56:13 AM USER: shannon
P:\PR62197\120270\400-Engineering\Roadway\Sheets\120270_GG001.dgn

SHEET NUMBER													PART. 01/S5K/28	ITEM ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
4	5	6	7	10	11	12	13	24	15	16	18	19							
													LS	201	11000	LS		ROADWAY	
													LS	201	11000	LS		CLEARING AND GRUBBING	
				43									43	202	23000	43	SY	PAVEMENT REMOVED	
				1,161	759	495							2,415	202	30000	2,415	SF	WALK REMOVED	
				6	175								181	202	32000	181	FT	CURB REMOVED	
					85	72							157	202	32500	157	FT	CURB AND GUTTER REMOVED	
					2								2	202	98100	2	EACH	REMOVAL MISC.:GATE POST REMOVED	5
				2,538									2,538	202	98400	2,538	SF	REMOVAL MISC.:BRICK PAVERS REMOVED, SALVAGED, AND DELIVERED, AS PER PLAN	4
									22	6	4	3	35	203	10000	35	CY	EXCAVATION	
											16	10	26	203	20000	26	CY	EMBANKMENT	
													859	204	10000	859	SY	SUBGRADE COMPACTION	
				561	163	135							243	204	50000	243	SY	GEOTEXTILE FABRIC	
			440										440	607	98000	440	FT	FENCE, MISC.:ORANGE PLASTIC CONSTRUCTION FENCE	7
				1,943	234	670							2,847	608	10000	2,847	SF	4" CONCRETE WALK	
				24	409	211							644	608	52000	644	SF	CURB RAMP	
				12	60	23							95	608	53020	95	SF	DETECTABLE WARNING	
				2,184									2,184	608	98000	2,184	SF	WALKWAY, MISC.:BRICK PAVER WALK	4
						3							3	SPECIAL	69050560	3	EACH	BICYCLE RACK	4
																		EROSION CONTROL	
2													2	659	00100	2	EACH	SOIL ANALYSIS TEST	
143													143	659	00300	143	CY	TOPSOIL	
1,286													1,286	659	10000	1,286	SY	SEEDING AND MULCHING	
65													65	659	14000	65	SY	REPAIR SEEDING AND MULCHING	
65													65	659	15000	65	SY	INTER-SEEDING	
0.17													0.17	659	20000	0.17	TON	COMMERCIAL FERTILIZER	
0.27													0.27	659	31000	0.27	ACRE	LIME	
7													7	659	35000	7	MGAL	WATER	
3													3	659	40000	3	MSF	MOWING	
													5,000	832	30000	5,000	EACH	EROSION CONTROL	
																		DRAINAGE	
					205	72							277	605	06000	277	FT	4" BASE PIPE UNDERDRAINS	
																		PAVEMENT	
				2	65	26							93	253	01000	93	SY	PAVEMENT REPAIR	
				45									45	304	20000	45	CY	AGGREGATE BASE	
				49									49	452	10020	49	SY	6" NON-REINFORCED CONCRETE PAVEMENT, CLASS QC 1P WITH QC/QA	
						23							23	609	12001	23	FT	COMBINATION CURB AND GUTTER, TYPE 2, AS PER PLAN	4
					58								58	609	23001	58	FT	COMBINATION CURB AND GUTTER, TYPE 4, AS PER PLAN	4
					49								49	609	24510	49	FT	CURB, TYPE 4-C	
					29								29	609	26000	29	FT	CURB, TYPE 6	
				874									874	609	26001	874	FT	CURB, TYPE 6, AS PER PLAN	4
																		WATER WORK	
				4	1								5	638	10800	5	EACH	VALVE BOX ADJUSTED TO GRADE	
																		TRAFFIC CONTROL	
							60						60	630	02100	60	FT	GROUND MOUNTED SUPPORT, NO. 2 POST	
							4						4	630	08600	4	EACH	SIGN POST REFLECTOR	
							26						26	630	80100	26	SF	SIGN, FLAT SHEET	
							4						4	630	84900	4	EACH	REMOVAL OF GROUND MOUNTED SIGN AND DISPOSAL	
							4						4	630	85100	4	EACH	REMOVAL OF GROUND MOUNTED SIGN AND REERECTION	
								2					2	630	86002	2	EACH	REMOVAL OF GROUND MOUNTED POST SUPPORT AND DISPOSAL	
	2												2	630	97700	2	EACH	SIGNING, MISC.:SOLAR POWERED RECTANGULAR RAPID FLASHING BEACON (RRFB) SIGN ASSEMBLY	5
							220						220	644	00630	220	FT	CROSSWALK LINE, 24"	

GENERAL SUMMARY

DESIGN AGENCY



DESIGNER

JPS

REVIEWER

ALR 6/2/2025

PROJECT ID

120270

SHEET

8

TOTAL

25

WAS MARIETTA SRTS FY2026

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 9/4/2025 TIME: 8:56:16 AM USER: shannon
P.:PR62197120270\400-Engineering\Roadway\Sheets\120270_GS001.dgn

[illegible]

SIGNING AND PAVEMENT MARKING SUBSUMMARY

DESIGN AGENCY	
	
DESIGNER	
BL	
REVIEWER	
ALR 6/2/2025	
PROJECT ID	
120270	
SHEET	TOTAL
13	25