

I:\ProjectData\WIL-20A-0.20\Design\Roadway\Sheets\95998\G001.dgn Sheet 10/7/2020 7:36:44 AM afintel

SHEET NUM.					PART.			ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
3	4	6	7		01/BRO/BR	02/STR/PV	03/SAF/OT						
ROADWAY													
LUMP						LUMP		201	11000	LS		CLEARING AND GRUBBING	
		312				312		202	23000	312	SY	PAVEMENT REMOVED	
			1,125			1,125		202	38000	1,125	FT	GUARDRAIL REMOVED	
			3			3		202	42010	3	EACH	ANCHOR ASSEMBLY REMOVED, TYPE E	
			3			3		202	42040	3	EACH	ANCHOR ASSEMBLY REMOVED, TYPE T	
			4			4		202	47000	4	EACH	BRIDGE TERMINAL ASSEMBLY REMOVED	
			1,000			1,000		203	20000	1,000	CY	EMBANKMENT	
		312				312		204	10000	312	SY	SUBGRADE COMPACTION	
		2.07				2.07		209	60500	2.07	MILE	LINEAR GRADING	
2.1						2.1		209	72050	2.1	MILE	PREPARING SUBGRADE FOR SHOULDER PAVING	
			1,062.5			1,062.5		606	15050	1,062.5	FT	GUARDRAIL, TYPE MGS	
			3			3		606	26150	3	EACH	ANCHOR ASSEMBLY, MGS TYPE E, MASH 2016	
			3			3		606	26550	3	EACH	ANCHOR ASSEMBLY, MGS TYPE T	
			4			4		606	35002	4	EACH	MGS BRIDGE TERMINAL ASSEMBLY, TYPE 1	
EROSION CONTROL													
			250			250		601	20010	250	CY	CRUSHED AGGREGATE SLOPE PROTECTION	
						1,000		832	30000	1,000	EACH	EROSION CONTROL	
PAVEMENT													
277						277		253	02000	277	CY	PAVEMENT REPAIR	
		16,480				16,480		254	01001	16,480	SY	PAVEMENT PLANING, ASPHALT CONCRETE, AS PER PLAN, 3 1/4"	3
		70				70		301	46000	70	CY	ASPHALT CONCRETE BASE, PG64-22	
		52				52		304	20000	52	CY	AGGREGATE BASE	
		2,350				2,350		407	20000	2,350	GAL	NON-TRACKING TACK COAT	
46		698				744		442	10001	744	CY	ASPHALT CONCRETE SURFACE COURSE, 12.5 MM, TYPE A (446), AS PER PLAN, PG 76-22M	3
54		817				871		442	10101	871	CY	ASPHALT CONCRETE INTERMEDIATE COURSE, 19 MM, TYPE A (446), AS PER PLAN, PG 76-22M	3
		204				204		617	10100	204	CY	COMPACTED AGGREGATE	
		2.07				2.07		618	41000	2.07	MILE	RUMBLE STRIPES, EDGE LINE (ASPHALT CONCRETE)	
		1.01				1.01	1.01	618	43000	1.01	MILE	RUMBLE STRIPES, CENTER LINE (ASPHALT CONCRETE)	
		5,284				5,284		874	20000	5,284	FT	LONGITUDINAL JOINT PREPARATION	
TRAFFIC CONTROL													
			96			96		621	00100	96	EACH	RPM	
			92			92		621	54000	92	EACH	RAISED PAVEMENT MARKER REMOVED	
			25			25		626	00116	25	EACH	BARRIER REFLECTOR, TYPE 5, BIDIRECTIONAL	
			96			96		630	03100	96	FT	GROUND MOUNTED SUPPORT, NO. 3 POST	
			7			7		630	08600	7	EACH	SIGN POST REFLECTOR	
			9			9		630	85100	9	EACH	REMOVAL OF GROUND MOUNTED SIGN AND REERECTION	
			8			8		630	86002	8	EACH	REMOVAL OF GROUND MOUNTED POST SUPPORT AND DISPOSAL	
			2.18			2.18		642	00104	2.18	MILE	EDGE LINE, 6", TYPE 1	
			2.14			2.14		642	00300	2.14	MILE	CENTER LINE, TYPE 1	
STRUCTURE REPAIRS													
FOR WIL-20A-0020 ESTIMATED QUANTITIES SEE SHEET NO. 14													
MAINTENANCE OF TRAFFIC													
	12					12		614	12460	12	EACH	WORK ZONE MARKING SIGN	
	5					5		614	12500	5	EACH	REPLACEMENT SIGN	
	5					5		614	12600	5	EACH	REPLACEMENT DRUM	
	3					3		614	21550	3	MILE	WORK ZONE CENTER LINE, CLASS III, 642 PAINT	
INCIDENTALS													
	LUMP					LUMP		614	11000	LS		MAINTAINING TRAFFIC	
	LUMP					LUMP		624	10000	LS		MOBILIZATION	
	LUMP					LUMP		623	10000	LS		CONSTRUCTION LAYOUT STAKES AND SURVEYING	

GENERAL SUMMARY

WIL - 20A - 0.00