



LOCATION MAP

LATITUDE: N 41°19'36" LONGITUDE: W 83°39'01"

HORIZONTAL SCALE IN MILES



PORTION TO BE IMPROVED	_____
INTERSTATE HIGHWAY	_____
FEDERAL ROUTES	_____
STATE ROUTES	_____
COUNTY & TOWNSHIP ROADS	_____
OTHER ROADS	_____

DESIGN DESIGNATION

CURRENT ADT (2026-)	5100
DESIGN YEAR ADT (2038-)	5600
DESIGN HOURLY VOLUME	700
DIRECTIONAL DISTRIBUTION	61%
TRUCKS (24 HOUR B&C)	11%
DESIGN SPEED	55 MPH
LEGAL SPEED	50 MPH
DESIGN FUNCTIONAL CLASSIFICATION:	URBAN MAJOR COLLECTOR
NHS PROJECT	NO

DESIGN EXCEPTIONS

NONE REQUIRED

ADA DESIGN WAIVERS

NONE REQUIRED

UNDERGROUND UTILITIES
 Contact Two Working Days
 Before You Dig

OHIO811.org
 Before You Dig

OHIO811, 8-1-1, or 1-800-362-2764
 (Non members must be called directly)

PLAN PREPARED BY:

KLEINFELDER
 1168 N. MAIN STREET
 Bowling Green, OH 43402
 419.352.7537

ENGINEER'S SEAL:

STATE OF OHIO
 DENNIS P. FITZGERALD
 E-70274
 REGISTERED PROFESSIONAL ENGINEER

SIGNED: *Dennis Fitzgerald*
 DATE: 2/19/26

STATE OF OHIO

DEPARTMENT OF TRANSPORTATION

WOO - SR25 - 6.64

FINDLAY PIKE ROADWAY IMPROVEMENTS

VILLAGE OF PORTAGE WOOD COUNTY, OHIO

INDEX OF SHEETS:

TITLE SHEET	1
SCHEMATIC PLAN	2-4
TYPICAL SECTIONS	5
GENERAL NOTES	6 - 7
MAINTENANCE OF TRAFFIC	8 - 28
GENERAL SUMMARY	29-30
SUBSUMMARIES	31-34
PLAN AND PROFILE	35 - 41
CROSS SECTIONS	42- 79
INTERSECTION DETAILS	80
DRIVEWAY DETAILS	81
TRAFFIC CONTROL PLANS	82- 88
ADA RAMP DETAILS	89 - 91
UTILITY DETAILS	92

STANDARD CONSTRUCTION DRAWINGS						SUPPLEMENTAL SPECIFICATIONS	SPECIAL PROVISIONS
BP-2.5	7/19/24	RM-1.1	1/20/23	TC-22.20	7/18/25	800-2023	7/18/25
BP-3.1	1/19/24	RM-2.1	7/19/13	TC-41.20	10/18/13	821	4/20/12
				TC-41.30	4/21/23	832	7/18/25
BP-5.1	7/18/25	MT-95.31	7/18/25	TC-41.40	10/18/13	874	4/17/20
BP-7.1	7/18/25	MT-95.32	7/18/25	TC-41.50	10/18/13	875	1/17/25
		MT-97.10	7/18/25			921	7/19/24
CB-2-2A, 2B, 2C	7/19/24	MT-97.12	7/18/25	TC-42.20	10/18/13	987	1/16/09
CB-3A	7/19/24	MT-99.20	4/19/19	TC-52.10	10/18/13		
					7/21/23		
DM-1.2	1/2/25	MT-101.60	1/17/25	TC-65.10	1/17/14		
		MT-101.90	7/17/20	TC-65.11	1/17/25		
MH-3	7/19/24	MT-102.20	4/19/19				
		MT-105.10	1/17/20	TC-71.10	7/18/25		
		MT-110.10	7/19/13	TC-74.10	7/21/23		

FEDERAL PROJECT NUMBER

E230262

RAILROAD INVOLVEMENT

NONE

PROJECT DESCRIPTION

PROJECT TO IMPROVE 0.48 MILES OF SR-25 IN THE VILLAGE OF PORTAGE INCLUDING RESURFACING, SPOT REPAIRS, NEW CURBS WITH ASSOCIATED DRAINAGE IMPROVEMENTS, NEW SIDEWALKS, AND INSTALLATION OF TRAFFIC CONTROL PER PLAN.

EARTH DISTURBED AREAS

PROJECT EARTH DISTURBED AREA:	0.77 ACRES
ESTIMATED CONTRACTOR EARTH DISTURBED AREA:	0.00 ACRES
NOTICE OF INTENT EARTH DISTURBED AREA:	N/A

2023 SPECIFICATIONS

THE STANDARD SPECIFICATIONS OF THE STATE OF OHIO, DEPARTMENT OF TRANSPORTATION, INCLUDING SUPPLEMENTAL SPECIFICATIONS LISTED IN THE PLANS, CHANGES LISTED IN THE PROPOSAL, AND THE SUPPLEMENTAL SPECIFICATIONS LISTED IN THE PLANS AND CHANGES LISTED IN THE PROPOSAL SHALL GOVERN THIS IMPROVEMENT.

I HEREBY APPROVE THESE PLANS AND DECLARE THAT THE MAKING OF THIS IMPROVEMENT WILL NOT REQUIRE THE CLOSING TO TRAFFIC OF THE HIGHWAY AND THAT PROVISIONS FOR THE MAINTENANCE AND SAFETY OF TRAFFIC WILL BE AS SET FORTH ON THE PLANS AND ESTIMATES.

Pat McColley, PE
 Pat McColley, P.E., S.I.
 District 02 Deputy Director

Pamela Boratyn
 Pamela Boratyn
 Director, Department of Transportation

DESIGN AGENCY	KLEINFELDER
DESIGNER	DS/GC
REVIEWER	BCS
PROJECT ID	10/28/25
SHEET	117658
TOTAL	1 92