

PID# 123996 State Job # 511452
Scope of Services Meeting Date & Time: 11/12/2026
Approved Final Scope of Services Date: _____
Location District 11, New Philadelphia

CONSULTANT BRIDGE INSPECTION

Scope of Services

1. Bridge Identification

County: **See Attached List Route: ** Section: ** District: **
SFN: ** Municipality: **
Street Name or Other Designation: **
Features Under the Bridge: **

2. Attendance (See Attached Sheet)

Consultant: TBD
Consultant Contracting Officer: TBD
Consultant Project Manager: TBD
ODOT Project Manager: Raymond Trivoli, P.E.

3. Project Description

Number of Lanes: _____ Year Built: _____ ADT: _____
Bridge Type: _____ Type of Service: _____
Overall Length: _____ Maintenance Responsibility: _____ Inspection Resp: _____

4. Available Plans and Inspection Reports:

	Yes	No
Original Construction Plans*		
As-Built Plans*		
Shop Drawings*		
Repair or Rehabilitation Plans*		
Inspection Reports		
Inventory Reports		
Physical Condition Reports		
Structural Analysis*		
Underwater Inspection Reports		
Maintenance Manual		
Fracture Critical Inspection Procedure		
Underwater Dive Inspection Procedure		
Complex Bridge Inspection Procedure		
Access to AssetWise**		

* Access to files is available on the following website: TBD
Contact Raymond Trivoli, P.E. for follow-up questions.

** Access to AssetWise may be made available at the discretion of ODOT. User change requests are available online at the AssetWise landing page: [AssetWise | Ohio Department of Transportation](#).

5. Inspection Intent:

Activity	TBD		
In-depth Element Level Inspection	X		
In-depth Inspection	X		
Routine Element Level Inspection	X		
Routine Inspection	X		
Update Bridge Inventory (both Ohio Bridge Inventory and SNBI)	X		
Scour Critical Evaluation	X		
Fracture Critical Inspection	X		
Fracture Critical Inspection Procedure (checklist)	X		
Underwater Inspection	X		
Underwater Dive Inspection Procedure (checklist)	X		
Immediate Action Recommendations	X		
Maintenance Recommendations & Repairs			
Structural Measurements where plans are not available	X		
Benchmarking/Surveying			
Structural Measurements where plans are not available	X		
Mentoring of ODOT Staff on Limited Onsite Inspections	X		

Inspection Intent Requirement Details for Inspection

- Examples
 - Components receiving a visual inspection include:
 - Components receiving a hands-on inspection include:
 - Inspection includes viewing as much as possible from _____ (ex. snooper or man lifts)
 - Inspection includes sounding, inspection and monitoring of wearing surface spalls and/or deterioration (consideration shall be given to TTC).
 - Side Scan Sonar shall be used for each bridge to obtain the necessary topography of the river bottom within 50 feet from upstream and downstream of the structure and accumulated debris collecting on the piers.

Inspection Intent Requirement Details for Inspection

Inspection Intent Requirement Details for Inspection

6. STRUCTURAL ANALYSIS:

Activity (ex. Gusset Plate, Cap-Pile-Pier Analysis)	Year			

Special Notes:

7. Inspection Services

Item	Description
Target Date(s) for Inspection:	Ex. January - December (Verify the month the Routine, Dive or Fracture Critical Inspection is due)
Traffic Control by	Consultant
Lane Closure Requirements	Per Standard Construction Drawings
Restrictions to Lane Closure	Note the Department's Permitted Lane Closure (PLC)
Property Owners Involved	TBD
Right of Entry by	TBD
RR Flaggers	As needed
Other (ex. Coast Guard)	
Special Equipment Anticipated for Access to remote areas - Snooper Rental - Rope Climbing - Bucket Truck - Ladder - Boat - Man Lift	As Needed
Other	

8. Consultant Bridge Inspection Requirements

1. The intent of this contract is for a Professional Engineer (Consultant) to make an in-depth (unless routine, Element Level, and/or fracture critical is specified) condition inspection of the noted bridge(s) and to report such findings in a formal report. The Consultant will complete the inspection in accordance with the latest Ohio Department of Transportation (ODOT) Manual of Bridge Inspection including more recent Addendums and FHWA's Bridge Inspector's Reference Manual (FHWA). Note when the previous inspection report contains Element Level data then an Element Level inspection shall be performed and values updated.
2. The State of Ohio may delete or postpone the inspection of a bridge from the contract up until the time that the physical inspection begins.
3. The Consultant shall be responsible to provide all necessary traffic control, including traffic control plans (unless otherwise specified), personnel, equipment, tools, and incidentals including ladders and scaffolding to access to all portions of the site. (The Consultant is only required to provide traffic control plans as necessary to obtain a permit. These bridges are inspected every year, and existing traffic control plans from prior years' permits are available and are allowed to be resubmitted for the permit for this inspection.)
4. All subconsultants used in the inspection shall be named in the proposal so that they can be approved as a sub-consultant at the time of the agreement.
5. The Consultant will not be responsible for structural conditions which occur after the date of the last site visit, providing the condition was not visibly evident at the time of the last visit and the Consultant used usual and customary procedures to inspect the bridge.
6. Any steel structure with lower lateral bracing, pins and hangers, fatigue prone connections, steel pier caps (either of box section or I section), bridges with transverse floor beams and stringers, or any other unusual connection details, shall be carefully inspected for cracks, poorly designed details, or poorly fabricated details. A recommendation shall be made, if necessary, whether a retrofit program or corrective modification should be taken with a description of the proposed solution, and if any traffic limitations should be initiated. Adequate access shall be provided so that all such details can be visually inspected within arm's reach (even for routine inspections).
7. Any observed section loss on members which are normally analyzed to determine safe load capacity of the bridge, shall be measured and documented quantitatively (ultrasonic thickness gauge, calipers etc.) to allow for subsequent re-analysis of the structure. Analysis of the structure will not be required of the Consultant unless specifically stated in the S.O.S. minutes.
8. The Consultant will not be responsible for conditions which are not obvious through usual and customary visual inspection or through standard state-of-the-art testing. The Consultant will not be responsible for identifying and evaluating portions of the bridge which comprise of poor quality materials and/or inadequate structural design unless obviously visible to a trained and experienced bridge inspector/engineer performing the inspection services in accordance with the customary standards of the profession.
9. Underwater inspection, requiring the use of divers, shall not be required unless specifically stated in the S.O.S. minutes. The Consultant will be required to probe around all substructure units located in water, unless the stream velocity or depth is such that probing is not feasible. All such findings shall be reported. The consultant will be required to complete or revise the Underwater Dive Inspection Procedure Checklist on file such that all UW inspection elements are identified, the inspection frequency is identified, inspection procedures are identified and all underwater elements are inspected according to those procedures.
10. If a Fracture Critical Inspection is specified, the Consultant must perform a hands-on inspection of all FCM's on both sides of the steel member. This inspection cannot be replaced with a drone.
11. In Depth Inspection

- a. If an in-depth inspection is specified, the Consultant will be required to visually inspect all main structural members of the bridge within an arm's reach distance. On welded girder type bridges, this will require access to both sides of each girder so that all fatigue prone connections can be inspected within arm's reach. Any cracks discovered and or suspected as a result of this hands-on visual inspection shall be documented and shall be further defined with the use of dye penetrant, magnetic particle or ultrasonic devices.
- b. If an in-depth inspection is being performed, all unsound concrete shall be delineated by sounding unless stated otherwise. All unsound areas shall be measured and reported in square feet of surface area. Coring or other means of testing shall not be done unless specifically stated in the S.O.S. meeting.

12. Destructive Testing

- a. Any additional destructive testing, other than that previously mentioned, shall not be done unless specifically stated in the S.O.S. meeting.
- b. Where, in the judgment of the Consultant, it is necessary to remove some portion of the structure to achieve complete and adequate inspection, no action shall be taken without prior approval of the District Bridge Engineer.

13. Gusset Plate Inspection, measurements, and data presentation-

- a. The consultant's inspection report shall include a schematic elevation view for each bridge showing all truss elements and gusset plates. This can be derived from original plans. On the schematic elevation the "as designed" and "as measured" net cross sectional area shall be displayed.
- b. Where there has been no observed section loss, one measurement for each element component or gusset plate shall suffice to verify "as-built" dimensions. Where corrosion has reduced the section of an element or gusset plate, measurements shall be taken at the areas of the least cross-sectional area. Photos and measurements using ultrasonic thickness gauge shall be provided for each area measured.
- c. For the case of gusset plates with corroded areas, measurements shall be taken across a vertical, horizontal, and block shear plane for all possible failure planes that have loss of section. A minimum of 10 spot measurements shall be taken across each plane. Each measurement location shall be marked with a black "X" permanent marker/paint stick on the member and a photo taken of that gusset plate with the marks. The measurement locations shall be spaced such that at least 6 measurements are taken in the corroded areas.
- d. The report shall include a photo and an elevation of any corroded gusset. The elevation shall include an outline of the corroded area, the location of each measurement, and the value of each measurement (either on the elevation or in a table).
- e. The inspection team shall examine each gusset plate from the side or profile. If it appears any gusset plates or member are "out of plane", measurements shall be taken using a 4' straight edge to quantify the severity of "out of plane".
- f. UT Equipment: Consultant shall use a UT gauge to acquire section properties. The Department may supply ultrasonic thickness gauge equipment and data collection software for use by the consultant to collect, download and process thickness data as specified by the Department.

14. Report Deliverables:

- a. The Consultant shall be responsible for identifying and noting all visible defects in the bridge whether as a result of deterioration, original construction or original design. The Consultant shall also be responsible for identifying and noting areas of potential failure as a result of anticipated deterioration, past construction or maintenance practice and/or inadequate original design. AssetWise is the Departments preferred method for

consultants to directly update inspection and inventory data. This however is at the discretion of each ODOT project manager and consultants may instead provide a written PDF report for ODOT to enter inspection dates and data. Specific report structure, drawings and inspection findings must be discussed and agreed upon during the SOS meeting.

b. AssetWise

- i. When ASSETWISE Access is required the consultant must obtain usernames, passwords, bridge-access for all team leaders. All data, commentary and files relevant to the bridge(s) inspected must be input in accordance with the Manual of Bridge Inspection including more recent Addendums. AssetWise Access requests are made through the AssetWise Landing Page: [AssetWise | Ohio Department of Transportation](#)
- ii. The consultant shall incorporate the photographs within the report (not at the Asset Level) assigned within the bridge sub-units (ex. Deck Photos, Superstructure Photos). All photographs shall be dated and labeled to indicate the precise day, location and view in which they were taken.
- iii. The ODOT Bridge Inspection Report shall be filled out for each bridge inspected in ODOT's AssetWise unless specified otherwise. Photos, notes and sketches shall be updated on elements within the scope of the inspection and added to ASSETWISE. The notes and numbers in all other sections of the inspection filled out in the previous schedule inspection not within the scope of the consultant's inspection shall not be deleted and shall remain unchanged unless specifically permitted by the District Bridge Engineer on a case-by-case basis. Final report approval shall be made by the Consultant P.E. The District Bridge Engineer must be permitted time to review any changes prior to final approval. The report shall be in accordance with the Manual of Bridge Inspection (ODOT). The consultant shall insert inspection data, photographs, maintenance recommendations and condition narrative into ASSETWISE for the District Bridge Engineer to review prior to final approval.
- iv. The consultant shall notify the District Bridge Engineer, as soon as practical after the physical field inspection of the structure is complete. The Consultant shall approve the final report in ASSETWISE after the District Bridge Engineer has reviewed any changes. The approval shall occur whichever happens first:
 1. within 90 days of the field inspection or
 2. February 14th the following year.

15. Notification:

- a. The Consultant shall notify the District Bridge Engineer at least two weeks in advance of the start of the actual inspection to allow scheduling of the required traffic control operations at the periods mutually agreed upon by the Consultant and the District; to inform the local authorities involved of the dates of the inspection; and to obtain any necessary right of entry for the Consultant. In some cases, as noted in the special provisions, the Consultant may be required to provide traffic control, notify involved local authorities, and obtain necessary right of entry. In all cases, the consultant must notify the District Bridge Department when the Consultant intends to begin the inspection, **each day** the Consultant is on the job, and when the Consultant is finished.
- b. The Consultant shall notify the District Bridge Engineer of any and all serious deficiencies immediately upon disclosure, in order that they may be observed by the Department from available scaffolding or access equipment. A phone call with followup email with photographs is preferred. A communication plan should be discussed during the SOS. After completion of the inspection, the Consultant's Professional Engineer must review

areas of special concern with field personnel and District Bridge personnel at the site. Serious deficiencies include but are not limited to loose concrete over traffic, reduction in safe load capacity, advanced scour or undermining and rapid changes in expected condition.

- c. The consultant will inform the District Bridge Engineer of the work location, number of personnel, any lane closures, the type of equipment, start time and finish times, as well as the number of anticipated working hours the consultant will have at the site that day.
 - d. The consultant will update the Department as to any changes from the previous days call if the consultant left early or stayed later than originally intended.
 - e. At the completion of physical inspection, the consultant shall provide a spread sheet with all the above information for each day out at the bridge. (The consultant will be given a number to call to leave a message with the information prior to the first day of inspection). This information will be used to keep local law enforcement apprised of who is out at the bridge, and to help us estimate inspection costs for future inspection contract. (It will not affect the cost of the agreed to lump sum payment for this contract)
16. At the completion of the physical inspection, the consultant shall provide a spread sheet with a log of the work location, number of personnel, and any lane closures, and type of equipment used each day.
17. All invoices for inspection services shall be submitted to the District Contract Manager for processing.

The State and Consultant agree that the Work to be performed for the bridge inspection, including the field work for each specific bridge included in the Agreement, shall commence and be completed within the same calendar year (March 1 to December 1). It is not the intent of the State to require the Consultant to perform field work for the bridge inspection during the months of December, January, and February. However, if unusual circumstances arise, the Consultant agree to perform the required field work during this period upon verbal authorization by the District Bridge Engineer, for a bridge inspection which has been previously authorized by the Director.

The State and the Consultant agree that inclement weather conditions will not be cause for an adjustment to the completion time established in the Agreement.

9. Physical Condition Report

A formal report describing the physical condition of the bridge, using photographs, sketches and drawings and including, evaluations, and recommendations is required. The report shall follow the ODOT Manual of Bridge Inspection including more recent addendums. Consultants should update existing deficiency maps and CADD drawings unless previous drawings cannot be made available.

Items	#### *	#### *
Field Report with Element Level Data		
Field Report		
Construction and Maintenance History		
Specialized Inspection Procedures (required for complex, underwater dive and fracture critical bridge inspections)		
Plan view of bridge with mapped out deficiencies		
Updated deficiency map		
Damage and/or Deterioration Evaluation (Include narratives describing the physical conditions, digital photographs, drawings, tables, etc.)		
Updated damage and/or deterioration evaluation		
Maintenance/Rehabilitation Recommendations (Include a maintenance schedule and any rehabilitation recommendations)		
Updated recommendations		
Testing Report(s) if authorized		

Subreports:

Underwater		
Mechanical, Electrical		
Scour/Hydraulic/Stream Evaluation (cross channel profile etc.)		
Structural Analysis		
Pin/Hanger/Hinges Detailed Inspection		
Other		

* Ratings, values, narrative and information shall be typed directly into ASSETWISE unless stated otherwise in SOS meeting. Indicate if AssetWise input will be performed by consultant or ODOT.

10. Final Report

Three hard bound copies and a PDF copy of the long PDF report should be submitted at the discretion of the District Bridge Engineer.

Number of Reports TBD, Delivered to Raymond Trivoli, P.E.

11. Completion Time

The consultant shall complete each year's inspection, including submitting the final report, within _____ (ex. Six) months from the date of authorization to proceed. The following dates are targets for report submittals:

A completed Inspection Form (not the entire report) is due in ASSETWISE by _____.

Draft due date for the entire report is due in ASSETWISE by _____.

The Formal report is due by _____ (not to exceed 90 days from the field report or February 28th of the following year).

A report shall not be considered complete until approved by the District Bridge Engineer.

12. Type of Agreement

- Lump sum compensations
- Actual costs plus fixed fee for testing items.
- Snooper or equipment Rental is if authorized.
- Traffic Control is included in lump sum fee.

13. Price Proposal

The consultant's price proposal shall conform to the current Requirements for Consultant Proposals found on Consultant Services website :

<http://www.dot.state.oh.us/Divisions/Engineering/Consultant/Pages/Manuals-and-Contract-Documents-.aspx>

14. Remarks / Special Instructions (Permits, Walkthroughs, etc.)

Coordination with ODOT CO Snooper if available and on the schedule by December 15 for the following year.

15. Information Handouts Required by Consultant and Available within ODOT

It is the consultant's responsibility to obtain the information handouts necessary to complete their file. This is not an inclusive listing.

- 1) Audit Requirements, Definitions and Guidelines.
- 2) Office of Accounting and Auditing Supplemental Information for Consulting Engineering Firms.
- 3) Ohio Manual of Uniform Traffic Control Devices.
- 4) Guidelines for Proposals for Consulting Services.
- 5) ODOT DBE/EDGE Requirements for Consultant Agreements.

16. Reference Materials Required by Consultant

It is the consultant's responsibility to obtain the bridge inspection manuals necessary to complete their file. This is not an exhaustive listing.

- National Bridge Inspection Program Metrics
 - ODOT Manual of Bridge Inspection and Inventory (2025 or newest edition)
 - Hydraulic Engineering Circular No. 18 "Evaluating Scour At Bridges" Fourth Edition Publication No. FHWA NHI 01-001, Date April 2012
 - Hydraulic Engineering Circular No. 20 "Stream Stability at Highway Structures"
 - Underwater Bridge Inspection, FHWA NHI 10-027, 2010
 - The Manual for Bridge Evaluation, 2011, with 2016 Revisions, AASHTO Publication
 - Bridge Inspector's Reference Manual, FHWA NHI 12-049, 2012
 - ODOT AssetWise Coding Guide
 - Other (ex. Bridge-Specific Maintenance Manual or Inspection Procedure):
 - FHWA Specifications for the National Bridge Inventory
-

Scope of Services Meeting Attendance

Date: _____, Location: _____

	Name	Representing	Email	Phone
1)				
2)				
3)				
4)				
5)				
6)				
7)				
8)				
9)				
10)				
11)				
12)				
13)				
14)				
15)				
16)				
17)				
18)				
19)				
20)				
21)				
22)				
24)				

SFN	Assetwise Asset Name Text	Featured Intersection	Assigned to:	Extra PPE	Confined Space	Dive	Notes	Month Due	Interval
0700096	BEL-00007-0109_(0700096)	NS RR. (SUBWAY)	Selected Consultant				CURSORY	06	12
0700185	BEL-00007-0622_(0700185)	LOCKWOOD RUN	Selected Consultant					03	12
0700215	BEL-00007-1149C_(0700215)	RAMP C OVER WEGEE CR	Selected Consultant					07	12
7904592	TJUS-00250-0114_(7904592)	BEACH CITY RESERVOIR	Selected Consultant			On Schd'l	Anticipate Inspection Cycle Moving to Fall	01	12
0700290	BEL-00007-1154A_(0700290)	RAMP A OVER WEGEE CR	Selected Consultant					07	12
0700320	BEL-00007-1449_(0700320)	PINCH RUN	Selected Consultant	Sewage	C		Routines every 6 months	04	12
0700339	BEL-00007-1279_(0700339)	NORFOLK SOUTHERN CORP.	Selected Consultant					07	12
0700347	BEL-00007-1553_(0700347)	SR 149 (26 ST.)	Selected Consultant					07	12
0700371	BEL-00149-0005L_(0700371)	MCMAHON CR	Selected Consultant			On Schd'l		05	24
0700460	BEL-00149-0005R_(0700460)	MCMAHON CREEK	Selected Consultant			On Schd'l		05	24
0700479	BEL-00007-1817L_(0700479)	SB 7 OVER RAMPS A AND B	Selected Consultant					07	12
0700487	BEL-00007-1830_(0700487)	WHISKEY RUN / ALONG 470	Selected Consultant		C		Move to May	06	24
0700541	BEL-00007-1975_(0700541)	US 250, RAMP, WHEELING CRE	Selected Consultant					03	12
0700223	BEL-00007-1152_(0700223)	WEGEE CR AND CR 7	Selected Consultant				Anticipate insp cycle moving to fall	02	24
0700592	BEL-00007-1629R_(0700592)	INDIAN RUN, CSX RR, ACCES	Selected Consultant				Use Bucket Truck for Seated Hinge	03	24
0700665	BEL-00007-2230_(0700665)	CENTER ST	Selected Consultant					03	12
0701181	BEL-00009-1861_(0701181)	POGUE RUN	Selected Consultant				CURSORY	03	24
0701211	BEL-00009-1950_(0701211)	WHEELING CREEK	Selected Consultant				Include Pile Section Loss Measurements & Calcs	04	12
0701246	BEL-00009-1976_(0701246)	MCCRACKEN RUN	Selected Consultant					05	12
0701300	BEL-00026-0354_(0701300)	SOUTH FORK CAPTINA CREEK	Selected Consultant					03	12
0701335	BEL-00026-0721_(0701335)	N FORK CAPTINA CREEK	Selected Consultant					03	24
0701564	BEL-00040-1713_(0701564)	IR 70	Selected Consultant					05	12
0701572	BEL-00040-1821_(0701572)	ST. CLAIR BIKEWAY(TUNNEL)	Selected Consultant					05	12
0701637	BEL-00040-2437_(0701637)	BRANCH OF WHEELING CREEK	Selected Consultant					05	12
0701750	BEL-00040-2641_(0701750)	BR WHEELING CR	Selected Consultant	C				05	12
0701785	BEL-00040-2716_(0701785)	SLAUGHTERHOUSE RUN	Selected Consultant	C				05	24
0701920	BEL-00070-0442L_(0701920)	SPENCER CR & CO RD 102	Selected Consultant					04	24
0701955	BEL-00070-0442R_(0701955)	SPENCER CR & CO RD 102	Selected Consultant					05	24
0702104	BEL-00070-1992_(0702104)	AULTS RUN	Selected Consultant		C		Routines every 6 months	05	24
0702137	BEL-00070-0775L_(0702137)	TWP RD 260 UNDER IR 70	Selected Consultant					07	12
0702161	BEL-00070-0775R_(0702161)	TWP RD 260 UNDER IR 70	Selected Consultant					05	24
0702595	BEL-00070-1783_(0702595)	ST. CLAIR BIKEWAY OLD RR	Selected Consultant					05	24
0702625	BEL-00070-1784_(0702625)	Chambers Run	Selected Consultant					05	24
0702668	BEL-00070-1817_(0702668)	SR 9	Selected Consultant					05	24
0702677	BEL-00070-1931_(0702677)	OVER IR-70	Selected Consultant					05	24
0702706	BEL-00070-1843_(0702706)	IR 70	Selected Consultant					05	24
0702722	BEL-00070-2000_(0702722)	CR 28A, MALL ROAD	Selected Consultant					05	24
0702730	BEL-00070-2037_(0702730)	IR 70	Selected Consultant					05	12
0702889	BEL-00070-2134N_(0702889)	IR 470 (WB LANES ONLY)	Selected Consultant					05	24
0702943	BEL-00070-2576_(0702943)	WHEELING CRIABND RR	Selected Consultant			Dive in 27		06	12
0703060	BEL-00070-2663D_(0703060)	MARION ST COMPLEX-RAMP D	Selected Consultant					06	24
0703095	BEL-00070-2684_(0703095)	SR7&767,RR WHLG.CR,OH R.	Selected Consultant					06	24
0703222	BEL-00147-0165_(0703222)	LEATHER WOOD CR	Selected Consultant					07	12
0703257	BEL-00147-0208_(0703257)	BR LEATHERWOOD CREEK	Selected Consultant					07	12

SFN	Assetwise Asset Name Text	Featured Intersection	Assigned to:	Extra PPE	Confined Space	Dive	Notes	Month Due	Interval
0703281	BEL-00147-0270_(0703281)	BR LEATHERWOOD CREEK	Selected Consultant					07	12
0703400	BEL-00147-0506_(0703400)	MUNIC. WALK(EX-RR TUNNEL)	Selected Consultant					07	12
0703478	BEL-00147-3303_(0703478)	BROOKS RUN	Selected Consultant					07	12
0703494	BEL-00147-3322_(0703494)	BROOKS RUN	Selected Consultant					07	12
0703524	BEL-00147-3376_(0703524)	BROOKS RUN	Selected Consultant					07	12
0703559	BEL-00147-3440_(0703559)	BROOKS RUN	Selected Consultant					07	12
0703583	BEL-00147-3528_(0703583)	BROOKS RUN	Selected Consultant					05	12
0703613	BEL-00147-3588_(0703613)	BR OF MCMAH ON CREEK	Selected Consultant					07	12
0703729	BEL-00148-0071_(0703729)	CAPTINA CR	Selected Consultant					05	12
0703850	BEL-00148-0556_(0703850)	LONG RUN	Selected Consultant				Routines every 6 months	05	12
0703885	BEL-00148-0699_(0703885)	CAPTINA CREEK	Selected Consultant					05	12
0703915	BEL-00148-0715_(0703915)	CAPTINA CREEK	Selected Consultant					05	12
0700584	BEL-00007-1629L_(0700584)	INDIAN RUN, CSX RR, ACCES	Selected Consultant				Use Bucket Truck for Seated Hinge, Anticipate insp c	02	24
0704113	BEL-00148-1157_(0704113)	PINEY CREEK	Selected Consultant					05	12
0704148	BEL-00148-1216_(0704148)	NORFOLK SOUTHERN CORP.	Selected Consultant					05	12
0704210	BEL-00148-1414_(0704210)	CAPTINA CREEK	Selected Consultant					05	12
0704296	BEL-00148-1604_(0704296)	CAPTINA CR	Selected Consultant					07	12
0704547	BEL-00148-2154_(0704547)	CAPTINA CREEK	Selected Consultant				Routines every 6 months	04	12
0704573	BEL-00148-2292_(0704573)	UNNMD TRIB OF CAPTINA CR	Selected Consultant			On Schd'l		04	12
0704598	BEL-00148-2434_(0704598)	CAPTINA CREEK	Selected Consultant			On Schd'l		05	12
0704652	BEL-00148-2541_(0704652)	PORTERS RUN	Selected Consultant					05	12
0704660	BEL-00148-2666_(0704660)	CAPTINA CR	Selected Consultant					05	12
0704709	BEL-00148-2707_(0704709)	NORFOLK SOUTHERN CORP.	Selected Consultant			Every Insp	Regularly deeper than chest waders	05	12
0704741	BEL-00149-2743_(0704741)	ABND.RR.TUNNEL (STREAM)	Selected Consultant	C				05	12
0704768	BEL-00149-0240_(0704768)	BRANCH OF MCMAHON CREEK	Selected Consultant					06	12
0704792	BEL-00149-0389_(0704792)	MCMAHON CREEK	Selected Consultant					05	12
0704938	BEL-00149-1082_(0704938)	WILLIAMS CREEK	Selected Consultant					05	12
0704946	BEL-00149-1273_(0704946)	MCMAHON CREEK	Selected Consultant			Every Insp	Perpetually submerged	05	12
0704954	BEL-00331-0024_(0704954)	BR BOGGS FORK	Selected Consultant					04	12
0705055	BEL-00149-1293_(0705055)	MCMAHON CREEK	Selected Consultant					03	12
0705136	BEL-00331-1352_(0705136)	WHEELING CR	Selected Consultant					03	12
0705179	BEL-00149-1954_(0705179)	BARKCAMP CRK	Selected Consultant					07	12
0705187	BEL-00149-3157_(0705187)	ABND.RR.TUNNEL(NO TRS)	Selected Consultant			Every Insp	Regularly deeper than chest waders	05	12
0705217	BEL-00149-1576_(0705217)	MCMAHON CREEK	Selected Consultant					05	12
0705233	BEL-00149-2074_(0705233)	MCMAHON CREEK	Selected Consultant					07	12
0705276	BEL-00331-0449_(0705276)	TRAIL RUN	Selected Consultant					03	12
0705292	BEL-00379-0321_(0705292)	BR BEAVER CREEK	Selected Consultant					03	24
0705306	BEL-00379-0019_(0705306)	BR OF ROCK CREEK	Selected Consultant					03	12
0705381	BEL-00647-0723_(0705381)	LITTLE SHORT CREEK	Selected Consultant					03	12
0705535	BEL-00800-0146_(0705535)	MILLERS RUN	Selected Consultant					03	24
0705578	BEL-00800-0223_(0705578)	CAPTINA CREEK	Selected Consultant					03	12
0705594	BEL-00800-0753_(0705594)	BR CAPTINA CR	Selected Consultant					03	12
0705608	BEL-00800-0853_(0705608)	TRIB OF N FORK CAPTINA C	Selected Consultant					03	12
0705676	BEL-00800-1480_(0705676)	MUSKRAT RUN	Selected Consultant					03	12

SFN	Assetwise Asset Name Text	Featured Intersection	Assigned to:	Extra PPE	Confined Space	Dive	Notes	Month Due	Interval
0705772	BEL-00800-1741_(0705772)	HENDRYSBURG RUN	Selected Consultant					03	24
0706361	BEL-00470-0636_(0706361)	RAMPS A & B OVER IR-470	Selected Consultant					05	12
0706396	BEL-00470-0654_(0706396)	SR7 NS & W&L RRS, OHIO R	Selected Consultant					04	24
0706787	BEL-00149-1106_(0706787)	MCMAHON CREEK	Selected Consultant					05	12
0707171	BEL-00149-1010_(0707171)	MCMAHON CREEK	Selected Consultant					05	12
0726117	BEL-001SP-0041_(0726117)	BARKCAMP CR/BELMONT LAKE	Selected Consultant			On Schd'l		06	12
0726184	BEL-001SP-0051_(0726184)	NORTH FORK BARKCAMP CREE	Selected Consultant			On Schd'l		06	12
1000500	CAR-00039-1815_(1000500)	FRIDAY CREEK	Selected Consultant					07	12
1000543	CAR-00039-1985_(1000543)	S SR OF FRIDAY CR	Selected Consultant					07	12
1001043	CAR-00164-0039_(1001043)	WHEELING & LAKE ERIE RR	Selected Consultant			On Schd'l		04	12
1001388	CAR-00183-0790_(1001388)	BIG SANDY CREEK	Selected Consultant					06	12
1001663	CAR-00332-0649_(1001663)	N FORK MCGUIRE CREEK	Selected Consultant			On Schd'l		03	24
1001869	CAR-00542-0563_(1001869)	ATWOOD RESERVOIR	Selected Consultant			On Schd'l		06	24
1001892	CAR-00542-0606_(1001892)	ATWOOD RESERVOIR	Selected Consultant			On Schd'l		07	12
1001922	CAR-00542-0682_(1001922)	ATWOOD RESERVOIR	Selected Consultant					07	24
1001957	CAR-00542-0864_(1001957)	BRANCH OF INDIAN FORK	Selected Consultant			On Schd'l		07	12
1500066	COL-00007-0587_(1500066)	JETHRO RUN	Selected Consultant		C			05	12
1500090	COL-00007-0595_(1500090)	CARPENTER RUN	Selected Consultant	Sewage	C			05	12
1500112	COL-00007-0311_(1500112)	STREAM	Selected Consultant		C			05	12
1500279	COL-00007-1487_(1500279)	MIDDLE FK LI'L BEAVER CR	Selected Consultant	Mirex			Anticipate insp cycle moving to fall	07	24
0704091	BEL-00148-1135_(0704091)	CAPTINA CREEK	Selected Consultant	Mirex				02	24
1500724	COL-00011-1523_(1500724)	MIDDLE FK LITTLE BEV CR	Selected Consultant	Mirex				07	12
1500759	COL-00011-1523R_(1500759)	MIDDLE FK LITTLE BEV CR	Selected Consultant	Mirex		??		07	12
1501291	COL-00014-1364_(1501291)	BEAVER LAKE	Selected Consultant					05	12
1501349	COL-00014-0143_(1501349)	MID FORK LITTLE BEAVER CR	Selected Consultant	Mirex				05	24
1501364	COL-0014T-0054L_(1501364)	MID FRK LITTLE BEAVER CR	Selected Consultant	Mirex			Include Pile Section Loss Measurements & Calcs	05	12
1501372	COL-0014T-0054R_(1501372)	MID FRK LITTLE BEAVER CR	Selected Consultant	Mirex			Include Pile Section Loss Measurements & Calcs	05	12
1501445	COL-00014-0871_(1501445)	MILL CREEK	Selected Consultant	Mirex			Include Pile Section Loss Measurements & Calcs	05	24
1501542	COL-00030-0248_(1501542)	SANDY CREEK	Selected Consultant			On Schd'l		03	12
1501747	COL-00030-1771_(1501747)	M FRK LTL BEAV CR&BIKWY	Selected Consultant	Mirex				05	12
1501763	COL-00030-1896_(1501763)	MID FORK LI'L BEAVER CR	Selected Consultant	Mirex				07	24
1502200	COL-00030-3126_(1502200)	CARPENTER'S RUN	Selected Consultant		C		Routines every 6 months	07	12
1502352	COL-00030-3564WB_(1502352)	WATERLINE STRUC.OVR US30	Selected Consultant					07	12
1502360	COL-00030-3543_(1502360)	APPROACH STRUCTURE	Selected Consultant					08	12
1502425	COL-00030-3442_(1502425)	USR 30, OHIO RIVER	Selected Consultant					09	12
1502728	COL-00039-2083_(1502728)	THOMPSON PARK CREEK	Selected Consultant					09	12
1502808	COL-00045-2066_(1502808)	MID FK LITTLE BEAVER CR	Selected Consultant	Mirex	C		CURSORY	05	24
1502859	COL-00046-0026_(1502859)	SULPHUR CREEK	Selected Consultant	NS Derail				05	12
1502905	COL-00046-0037_(1502905)	LESUE RUN	Selected Consultant	NS Derail				03	12
1503162	COL-00062-0199_(1503162)	MAHONING RIVER	Selected Consultant				Include Pile Section Loss Measurements & Calcs	03	24
1503286	COL-00062-1137_(1503286)	NS RR(AMTRAK)& PENN AVE	Selected Consultant				Snooper to Remove Spalls over Tracks	12	12
1503294	COL-00062-1150_(1503294)	MID FORK LITTLE BEAVER C	Selected Consultant	Mirex				02	24
1500430	COL-00009-0042_(1500430)	BR SANDY CR	Selected Consultant				Anticipate insp cycle moving to fall	11	24
1503766	COL-00154-1424_(1503766)	LESUE RUN	Selected Consultant	NS Derail					

SFN	Assetwise Asset Name Text	Featured Intersection	Assigned to:	Extra PPE	Confined Space	Dive	Notes	Month Due	Interval
1504053	COL-00164-1431_(1504053)	MIDDLE FRK LITTLE BEVR CR	Selected Consultant	Mirex				07	24
1504290	COL-00165-0547_(1504290)	SULPHUR CREEK	Selected Consultant	NS Derail				11	24
1504452	COL-00170-0469_(1504452)	LITTLE BEAVER CREEK	Selected Consultant	Mirex				04	24
1504533	COL-00170-1103_(1504533)	BULL CREEK	Selected Consultant	NS Derail				03	12
1503308	COL-00014-0197_(1503308)	NS RR (CARRIES AMTRAK)	Selected Consultant				Anticipate insp cycle moving to fall	02	24
1504584	COL-00170-1469_(1504584)	SULPHUR CREEK	Selected Consultant	NS Derail				04	24
1504797	COL-00173-1108_(1504797)	MIDDLE FK LIL BEAVER CR	Selected Consultant	Mirex				05	12
1504959	COL-00658-0161_(1504959)	MIDDLE FRK LIL BEAVER CR	Selected Consultant	Mirex				05	12
1504975	COL-00344-0438_(1504975)	MIDDLE FRK LITTLE BEV CR	Selected Consultant	Mirex				05	12
1505009	COL-00344-0581_(1505009)	NS RR(AMTRAK), CHERRY V.R	Selected Consultant				Include Pile Section Loss Measurements & Calcs. An	02	12
1504576	COL-00170-1895_(1504576)	N FORK LITTLE BEAVER CR	Selected Consultant					03	12
1505130	COL-00164-2394_(1505130)	NS RR, AMTRAK	Selected Consultant					03	12
1505408	COL-00518-0099_(1505408)	WILLARD RUN (BRUSH CR)	Selected Consultant			On Schd'l	Routines every 6 months	05	12
1505858	COL-00644-0587_(1505858)	WILLARD RUN	Selected Consultant					02	12
1505106	COL-00164-2344_(1505106)	E BR MID FRK LITTLE BVR	Selected Consultant				Include Pile Section Loss Measurements & Calcs. An	02	12
3400735	HAS-00022-1173_(3400735)	BRUSHY FORK	Selected Consultant			On Schd'l	Anticipate insp cycle moving to fall	02	24
3401588	HAS-00250-0543_(3401588)	TAPPAN LAKE	Selected Consultant			On Schd'l	Anticipate insp cycle moving to fall	02	24
3401685	HAS-00250-0934_(3401685)	BEAVER DAM RUN TAPPAN LK	Selected Consultant			On Schd'l	Check with OSE to see if this bridge still needs a dive	02	24
3401715	HAS-00250-0977_(3401715)	CLEAR FORK CR TAPPAN LAK	Selected Consultant			On Schd'l		08	12
3402304	HAS-00151-2703_(3402304)	EDINGTON RUN TAPPAN LAKE	Selected Consultant			On Schd'l		02	24
3401782	HAS-00250-1194_(3401782)	W & LE RR (TUNNEL)	Selected Consultant				Anticipate insp cycle moving to fall	07	12
3402495	HAS-00250-2221_(3402495)	STREAM	Selected Consultant				Anticipate insp cycle moving to fall	02	24
3402681	HAS-00250-2968_(3402681)	COL. & OHIO R.RR SPUR	Selected Consultant				Anticipate insp cycle moving to fall	02	24
3402525	HAS-00250-2255_(3402525)	OLD RR.TUNNEL(NO TRACK)	Selected Consultant			Every Insp	Regularly deeper than chest waders	04	12
3403157	HAS-00646-2020_(3403157)	MIDDLE FORK SHORT CR	Selected Consultant				Anticipate insp cycle moving to fall	02	24
3403246	HAS-00799-0563_(3403246)	SALEM CREEK	Selected Consultant			On Schd'l	Routines every 6 months	06	12
3403297	HAS-00800-0932_(3403297)	MCFADDEN RUN	Selected Consultant			On Schd'l	Routines every 6 months	12	12
3410000	HAS-00799-03.91_(3410000)	BRUSHY FORK CREEK	Selected Consultant			New '27	Include Pile Section Loss Measurements & Calcs	05	12
3410001	HAS-00799-04.53_(3410001)	CLENDENNING LAKE	Selected Consultant			On Schd'l		11	24
3800229	HOL-00039-0594_(3800229)	CLENDENNING LAKE	Selected Consultant			On Schd'l		11	24
3800458	HOL-00039-1699_(3800458)	CRAB RUN	Selected Consultant				Include Pile Section Loss Measurements & Calcs	03	12
3800512	HOL-00039-1716_(3800512)	KILLBUCK CR OVERFLOW	Selected Consultant				Include Pile Section Loss Measurements & Calcs	03	24
3800571	HOL-00039-2917_(3800571)	KILLBUCK CREEK	Selected Consultant			On Schd'l	Include Pile Section Loss Measurements & Calcs	04	12
3800679	HOL-00060-0205_(3800679)	WALNUT CREEK	Selected Consultant				Include Pile Section Loss Measurements & Calcs	03	12
3800784	HOL-00060-0441_(3800784)	BR KILLBUCK CR	Selected Consultant			Every Insp	Perpetually submerged	07	24
3801276	HOL-00062-1215_(3801276)	SHRIMPLIN RUN	Selected Consultant			On Schd'l	Include Pile Section Loss Measurements & Calcs	04	12
3801330	HOL-00062-1669_(3801330)	KILLBUCK CREEK OVERFLOW	Selected Consultant				Dive inspection plus Include Pile Section Loss Measu	04	12
3801489	HOL-00062-2421_(3801489)	Branch Killbuck Creek	Selected Consultant					03	24
3801500	HOL-00062-2506_(3801500)	SHARPS RUN	Selected Consultant					03	24
3801586	HOL-00062-3105_(3801586)	DOUGHTY CREEK	Selected Consultant					03	24
3801810	HOL-00083-1356_(3801810)	BRANCH OF INDIAN TRAIL C	Selected Consultant					03	24
3801888	HOL-00083-1510_(3801888)	MARTIANS CREEK	Selected Consultant				Include Pile Section Loss Measurements & Calcs	04	12
		SALT CREEK	Selected Consultant				Include Pile Section Loss Measurements & Calcs	07	24

SFN	Assetwise Asset Name Text	Featured Intersection	Assigned to:	Extra PPE	Confined Space	Dive	Notes	Month Due	Interval
3801896	HOL-00083-1669_(3801896)	TEA RUN	Selected Consultant				Include Pile Section Loss Measurements & Calcs	04	12
3802124	HOL-00179-0395_(3802124)	CRAB RUN	Selected Consultant				Include Pile Section Loss Measurements & Calcs	07	12
3802809	HOL-00520-0967_(3802809)	BLACK CREEK	Selected Consultant				Include Pile Section Loss Measurements & Calcs	08	24
4100050	JEF-00007-0166_(4100050)	W&LE RR, NS RR MR-641 OH	Selected Consultant				Use Bucket Truck	06	12
4100085	JEF-00007-0245_(4100085)	SHORT CREEK	Selected Consultant			On Schd'l			24
4100107	JEF-0150A-0012_(4100107)	SERVICE RD A OVER SHORTC	Selected Consultant			On Schd'l	New W&LE Rail Line		12
4100115	JEF-00007-0288_(4100115)	CR 17A (OLD SR7) W&LE RR	Selected Consultant					05	24
4100212	JEF-00007-0688_(4100212)	SALT RUN	Selected Consultant					06	12
4100433	JEF-00007-0993SR_(4100433)	TARRS RUN(MKT ST/RAMP B)	Selected Consultant					05	24
4100573	JEF-00007-1277_(4100573)	W. & L.E. RR(SUBWAY)	Selected Consultant					06	12
4100875	JEF-00007-1573_(4100875)	WELLS RUN	Selected Consultant		C		CURSORY	05	12
4100964	JEF-00007-1642_(4100964)	SR-7, RR & OHIO RIVER	Selected Consultant					07	24
4101057	JEF-00007-1892_(4101057)	WILLS CREEK	Selected Consultant		C		CURSORY	05	12
4101383	JEF-00007-1892_(4101383)	NORFOLK SOUTHERN CORP.	Selected Consultant					07	12
4101405	JEF-00007-2861_(4101405)	JEREMY RUN	Selected Consultant		C			09	24
4101472	JEF-00007-3022_(4101472)	DSCHARGE DUCT OHIO EDISON	Selected Consultant					12	12
4101502	JEF-00007-3050_(4101502)	INTAKE DUCT OHIO EDISON	Selected Consultant		C		CURSORY	07	24
4101561	JEF-00007-3095_(4101561)	ACCESS DR (CONVYR REMVD)	Selected Consultant		C		CURSORY	06	12
4101626	JEF-00007-3346_(4101626)	NS RR SPUR	Selected Consultant					12	12
4101650	JEF-00007-3380_(4101650)	NS RR, YELLOW CREEK	Selected Consultant			On Schd'l		09	12
4101839	JEF-00022-0698L_(4101839)	TR-166, W&LE RR, CROSS CR	Selected Consultant					04	12
4101863	JEF-00022-0698R_(4101863)	TR-166, W&LE RR, CROSS CR	Selected Consultant					04	12
4101898	JEF-00022-0747_(4101898)	CEDAR LICK RUN	Selected Consultant		C			05	12
4101936	JEF-00022-1232D_(4101936)	BR. WILLS CREEK & C-600	Selected Consultant		C			05	12
4101960	JEF-00022-1632_(4101960)	SR7(VETS.MEM.BR@OHIO R)	Selected Consultant			On Schd'l	Border Bridge and NS	06	12
4102428	JEF-00150-1294_(4102428)	SHORT CREEK	Selected Consultant				Dive Inspection plus Include Pile Section Loss Measu	06	24
4103068	JEF-00164-0599_(4103068)	YELLOW CR	Selected Consultant				Include Pile Section Loss Measurements & Calcs	07	12
4103181	JEF-00213-1518_(4103181)	NORTH FORK YELLOW CRK	Selected Consultant			On Schd'l	Include Pile Section Loss Measurements & Calcs	03	12
4103211	JEF-00213-1641_(4103211)	YELLOW CR	Selected Consultant					06	12
4103270	JEF-00213-1844_(4103270)	COL & OH RIVER RR	Selected Consultant					07	24
4104013	JEF-00022-1146_(4104013)	WILLS CREEK	Selected Consultant		C			07	12
4104056	JEF-00022-1182_(4104056)	WILLS CREEK	Selected Consultant		C			07	12
4104072	JEF-00022-1191_(4104072)	WILLS CREEK	Selected Consultant		C			07	12
4104102	JEF-00022-1234_(4104102)	BR. WILLS CREEK	Selected Consultant		C			07	12
4104137	JEF-00022-1295_(4104137)	WILLS CREEK	Selected Consultant		C			07	12
4104161	JEF-00022-1302_(4104161)	WILLS CREEK	Selected Consultant		C			07	24
4104277	JEF-00022-1481_(4104277)	RAMP E OVR. US 22 & CR 43	Selected Consultant					07	12
4104382	JEF-00022-1496EB_(4104382)	WILLS CREEK	Selected Consultant					07	12
7900334	TUS-00036-12.05_(7900334)	TUSCARAWAS RIVER	Selected Consultant			On Schd'l		05	24
7900384	TUS-00036-1724T_(7900384)	COL & OH R RR(TRENTON CONN	Selected Consultant					09	24
7900511	TUS-00036-1817I_(7900511)	BIG STILLWATER CR(RAMP J	Selected Consultant			On Schd'l		09	12
7900600	TUS-00250-2251L_(7900600)	STILLWATER CR AND CO RD6	Selected Consultant			On Schd'l		09	24
7900635	TUS-00250-2251R_(7900635)	STILLWATER CR AND CO RD6	Selected Consultant			On Schd'l		09	24
7901534	TUS-00039-1294_(7901534)	TUSCARAWAS RIVER	Selected Consultant			On Schd'l		09	12

SFN	Assetwise Asset Name Text	Featured Intersection	Assigned to:	Extra PPE	Confined Space	Dive	Notes	Month Due	Interval
7902077	TUS-00077-0388L_(7902077)	TUSCARAWAS RIVER	Selected Consultant			On Schd'l		09	24
7902107	TUS-00077-0388R_(7902107)	TUSCARAWAS RIVER	Selected Consultant			On Schd'l		09	24
7902131	TUS-00077-0502L_(7902131)	COL.&OH.R.R.RR,TWP RD 105	Selected Consultant					07	12
7902166	TUS-00077-0502R_(7902166)	COL.&OH.R.R.RR,TWP RD 105	Selected Consultant					07	12
7902174	TUS-00077-0510_(7902174)	TRIB OF TUSCARAWAS RIVER	Selected Consultant					08	12
7902433	TUS-00077-0926_(7902433)	I77 BUCKHORN CR PCRR	Selected Consultant	C				09	12
7902972	TUS-00077-2195L_(7902972)	ACCESS RD (ABND.RR.BED)	Selected Consultant					09	12
7903006	TUS-00077-2195R_(7903006)	ACCESS RD (ABND.RR.BED)	Selected Consultant					09	12
7903030	TUS-00077-2217L_(7903030)	SUGAR CREEK	Selected Consultant			On Schd'l		08	24
7903065	TUS-00077-2217R_(7903065)	SUGAR CREEK	Selected Consultant			On Schd'l		08	24
7903383	TUS-00077-2589_(7903383)	TRIB OF SUGAR CREEK	Selected Consultant	C				10	12
7903456	TUS-00077-2674_(7903456)	I77 PEN CENT RR SUGAR CR	Selected Consultant			On Schd'l		09	24
7903480	TUS-00077-2762_(7903480)	TRIB OF SUGAR CREEK	Selected Consultant	C				08	12
7903634	TUS-00077-2781L_(7903634)	R.J. CORMAN RAILROAD	Selected Consultant					09	12
7903669	TUS-00077-2781R_(7903669)	R.J. CORMAN RAILROAD	Selected Consultant					09	12
7903936	TUS-00077-3495L_(7903936)	TUSCARAWAS RIVER	Selected Consultant			On Schd'l		09	24
7903960	TUS-00077-3495R_(7903960)	TUSCARAWAS RIVER	Selected Consultant			On Schd'l		09	24
7904088	TUS-00093-0802_(7904088)	OHIO CENTRAL RR.	Selected Consultant					08	12
7904266	TUS-00212-0349_(7904266)	TUSCARAWAS RIVER	Selected Consultant			On Schd'l		06	12
7904479	TUS-00212-1220_(7904479)	WHEELING & LAKE ERIE RR.	Selected Consultant					08	12
3902746	HAS-00258-0274_(3902746)	LAUREL CREEK	Selected Consultant			On Schd'l	Include Pile Section Loss Measurements & Calcs. An	02	12
7904622	TUS-00250-0511_(7904622)	SUGAR CREEK	Selected Consultant			On Schd'l		09	12
7904800	TUS-00250-1232L_(7904800)	OVER RAMP E AND STONE CR	Selected Consultant					09	12
7904835	TUS-00250-1232R_(7904835)	OVER I77, RAMP E.&STONE C	Selected Consultant				Was Consor 2026 A and then moved to OSE	04	12
7904959	TUS-00250-1504L_(7904959)	TUSCARAWAS RIVER	Selected Consultant			On Schd'l		05	24
7904983	TUS-00250-1504R_(7904983)	TUSCARAWAS RIVER	Selected Consultant			On Schd'l		07	12
7905017	TUS-00250-1576L_(7905017)	R. J. CORMAN RR.	Selected Consultant					09	24
7905041	TUS-00250-1576R_(7905041)	R. J. CORMAN RR.	Selected Consultant					09	24
7905254	TUS-00250-1906L_(7905254)	R.J. CORMAN RR & PIKE RU	Selected Consultant					04	12
7905289	TUS-00250-1906R_(7905289)	R.J. CORMAN RR & PIKE RU	Selected Consultant					04	12
7905319	TUS-00250-1998L_(7905319)	BIG STILLWATER CR	Selected Consultant			On Schd'l		07	12
7905343	TUS-00250-1998R_(7905343)	BIG STILLWATER CREEK	Selected Consultant			On Schd'l		07	12
7905408	TUS-00250-2187WR_(7905408)	Stillwater Creek	Selected Consultant			On Schd'l		12	24
7905432	TUS-00250-2187WL_(7905432)	Stillwater Creek	Selected Consultant			On Schd'l		05	12
7905467	TUS-00258-0020_(7905467)	COL & OH RIVER RR	Selected Consultant					08	12
7905491	TUS-00258-0042_(7905491)	TUSCARAWAS RIVER	Selected Consultant			On Schd'l	Include Pile Section Loss Measurements & Calcs	08	24
7905564	TUS-00258-0389_(7905564)	BROWNING RUN	Selected Consultant				Dive in 26	08	12
7905629	TUS-00258-0600_(7905629)	DUNLAP CREEK	Selected Consultant				Include Pile Section Loss Measurements & Calcs	08	12
7905653	TUS-00258-1830_(7905653)	LAUREL CREEK	Selected Consultant			On Schd'l		08	12
7905785	TUS-00259-0011_(7905785)	TUSCARAWAS RIVER	Selected Consultant			On Schd'l		08	12
7906005	TUS-00416-1088_(7906005)	TUSCARAWAS RIVER	Selected Consultant			On Schd'l		07	12
7906021	TUS-00416-1124_(7906021)	R.J. CORMAN RAILROAD	Selected Consultant					09	12
7906129	TUS-00416-1483_(7906129)	TUSCARAWAS RIVER	Selected Consultant			On Schd'l		04	24
7906374	TUS-00800-0038_(7906374)	WEAVERS RUN	Selected Consultant				Include Pile Section Loss Measurements & Calcs	09	12

SFN	Assetwise Asset Name Text	Featured Intersection	Assigned to:	Extra PPE	Confined Space	Dive	Notes	Month Due	Interval
7906447	TUS-00800-0192_(7906447)	STILLWATER CREEK	Selected Consultant					07	12
7906633	TUS-00800-2186_(7906633)	TUSCARAWAS RIVER	Selected Consultant			On Schd'l	Routines every 6 months	04	24