



CUY-90-14.90

PID 77332/85531

APPENDIX EX-08

**Inner Belt Freeway – Part 4 – West Approach to Central Viaduct (CUY-42R-17.43)
(Reference Document)**

State of Ohio
Department of Transportation
Jolene M. Molitoris, Director

**Innerbelt Bridge
Construction Contract Group 1 (CCG1)**

8-0

IMPROVEMENT IS ESPECIALLY DESIGNED FOR THROUGH TRAFFIC AND HAS BEEN DECLARED A LIMITED ACCESS HIGHWAY OR FREEWAY BY ACTION OF THE DIRECTOR OF HIGHWAYS IN ACCORDANCE WITH THE PROVISIONS OF SECTION 5511.02 REVISED CODE OF OHIO.

MICROFILMED
FEB 25 1983

STATE OF OHIO
DEPARTMENT OF HIGHWAYS

INNER BELT FREEWAY

CUY-42R-17.43
CUYAHOGA COUNTY
CITY OF CLEVELAND


LIMITED ACCESS

PART 4 - WEST APPROACH TO CENTRAL VIADUCT

INDEX OF SHEETS

1 TITLE SHEET	37 RAMP W-1 RETAINING WALL
2 SCHEMATIC PLAN AND PROFILE	38 ABUTMENT W-2
3 RIGHT OF WAY PLAN	39-44 PIERS
4-5 GENERAL NOTES	45 FRAMING PLAN
6 SUMMARY OF QUANTITIES	46 BEAM ELEVATIONS
7-8 TYPICAL CROSS SECTIONS	47-49 GIRDER ELEVATIONS
9 PAVEMENT DETAILS	50 GIRDER FIELD SPLICES
10-11 PROFILES-RAMPS AND LANES	51 STIFFENER AND JACKING DIAPHRAGM DETAILS
12 INTERSECTION DETAILS	52 DEAD LOAD DEFLECTION DIAGRAMS
13-14 MISCELLANEOUS DETAILS	53 CROSS FRAMES
15 EXISTING UTILITIES	54 CROSS FRAMES AND SUPERSTRUCTURE DETAILS
16-16A LIGHTING DETAILS	55-56 BOX GIRDER
17 DRAINAGE PLAN	57-58 EXPANSION JOINTS
18-19 DRAINAGE PROFILES	59 SHOES
19A SPECIAL FRAME AND MANHOLE COVERS	60-61 SLAB PLANS
20-28 CROSS SECTIONS	62 SLAB DETAILS
	63 DECK CONTOURS AND HANDRAIL SPACING
	64 SLAB PLAN RAMP W-2
	65 DRAINAGE DETAILS
	66 LIGHTING DETAILS
	67 HANDRAIL DETAILS

NOTE:
THIS SET OF PLANS, PART 4 OF THE INNER BELT FREEWAY, EXTENDS FROM WEST END PIER OF CENTRAL VIADUCT WESTWARD TO STA. 12+42.50.
PARTS 1 THRU 3 ARE UNDER PREVIOUS CONTRACTS.



DELIVERY POINT: N.Y.C. & ST.L. RR. AVERAGE HAUL: 1/2 MILE

THE STANDARD SPECIFICATIONS OF THE STATE OF OHIO DEPARTMENT OF HIGHWAYS, INCLUDING CHANGES AND SUPPLEMENTAL SPECIFICATIONS LISTED IN THE PROPOSAL SHALL GOVERN THIS IMPROVEMENT.

I HEREBY APPROVE THESE PLANS AND DECLARE THAT THE MAKING OF THIS IMPROVEMENT WILL NOT REQUIRE THE CLOSING TO TRAFFIC OF THE HIGHWAY AND THAT PROVISIONS FOR THE MAINTENANCE AND SAFETY OF TRAFFIC WILL BE AS SET FORTH IN THE PLANS AND ESTIMATE.


THE RIGHT OF WAY FOR THIS IMPROVEMENT WILL BE PROVIDED BY THE STATE OF OHIO.

APPROVED
DATE 6-7-56 *Louis R. Drasler* DIRECTOR OF PUBLIC SERVICE, CITY OF CLEVELAND
APPROVED
DATE 6-7-56 *Richard A. Gierke* DIVISION DEPUTY DIRECTOR
APPROVED
DATE 6-21-56 *John J. Hume, Jr.* DEPUTY DIRECTOR OF PLANNING AND PROGRAMMING
APPROVED
DATE 6-18-56 *Wm. J. Oberman* ENGINEER OF BRIDGES
APPROVED
DATE 6-18-56 *Ed. J. Sutor* ENGINEER OF LOCATION AND DESIGN
APPROVED
DATE 6-19-56 *H. F. Suredel* DEPUTY DIRECTOR OF DESIGN AND CONSTRUCTION
APPROVED
DATE 6-21-56 *V. J. Klamnik* FIRST ASSISTANT DIRECTOR
APPROVED
DATE 6-21-56 *J. D. [Signature]* DIRECTOR OF HIGHWAYS

LINE DATA

BEGIN PROJECT STA. 12+42.50	
END PROJECT STA. 16+13.02	
NET LENGTH OF PROJECT (STRUCTURE) ADDITIONS	370.52 LIN. FT. OR 0.070 MILE.
FREEWAY STA. 5+00(±) TO STA. 12+42.50	742.50 ± LIN. FT.
ABBEEY AVE. STA. 6+97.42 TO STA. 7+86.87	689.45 LIN. FT.
TOTAL NET LENGTH OF WORK	1802.47 LIN. FT. OR 0.341 MILE

LOCATION PLAN



PORTION TO BE IMPROVED
OTHER HIGHWAYS & STREETS

H. G. SOURS
ASSOCIATE
COLUMBUS

PREPARED AND RECOMMENDED BY
HOWARD, NEEDLES, TAMMEN & BERGENDOFF
CONSULTING ENGINEERS

KANSAS CITY CLEVELAND NEW YORK
L. J. Bergendoff

SUPPLEMENTAL SPECIFICATIONS

NUMBER	DATE	NUMBER	DATE
B-119 REV.	12-14-55	M-206.14	7-15-49
L-209.12	7-17-54	M-109.23	REV. 4-20-56
5	6-8-55		
M-110.27	9-9-52		
S-114	8-30-55		

STANDARD DRAWINGS

NUMBER	DATE	NUMBER	DATE
L-3	4-1-50	I-8 M.H. NO. 1	5-1-52
L-3-A	4-1-50	I-15 NO. 1	8-1-55
RI-1	1-3-55	I-15 NO. 2	12-1-54
B-T-71R	3-2-53	BT 50-70-71E	10-1-47
LJ NO. 1	7-1-55	AS-1-54	12-1-54
I-1, 2, 3, 4, & 5	2-20-45	G-7.07	6-1-56
I-8CB NO. 2-2A&B	5-1-52	I-8MH NO. 1-A	1-3-55
I-8CB NO. 3	5-1-52	I-12	7-1-54
I-8CB NO. 3A	5-1-52	L-1	4-1-50
I-8 I NO. 2	12-1-54	TJ	5-1-56
OS-1	7-1-55	I-8 M.H. NO. 2	5-1-52
		I-15 NE 2A	7-2-56


DEPARTMENT OF COMMERCE
BUREAU OF PUBLIC ROADS

APPROVED _____ DATE _____
DISTRICT ENGINEER

FILE NO. CUYAHOGA COUNTY 00079-R
SEC. _____
DATE OF LETTING _____, 195____
CONTRACT NO. _____


FED. ROAD DIV. NO.	STATE	FED. AID PROJ. NO.	TYPE FUNDS	2
2	OHIO			67

CUYAHOGA COUNTY
CITY OF CLEVELAND
INNER BELT FREEWAY - PART 4
WEST APPROACH TO CENTRAL VIADUCT
CUY - 42R-1743
SCHEMATIC PLAN AND PROFILE




WEST APPROACH VIADUCT
TYPE: CONTINUOUS SPAN STEEL GIRDER WITH CONCRETE DECK & SUBSTRUCTURE
SPAN: VARIES
ROADWAY: 2 @ 52'-0" WITH 2'-3" SIDEWALKS
LOADING: CF 2000
SKEW: VARIES
CLEARANCE: VARIES
SURFACE: 2 1/2" ASPHALTIC CONCRETE


Marker will be furnished and erected on the right by the State before acceptance of this improvement.




PARTIAL CROSS SECTION OF EXISTING WEST 14TH STREET
ABBEE AVENUE TO KENILWORTH AVENUE
Scale: 1"=10'




CROSS SECTION OF EXISTING WEST 13TH PLACE
UNIVERSITY ROAD TO THE END
Scale: 1"=10'




PARTIAL CROSS SECTION OF EXISTING WEST 14TH STREET
ABBEE AVENUE TO UNIVERSITY ROAD
Scale: 1"=10'




CROSS SECTION OF EXISTING ABBEE AVENUE
W. 14TH STREET TO W. 20TH STREET
Scale: 1"=10'



CROSS SECTION OF EXISTING FAIRFIELD AVENUE
W. 14TH STREET TO SCRANTON ROAD
Scale: 1"=10'



CROSS SECTION OF EXISTING FAIRFIELD AVENUE
W. 14TH STREET TO W. 10TH STREET
Scale: 1"=10'




INNER BELT FREEWAY PROFILE
Scale: Hor: 1"=100'
Vert: 1"=20'

SCALE As Shown
MADE BY B. DATE 3-3-55 HOWARD, NEEDLES, TAMMEN & BERGENDOFF CONSULTING ENGINEERS
TRCD BY M.Q. DATE 12-14-55 KANSAS CITY CLEVELAND NEW YORK
CKD BY H.K.M. DATE 12-16-55
914 SHEET 2

CUYAHOGA COUNTY
CITY OF CLEVELAND
INNER BELT FREEWAY-PART 4
WEST APPROACH TO CENTRAL VIADUCT
CUY-42R-1743

RIGHT OF WAY

MICROFILMED
FEB 25 1983



DEED AREA	Sq. FT. TAKE	PARCEL NO.	OWNER	Sq. FT. RESIDUE
16,352.00	4,844.00	11	Reeves Cleaning Co. Hillcomb Realty Co.	11,508.00
3,360.00	ALL	12	Thos & J. Borylski	0.00
3,360.00	"	13	Mary Babinchak	0.00
3,584.00	"	14	Meribetts & Wm. Mihalik	0.00
3,472.00	"	15	Mike & Anna Fekete	0.00
1,058.14	"	16-A	R. F. I. Sapienza & J. P. Arcara	0.00
926.29	"	16-B	Homer & Agnes Cox	0.00
928.29	"	16-C	John R. & Birdie T. Meltach	0.00
921.94	"	16-D	Esther T. Williams	0.00
923.05	"	16-E	Dale & Vera Yeager	0.00
1,233.29	"	16-F	Roy & Helen Bartoszek	0.00
6,144.12	"	24	Rev. Andrew Chernyshin	0.00
9,153.20	"	25	Joseph & Theodora Banczuk	0.00
21,063.40	"	26	John F. & Helen Marshall	0.00
30,233.28	29,208.28	27	Michael Mizenko	1,025.00
15,122.25	12,861.75	28	John Lisa	2,260.50
7,562.94	5,962.44	29	Sam Broszko	1,600.50
22,693.77	16,011.27	30	Anthony J. Toman	6,682.50
15,133.14	9,754.14	31	Rose Thomas & E. C. Ziglar	5,379.00
9,174.20	5,914.20	32	Carl & Anna Lemmermann	3,260.00
6,900.00	ALL	33	Sinclair Refining Co.	0.00
15,048.00	230.50	34	Greek Orthodox Church	14,817.50
18,468.00	1,630.12	35	Caroline Rice	16,837.87
11,628.00	1,867.87	36	Estelle Zwolinski & Agnes S. Toman	9,760.12
15,048.00	3,993.00	37	Dr. Martin Luther Evangelical Church	11,055.00
22,572.00	10,098.00	38	Slovak Lutheran Church-Congregation-Same Owner, Parc. 37	12,474.00
7,524.00	4,422.00	39	Slovak Lutheran Church-Congregation-Same Owner, Parc. 37	3,102.00
8,778.00	5,813.50	40	David Murad	2,964.50
8,778.00	6,525.75	41	David Murad	2,252.25
15,048.00	12,870.00	42	Walter & Amy R. Higs	2,178.00
7,980.00	ALL	43	Constantine Nicholan	0.00
7,980.00	"	44	George F. & Isabel Siebert M. & E. Adamczyk	0.00
11,019.24	"	45	Julius, Margt., & Wm. F. McGuire	0.00
11,019.24	"	46	Nellie Bukhair	0.00
11,343.00	"	47	Marvin & Ethel M. Cary	0.00
10,716.00	"	48	Earl T. Benjamin, TRS.	0.00
10,228.96	"	49	Cleveland Trust Co.	0.00
6,124.61	"	50	Vincent & Mary Triner	0.00
5,375.63	"	51	Catherine Zemba	0.00
5,375.63	"	52	Petro Petrick	0.00
3,000.00	0.00	39-A	Same Owner, Parcel 37	3,000.00
12,656.25	ALL	1	Sophia M. Maske W.G. Lewicky	0.00
5,263.78	"	22	Josephine Bellitto H. Cesar & G. M. Finesilver	0.00
1,849.10	"	23	Ernesto Rodriguez Nelson N. Moss	0.00

SCALE 1" = 50'
MADE BY DATE 12-19-55 HOWARD, NEEDLES, TAMMEN & BERENDOFF CONSULTING ENGINEERS
TRCD. BY DATE 1-12-56 KANSAS CITY CLEVELAND NEW YORK
CKD. BY DATE 5-4-56 914 SHEET 3

GENERAL NOTES

FED. ROAD DIV. NO.	STATE	FED. AID PROJ. NO.	TYPE FUNDS
2	OHIO		

CUYAHOGA COUNTY
CITY OF CLEVELAND
INNER BELT FREEWAY - PART 4
WEST APPROACH TO CENTRAL VIADUCT
CUY - 42R - 17.43

GENERAL NOTES

GENERAL

DESIGN STANDARDS

THE GEOMETRIC DESIGN FOR THE ROADWAY AND STRUCTURES WHICH COMPRISE THIS PROJECT IS BASED ON THE FOLLOWING DESIGN SPEEDS AS OUTLINED BY THE A.A.S.H.O. POLICIES ON GEOMETRIC HIGHWAY DESIGN:

FREEWAY	50 MPH
RAMPS	35 MPH

MINIMUM HORIZONTAL AND VERTICAL SIGHT DISTANCES HAVE BEEN PROVIDED, BASED ON THE A.A.S.H.O. POLICIES ON GEOMETRIC HIGHWAY DESIGN, AND CONSISTENT WITH THE DESIGN SPEEDS OF THE VARIOUS ROADWAYS.

FIELD OFFICE

THE CONTRACTOR SHALL PROVIDE A SUITABLE FIELD OFFICE IN ACCORDANCE WITH SEC. S-0.01(b) HAVING A MINIMUM OF 500 SQ. FT. OF FLOOR SPACE. THE CONTRACTOR SHALL HAVE A TELEPHONE INSTALLED AND MAINTAINED DURING CONSTRUCTION OF THIS PROJECT.

PERMITS, LAWS AND REGULATIONS

THE CONTRACTOR SHALL SECURE, AT HIS OWN EXPENSE, ALL NECESSARY PERMITS FROM THE MUNICIPAL OR OTHER PUBLIC AUTHORITIES, SHALL GIVE ALL NOTICES REQUIRED BY LAW OR MUNICIPAL ORDINANCES, AND SHALL PAY ALL FEES AND CHARGES INCIDENT TO THE DUE AND LAWFUL PROSECUTION OF THE WORK COVERED BY THIS CONTRACT.

UNDERGROUND UTILITIES

THE LOCATIONS OF THE UNDERGROUND UTILITIES SHOWN ON THE PLANS HAVE BEEN OBTAINED BY DILIGENT FIELD CHECKS AND SEARCHES OF AVAILABLE RECORDS. IT IS BELIEVED THEY ARE ESSENTIALLY CORRECT, BUT THE STATE OF OHIO MAKES NO GUARANTEES AS TO THEIR ACCURACY OR COMPLETENESS.

UTILITY NOTE

ANY AND ALL WORK REQUIRED FOR REMOVING, RELOCATING AND CONSTRUCTION OF NEW FACILITIES FOR PRIVATE OR PUBLIC UTILITIES WILL BE DONE BY AND AT THE EXPENSE OF THE RESPECTIVE OWNERS UNLESS OTHERWISE NOTED ON THE PLANS.

WATER METER BOXES

THE CITY WATER DEPARTMENT WILL RELOCATE ALL PRIVATELY OWNED WATER METER BOXES AND THIS ITEM WILL NOT BE INCLUDED AS A PART OF THE WORK TO BE PERFORMED BY THE STATE CONTRACTOR.

WORK BY THE CITY OF CLEVELAND

THE CITY WILL PROVIDE FOR THE REMOVAL OR DISPOSAL OF ALL EXISTING BUILDINGS WITHIN THE LIMITS OF THE EASEMENT LINES TO THE TOP OF THE EXISTING FOUNDATIONS.

TRAFFIC

WHERE ANY OF THE WORK CALLED FOR UNDER THIS CONTRACT INVOLVES THE CLOSING OF EXISTING STREETS AND/OR THE RE-ROUTING OF TRAFFIC, THE CONTRACTOR FOR THIS PROJECT SHALL PROSECUTE TO THE FULLEST EXTENT THE WORK INVOLVED SO AS TO REDUCE TO A MINIMUM THE LENGTH OF TIME THAT THE STREETS CONCERNED WILL BE CLOSED TO TRAFFIC.

IN ADDITION TO THE ABOVE, SECTION 6-4.05 "MAINTENANCE OF LOCAL TRAFFIC" WILL BE IN FORCE DURING THE ENTIRE LIFE OF THE CONTRACT.

ATTENTION IS DIRECTED PARTICULARLY TO THE NEED FOR PROVIDING ADEQUATE FACILITIES TO ACCOMMODATE SCHOOL CHILDREN AND OTHER PEDESTRIAN TRAFFIC IN THE VICINITY OF THE PROJECT. THE CONTRACTOR SHALL PROVIDE AND MAINTAIN SUCH TEMPORARY BOARD WALKS, CINDER WALKS, HANDRAILS ADJACENT TO EXCAVATIONS, ETC. AS MAY BE NECESSARY TO ACCOMMODATE IN A REASONABLE AND SAFE MANNER PEDESTRIAN TRAFFIC IN THE VICINITY OF THE PROJECT.

ALL OF THE ABOVE ARE INCLUDED IN THE LUMP SUM BID FOR "MAINTAINING TRAFFIC".

AGGREGATE AND CALCIUM CHLORIDE ARE CARRIED IN THE GENERAL SUMMARY TO BE USED AS DIRECTED BY THE ENGINEER, FOR THE MAINTENANCE OF LOCAL TRAFFIC.

PAVEMENT

PLACING AND FINISHING CONCRETE PAVEMENT

APPROVED FLEXIBLE FORMS SHALL BE USED FOR CONSTRUCTION OF CIRCULAR PAVEMENT EDGES HAVING A RADIUS OF 200 FT. OR LESS, CIRCULAR CONCRETE CURBS AND CONCRETE CURB TRANSITIONS OF SHORT RADII.

PARTICULAR CARE SHALL BE EXERCISED BY THE CONTRACTOR IN OBTAINING IN A UNIFORM MANNER THE CURB TRANSITIONS CALLED FOR ON THE PLANS.

SIDEWALK

IN LIEU OF THE SURFACE GROOVING CALLED FOR IN THE SPECIFICATIONS, STEEL PLATES 1/8 INCH IN THICKNESS SHALL BE USED TO DIVIDE THE WALK, FOR ITS FULL WIDTH AND THICKNESS, INTO BLOCKS APPROXIMATELY 5 FEET IN LENGTH UNLESS OTHERWISE ORDERED BY THE ENGINEER. THE STEEL PLATES SHALL BE REMOVED AS SOON AS THE CONCRETE HAS SUFFICIENTLY SET THAT THE REMOVAL OF THE PLATE WILL NOT DISTURB OR DAMAGE THE FORMED JOINT.

THE LIMITS AND QUANTITY OF NEW SIDEWALK AS SHOWN ON THE PLANS MAY BE ADJUSTED BY THE ENGINEER.

ROADWAY

REMOVAL OF TREES AND STUMPS

ALL TREES AND STUMPS WITHIN THE LIMITS OF THE RIGHT OF WAY SHALL BE DISPOSED OF AS SPECIFIED IN SECTION E-1.03 OF THE CONSTRUCTION AND MATERIAL SPECIFICATIONS.

TREES SHALL NOT BE REMOVED, REGARDLESS OF SIZE, UNTIL SPECIFICALLY AND CONSPICUOUSLY MARKED BY THE ENGINEER.

PAYMENT FOR THE REMOVAL OF TREES AND STUMPS IS INCLUDED IN THE UNIT PRICE BID FOR ITEM E-1, ROADWAY EXCAVATION.

REMOVAL OF REFUSE AND DEBRIS

ANY EXISTING REFUSE, DEBRIS OR ANY OTHER UNSUITABLE MATERIAL SHALL BE REMOVED AND DISPOSED OF BY THE CONTRACTOR IN ACCORDANCE WITH ITEM E-1. THE QUANTITY OF REFUSE OR DEBRIS, OR OTHER UNSUITABLE MATERIAL REMOVED AND DISPOSED OF WILL BE DETERMINED BY FINAL CROSS SECTIONS, AND THE YARDAGE SO DETERMINED WILL BE PAID FOR AT THE CONTRACT UNIT PRICE BID FOR ROADWAY EXCAVATION, ITEM E-1.

REMOVAL MISCELLANEOUS

THE REMOVAL AND DISPOSAL OF ANY EXISTING PAVEMENT, SIDEWALK, BUILDING FOUNDATIONS, STEPS, CELLAR FLOORS, WELL COVERS, CISTERN COVERS, SEPTIC TANKS, CONCRETE BASES, WALLS, CURB, CURB AND GUTTER, RAILS, TIES, POLE STUBS, HEADWALLS, PIPES, DRIVEWAYS AND GARAGE FLOORS, OR OTHER MASONRY LYING WITHIN THE LIMITS OF RIGHT OF WAY (AND NOT SPECIFICALLY PAID FOR UNDER A SEPARATE ITEM) SHALL BE CLASSIFIED AS EXCAVATION AND PAID FOR UNDER THE EXCAVATION ITEM OF WHICH THEY ARE A PART. WHERE REMOVAL OF ANY PAVEMENT LYING WITHIN THE LIMITS OF ROADWAY EXCAVATION, ITEM E-1, OR EXCAVATION FOR STRUCTURES, ITEM E-2, IS PAID FOR UNDER A SEPARATE ITEM, THE PAY LIMITS FOR EXCAVATION, ITEM E-1 OR E-2, SHALL BE TO THE BOTTOM OF PAVEMENT.

PAVEMENTS, SIDEWALKS, STEPS, CELLAR FLOORS OR OTHER MASONRY SHALL BE REMOVED TO A DEPTH OF THREE (3) FEET BELOW THE PROPOSED PAVEMENT SUBGRADE IF LOCATED WITHIN THE PROPOSED PAVEMENT AREA, AND TO A DEPTH OF THREE (3) FEET BELOW THE PROPOSED FINISHED SURFACE IF LOCATED OUTSIDE THE PROPOSED PAVEMENT AREA.

PAVEMENTS, SIDEWALKS, CELLAR FLOORS OR OTHER MASONRY BELOW THE ABOVE LIMITS SHALL BE BROKEN UP INTO PORTIONS WHOSE AREA DOES NOT EXCEED ONE (1) SQUARE FOOT, BUT NEED NOT BE REMOVED.

PAYMENT FOR ALL OF THE ABOVE OPERATIONS SHALL BE INCLUDED IN CONTRACT UNIT PRICE BID FOR ROADWAY EXCAVATION, ITEM E-1, AND EXCAVATION FOR STRUCTURES, ITEM E-2.

ADDITIONAL EXCAVATION NECESSARY TO PERFORM ANY OF THE ABOVE OPERATIONS SHALL BE PAID FOR AT THE CONTRACT UNIT PRICE BID PER CUBIC YARD FOR ROADWAY EXCAVATION, ITEM E-1, AND EXCAVATION FOR STRUCTURES, ITEM E-2.

BASEMENTS, WELLS, CISTERNS, SEPTIC TANKS, AND UNNATURAL DEPRESSIONS WITHIN THE LIMITS OF THE RIGHT OF WAY SHALL BE BACKFILLED WITH BROKEN FOUNDATION MASONRY OR ROCK PLACED AS ROCK EMBANKMENT ACCORDING TO SECTION E-1.08 OF THE CONSTRUCTION AND MATERIAL SPECIFICATIONS.

SANDSTONE CURB RESET

All salvagable sandstone curb removed for reuse under Item E-3 shall be reset. An estimated quantity of 2000 Lin. Ft. has been assumed to be salvagable and listed in the general summary.

New sandstone curb, furnished and placed, shall not be interspersed with salvaged curb.

COMPACTION OF SOIL BACKFILL

SPECIAL CARE SHALL BE TAKEN TO PROPERLY COMPACT SOIL BACKFILL PLACED ADJACENT TO AN EXISTING PAVEMENT EDGE.

ROUNDING OF CORNERS ON CROSS SECTIONS

THE ROUNDED CORNERS, SHOWN ON STANDARD DRAWING RI-1, APPLY TO ALL CROSS SECTIONS EVEN THOUGH OTHERWISE SHOWN IN THESE PLANS.

SPECIAL DITCHES

FOR SPECIAL DITCH GRADES, SEE CROSS SECTIONS AND DRAINAGE PLANS.

TILE FOR SUB-GRADE DRAINAGE

6 IN. DRAIN TILE SHALL BE FURNISHED AND PLACED BY THE CONTRACTOR, IN MANHOLES, CATCH BASINS AND INLETS FOR SUBGRADE DRAINAGE, WHERE AND AS DIRECTED BY THE ENGINEER. PAYMENT FOR SAME SHALL BE INCLUDED IN THE PRICE BID PER "EACH" FOR MANHOLES, CATCH BASINS AND INLETS.

CONNECTIONS TO EXISTING SEWERS

AT PLACES WHERE THE PLANS PROVIDE FOR PROPOSED DRAINAGE PIPE TO BE CONNECTED TO EXISTING PIPES, IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO LOCATE THE EXISTING PIPE BOTH AS TO LINE AND GRADE, BEFORE HE STARTS TO LAY THE PROPOSED SEWER. THE COST OF THIS OPERATION SHALL BE INCLUDED IN THE PRICE BID FOR ITEM 1-2 STORM SEWER.

THE CONTRACTOR SHALL SO CONDUCT HIS OPERATIONS THAT THE FLOW OF ALL EXISTING SEWERS WILL BE MAINTAINED AT ALL TIMES. ANY ADDITIONAL LABOR OR COST INVOLVED IN MAINTAINING THIS FLOW BY PUMPING OR BY ANY OTHER APPROVED METHOD WHICH IS NECESSARY FOR THE COMPLETION OF THIS PROJECT SHALL BE INCLUDED IN THE PRICE BID PER LINEAR FOOT OF STORM SEWERS, ITEM 1-2.

SEEDING AND PROTECTING

QUANTITIES FOR SEEDING ARE CALCULATED FOR THE SOIL AREAS BETWEEN LINES TEN (10) FEET OUTSIDE THE CONSTRUCTION LIMITS AS SHOWN ON THE CROSS SECTIONS OR TO THE R/W LINE IF SUCH LINE IS LESS THAN TEN (10) FEET FROM THE CONSTRUCTION LIMITS.

ALL AREAS OUTSIDE THESE LIMITS WHERE THE VEGETATIVE GROWTH HAS BEEN INJURIOUSLY DISTURBED OR DESTROYED BY THE CONTRACTOR SHALL BE RESTORED AND SEEDED IN ACCORDANCE WITH THE PROVISIONS OF ITEM L-9 BY THE CONTRACTOR AT HIS OWN EXPENSE.

L-9 COMMERCIAL FERTILIZER

ALL AREAS TO BE SEEDED OR SODDED SHALL HAVE COMMERCIAL FERTILIZER (10-6-4) APPLIED AT THE RATE OF TWENTY (20) POUNDS PER 1,000 SQ. FT. THE FOLLOWING SEED MIX SHALL BE USED ON ALL AREAS:

20% KENTUCKY BLUEGRASS (POA PRATENSIS)
20% KENTUCKY 31 PESCUE (FESTUCA ELATIOR VAR KY. 31)
40% CREEPING REDFESCUE (FESTUCA RUBRA)
15% RED TOP (AGROSTIS ALBA)
5% WHITE DUTCH CLOVER (TRIFOLIUM REPENS)

UTILITIES

FOLLOWING, IS A LIST OF THE UTILITIES WITHIN THE LIMITS OF PART 4 CONSTRUCTION:

EAST OHIO GAS CO.
CITY OF CLEVELAND WATER DEPT.
CLEVELAND ELECTRIC ILLUMINATING CO.
MUNICIPAL ELECTRIC LIGHT AND POWER CO.
OHIO BELL TELEPHONE CO.

OTHER NOTES

LIGHTING - SHEET - 5

DRAINAGE - SHEET - 17

STRUCTURES - SHEET - 30

MICROFILMED
FEB 25 1983

EARTHWORK QUANTITIES	
ITEM	QUANTITY
Total Excavation	19,059
Total Embankment	20,870
Total Embankment +1.15	24,000
Total Borrow	5,000

GENERAL SUMMARY ESTIMATED QUANTITIES

FED. ROAD DIV. NO.	STATE	FED. AID PROJ. NO.	TYPE FUNDS	6 67
2	OHIO			

CUYAHOGA COUNTY
CITY OF CLEVELAND
INNER BELT FREEWAY - PART 4
WEST APPROACH TO CENTRAL VIADUCT
CUY-42R-1743

QUANTITIES

TYPE CODE 7221

ITEM NO.	RAMPS			LANES		STREETS					GENERAL	TOTAL	ITEM NO.	UNIT	DESCRIPTION	
	W-1	W-2	W-3	A	B	ABBEY	FAIRFIELD	W. 13TH. PL.	W. 14TH.	W. 15TH.						
PAVEMENT																
B-33	249	174	241	385	262							1311	B-33	Sq. Yds.	3" Bituminous Macadam Base Course, Type "A"	
B-119	35	24	33	53	36							181	B-119	Cu. Yds.	Crushed Aggregate Base Course	
I-7	75	96										171	I-7	Sq. Yds.	Reinforced Concrete Approach Slabs (T=13")	
I-11												2000	I-11	Lin. Ft.	Sandstone Curb Reset	
I-11	682	896	576	762	997	790						2703	I-11	Lin. Ft.	6" x 18" Sandstone Curbs, as per plan.	
I-12				164								164	I-12	Lin. Ft.	Standard Type 2 Modified Curb and Gutter	
I-22			225	712	627	103						1667	I-22	Cu. Yds.	Subbase, Grading "C" or "D"	
T-30	87	61	84	135	96							463	T-30	Gal.	Bituminous Prime Coat, Sec. M 5.7 Rt-2 of Rt-3, or Sec. M 5.3, MC-0 or MC-1	
T-31	62	44	60	96	66							328	T-31	Gal.	Bituminous Surface Treatment - Bituminous Material, as per plan.	
T-31	2	2	2	3	2							11	T-31	Cu. Yds.	Bituminous Surface Treatment - No. 6 Aggregate	
T-71	1730	2190	1082	1631	1422	1293						9348	T-71	Sq. Yds.	9" Reinforced Portland Cement Concrete Pavement	
ROADWAY																
E-1			862	3509	12,738	1950						19,059	E-1	Cu. Yds.	Roadway Excavation, as per plan.	
E-1												10,574	E-1	Sq. Yds.	Compacted Subgrade	
E-4												3,000	E-4	Cu. Yds.	Borrow	
E-8							117	24	13	4516	3	4673	E-8	Sq. Yds.	Removal and Disposal of Existing Rigid Pavement	
E-8							356	109	60	1645		2170	E-8	Lin. Ft.	Removal for Reuse of Existing Curb (Sandstone)	
Special												120	Special	Lin. Ft.	Temporary Barricade	
Special												1	Special	Each	Single Pole Overhead Sign Assembly, Type "A"	
E-11												156	E-11	M. Gal.	Water	
I-13							4808	819				5627	I-13	Sq. Ft.	4" Concrete Sidewalk, as per plan.	
I-15	6625	400	300									1362.5	I-15	Lin. Ft.	Guard Rail, Steel Beam Type (Deep), As per plan	
L-9			3,117	10,551	10,737	1217						25,622	L-9	Sq. Yds.	Seeding and Protecting, as per plan	
L-9												2.31	L-9	Tons	Commercial Fertilizer (10-6-4)	
L-10	83											83	L-10	Sq. Yds.	Sodding including 2" galvanized wire mesh	
T-10												50	T-10	Cu. Yds.	Traffic Compacted Surface Course for Maintaining Traffic	
M-10												1	M-10	Tons	Calcium chloride Furnished and Applied for Maintaining Traffic	
S-25												Lump	Lump	# S-25	Lump Sum	Electrical Lighting System Part A
S-25												Lump	Lump	# S-25	Lump Sum	Electrical Lighting System Part B
S-25												Lump	Lump	S-25	Lump Sum	Electrical Grounds for Structure

DRAINAGE

ITEM NO.	DESCRIPTION	UNIT	TOTAL
I-2	12" Class A Storm Sewers	Lin. Ft.	247
I-2	12" Class A Storm Sewers Under Pavement or Approaches, Sec. M-6.5(b) or Sec. M-6.8(b)	Lin. Ft.	89
I-2	12" Class B Storm Sewers	Lin. Ft.	381
I-2	12" Class B Storm Sewers Under Pavement or Approaches	Lin. Ft.	545
I-2	15" Class B Storm Sewers	Lin. Ft.	145
I-2	15" Class B Storm Sewers Under Pavement or Approaches	Lin. Ft.	442
I-4	6" Underdrains	Lin. Ft.	4565
I-8	Standard No. 2-2-A Catch Basins	Each	10
I-8	Standard No. 3 Catch Basins	Each	4
I-8	Standard No. 3-A Catch Basins	Each	7
I-8	Standard No. 2-6 Inlets	Each	3
I-8	Standard No. 2-10 Inlets	Each	5
I-8	Standard No. 1 Manholes	Each	2
I-8	Standard No. 2 Manholes	Each	1
I-8	Manholes Adjusted to Grade	Each	4*
I-8	Manhole Frames and Covers, Furnished and Placed (City Standard Casting)	Each	4*
I-16	Manholes Abandoned	Each	1
I-16	Inlets Abandoned	Each	8

STRUCTURES OVER 20 FT. SPAN
For Quantities, Bridge No. CUY-42R-17.50, see Sheet N° 31.

* 100% City Participation
No Federal Participation on Abbey Ave.
* State and Federal Funds Do Not Participate on 1 San. M.H. Adjusted to Grade and 1 M.H. Frame and Cover Furnished and Placed. See sheet 19-A for Frame and Cover.


SCALE None
MADE BY DATE HOWARD, NEEDLES, TAMMEN & BERGENDOFF CONSULTING ENGINEERS
TRCD DATE 1-27-56
CKD DATE 4-27-56
KANSAS CITY CLEVELAND NEW YORK
914 SHEET 6

TYPE T-71


FED. ROAD DIV. NO.	STATE	FED. AID PROJ. NO.	TYPE FUNDS	7/67
2	OHIO			

UNCORRECTED
FEB 25 1968


CUYAHOGA COUNTY
CITY OF CLEVELAND
INNER BELT FREEWAY - PART 4
WEST APPROACH TO CENTRAL VIADUCT
CUY-42R-17.43
TYPICAL CROSS SECTIONS




LANE B
STA. 0+61.52 TO STA. 2+4000=178.48 LIN. FT.



RAMP W-2
STA. 8+96.92 TO STA. 10+96.47=199.55 LIN. FT.




LANE A
STA. 3+25.00 TO STA. 7+63.67=438.67 LIN. FT.
Sta. 7+63.67 to Sta. 2+18.59, Approach



RAMP W-2
Sta. 0+00.00 to Sta. 5+22.00 Structure
Sta. 5+22.00 to Sta. 5+47.00 Approach Slab
Sta. 5+47.00 to Sta. 6+11.02, Approach
STA. 6+11.02 TO STA. 8+96.92 = 285.90 LIN. FT.

Guard Rail:
Rt. Sta. 6+41.75 to 7+75.00
Lt. Sta. 5+32.00 to 7+86.44

PARTIAL SECTION
LANE A
Sta. 6+05.00 to Sta. 7+68.59




LANE A
STA. 1+97.13 TO STA. 3+25.00=127.87 LIN. FT.

Note:
Stabilized Shoulder
to be sloped 3/8" per ft
for Normal Pavement
slope of 3/8" per ft.

LEGEND

- (A) 9" Reinforced Portland Cement Concrete Pavement, Item T-71
- (B) 6"x18" Sandstone Curb (See Pav't Details for Gutter), Item I-11
- (C) Standard Type 2 Modified Curb and Gutter, Item I-12
- (K) Standard Longitudinal key joint
- (L) Standard Longitudinal Joint
- (1) 3" Penetration Macadam Base Course, Item B-33
- (2) 5" Crushed Aggregate Base, Item B-119
- (3) Bituminous Prime Coat, Item T-30, Sec. M-5.7 RT-2 or RT-3 or Sec. M-5.3 MC-0 or MC-1 applied at rate of 0.35 gal. per sq. yd.
- (4) Subbase (Grading Cor. D), Item I-22
- (5) 6" Underdrain - See Sheet 14, Detail I For Details of Underdrain Trench.
- (6) Item T-31 Seal Coat using 0.25 gal. bituminous material and 0.008 c.y. No. 6 Aggregate per sq. yd. (Fortype of Bituminous Material see table on sheet 8)



LANE B
STA. 2+40.00 TO STA. 5+44.90=304.90 LIN. FT.




MICROFILMED
FEB 25 1983

TYPE T-71

FED. ROAD DIV. NO.	STATE	FED. AID PROJ. NO.	TYPE FUNDS	8
2	OHIO			67

CUYAHOGA COUNTY
CITY OF CLEVELAND
INNER BELT FREEWAY - PART 4
WEST APPROACH TO CENTRAL VIADUCT
CUY-42R-17.43

TYPICAL CROSS SECTIONS



- LEGEND**
- (A) 9" Reinforced Portland Cement Concrete Pavement, Item T-71
 - (B) 6"x18" Sandstone Curb, Item I-11
 - (C) 4" Portland Cement Concrete Sidewalk, Item I-13
 - (L) Standard Longitudinal Joint
 - (1) 3" Penetration Macadam Base Course, Item B-33
 - (2) 5" Crushed Aggregate Base, Item B-119
 - (3) Bituminous Prime Coat, Item T-30, Sec. M-5.7 RT-2 or RT-3 or Sec. M-5.3 MC-0 or MC-1 applied at rate of 0.35 gal. per sq. yd.
 - (4) Subbase (Grading C or D), Item I-22
 - (5) 6" Underdrain. See Sheet 14, Detail I for Details of Underdrain Trench.
 - (6) *Item T-31 Seal Coat using 0.25 gal. bituminous material and 0.008 cu. yd. No. 6 Aggregate per sq. yd.




*Item T-31. The variety and grade of bituminous material used in the seal coat shall depend upon the type of bituminous material used in the B-33 Bituminous Macadam Base Course as specified in the following table:

Bituminous Material Used in Item B-33	Bituminous Material to be used for Item T-31
Sec. M-5.7 RT-11 or RT-12	Sec. M-5.7 RT-8 or RT-9
Sec. M-5.1 (B5-100) or Sec. M-5.5 RS-1	Sec. M-5.2 RC-3; Sec. M-5.3 MC-5; Sec. M-5.5 RS-1 or RS-2; or Sec. M-5.12 CBAE-3

MICROFILMED
FEB 25 1983

FED. ROAD DIV. NO.	STATE	FED. AID PROJ. NO.	TYPE FUNDS	9
2	OHIO			67

CUYAHOGA COUNTY
CITY OF CLEVELAND
INNER BELT FREEWAY - PART 4
WEST APPROACH TO CENTRAL VIADUCT
CUY-42R 17.43
PAVEMENT DETAILS



SCALE 1"=50'
MADE BY DATE HOWARD, NEEDLES, TAMMEN & BERGENS DOFF CONSULTING ENGINEERS
TRCD. B.M.O. DATE 1-4-56 KANSAS CITY CLEVELAND NEW YORK
CKD. H.K.M. DATE 1-9-56
914 SHEET 9



MICROFILMED
FEB 25 1983

FED. ROAD DIV. NO.	STATE	FED. AID PROJ. NO.	TYPE FUNDS
2	OHIO		

10
67



CUYAHOGA COUNTY
CITY OF CLEVELAND
INNER BELT FREEWAY - PART 4
WEST APPROACH TO CENTRAL VIADUCT
CUY - 42 R - 17.43

PROFILES OF LANES AND RAMPS



Note: Profile Grade is on Baseline.

Bench Mark:
BM 369, Approx. 41' N of
of Kenilworth Ave. and 39' E
of c. of W. 14th St.
Elev. 678.294





RECORDED
FEB 25 1967

FED. ROAD DIV. NO.	STATE	FED. AID PROJ. NO.	TYPE FUNDS	11 67
2	OHIO			

CUYAHOGA COUNTY
CITY OF CLEVELAND
INNER BELT FREEWAY - PART 4
WEST APPROACH TO CENTRAL VIADUCT
CUY-42R-1743


PROFILE OF
RAMPS AND STREETS




Bench Mark:
OM 369, Approx 41' N. of &
of Kenilworth Ave. and 39' E.
of & of W 14th St
Elev. 678.294

CUYAHOGA COUNTY
CITY OF CLEVELAND
INNER BELT FREEWAY - PART 4
WEST APPROACH TO CENTRAL VIADUCT
CUY-42R-17.43
INTERSECTION DETAILS
AND CONTOURS


MICROFILMED
FEB 25 1983




FAIRFIELD AVE., LANE "A", LANE "B" & RAMP "W-1" & RAMP "W-2"




LANE "B" & RAMP "W-2"




RAMP "W-2" & RAMP "W-3"




ABBAY AVE. & RAMP "W-3"



ABBAY AVE., LANE "A" & W. THIRTEENTH PLACE



ABBAY AVE. & W. FOURTEENTH ST.



ABBAY AVE. & LANE "B"


LEGEND
L - Standard Longitudinal Joint
Z - Standard Key Joint Without Tie Bars
K - Expansion Joint Without Dowels
*E - Expansion Joint With Dowels
*C - Standard Contraction Joint
B - Butt Joint Without Tie Bars
* Note: Only a part of the required expansion and contraction joints are shown on these details. The maximum spacing of contraction joints and the location of expansion joints at structures shall in all cases be in accordance with Std Drawing No. T.1 and the specifications.

MICROFILMED
FEB 25 1960


FED. ROAD DIV. NO.	STATE	FED. AID PROJ. NO.	TYPE FUNDS	13 67
2	OHIO			

CUYAHOGA COUNTY
CITY OF CLEVELAND
INNER BELT FREEWAY - PART 4
WEST APPROACH TO CENTRAL VIADUCT
CUY-42 R-17.43


MISCELLANEOUS DETAILS





DETAIL "A"
TYPE 2 MODIFIED CURB AND GUTTER
Not to Scale



DETAIL "D"
PLAN OF CURB AND GUTTER TRANSITION
Scale: $\frac{3}{8}$ " = 1'-0"




DETAIL "B"
TYPICAL NOSE AND THROAT DETAILS
MERGING RAMP
Scale: 1" = 20'




* Note:
1" Radius for 6" Gutter
3" Radius for 4" Gutter
Concrete nose to be Class "D" concrete and shall be included in price bid per linear foot of Item 1-11, 6" x 18" Sandstone Curb.

DETAIL "E"
NOSE TERMINATION OF SANDSTONE CURB
Scale: $\frac{3}{4}$ " = 1'-0"



DETAIL "C"
TYPICAL NOSE AND THROAT DETAILS
DIVERGING RAMP
Scale: 1" = 20'




Note:
For location of guard rail, see typical sections. For details of guard rail and guard rail posts see Ohio State Highway Dept. Standard Drawings I-15 Nos. 1 & 2. For shoulder widths and slopes see Typical Sections.

DETAIL "F"
GUARD RAIL DETAILS
Not to Scale



CUYAHOGA COUNTY,
CITY OF CLEVELAND
INNER BELT FREEWAY - PART 4
WEST APPROACH TO CENTRAL VIADUCT
CUY-42 R-17.43

MISCELLANEOUS DETAILS
AND
APPROACH SLABS



MICROFILMED
FEB 25 1963



**APPROACH SLAB
RAMP "W-2"**
Scale: 3/8" = 1'-0"




**APPROACH SLAB
RAMP "W-1"**
Scale: 3/8" = 1'-0"



SECTION A-A


SECTION B-B



DETAIL "H"
CURB AND SHOULDER TRANSITION
Not to Scale


Note:
Prior to placement of sod, galvanized Straight Line Poultry Fence or equivalent having 2" mesh and all wires No. 20 Gauge shall be placed on the finished grade. The 4' wide strands shall be placed at right angles to the direction of flow. The edges of each strand shall be staked with 1" x 1" x 8" wood stakes, placed at a maximum spacing of 4' and driven flush with finished grade. Each strand of fencing shall be fastened together at twelve inch intervals by means of hog rings and the fence shall be secured to the wood stakes by metal staples.
Sod shall be laid in accordance with Construction and Material specifications, Section L-10.07.
The price bid per sq. yd. for Sodding (including 2" galvanized wire mesh) shall constitute full compensation for furnishing all labor, equipment, tools, and incidentals necessary to complete this item in place, completed and accepted.
For location of Special Berm and Slope Protection see Paving Plans, Sheet No. 9

DETAIL "G"
SPECIAL BERM AND SLOPE PROTECTION
Not to Scale



DETAIL "I"
CURB-UNDERDRAIN DETAILS
Scale: 1" = 1'-0"

ESTIMATED QUANTITIES			
Item	Description	Ramp "W-1"	Ramp "W-2"
1-7	Reinforced Concrete Approach Slabs (T=13")	7.5 Sq. Yds.	96 Sq. Yds.




DETAIL "J"
**TYPICAL SHOULDER TRANSITION
AT WING WALL**
Not to Scale

UNRECORDED
FEB 25 1963

FED. ROAD DIV. NO.	STATE	FED. AID PROJ. NO.	TYPE FUNDS	15 67
2	OHIO			

CUYAHOGA COUNTY
CITY OF CLEVELAND
INNER BELT FREEWAY-PART 4
WEST APPROACH TO CENTRAL VIADUCT
CUY-42R-1743
EXISTING UTILITIES



EXISTING UTILITIES








LEGEND

R/W	MELP		
CURB	CEI LIGHT	/	/
SEWER	OBT	—	—
WATER	LIGHT POLE	⊕	
GAS	POLE (GENERAL)	⊗	

SCALE 1"=50'
MADE BMO DATE 1-5-59 HOWARD, NEEDLES, TAMMEN & BERGENDOFF
TRCD BMO DATE 1-7-59 CONSULTING ENGINEERS
CKD HKM DATE 5-4-56 KANSAS CITY CLEVELAND NEW YORK
914 SHEET 15

GUYAHOGA COUNTY
CITY OF CLEVELAND
INNER BELT FREEWAY - PART 4
WEST APPROACH TO CENTRAL VIADUCT
CUY-42 R-17.43
LIGHTING DETAILS

MICROFILMED
FEB 25 1963



- LEGEND**
- Underdeck lighting luminaire equal to G.E. Form 205
 - II, 15000 lumens, 10' bracket
 - III, 15000 lumens, 10' bracket, use 8' bracket at Sta. 6+00, Abbey. & at Sta. 0+24 - Ramp "W-1"
 - III, 10000 lumens, 10' bracket, use 8' brackets at Sta. 0+24, Ramp "W-1"
 - III, 10000 lumens, 15' bracket.
 - * Glare shield
 - Future roadway lights. Conduits and parapet junction boxes by Contractor.
 - ▲ OISC distribution transformer, 3Kva, 110/220Vac. sec. for underdeck lighting, by Power Co.
 - No. 8 AWG, 5000 V. cable, 6.6 A. Series street lighting circuit.
 - Underdeck lighting circuit
 - Transit duct designation, 3" dia., with Pull Box at the end, by Contractor.
 - ▲ Constant current transformers, 30 kw, 6.6 Amp., 7200 V. primary, 60 cycle, by Power Co.

CUYAHOGA COUNTY
CITY OF CLEVELAND
INNER BELT FREEWAY - PART 4
WEST APPROACH TO CENTRAL VIADUCT
CUY- 42 R-17.43
DRAINAGE PLAN

GENERAL NOTES

Sewers are designed by the Rational Formula based on a 10-year storm frequency flowing full.


Minimum Velocity of flow is 3.0 F.P.S. for main lines and 2.5 F.P.S. for laterals.

All stubs for bridge drainage are to be 12-inch diameter concrete pipe, set on line and grade as specified on the profiles and on the bridge plans. The stubs shall extend a minimum distance of 1 foot 0 inch outside the drainage structures.

Pipe sewers connected to existing catch basins are not shown on the plans. Where sewer pipes not shown are encountered during construction, the pipes shall be cut at the limits of construction and plugged to the satisfaction of the Engineer. Payment for cutting and plugging shall be included in the unit price bid for item E-1, "Excavation."

Payment for the removal and/or abandoning of pipe outlets necessitated by the abandoning of existing catch-basins or manholes, will be included in the unit price bid for Item I-16, "Manholes, Catch Basins, or Inlets Abandoned", unless payment is otherwise authorized specifically under other items in the plans.

Where it is necessary under Item I-8, "Manholes adjusted to grade" to replace unsatisfactory manhole frame and cover castings, payment for the new castings shall be made at the contract unit price bid per each for Item I-8 "Manhole Frame and Cover (Light)" and Item I-8 "Manhole Frame and Cover (Heavy)". Payment shall constitute full compensation for furnishing, hauling and placing all castings and any incidentals necessary to complete the item to the satisfaction of the Engineer.



LEGEND

- Existing Sewer
- Existing Catch Basin or Manhole
- Proposed Sewer
- Proposed Inlet, Catch Basin or Manhole
- Underdrain
- - - Ditch Center-line

CODE	LOCATION	DESCRIPTION	ELEV.	REMARKS
A-1	5+86 Fairfield Ave 19' Lt.	3A Catch Basin	677.85	
A-2	2+07 W-1	2-6 Inlet	679.19	
A-3	1+88 B A	17' Rt.	676.12	Top of Grate 676.95
A-4	1+00 B A	2-6 Inlet	676.30	
A-5	0+76 B A	3 Catch Basin	676.15	
A-7	8+93 B W-2	2-10 Inlet	676.95	
A-8	5+84 B B	2-6 Inlet	675.55	
A-9	6+38 B B	3 Catch Basin	675.28	
A-10	6+20 B B	14' Lt.	673.21	Top of Grate 674.04
A-11	6+90 B B	53' Rt.	673.69	Top of Grate 674.52
A-12	10+75 B W-2	28' Rt.	675.66	
A-13	11+55 B W-2	14' Rt.	676.20	
A-14	4+70 B W-3	17' Rt.	675.17	Top of Grate 676.00
A-15	5+04 B W-3	24.5' Lt.	677.98	
A-16	1+11 Abbey Ave	20' Rt. of q	678.55	
A-17	0+10 B B	2-10 Inlet	676.02	
A-18	1+00 B B	11.5' Rt.	673.50	Top of Grate 674.33
A-19	1+48 B B	3 Catch Basin	674.38	
A-20	3+35 B B	49.5' Rt.	670.90	Top of Grate 671.73
A-21	1+75 B B	11' Rt.	673.51	Top of Grate 674.34
A-22	2+50 B B	2-10 Inlet	675.44	
A-23	1+62 B B	32' Lt.	672.97	Top of Grate 673.80
A-24	1+61.5 B B	45' Lt.	673.80	Top of Cover
A-25	5+90 B A	30' Lt.	675.78	Top of Grate 676.61
A-26	6+00 B A	17' Lt.	675.97	
A-27	7+10 B A	19' Lt.	674.11	
A-28	7+18 B A	18' Rt.	672.87	Top of Grate 673.10
A-29	7+55 B A	45' Lt.	678.01	Top of Cover
A-30	6+14.52 Abbey Ave	20' Rt. of q	674.26	
A-31	6+14.52 Abbey Ave	20' Lt. of q	674.26	
A-32	7+49 W 13th Pl.	10' Rt. of q	675.61	
A-33	7+49 W 13th Pl.	3' Rt. of q	675.10	Top of Cover

CODE	LOCATION	DESCRIPTION	ELEV.	REMARKS
B-1	5+50 Fairfield Ave. 6' Lt. q	Manhole		Undisturbed
B-2	5+57 Fairfield Ave. 18' Lt. q	Catch Basin		Abandon
B-3	14+92 W 14th St.	22' Lt. q		Abandon
B-4	5+00 Fairfield	19' Lt. q	676.71	Adjust to Grade
B-5	14+92 W 14th St.	25' Lt. q		Abandon
B-6	12+58 W 14th St.	25' Lt. q		Abandon
B-7	12+48 W 14th St.	Manhole		Abandon
B-8	12+54 W 14th St.	25' Lt. q		Abandon
B-9	11+01 W 14th St	33' Rt. q	675.81	Adjust to Grade
B-10	10+03 W 14th St.	Manhole	676.21	Adjust to Grade
B-11	7+97 W 14th St.	25' Lt. q		Abandon
B-12	8+00 W 14th St.	25' Lt. q		Abandon
B-13	1+01 W 14th St.	Manhole		Undisturbed
B-14	7+20 W 14th St	Manhole		Undisturbed
B-15	6+98 W 14th St	45' Lt. q		Abandon
B-16	4+49 Abbey Ave.	1' Lt. q		Undisturbed
B-17	6+76 W 14th St.	33' Rt. q		Undisturbed
B-18	6+40 W 14th St.	48' Lt. q	675.11	Adjust to Grade

CODE	STREET	FROM	TO	SIZE	LENGTH	REMARKS
E-1	Fairfield	B-1	B-4	18	48	Undisturbed
E-2	W. Fourteenth	B-4	B-7	No. 4C	264	Undisturbed
E-3	W. Fourteenth	B-7	B-10	No. 4C	241	Undisturbed
E-4	W. Fourteenth	B-10	B-14	No. 5C	278	Undisturbed
E-5	W. Fourteenth	B-14	B-17	No. 5C	51	Undisturbed
E-6	Abbey Ave.	B-19	B-16	12	345	Undisturbed
E-7	W. Fourteenth	B-16	B-17	12	78	Undisturbed
E-8	W. Fourteenth	B-17	North	24		Undisturbed
E-9	W. Thirteenth	A-31	North	12		Undisturbed


CODE	LOCATION	ITEM I-2		LIN. FT.			
		CLASS A	CLASS B	CL. A U.P.	CL. B U.P.	CL. A U.P.	CL. B U.P.
P-1	Fairfield Ave.	A-1	B-1				
P-2	Lane A	A-2	A-3				
P-3	Rt. of Lane A	A-3	A-4			85	
P-4	Lane A	A-4	A-5				19
P-5	Lane A - Ramp W-1	A-5	B-4				65
P-7	Lane B	A-7	A-8				46
P-8	Lane B	A-8	A-9				51
P-9	Left of Lane B	A-10	A-9	21			
P-10	Lane B - Ramp W-2	A-9	A-12				85
P-11	Right of Ramp W-2	A-11	A-12	29			
P-12	Ramp W-2	A-12	A-13				72
P-13	Ramp W-2 - Lane B	A-13	B-4				45
P-14	Ramp W-3	A-14	A-15		52		
P-15	Ramp W-3	A-15	A-16				37
P-16	Abbey Ave.	A-16	B-13				19
P-17	Rt. of Lane B	A-17	A-18				
P-18	Lt. of Lane B	A-18	A-19			44	
P-19	Rt. of Lane B	A-20	A-21	157			
P-20	Rt. of Lane B	A-21	A-19	26			
P-21	Lane B	A-19	A-23				34
P-22	Lt. of Lane B	A-22	A-23			96	
P-23	Lt. of Lane B	A-23	A-24				10
P-24	Lt. of Lane A	A-25	A-26	14			
P-25	Lane A	A-26	A-27				102
P-26	Lane A	A-28	A-27			37	
P-27	Lt. of Lane A	A-27	A-29				47
P-28	Rt. of Abbey Ave.	A-29	A-30				68
P-29	Abbey Ave.	A-30	A-31				38
P-30	Lt. of Abbey Ave.	A-31	B-14				112
P-31	West 13th Pl.	A-32	A-33				10
P-32	West 14th St.	Pier 2A	B-14				35
P-33	Abutment W-2		A-21				50
P-34	Lt. of Lane A	1-W-1	A-29				25
P-35	Abbey Ave.	Dier 2A	A-29				90
P-36	Lane B	1-W-2	A-18				50

- NOTES**
- Abbreviations:**
Rt - Right
Lt - Left
U.P - Under Pavement
Directions are noted as: E, W, So. & No.
 - Call-Letters:**
Drainage structures and pipes are prefixed with the following call letters.
A - Proposed Structures
P - Proposed Pipe Sewers
B - Existing Structures
E - Existing Pipe Sewers
For sewer profiles see Sheets 13 and 19
The direction of sewer flow is indicated by arrows.
 - Elevations:**
Elevations shown in the tables are normal grade or gutter elevations for the center-line of the structure at the curb face for 3, and 3A catch basins; normal ditch and center of structure for 2-2-A catch basins; top of cover at the center for manholes; normal grade at the intersection of the center-line of cover and at curb face for all 2-6 and 2-10 inlets.
 - Underdrain Connections:**
For details of Pipe Underdrain Outlet see Standard Construction Drawings I-1, 2, 3, 4 & 5


UNRECORDED
FEB 25 1963

FED. ROAD DIV. NO.	STATE	FED. AID PROJ. NO.	TYPE FUNDS	18 67
2	OHIO			


CUYAHOGA COUNTY
CITY OF CLEVELAND
INNER BELT FREEWAY - PART 4
WEST APPROACH TO CENTRAL VIADUCT
CUY-42 R-17.43
DRAINAGE PROFILES




SEWER PROFILE A-1 TO B-1




SEWER PROFILE A-2 TO B-4




SEWER PROFILES A-7 TO B-4




SEWER PROFILE A-10 TO A-9



SEWER PROFILE A-11 TO A-12



SEWER PROFILES A-14 TO B-13



SEWER PROFILES A-17 TO A-19

LIST OF SEWER PROFILES On This Street


P-1	P-10
P-2	P-11
P-3	P-12
P-4	P-13
P-5	P-14
P-6	P-15
P-7	P-16
P-8	P-17
P-9	P-18

Note:
Scales: Horz. 1"=20'
Vert. 1"=5'


SCALE See Note
MADE BY DATE 2-3-56 HOWARD, NEEDLES, TAMMEN & BERGENOFF
TRCD BY DATE 2-8-56 CONSULTING ENGINEERS
KANSAS CITY CLEVELAND NEW YORK
914 SHEET 18

CUYAHOGA COUNTY
CITY OF CLEVELAND
INNER BELT FREEWAY - PART 4
WEST APPROACH TO CENTRAL VIADUCT
CUY - 42 R - 17.43


DRAINAGE PROFILES




SEWER PROFILES A-20 TO A-24



SEWER PROFILE A-22 TO A-23




SEWER PROFILE A-18 TO PIER I-W-2




SEWER PROFILES A-25 TO B-14


LIST OF SEWER PROFILES ON THIS SHEET	
P-19	P-25
P-20	P-26
P-21	P-27
P-22	P-28
P-23	P-29
P-24	P-30
	P-31
	P-32
	P-33
	P-34
	P-35
	P-36




SEWER PROFILE A-21 TO ABUTMENT W-2



SEWER PROFILE A-26 TO A-27



SEWER PROFILE A-32 TO A-33



SEWER PROFILE A-29 TO PIER IWI AND PIER 2A


SPECIAL MANHOLE FRAME

STANDARD CITY TYPE

Scale 3" = 1'-0"

MICROFILMED
FEB 25 1963


Grind or Chip these edges to smooth round and regular condition



PLAN

NOTE:-
All castings to be in accordance with Section M-7.2 of the Construction and Material Specifications.

NOTE:-
This Lug to be between top of frame and top of cover seat only and shall be cast without batter.




SECTION "A-A"

Weight of Frame 355 lbs.


SPECIAL COVER

STANDARD CITY TYPE

Scale 3" = 1'-0"



PLAN



SECTION "A-A"

PART SECTION "B-B"
Scale 1/2" = 1"


SIDE ELEVATION OF NOTCHES

Weight of Cover 155 lbs.


SPECIAL GRATED COVER

STANDARD CITY TYPE

Scale 3" = 1'-0"



PLAN



SECTION "A-A"

SECTION "B-B"
Scale 1/2" = 1"


"C-C" "D-D"
Scale 1/2" = 1"

This surface shall be chilled & chipped or ground to smooth round regular edges.
This surface shall be straight and smooth.

FED. ROAD DIV. NO.	STATE	FED. AID. PROJ. NO.	TYPE FUNDS	20 67
2	OHIO			

CUYAHOGA COUNTY
CITY OF CLEVELAND
INNER BELT FREEWAY - PART 4
WEST APPROACH TO CENTRAL VIADUCT
CUY - 42R - 17.43

CROSS SECTIONS



STATION	SEEDING		SUBBASE		EARTHWORK			
	WIDTH L.F.	AREA SQ. YD.	AREA S.F.	VOL. C.Y.	END AREA EXC.	AREA EMB.	VOLUME EXC.	VOLUME EMB.
3+00	81		29		65	280		
		380		50		111	468	
2+50	555		25		55	225		
		250		46		136	296	
2+00	55		25		92	94		
		167		43		147	106	
1+50	25		21		67	20		
		122		37		132	21	
1+00	19		19		76	2.5		
		97		37		150	3	
0+50	16		21		86	1		
		29		13		53	1	
0+17	0		0		0			

SCALE 1" = 10'-0"
 MADE BY DATE 2-2-56 HOWARD, NEEDLES, TAMMEN & BERGENDOFF
 TRCD. DATE 2-21-56 CONSULTING ENGINEERS
 CRO. DATE 5-4-56 KANSAS CITY CLEVELAND NEW YORK
 914 SHEET 20

Note: Sta. 0+17 Lane "A" C=0; F=0


LANE "A" STA. 0+17 TO STA. 3+00

200 180 160 140 120 100 80 60 40 20 0 20 40 60

FED. ROAD DIV. NO.	STATE	FED. AID PROJ. NO.	TYPE FUNDS	21 67
2	OHIO			

CUYAHOGA COUNTY
CITY OF CLEVELAND
INNER BELT FREEWAY - PART 4
WEST APPROACH TO CENTRAL VIADUCT
CUY-42R-17.43

CROSS SECTIONS



L.F.	SEEDING		SUBBASE		EARTHWORK		VOL.	END AREA	VOL.
	AREA	AREA	S.F.	C.Y.	EXC.	EMB.			
5+71	215		29		178	1158			
		118		54		31	220		
5+66	211		29		160	1208			
		1441		53		363	2550		
5+00	182		28		137	879			
		938		52		217	1442		
4+50	156		28		97	681			
		791		52		155	1090		
4+00	129		28.5		70	497			
		646		53		111	801		
3+50	104		28.5		50	368			
		515		53		107	600		


SCALE 1"=10'-0"
MADE JHW DATE 2-4-56 HOWARD, NEEDLES, TAMMEN & BERGENOFF
TRCD BMO DATE 2-22-56 CONSULTING ENGINEERS
CKD/HKM DATE 5-4-56 KANSAS CITY CLEVELAND NEW YORK
914 SHEET 21

220 200 180 160 140 120 100 80 60 40 20 0 20 40 50

LANE "A" STA. 3+50 TO STA. 5+71

CUYAHOGA COUNTY
CITY OF CLEVELAND
INNER BELT FREEWAY - PART 4
WEST APPROACH TO CENTRAL VIADUCT
CUY - 42R-17.43

CROSS SECTIONS




SEEDING WIDTH	SUBBASE AREA	EARTHWORK VOL.	END AREA		VOLUME	
			EXC.	EMB.	EXC.	EMB.
L.F.	SQ. YD.	S.F.	C.Y.			
7+98.59	0	0	0	0	0	0
6+90	957	18			323	16
7+31.5	257	14.5	260	13		
6+90	1190	22			403	440
6+90			Conic Sections		166	114
6+90	259	14.5	264	560		
6+83.5	175	5			64	221
6+83.5	225	28.5	270	1272		
6+83.5	249	11			100	491
6+73.5	222	28.5	267	1377		
6+73.5	1186	53			471	2350
6+25	218	31	257	1252		
6+25	1300	60			435	2410

SCALE 1"=10'-0"
MADE J.H.K. DATE 1-1-56
TRD.B.M.O. DATE 2-20-56
C.K.D.H.K.M. DATE 5-4-56

HOWARD, NEEDLES, TAMMEN & BERGENDOFF
CONSULTING ENGINEERS
KANSAS CITY CLEVELAND NEW YORK

914 SHEET 22

CUYAHOGA COUNTY
CITY OF CLEVELAND
INNER BELT FREEWAY - PART 4
WEST APPROACH TO CENTRAL VIADUCT
CUY-42R-17.43
CROSS SECTIONS



L.F.	SEEDING		SUBBASE		EARTHWORK			
	WIDTH	AREA	AREA	VOL.	END AREA		VOLUME	
	sq. yd.	sq. ft.	sq. ft.	cy.	Exc.	Emb.	Exc.	Emb.
2+21	108	24		277	553			
		104		8			95	195
2+11.5	89	24 (Ahead) 9 (Back)		261	523 (Ahead) 0 (Back)			57
		316		12			308	0
1+75	67		9	194	0			
		257		12			227	1
1+38	58		9	137	1			
		302		13			239	6
1+00	85		9	202	7			
		316		16			246	6
0+50	29		8	63	0			
		81		7			58	0
0+00	0		0	0	0			


SCALE 1"=10'-0"
MADE JHK DATE 1-11-56 HOWARD, NEEDLES, TAMMEN & BERGENDOFF
TRCD BWO DATE 2-20-56 CONSULTING ENGINEERS
CKD HAM DATE 3-4-56 KANSAS CITY CLEVELAND NEW YORK
914 SHEET 23

STA. 0+50 B LANE "B" 676.5
STA. 0+00 C=0; F=0

LANE "B" STA. 0+00 TO STA. 2+21

CUYAHOGA COUNTY
CITY OF CLEVELAND
INNER BELT FREEWAY - PART 4
WEST APPROACH TO CENTRAL VIADUCT
CUY-42R-17.43

CROSS SECTIONS




STA.	L.F.	SEEDING		SUBBASE		EARTHWORK			
		AREA	VOL.	AREA	VOL.	END AREA		VOLUME	
		SQ. YD.	CY.	S.F.	CY.	EXG.	EMB.	EXG.	EMB.
4+50	200	31		685	163				
4+00	207	30		748	286				
3+50	197	27		471	327				
3+00	150	28		609	406				
2+50	122	26.5		415	475				
	371	27			372	568			

SCALE 1" = 10'-0"
 MADE JHK DATE 1-17-56 HOWARD, NEEDLES, TAMMEN & BERGENOFF
 TRCD BMO DATE 2-22-56 CONSULTING ENGINEERS
 CKD H.A.M. DATE 5-4-56 KANSAS CITY CLEVELAND NEW YORK
 914 SHEET 24

FED. ROAD DIV. NO.	STATE	FED. AID PROJ. NO.	TYPE FUNDS	25 67
2	OHIO			

CUYAHOGA COUNTY
CITY OF CLEVELAND
INNER BELT FREEWAY - PART 4
WEST APPROACH TO CENTRAL VIADUCT
CUY-42R-17.43
CROSS SECTIONS



STA.	SEEDING		SUBBASE		EARTHWORK			
	WIDTH	AREA	AREA	VOL.	END AREA		VOLUME	
	L.F.	SQ.YD.	S.F.	C.Y.	EXC.	EMB.	EXC.	EMB.
8+54.32	0	0	0	0	0	0	0	0
		98		19			88	2
8+13	43		25		115	3		
		340		51			298	7
7+50	54		19		140	3		
		375		35			356	29
7+00	61		19		245	28		
		573		35			633	70
6+50	125		19		439	48		
		797		35			1040	46
6+00	162		19		684	2		
		903		42			1326	2
5+50	163		26.5		747	0		
		914		50			1302	6
5+00	166		28		661	7		
		1017		55			1245	157

SCALE 1"=10'-0"
MADE JHK DATE 1-23-56
TRCD BMO DATE 2-21-56
CKD H.R.M. DATE 3-4-56


HOWARD, NEEDLES, TAMMEN & BERGENDOFF
CONSULTING ENGINEERS
KANSAS CITY, CLEVELAND, NEW YORK

914 SHEET 25

LANE "B" STA. 5+00 TO STA. 8+54.32

CUYAHOGA COUNTY
CITY OF CLEVELAND
INNER BELT FREEWAY - PART 4
WEST APPROACH TO CENTRAL VIADUCT
CUY-42 R-17.43

CROSS SECTIONS




	SEEDING		SUBBASE		EARTHWORK			
	WIDTH	AREA	AREA	VOL.	END AREA		VOLUME	
	L.F.	SQ. YD.	S.F.	CY.	EXC.	EMB.	EXC.	EMB.
2+50	82		13	12	432			
		238		15			12	500
2+18	52		13	9	411			
		283		21			15	719
1+69	52		10	8	380			
		165		9			7	403
1+40.5	52		7	5	383			
		55		2			1	135
1+31	53		6	3	385			
		52		2 (Wedge)			1	115
1+22	50		3	3	302 (Ahead) 645 (Back)			
		34		0			0	83
1+18	101		0	3	480			
		35		0			1	52
1+15	107		0	3	457 (Ahead) 382 (Back)			
		153		0			1	99
1+01	90		0	0	0		0	
								35 (Conic Section)

SCALE 1" = 10'-0"
 MADE/CHK DATE 12-14-56 HOWARD, NEEDLES, TAMMEN & BERGENDOFF
 TRCD/ENR DATE 2-22-58 CONSULTING ENGINEERS
 CKD/HAM DATE 3-4-56 KANSAS CITY CLEVELAND NEW YORK
 914 SHEET 26

STA. 1+01 C=0; F=0; Seeding = 90'

RAMP "W-3" STA. 1+01 TO STA. 2+50

CUYAHOGA COUNTY
CITY OF CLEVELAND
INNER BELT FREEWAY - PART 4
WEST APPROACH TO CENTRAL VIADUCT
CUY-42R-17.43
CROSS SECTIONS




STA	SEEDING		SUBBASE		EARTHWORK			
	WIDTH L.F.	AREA SQ.YD.	AREA S.F.	VOL. C.Y.	END AREA		VOLUME	
					EXC.	EMB.	EXC.	EMB.
5+97.1	0	0	0	0	0	0	0	0
		73		5			35	0
5+50	30		6		40	0		
		223		37			197	0
5+05	43		30		196	0		
		223		36			314	0
4+50	46		13		113	0		
		308		24			146	30
4+00	65		13		45	32		
		411		24			65	182
3+50	83		13		30	165		
		431		24			42	412
3+00	72		13		15	279		
		428		24			25	658

SCALE 1" = 10'-0"
MADE JHK DATE 12-7-55 HOWARD, NEEDLES, TAMMEN & BERGENDOFF
TRCD BMO DATE 2-21-56 KANSAS CITY CLEVELAND NEW YORK
CKD H.K.M. DATE 5-4-56

CUYAHOGA COUNTY
 CITY OF CLEVELAND
INNER BELT FREEWAY - PART 4
 WEST APPROACH TO CENTRAL VIADUCT
 CUY - 42R - 17.43
 CROSS SECTIONS

Note: Sta. 7+87± C=0; F=0




L. F.	SEEDING		SUBBASE		EARTHWORK			
	WIDTH	AREA	AREA	VOL.	END AREA	VOLUME		
	SQ. YD.	S.F.	C.Y.	EXC.	EMB.	EXC.	EMB.	
7+87	0	0	0	0	0	0	0	
		88		8		131	0	
7+50	43	12		192				
		256		22		423		
7+00	49	12		263				
		280		22		494		
6+50	52	12		268				
		297		22		506		
6+00	55	12		278				
		239		22		341		
5+50	31	12		90				
		57		7		55	0	
5+17±	0	0		0	0	0	0	

SCALE 1" = 10'-0"
 MADE JHK DATE 1-3-56 HOWARD, NEEDLES, TAMMEN & BERGENDOFF
 TRCD. BMD DATE 2-3-56 CONSULTING ENGINEERS
 OKD. HKM. DATE 5-4-56 KANSAS CITY CLEVELAND NEW YORK
 914 SHEET 28



Note: Sta. 5+17± C=0; F=0

ABBAY AVE. EXT. STA. 5+17± TO STA. 7+87±

CUYAHOGA COUNTY
CITY OF CLEVELAND
**INNER BELT FREEWAY
WEST APPROACH VIADUCT**
CUY - 42R - 17.43



PROPOSED STRUCTURE
Type: Continuous steel beams and girders with concrete deck and substructure.
Span: Varies (see plan)
Roadway: 2 @ 52'-0" with 2'-3'-0" sidewalks
Loading: CF 8000
Skew: Varies.
Surface Course: 2 1/2" asphaltic concrete (not part of this contract)



Note:
Average vertical pile length for all piers, abutments, and for the retaining wall = 60'-0"

U. S. ROUTE 42 RELOCATION
**INNER BELT FREEWAY
WEST APPROACH VIADUCT**
BR. NO. CUY-42R-1750

GENERAL PLAN AND ELEVATION
CLEVELAND CUYAHOGA COUNTY OHIO

SCALE 1" = 30' 0"
MADE A.S.B. DATE 2-17-56
TRCD M.A.C. DATE 6-2-56
CKD C.C.R. DATE 2-27-56

HOWARD, NEEDLES TAMMEN & BERGENDOFF
CONSULTING ENGINEERS
KANSAS CITY CLEVELAND NEW YORK
914 (2)WB SHEET 29

Rev 11-26-56
Rev. 7-5-56

UNAPPROVED
FEB 25 1956

GENERAL NOTES

FED. ROAD DIST. NO.	STATE	FEDERAL AID PROJECT NO.	TYPE FUNDS
2	OHIO		

30
67

CUYAHOGA COUNTY
CITY OF CLEVELAND
INNER BELT FREEWAY
WEST APPROACH VIADUCT
CUY-42R-1743

1. SPECIFICATIONS

- A. DESIGN SPECIFICATIONS - Specifications for design of Highway structures of the State of Ohio Department of Highways, October 1, 1951, together with revisions thereof dated July 15, 1952, April 1, 1954, and February 1, 1955, with a load frequency rating CP-2000-51.
- B. CONSTRUCTION SPECIFICATIONS - Construction and Material Specifications of the State of Ohio Department of Highways, dated January 1, 1955.
- Supplemental Specifications of the State of Ohio Department of Highways number S-114, dated August 30, 1955.

2. DATUM FOR ELEVATIONS

All elevations are Regional Geodetic Survey Data.

3. BORINGS

Boring information, logs and samples of materials encountered may be examined in the Cleveland City Engineer's Office, but the borings are not guaranteed to present a complete picture of subsurface conditions to be encountered.

4. PILING

- A. Piles shall be driven to a minimum bearing capacity of 40 tons for the abutments and retaining wall and 50 tons for the piers. The length of penetration of every pile shall be at least 80% of the estimated average pay length of the pertinent piers, abutment or retaining wall as indicated on the plans unless a lesser penetration is approved by the Director.
- B. The pile space dimensions given on the plans are at the level of the bottom of footing.

5. UTILITIES

Any utility facilities encountered at the site of the work which will interfere with portions of the finished Freeway or structures, will be removed or relocated by others, unless otherwise shown. The Contractor shall coordinate his operations with the work of the utility owners or others who may be making the relocations and shall notify the owners of the utilities of his schedule sufficiently in advance to permit them to make the necessary alterations.

6. CLASS OF CONCRETE

All superstructure concrete shall be Class "C".

All substructure concrete shall be either Class "C" or Class "E" as shown in the plans.

7. GRAVEL

Gravel, if used as coarse aggregate, shall be according to Section M-3.93 instead of M-3.91 for Class "C" concrete in the superstructure. Gravel meeting the requirements of Section M-3.93 also may be used for other concrete in this structure.

8. CONCRETE FINISH

The railing parapets, curb faces, fascias of decks and exposed surfaces of substructure units and retaining wall shall receive a rubbed surface finish. All other exposed surfaces shall be governed by the provisions of Item S-1.

9. REINFORCING STEEL

Reinforcing steel shall conform to Item S-4 of the Construction and Material Specifications. Bars shall have deformations conforming to A.S.T.M. Designation A-305.

All laps in reinforcing bars at splices will be 30 bar diameters.

Bars shall be, unless otherwise shown, 3 inches clear from the face of the concrete in the bottoms of footings, 1 inch clear in slabs and 2 inches clear elsewhere.

Bar sizes are designated on the plans by numbers, the first digit in three digit marks and the first two digits in four digit marks indicate the size of the bar.

10. WATERPROOFING

Expansion and contraction joints shall be waterproofed as shown on the plans.

Type "C" waterproofing, for surfaces in contact with bituminous wearing surface, shall be furnished under another contract.

11. BITUMINOUS WEARING SURFACE

The bituminous wearing surface shall be furnished under another contract.

12. SUB DRAINAGE FOR BITUMINOUS WEARING SURFACE

The copper tubes required on the bridge deck slab, for sub-drainage, will be paid for at the contract unit price per cubic yard of superstructure concrete under Item S-1.

The steel angles over the copper tubes shall be furnished under another contract.

13. DIMENSIONS

Dimensions given on the plans are measured horizontally and at 60° F. unless shown otherwise.

14. STRUCTURAL STEEL

- A. WELDED STEEL - The steel for beams A, B, C, D and E shall conform to A.S.T.M. Designation A-373. All other structural steel shall conform to either A.S.T.M. A-7 (as per Section M-7.4(a) of the Construction and Material Specifications) or to A-373.
- B. All welding shall be Class "A".
- C. CARBON STEEL CASTINGS - ^{Erection only} Erected, Item S-7, refers to the castings for the expansion joint at the West End Pier. They are on the construction site and shall be erected under this contract.
- D. PAYMENT FOR STRUCTURAL STEEL - In accordance with Sec. S-7.28, the weight of waste material, such as is removed by burning, cutting, coping, clipping, machining, punching, drilling, etc., shall not be considered as pay weight. However, material removed to form rivet and bolt holes shall be included in the pay quantity provided that only those portions of the rivets and bolts projecting beyond the holes are included in the pay quantity. Furthermore, any thickness and weight of members in excess of that called for on the plans (due to overweight or other cause) shall not be included in determining the weight to be paid for, unless an increase in the size of a member has been requested by the Director.

E. Painting of superstructure metalwork shall be according to Item S-8 of the Construction and Material Specifications except as modified herein.

1. Coats of Paint

The paint shall be applied by brushing in four coats as follows:

- a. A first coat of red lead paint applied in the shop on clean metal surfaces prepared for painting as specified in Section S-8.03.
- b. A second coat of red lead paint applied in the field after erection. For surfaces that will be inaccessible after erection, this second coat may be applied either in the shop or in the field.
- c. A third and a fourth coat consisting of white lead paint. The fourth coat shall be tinted a medium shade of gray that meets the approval of the Director of Highways and the City of Cleveland.
- d. Light standards and the steel parts of handrails shall be painted with a first and a second coat of red lead paint as specified for the remainder of the structural steel, but the third and fourth coats shall be of aluminum paint.

2. Materials

a. The paint to be used for the first and second red lead coats shall be of the following composition and properties:

Paint

Red lead (97% grade) - 99.6% (minimum)
Aluminum Stearate - 0.3 - 0.4%

Vehicle

Raw linseed oil 35% to 50%
* Pale heat bodied linseed oil (2) 15% to 30%
Volatile mineral spirits and drier 35% (maximum)

* The acid number of this oil shall not be over 11, the color not darker than 7 (Gardener 1933) and shall have a Wijs iodine value of 110 - 125.

Paint	First Coat	Second Coat
Pigment	73% (minimum)	77% (minimum)
Vehicle	27% (maximum)	23% (maximum)
Weight per gallon	21.0 Lbs. (minimum)	24.0 Lbs. (minimum)

Consistency 175 Gr to 250 Gr. (A.S.T.M. Method D562-42T or Federal Specification TT-P-141a, Method 428.1)

Fineness of grind 5 (minimum)

Drying Time-Set to Touch-6 Hours (maximum) and Dry through-36 Hours (maximum)

The paint shall be well ground, shall not settle excessively or cake in the container, shall be readily broken up with a paddle to a smooth uniform paint having good brushing properties. The paint, when brushed on a clean, smooth steel panel maintained in a vertical position, shall dry to a smooth uniform finish free from roughness, grit, unevenness, streaking, separation, running, curtaining and sagging. For contrast between the first and second coats, the second coat shall be tinted with lamp-black-in-oil to change its color to a chocolate brown.

b. The white lead third and fourth coats of paint shall conform to Section M-9.6(b) of the Construction and Material Specifications.

c. The aluminum third and fourth coats of paint shall conform to Section M-9.12 of the Construction and Material Specifications.

15. HANDRAIL

The finished handrail shall be free of burrs, sharp corners and rough surfaces.

The final adjustment of the handrail shall be such that the aluminum tubing shall not depart more than 1/8 inch from correct line or grade, and shall show no abrupt kinks.

The Contractor shall furnish a pattern of the cast aluminum handrail post to the City of Cleveland for use in future replacement of damaged posts.

16. ROADWAY DRAINAGE SYSTEM

This item consists of all 6 inch round galvanized steel or wrought iron pipe, cleanouts, reducers, elbows, scuppers, and Type A and B hangers.

The 12 inch round pipe, including tees, from the piers and abutment to the inlets is included in the roadway quantities.

17. ELECTRIC LIGHTING SYSTEM

For general notes and payment for lighting system see Sheet 5.

U. S. ROUTE 42 RELOCATION
INNER BELT FREEWAY
WEST APPROACH VIADUCT
BR. NO. CUY-42R-1750

GENERAL NOTES

CLEVELAND CUYAHOGA COUNTY OHIO

SCALE
MADE 836 DATE 2-1-56
TRCD. DATE
CKD VPS DATE 2-10-56

HOWARD, NEEDLES, TAMMEN & BERGENDOFF
CONSULTING ENGINEERS
KANSAS CITY CLEVELAND NEW YORK
914(2)WB SHEET 30

REVISED
FEB 25 1956

FED. ROAD DIV. NO.	STATE	FEDERAL AID PROJECT NO.	TYPE FUNDS
2	OHIO		

31
67

CUYAHOGA COUNTY
CITY OF CLEVELAND
INNER BELT FREEWAY
WEST APPROACH VIADUCT
CUY-42R-17.43

ESTIMATED QUANTITIES

ITEM	DESCRIPTION	UNIT	SUPER-STRUCTURE	ABUTMENT W-1	RAMP W-1 RET WALL	PIER IW-1	ABUTMENT W-2	PIER IW-2	PIER 2W-2	PIER 1A	PIER 2A	PIER 3A	WEST END PIER	GENERAL	TOTAL	AS BUILT
E-2	COFFERDAMS, CRIBS AND SHEETING	LUMP SUM												Lump Sum		
E-2	UNCLASSIFIED EXCAVATION	CU. YDS.		90	193	65	119	74	74	222	314	204,809			1,355	C-3, +5 1360
S-1	CLASS "C" CONCRETE-PIER COLUMNS AND CAPS	CU. YDS.				20		31	16	108	125	90			380	
S-1	CLASS "C" CONCRETE - SUPERSTRUCTURE	CU. YDS.	1,805										10 20		1,815	C-15 +10 1825
S-1	CLASS "E" CONCRETE-ABUTMENTS, RET. WALL AND WEST END PIER	CU. YDS.		63	94 106		83						350 366		500	C-15 +16 618
S-1	CLASS "E" CONCRETE-FOOTINGS	CU. YDS.				23		27	24	85	130	86 90			375	C-3 +4 379
S-3	WATERPROOFING - PREMOLDED SEALING STRIP	LIN. FT.			15										15	
S-3	TYPE "B" WATERPROOFING	SQ. YDS.			2										2	
S-4	REINFORCING STEEL	LBS.	563,601	4,369	6,882	6,058	5,290	9,757	5,907	31,501	35,954	28,807 29,723	20,695	819	219,635	C-3 +381 C-16 +824 719,332
S-7	STRUCTURAL STEEL	LBS.	3,498,000												3,498,000	C-16 C-38,781 3,536,781
S-7	CARBON STEEL CASTINGS	LBS.	30,800												30,800	C-16 C-11,390 19,410
S-7	CARBON STEEL CASTINGS - ERECTION ONLY	LBS.	14,300												14,300	C-16 C-4,910 13,710
S-7	HIGH STRENGTH STEEL CASTINGS AND FORGINGS	LBS.	30,700												30,700	C-16 C-6,618 22,082
S-8	FIELD PAINTING OF STRUCTURAL STEEL AND CASTINGS (3 COATS)	LBS.	3,573,800												3,573,800	C-16 C-19,183 3,592,983
S-9	1" GRAY RUBBER PREFORMED EXPANSION JOINT FILLER	SQ. FT.			20					65	54	51			190	
S-14	RAILING (ALUMINUM RAIL AND SUPPORTS, CONCRETE PARAPET AND END POSTS)	LIN. FT.	1,354,138												1,354	C-15, +30 1384
S-16	FIRST TEST PILE (14" CAST-IN-PLACE REINFORCED CONCRETE)	LUMP SUM												Lump Sum		
S-17	FIRST PILE TEST LOAD	LUMP SUM												Lump Sum		
S-17	SUBSEQUENT PILE TEST LOADS	EACH												1-0		C-14, -1 -0-
S-18	12" CAST-IN-PLACE REINFORCED CONCRETE PILES	LIN. FT.		729	1215		729								2,673	C-14-1170 1503
S-18	14" CAST-IN-PLACE REINFORCED CONCRETE PILES	LIN. FT.				840		900	735	3,660	5,834	2,880			14,849	C-14-8695 6154
S-29	POROUS BACKFILL	CU. YDS.		3	12		5								20	
S-29	ROADWAY DRAINAGE SYSTEM	LBS.	2,300			500	100	500			1,100				4,500	

* SEE NOTE 14 ON SHEET 30.
△ SEE NOTE 16 ON SHEET 30.

U. S. ROUTE 42 RELOCATION
INNER BELT FREEWAY
WEST APPROACH VIADUCT
BR. NO. CUY-42R-1750

ESTIMATED QUANTITIES

CLEVELAND CUYAHOGA COUNTY OHIO



SCALE: _____
MADE: R.B.G. DATE: 3-27-56
TRCD: R.B.G. DATE: 3-31-56
CKD: J.S.H. DATE: 3-28-56

HOWARD, NEEDLES, TAMMEN & BERGENDOFF
CONSULTING ENGINEERS
KANSAS CITY CLEVELAND NEW YORK

914 (2) WB SHEET 31


CUYAHOGA COUNTY
CITY OF CLEVELAND
INNER BELT FREEWAY
WEST APPROACH VIADUCT
CUY-42R-17.43

LEGEND

Structures to be removed 
Structures to remain 

* These utilities to be removed by others.

▲ See sheet 39 for constructions adjacent to 5' brick sewer.




GROUND PLAN
Scale: 1" = 30'-0"

Boring	Station	Soil Description	Elevation	
BW-1	4	Small Gravel	675.8	
	13		657.8	
	18			
	20	Wet	633.8	
	18		623.8	
	78	Fine	613.8	
	26			
	42	Plastic		
	16			
	12	Moist Plastic	575.8	
	BW-2	4	Dirty	678.5
		9	Small	666.5
56			653.0	
41			654.0	
41		Yellow		
90		Wet, Yellow		
52		Gray		
297				
22		Fine	616.5	
22			617.5	
52		Plastic		
31				
21		578.5		
BW-3	8	Moist, Plastic	374.7	
	11	Plastic		
	39			
	29		594.7	
	15	Gray		
	20			
	18	Fine	626.7	
	29			
	21			
	25	Coarse		
	8			
	BW-4	10	Gray, Plastic	575.1
10		Gray, Plastic		
16		Gray		
29			595.1	
17		Soft & Plastic		
6				
19		Yellow	625.1	
31		Yellow, Dry		
54		Gray		
15		Yellow	655.1	
11			667.1	
BW-5		12	Moist, Gray Plastic	579.6
	14	Gray Plastic		
	18	Gray Plastic		
	38			
	12	Gray Moist	609.6	
	115	Fine Gray		
	46	Fine		
	20		659.6	
	34	Coarse Sand		
	6		679.6	
	BW-6	18	Gray Soft, Plastic	581.5
		23		
44		Gray, Medium Hard		
10		Gray	611.5	
138		Fine Dry	621.5	
84		Fine Gray	631.5	
28		Gray		
22		Yellow		
37			664.5	
9			661.5	
9			675.2	
BORING I		11	Very Stiff	546.3
	15			
	15			
	18	Very Stiff		
	6	Medium		
	11	Stiff		
	21	Compact, Fine, Wet	615.0	
	78			
	18	Compact, Med, Wet		
	16	Compact, Medium		
	14			
	12	Compact, Medium	659.8	
11		650.5		
2	19	Very Stiff	545.2	
	16			
	9	Medium		
	14	Very Stiff		
	15			
	9	Stiff		
	73	Fine, Wet	617.2	
	35		614.2	
	13	Med Wet	647.2	
	75			
	9	Stiff		
	15	Very Stiff		
7	Medium			
7		673.7		
45	Coarse	675.2		

BORING LOGS
Scale: 1" = 20' vert

BORING LEGEND














BORING NOTES:
With reference to Boring 1:
1. In column "A", the figures 12, 11, 14, etc. are the hammer blows required to advance the casing one foot.
2. Column "B" shows the legend of soil types and ground water elevation.
3. Column "C" shows soil classification.
4. Column "D" shows elevations of soil levels. Elevation at top is top of ground, elevation at bottom is bottom of hole.

U. S. ROUTE 42 RELOCATION
INNER BELT FREEWAY
WEST APPROACH VIADUCT
BR. NO. CUY-42R-1750
GROUND PLAN AND BORING DATA
CLEVELAND CUYAHOGA COUNTY OHIO
SCALE: As shown
MADE WEG DATE: 2-28-56
TRCD DATE: 3-1-56
HOWARD, NEEDLES, TAMMEN & BERGENDOFF CONSULTING ENGINEERS
KANSAS CITY CLEVELAND NEW YORK
914(2)WB SHEET 32

MICROFILMED
FEB 85 R23

FED. ROAD DIV NO	STATE	FEDERAL AID PROJECT NO	TYPE FUNDS	38 67
2	OHIO			

CUYAHOGA COUNTY
CITY OF CLEVELAND
**INNER BELT FREEWAY
WEST APPROACH VIADUCT**
CUY-42R-17.43



Legend:
n.f. indicates near face
f.f. indicates far face

Notes:
All piles are 12" Cast-in-Place reinforced concrete, battered 3 in 12 where shown.
For Type A and B hanger details and for scupper details, see Sheet 65.
Rustications shall parallel grade, for rustication detail see Sheet 36.
Entire abutment to be class E concrete.
Abutment backwall is to be poured after expansion joint is attached to superstructure.
Average vertical pile length = 60'-0".
All backfill under overhanging safety walk to be porous backfill.

U.S. ROUTE 42 RELOCATION
**INNER BELT FREEWAY
WEST APPROACH VIADUCT**
BR. NO. CUY-42R-1750

ABUTMENT W2

CLEVELAND CUYAHOGA COUNTY OHIO

SCALE 1/4" = 1'-0" unless shown
MADE & APPROX DATE 1-23-56
TRCD. DATE 6-25-56
CKD. DATE 2-14-56


HOWARD, NEEDLES & BERGENDOFF
CONSULTING ENGINEERS
KANSAS CITY CLEVELAND NEW YORK
914 (2) WB SHEET 38

CUYAHOGA COUNTY
CITY OF CLEVELAND
INNER BELT FREEWAY
WEST APPROACH VIADUCT
CUY-42R-17.43

MARK	NUMBER	LENGTH	TYPE	DIMENSIONS				SERIES INCR- MENT	WEIGHT (LBS.)
				A	B	C	D		
PIER 2A CONTINUED									
603	13	10'-0"	Str.						195
604	4	43'-6"	Str.						261
605	4	21'-6"	Str.						129
606	4	38'-3"	Str.						230
607	4	36'-3"	Str.						218
801	50	14'-4"	102	12'-2"	1'-1"				1,913
1001	4	27'-11"	122	18'-5"	2'-6"	2'-3"	1'-7"		481
1002	4	44'-8"	122	35'-2"	2'-6"	2'-3"	1'-7"		769
1003	3	17'-6"	Str.						226
TOTAL									35,954
PIER 3A									
401	42	4'-8"	103	2'-8"	1'-0"				131
501	84	13'-6"	104	2'-8"	3'-8"	5"			1,183
502	123	13'-6"	104	3'-2"	3'-2"	5"			1,732
503	44	12'-1"	104	2'-5 1/2"	3'-2"	5"			554
601	72, 76	11'-0"	102	9'-8"	8"				1,190
602	16	28'-6"	Str.						685
603	10	9'-6"	Str.						143
801	15	10'-0"	Str.						401
802	4	17'-6"	Str.						187
901	12	12'-8"	102	10'-2"	1'-3"				577
902	2	9'-0"	Str.						61
1001	20	14'-0"	102	11'-2"	1'-5"				1,205
1002	40	13'-0"	102	10'-2"	1'-5"				2,238
1003	8	15'-6"	Str.						534

MARK	NUMBER	LENGTH	TYPE	DIMENSIONS				SERIES INCR- MENT	WEIGHT (LBS.)
				A	B	C	D		
1101	24	11'-4"	101	9'-9"	1'-7"				1,445
1102	92	7'-10"	101	6'-3"	1'-7"				3,829
1103	24	13'-9"	Str.						1,753
1104	12	13'-6"	Str.						861
1105	20	14'-3"	Str.						1,514
1106	12	14'-9"	Str.						940
1107	24	16'-0"	Str.						2,040
1108	10	38'-6"	Str.						2,046
1109	10	20'-0"	Str.						1,063
1110	12	32'-4"	106	27'-6"	2'-9"	2'-1"	1'-9"		2,061
1111	4	12'-9"	Str.						271
1112	4	10'-3"	Str.						218
TOTAL									28,802
WEST END PIER									
501	34	13'-11"	107	12'-3"	1'-8"				494
502	10	17'-11"	107	16'-3"	1'-8"				187
503	4	24'-4"	107	22'-8"	1'-8"				102
504	84	16'-1"	103	12'-1"	2'-0"				1,409
505	2 Series 21	15'-6" to 17'-0"	Str.					0'-0 15/16"	712
506	10	16'-6"	Str.						172
507	8	15'-3"	107	9'-6"	5'-9"				127
508	44	14'-0"	Str.						643
509	2 Series 7	28'-8" to 29'-8"	116	14'-10" to 15'-4"	2'-0" to 2'-3"	3'-2"	1'-9"	0'-2"	426
510	6	36'-4"	104	14'-7"	3'-2"	5"			227
511	6	12'-0"	Str.						75
512	20	10'-7"	115	3'-11"	3'-1"	3'-0"	7"		221
513	12	7'-6"	Str.						92
514	44	13'-3"	107	11'-6"	1'-9"				608
601	32	12'-0"	Str.						577
602	22	16'-3"	Str.						537
603	14	8'-0"	Str.						168
604	12	10'-8"	103	4'-8"	3'-0"				192
605	10	11'-5"	103	5'-5"	3'-0"				172
801	42	27'-0"	Str.						3,028
802	18	18'-0"	Str.						865
803	40	29'-9"	Str.						3,177
804	28	20'-6"	Str.						1,533
805	38	14'-3"	Str.						1,446
806	26	11'-0"	Str.						764
807	6	12'-0"	107	6'-0"	6'-0"				192
808	72	13'-3"	Str.						2,547
TOTAL									20,695
REPLACEMENT BARS									
499	4	3'-3"	Str.						9
599	14	3'-6"	Str.						51
699	28	4'-0"	Str.						168
799	20	4'-3"	Str.						174
899	4	4'-6"	Str.						48
999	2	4'-9"	Str.						32
1099	2	5'-3"	Str.						45
1199	10	5'-6"	Str.						292
TOTAL									819

FEB 25 1959



BENDING DIAGRAMS

Note: All bar dimensions are "out" to "out."


U. S. ROUTE 42 RELOCATION
INNER BELT FREEWAY
WEST APPROACH VIADUCT
BR. NO. CUY-42R-1750

REINFORCEMENT SCHEDULE


CLEVELAND CUYAHOGA COUNTY OHIO

SCALE: _____ HOWARD, NEEDLES, TAMMEN & BERGENDOFF
MADE RSC DATE 5-10-56 CONSULTING ENGINEERS
TRCD. 212 DATE 5-24-56 KANSAS CITY CLEVELAND NEW YORK
CKD. 266 DATE 5-11-56 914(2)WB SHEET-35


CUYAHOGA COUNTY
CITY OF CLEVELAND
INNER BELT FREEWAY
WEST APPROACH VIADUCT
CUY-42R-17.43




ANCHOR BOLT SETTING PLAN
Scale 2"=1'-0"




SECTION B-B
Scale 3/8"=1'-0"




SECTION A-A
Scale 3/8"=1'-0"




RUSTICATION DETAIL
FULL SIZE




PLAN
Scale 1/2"=1'-0"




ELEVATION E-E
Scale 3/8"=1'-0"



ELEVATION
Scale 1/2"=1'-0"



ELEVATION D-D
Scale 3/8"=1'-0"



FOOTING PLAN
Scale 1/4"=1'-0"

Note: All piles to be 12" dia cast-in-place reinforced concrete, battered 3 in 12 where shown. Rustication shall be parallel to grade. Entire abutment to be Class E concrete. Abutment backwall is to be poured after expansion joint is attached to superstructure. For handrail post spacing on west wingwall, see Sheet 63. Average vertical pile length = 60'-0". All backfill under overhanging safety walk to be porous backfill.

U. S. ROUTE 42 RELOCATION
INNER BELT FREEWAY
WEST APPROACH VIADUCT
BR. NO. CUY-42R-1750
ABUTMENT W I
CLEVELAND CUYAHOGA COUNTY OHIO


SCALE As Noted
MADE 2/27/36 DATE 1-27-36
TRCD DATE
CKD PCY DATE 3-14-36

HOWARD, NEEDLES, TAMMEN & BERGENDOFF
CONSULTING ENGINEERS
KANSAS CITY CLEVELAND NEW YORK
914(2)WB SHEET 36

FED. ROAD DIV. NO.	STATE	FEDERAL AID PROJECT NO.	TYPE FUNDS
2	OHIO		


37
67

CUYAHOGA COUNTY
CITY OF CLEVELAND
INNER BELT FREEWAY
WEST APPROACH VIADUCT
CUY-42R-17.43




ELEVATION

PLAN




TYPICAL SECTION




FOOTING PLAN

Premolded Sealing Strip in 13"x3" recess from top of footing to 9" below top of curb.




CONTRACTION JOINT DETAIL


NOTES:
All piles are 12" ϕ cast in place reinforced concrete battered 3 in 12 where shown.
For handrail details see sheet G7.
For rustication detail see sheet 3G.
Entire retaining wall including footing shall be Class "E" concrete.
For handrail post spacing see sheet G3.
Average vertical pile length = 60'-0".



DETAIL "A"



ELEVATION B-B



EXPANSION JOINT DETAIL

U. S. ROUTE 42 RELOCATION
INNER BELT FREEWAY
WEST APPROACH VIADUCT
BR. NO. CUY-42R-1750
RAMP W1 RETAINING WALL
CLEVELAND CUYAHOGA COUNTY OHIO

SCALE 3/4" = 1'-0" UNLESS NOTED
MADE FEB. DATE 1-20-56
TRCO DATE
CHD W.P.O. DATE 7-13-56






HOWARD, NEEDLES, TAMMEN & BERGENOFF
CONSULTING ENGINEERS
KANSAS CITY CLEVELAND NEW YORK
914(2)WB SHEET- 37

RECEIVED
FEB 25 1956

FED. ROAD DIV. NO.	STATE	FEDERAL AID PROJECT NO.	TYPE FUNDS
2	OHIO		

39
67

**CUYAHOGA COUNTY
CITY OF CLEVELAND
INNER BELT FREEWAY
WEST APPROACH VIADUCT
CUY-42R-17.43**











Notes for Driving Piles "A" Through "F"

The location of the 5' brick sewer as shown on the plans is to be considered approximate only and, before proceeding with any construction operations which might cause damage to the sewer, the contractor shall determine the exact location by borings, excavations, surveys, or other suitable means. If the location varies considerably from that shown and interferes with the piling, the design of the pier will be modified as required.

Pile driving operations shall be so conducted as to minimize vibration which might cause damage to the sewer. Driving shall be supplemented by air jetting or by pre-boring. Piling shall be driven successively on alternate sides of the sewer to avoid cumulative displacement.

The contractor shall, at his own expense and to the satisfaction of the city, repair any damage which may result from his construction operations.

Payment for the protection of the sewer against damage due to pile driving and payment for air jetting or pre-boring shall be considered as included in the price bid per linear foot of pile.



Note: All piles are 14" cast in place reinforced concrete, battered 3 in 12 unless otherwise shown.
Average pile length Pier IW2=60'-0"
Average vertical pile length Pier 2W2=60'-0"

Contractor to adjust top cap reinforcing to clear drilled holes for anchor bolts.

All footings to be class "E" concrete, columns and cap beams to be class "C" concrete.

Flow line Elev. of 5'-0" Brick Sanitary Sewer at Pier IW2 is 631.2.

U. S. ROUTE 42 RELOCATION
**INNER BELT FREEWAY
WEST APPROACH VIADUCT**
BR. NO. CUY-42R-1750






PIER IW2 AND PIER 2W2

CLEVELAND CUYAHOGA COUNTY OHIO

SCALE: As Shown
MADE: JULY DATE: 2-28-56
TRCD: DATE: _____
CKD: JSH DATE: 3-3-56

HOWARD, NEEDLES, TAMMEN & BERGENDOFF
CONSULTING ENGINEERS
KANSAS CITY, CLEVELAND, NEW YORK
914(2)WB SHEET-39

CUYAHOGA COUNTY
CITY OF CLEVELAND
INNER BELT FREEWAY
WEST APPROACH VIADUCT
CUY - 42R - 17.43



Girder	Dimensions			
	A	B	C	D
Q	10 15/16"	1'-0 3/8"	6 1/2"	9 3/8"
J, M, N	11 1/8"	1'-0 1/4"	5 1/2"	8 7/8"
K, L, O, P	11 1/8"	1'-1 1/8"	6 1/8"	9 1/8"

Notes:
All piles are 14" cast-in-place reinforced concrete.
Average pile length = 60'-0"

Contractor to adjust top cap re-inforcing to clear drilled holes for anchor bolts.
All footings to be Class E concrete, columns and cap beams to be Class C concrete.





U. S. ROUTE 42 RELOCATION
INNER BELT FREEWAY
WEST APPROACH VIADUCT
BR. NO. CUY-42R-1750

PIER 3A
CLEVELAND CUYAHOGA COUNTY OHIO

SCALE: As shown
MADE: CCE DATE: 2-12-56
TRCD: CAL DATE: 3-30-56
CKD: ASR DATE: 2-24-56

HOWARD, NEEDLES, TAMMEN & BERGENDOFF
CONSULTING ENGINEERS
KANSAS CITY, CLEVELAND, NEW YORK
914 (2)WB SHEET 40

**CUYAHOGA COUNTY
CITY OF CLEVELAND
INNER BELT FREEWAY
WEST APPROACH VIADUCT
CUY - 42R - 17.43**






DIMENSIONS					
Girder	φ	A	B	C	D
F	21'-01'-09"	11 3/8"	8"	7 1/8"	8 3/8"
I	13'-35'-50"	11 3/8"	9"	2 3/8"	7 3/8"
G	28'-00'-00"	11 9/8"	6 3/8"	1/2"	9 3/8"
J	7'-00'-00"	1'-0 3/4"	11 1/8"	5 1/2"	8 1/8"
K,L,O,P	7'-00'-00"	1'-0 3/8"	11 1/8"	4 1/2"	7 1/8"
M,N,Q	7'-00'-00"	11"	9 1/8"	3 1/2"	6 1/8"
S,T	3'-28'-35"	10 13/8"	10 3/8"	4 3/8"	5 3/8"
R	1'-30'-00"	10 3/8"	10 3/8"	5 1/4"	4 3/8"

* Indicates dimension or angle is on opposite side of reference line to that shown on sketch

ANCHOR BOLT SETTING PLAN

Notes:
 For sections and Footing plan see Sheet 42.
 All piles to be 14" φ cast in place reinforced concrete, batter 3 in 12 where shown.
 Contractor to adjust top cap reinforcing to clear drilled holes for anchor bolts.
 All Footings to be Class E Concrete, columns and cap beams to be Class C Concrete.
 Average vertical pile length = 60'-0"



DIMENSIONS					
Girder	φ	A	B	C	D
F	21'-01'-09"	12 3/8"	8 3/8"	9"	8 3/8"
I	13'-35'-50"	12 3/8"	10"	2 3/8"	7 3/8"
G	28'-00'-00"	12 3/8"	7 3/8"	1"	9 3/8"
J	7'-00'-00"	12 3/8"	11 1/8"	5 1/2"	8 1/8"
K,L,O,P	7'-00'-00"	12 3/8"	11 1/8"	4 1/2"	7 1/8"
M,N,Q	7'-00'-00"	12"	10 13/8"	3 1/2"	6 3/8"
S,T	3'-28'-35"	11 3/8"	11 3/8"	4 3/8"	5 3/8"
R	1'-30'-00"	11 3/8"	11 3/8"	5 3/8"	4 1/8"

Revised - 4-10-57


U. S. ROUTE 42 RELOCATION
**INNER BELT FREEWAY
 WEST APPROACH VIADUCT**
 BR. NO. CUY - 42R - 1750

PIER 2A


CLEVELAND CUYAHOGA COUNTY OHIO

SCALE 3/8" = 1'-0"
 MADE R58 DATE 5-12-56 HOWARD, NEEDLES, TAMMEN & BERGENOFF CONSULTING ENGINEERS
 TRCD DATE 5-16-56 KANSAS CITY CLEVELAND NEW YORK
 CKD ABR DATE 5-16-56 914(2)WB SHEET- 41


CUYAHOGA COUNTY
CITY OF CLEVELAND
**INNER BELT FREEWAY
WEST APPROACH VIADUCT**
CUY-42R-17.43




SECTION A-A
SECTION B-B




SECTION C-C
SECTION D-D




SECTION E-E
SECTION F-F




SECTION G-G




VIEW V-V
Scale: 1/2"=1'-0"
ELEVATION N-N
Scale: 1/2"=1'-0"




PIER IWI
ANCHOR BOLT SETTING PLAN
No Scale




SECTION K-K
Scale: 1/2"=1'-0"




SECTION L-L
Scale: 1/2"=1'-0"




SECTION M-M
Scale: 1/2"=1'-0"




PLAN PIER IWI
Scale: 1/2"=1'-0"




ELEVATION PIER IWI
Scale: 1/2"=1'-0"



FOOTING PLAN PIER IWI
Scale: 1/2"=1'-0"




ELEVATION J-J
Scale: 1/2"=1'-0"



ELEVATION H-H
Scale: 1/2"=1'-0"

Notes:
Contractor to adjust top cap reinforcing steel to clear drilled holes for anchor bolts
For additional drainage details see sheet 65.



PIER 2A FOOTING PLAN
Scale: 1/8"=1'-0"

Note
All piles to be 14" cast-in-place reinforced concrete battered 3 in 12 where shown.
Average pile length for Pier IWI=60'-0".
All footings are class "E" concrete, all columns and cap beams are class "C" concrete.

U. S. ROUTE 42 RELOCATION
**INNER BELT FREEWAY
WEST APPROACH VIADUCT**
BR. NO. CUY-42R-1750

PIER IWI AND PIER 2A DETAILS
CLEVELAND CUYAHOGA COUNTY OHIO

SCALE: 1/2"=1'-0" unless shown
MADE: DFB DATE: 2-27-56
TRCD: DATE: KANSAS CITY CLEVELAND NEW YORK
CKD: PCY DATE: 3-12-56 914(2)WB SHEET-42




HOWARD, NEEDLES, TAMMEN & BERGENDOFF
CONSULTING ENGINEERS

FEB 25 1966



FED. ROAD DIV. NO.	STATE	FEDERAL AID PROJECT NO.	TYPE FUNDS
2	OHIO		

43
67

CUYAHOGA COUNTY
 CITY OF CLEVELAND
 INNER BELT FREEWAY
 WEST APPROACH VIADUCT
 CUY-42R-17.43



GIRDER	DIMENSIONS			
	A	B	C	D
I.M.N.R.	11 1/2"	1'-0 3/4"	5 1/2"	8 3/8"
J.Q.	11 1/2"	1'-1 1/8"	6 1/2"	9 1/2"
K.L.O.P.	11 1/2"	1'-2 1/8"	8 3/8"	11 1/2"




NOTES:
 All piles are 14" cast in place reinforced concrete. Contractor to adjust top cap reinforcing to clear drilled holes for anchor bolts.
 Average pile length = 60'-0".
 All footings to be Class "E" concrete, columns and cap beams to be Class "C" concrete.

U. S. ROUTE 42 RELOCATION
 INNER BELT FREEWAY
 WEST APPROACH VIADUCT
 BR. NO. CUY-42R-1750
PIER 1A
 CLEVELAND CUYAHOGA COUNTY OHIO


SCALE 3/8" = 1'-0" unless shown
 MADE I.N. DATE 2-21-56
 TRCD DATE
 CKD PHH DATE 3-14-56

HOWARD, NEEDLES, TAMMEN & BERGENDOFF
 CONSULTING ENGINEERS
 KANSAS CITY CLEVELAND NEW YORK
 914(2)WB SHEET- 43


CUYAHOGA COUNTY
CITY OF CLEVELAND
**INNER BELT FREEWAY
WEST APPROACH VIADUCT**
CUY-42R-17.43




Note: West Pier shown. East Pier similar except as noted.




SECTION B-B



SECTION C-C




PLAN



ELEVATION


END-ELEVATION




PEDESTAL DETAIL
(East Pier Only)

Scale: 3/8" = 1'-0"


DETAILS OF PIER TOP
Scale: 3/8" = 1'-0"




RUSTICATION DETAIL
Scale: 6" = 1'-0"




ELEVATION
Looking out from Viaduct



VIEW E-E



VIEW F-F



VIEW G-G

Legend:
n.f. denotes near face.
f.f. denotes far face.
e.f. denotes each face.

Note:
Entire pier is to be Class E Concrete, except portion above top of side walk which shall be Class C Concrete.

U. S. ROUTE 42 RELOCATION
**INNER BELT FREEWAY
WEST APPROACH VIADUCT**
BR. NO. CUY-42R-1750

WEST END PIER

CLEVELAND CUYAHOGA COUNTY OHIO

SCALE: 3/8" = 1'-0" (as shown)
MADE P.E.B. DATE 1-6-56
TRCD DATE
CHD R.S.E. DATE 2-13-56

HOWARD, NEEDLES, TAMMEN & BERGENDOFF
CONSULTING ENGINEERS
KANSAS CITY CLEVELAND NEW YORK

914(2)WB SHEET-44


MICROFILMED
FEB 25 1963

FED. ROAD DIV. NO.	STATE	FEDERAL AID PROJECT NO.	TYPE FUNDS
2	OHIO		

45
67

CUYAHOGA COUNTY
CITY OF CLEVELAND
**INNER BELT FREEWAY
WEST APPROACH VIADUCT**
CUY - 42R - 17.43

Note:
Angles marked "A" are 83°00'00"
Angles marked thus \sphericalangle are 90°00'00"
Beams, girders and cross frames are shown thus
Stringers are shown thus
Lower lateral system is shown thus (ST 6WF 13.5)
For beam and girder lengths and details, see Elevations Sheets 46 through 49.
Members marked "CB" are cantilever brackets. For details see Sheet 54.
Marks "A" through "H" and "K" through "M" refer to cross frames. See details on Sheets 53 and 54.
Marks "J1" through "J4" refer to jacking diaphragms. See details on Sheet 51.
Elevations shown are to top of top flanges on rolled beams and to back of top flange angles on girders.
For location and details of light brackets for under bridge lighting, see Sheet 66.
All rivets $\frac{1}{2}$ " ϕ .



U. S. ROUTE 42 RELOCATION
**INNER BELT FREEWAY
WEST APPROACH VIADUCT**
BR. NO. CUY-42R-1750

FRAMING PLAN

CLEVELAND CUYAHOGA COUNTY OHIO

SCALE 1/16" = 1'-0"
MADE RSG DATE 12-27-55
TRCD CAL DATE 3-27-56
CKD RGC DATE 3-19-56

HOWARD, NEEDLES, TAMMEN & BERGENDOFF
CONSULTING ENGINEERS
KANSAS CITY CLEVELAND NEW YORK
914 (2) WB SHEET- 45

REVISIONS
FEB 25 1958

FED. ROAD DIV. NO.	STATE	FEDERAL AID PROJECT NO.	TYPE FUNDS
2	OHIO		

46
67

**CUYAHOGA COUNTY
CITY OF CLEVELAND
INNER BELT FREEWAY
WEST APPROACH VIADUCT
CUY-42R-17.43**




















FIELD SPICE WELDING PROCEDURE

1. Raise the abutment ends of beams A, C, D and E the following amounts:

BEAM A	BEAM C	BEAM D	BEAM E
1 1/4"	1 3/8"	1 1/8"	1 5/8"

2. Buff-weld the beam flanges and web. Make one pass in each flange, then one pass in the web; repeat until welds are completed.
3. Weld the bottom and top cover plates.
4. Lower the beam ends to final position.

Note:
For Dead Load Deflection Diagrams, see Sheet 52.



**U. S. ROUTE 42 RELOCATION
INNER BELT FREEWAY
WEST APPROACH VIADUCT
BR. NO. CUY-42R-1750**





BEAM ELEVATIONS AND DETAILS

CLEVELAND CUYAHOGA COUNTY OHIO


SCALE: As noted
MADE: 3.5.58 DATE: 1-9-56
TRCD: P.R. DATE: 6-4-56
CKD: P.S.G. DATE: 3-14-56

HOWARD, NEEDLES, TAMMEN & BERGENS
CONSULTING ENGINEERS
KANSAS CITY CLEVELAND NEW YORK
914(2)WB SHEET 46



CUYAHOGA COUNTY
CITY OF CLEVELAND
INNER BELT FREEWAY
WEST APPROACH VIADUCT
CUY-42R-17.43





GIRDER ELEVATIONS
No Scale



SECTION A-A
Scale: 1/2" = 1'-0"








Notes:
Intermediate stiffeners are 2'-Ls 5x3 x 1/8 crimped unless called for on one side only, then they are 1'-L 5x3 1/2 x 1/8 welded to flange shown.
Floor beam connection angles at panel points are 7x4 x 1/8 angles on extended fills. See Sheet 53 for bearing and intermediate stiffener detail see Sheet 51.
for field splices see Sheet 50.
Material, dimensions and rivet pitch shown are common to top and bottom of Girder.





FED. ROAD DIV. NO.	STATE	FEDERAL AID PROJECT NO.	TYPE FUNDS
2	OHIO		

48
67

CUYAHOGA COUNTY
CITY OF CLEVELAND
INNER BELT FREEWAY
WEST APPROACH VIADUCT
CUY-42R-17.43



GIRDER ELEVATIONS
No Scale



Note: Vertical offsets are back to back of IS.

NOTES:
Intermediate stiffener angles are 2 @ 5"x3 1/2"x 1/2" crimped on girders M & N, and crimped on 4" Fill on girders K, L & O.
Floorbeam connection angles at panel points are 2 @ 7"x4"x 1/2" on 1" Fill for girders K, L & O and on 3" Fill on girders M & N.
For Bearing Stiffener sizes & details See Sheet 51
For end of cover plate and web splice detail See Sheet 47.
For field splice details See Sheet 50
Material, dimensions and rivet pitch shown are common to top & bottom of girder.








U. S. ROUTE 42 RELOCATION
INNER BELT FREEWAY
WEST APPROACH VIADUCT
BR. NO. CUY-42R-1750

GIRDER ELEVATIONS
CLEVELAND CUYAHOGA COUNTY OHIO

SCALE As Shown
MADE & DATE 2-3-36
TRCD DATE
CKD MPO DATE 3-15-36

HOWARD, NEEDLES, TAMMEN & BERGENOFF
CONSULTING ENGINEERS
KANSAS CITY CLEVELAND NEW YORK
914(2)WB SHEET 48

CUYAHOGA COUNTY
CITY OF CLEVELAND
INNER BELT FREEWAY
WEST APPROACH VIADUCT
CUY-42R-17.43



Notes:

- Intermediate stiffeners are 2 Ls 5x3 1/2 x 1/2, unless called for on one side only, then they are 1 L 5x3 1/2 x 3/16 welded to flange shown. Crimp on girders Q, R, S and T, crimp and fill 1/4 on girder R.
- Fillet beam connection angles at panel points are L 7x4 x 1/2 on extended fills. See Sheet 53.
- For bearing stiffener sizes and details, and for intermediate stiffener details see Sheet 51.
- For end of cover plate and web splice, see Sheet 47.
- For Field Splice Detail see Sheet 50.
- Material, dimensions and rivet pitch shown are common to top and bottom of girder.

GIRDER ELEVATIONS
No Scale

U. S. ROUTE 42 RELOCATION
INNER BELT FREEWAY
WEST APPROACH VIADUCT
BR. NO. CUY-42R-1750


GIRDER ELEVATIONS

CLEVELAND CUYAHOGA COUNTY OHIO


SCALE AS SHOWN
MADE JSL DATE 2-14-56
TRCD DATE
CHK WPO DATE 3-15-56

HOWARD, NEEDLES, TAMMEN & BERGENDOFF
CONSULTING ENGINEERS
KANSAS CITY CLEVELAND NEW YORK
914(2)WB SHEET-49


**CUYAHOGA COUNTY
CITY OF CLEVELAND
INNER BELT FREEWAY
WEST APPROACH VIADUCT
CUY-42R-17.43**




FIELD SPLICE-GIRDERS R & T




FIELD SPLICE-GIRDERS K, L, O & P




**FIELD SPLICE-GIRDER J
NEAR PIER 2A**




FIELD SPLICE-GIRDERS G, M, N, Q & S




FIELD SPLICE-GIRDER I



**FIELD SPLICE-GIRDER J
NEAR PIER 1A**



**CROSS FRAME "H" AT SPLICE
Top Plan Similar**



**CROSS FRAME "G" OR "D" AT SPLICE
FIELD SPLICE AT BEND POINTS
GIRDERS F, I & R**

Note:
Splice shown is for Girders "F" and "I"
Splice for Girder "R" is similar by rotation.

U. S. ROUTE 42 RELOCATION
**INNER BELT FREEWAY
WEST APPROACH VIADUCT**
BR. NO. CUY-42R-1750

GIRDER FIELD SPLICES

CLEVELAND CUYAHOGA COUNTY OHIO

SCALE: 1/2" = 1'-0"
MADE W.P.O. DATE 2-14-56
TRCD DATE
CKD ASR DATE 3-13-56

HOWARD, NEEDLES, TAMMEN & BERGENOFF
CONSULTING ENGINEERS
KANSAS CITY CLEVELAND NEW YORK
914(2)WB SHEET-50




CUYAHOGA COUNTY
CITY OF CLEVELAND
**INNER BELT FREEWAY
WEST APPROACH VIADUCT**
CUY-42R-17.43

TABLE OF BEARING STIFFENERS AND FILL PLATES

Girder	Fills	Pier 3A, IW1 or IW2		Pier 2A		Pier 1A		West End Pier	
		Brg. Stiff.	Detail	Brg. Stiff.	Detail	Brg. Stiff.	Detail	Brg. Stiff.	Detail
Girder F	5/8"	4Ls 7x4x3/8	C	4Ls 7x4x3/8	C				
Girder G	5/8"	4Ls 7x4x3/8	C	4Ls 7x4x3/8	C				
Girder H	3/4"	4Ls 7x4x3/8	C						
Girder I	5/8"			4Ls 7x4x3/8	C	4Ls 7x4x3/8	C		
Girder J	3/4"	4Ls 7x4x3/8	C	4Ls 7x4x3/8	A	4Ls 7x4x3/8	C	4Ls 7x4x3/8	D
Girders K, L, O & P	1"	4Ls 7x4x3/8	B	4Ls 7x4x3/8	B	4Ls 7x4x3/8	A	4Ls 7x4x3/8	D
Girders M & N	5/8"	4Ls 7x4x3/8	C	4Ls 7x4x3/8	C	4Ls 7x4x3/8	C	4Ls 7x4x3/8	D
Girder Q	5/8"	4Ls 7x4x3/8	C	4Ls 7x4x3/8	C	4Ls 7x4x3/8	C	4Ls 7x4x3/8	D
Girder R	3/4"	4Ls 7x4x3/8	C	4Ls 7x4x3/8	C	4Ls 7x4x3/8	C		
Girder S	5/8"	4Ls 7x4x3/8	C	4Ls 7x4x3/8	C				
Girder T	3/4"	4Ls 7x4x3/8	C	4Ls 7x4x3/8	C				

TABLE OF DEAD LOAD REACTIONS FOR JACKING (IN TONS)

Girder	F	G	H	I	J	K	L	M	N	O	P	Q	R	S	T
Pier 1A	-	-	-	145	184	230	223	171	171	218	215	167	110	-	-
Pier 2A	129	111	-	110	231	202	202	157	157	202	202	145	140	97	125
Pier 3A	-	-	-	-	119	115	115	93	93	115	115	95	-	-	-
Pier IW1	-	-	-	-	-	-	-	-	-	-	-	-	74	85	91
Pier IW2	80	105	108	-	-	-	-	-	-	-	-	-	-	-	-




Note: 7x4x3/8 Stiffener Angles at Jacking Points shall be milled to bear top and bottom. Stiffener Angles at Jacking Points shall be normal to floor beams or to flange angles. For location of Jacking Diaphragms see Framing Plan Sheet No. 45

U. S. ROUTE 42 RELOCATION
**INNER BELT FREEWAY
WEST APPROACH VIADUCT**
BR. NO. CUY-42R-1750
**STIFFENER AND JACKING DIAPHRAGM
DETAILS**
CLEVELAND CUYAHOGA COUNTY OHIO

SCALE: 1/2" = 1'-0" HOWARD, NEEDLES, TAMMEN & BERGENDOFF
MADE P.C.C. DATE 2-7-56 CONSULTING ENGINEERS
TRCD DATE KANSAS CITY CLEVELAND NEW YORK
CKD ZDD DATE 3-14-56 914(2)WB SHEET 51

FED. ROAD DIV. NO.	STATE	FEDERAL AID PROJECT NO.	TYPE FUNDS	52 67
2	OHIO			

CUYAHOGA COUNTY
CITY OF CLEVELAND
INNER BELT FREEWAY
WEST APPROACH VIADUCT
CUY-42R-17.43



Notes:
Amount of total dead load deflection is shown above diagram, amount of dead load deflection due to concrete only is shown below diagram.
Girder deflections are shown at tenth points of spans unless shown otherwise.
Rolled beam deflections are shown at quarter points of spans.
Rolled beams shall not be cambered.
Girders will be cambered for total dead load deflection plus vertical curve correction.
For vertical curve data see sheets 29 & 63

U. S. ROUTE 42 RELOCATION
INNER BELT FREEWAY
WEST APPROACH VIADUCT
BR. NO. CUY-42R-1750
DEAD LOAD
DEFLECTION DIAGRAMS
CLEVELAND CUYAHOGA COUNTY OHIO


SCALE: No scale
MADE R.S.G. DATE 1-31-56
TRCD DATE
CKD CCE DATE 3-1-56

HOWARD, NEEDLES, TAMMEN & BERGENDOFF
CONSULTING ENGINEERS
KANSAS CITY CLEVELAND NEW YORK
914(2)WB SHEET 52


FED. ROAD DIV. NO.	STATE	FEDERAL AID PROJECT NO.	TYPE FUNDS
2	OHIO		

53
67


CUYAHOGA COUNTY
CITY OF CLEVELAND
INNER BELT FREEWAY
WEST APPROACH VIADUCT
CUY-42R-17.43




CROSS FRAME A



CROSS FRAME B



CROSS FRAME C



TYPICAL CROSS FRAME CONNECTION ANGLE


Note: Cross Frame L 3x3x5/8. Weld sides of vertical legs and top side of horizontal legs to beams with 1/4 continuous Fillet Weld.

Note: Cross Frame L 4x4x3/16


Note: For details of expansion joint at Cross Frames A and C see Sheet 64.

Fill as necessary to avoid crimping angle (See girder elevations)


REPRODUCTION FEB 25 1956




SECTION B-B CROSS FRAMES E AND F




SECTION D-D CROSS FRAMES E AND F




SECTION K-K




SECTION B-B CROSS FRAME D




SECTION D-D CROSS FRAME D




SECTION G-G



SECTION I-I




ELEVATION




CROSS FRAME D AT BOX GIRDER


Note: For Cross Frames D and E at expansion rollers, 24 WF shall be raised and coped as on cross-frame M and beveled shims shall be used to connect ST 6 WF to girders as on cross-frame M. see Sheet 54.



ELEVATION




ELEVATION




SECTION L-L

Note: Bend 1/8 inch web PL for skewed connection. End of gusset if no cross lateral. Cross lateral ST 6 WF 13.5.


CROSS FRAME H



SECTION C-C




SECTION E-E




SECTION F-F

CROSS FRAMES D, E AND F



SECTION H-H



SECTION J-J

CROSS FRAME G

U. S. ROUTE 42 RELOCATION
INNER BELT FREEWAY
WEST APPROACH VIADUCT
BR. NO. CUY-42R-1750

CROSS FRAMES

CLEVELAND CUYAHOGA COUNTY OHIO

SCALE 1/2" = 1'-0"
MADE R.S.C. DATE 2-18-56
TRCD DATE
CKD R.G.C. DATE 3-13-56


HOWARD, NEEDLES, TAMMEN & BERGENOFF
CONSULTING ENGINEERS
KANSAS CITY CLEVELAND NEW YORK
914(2)WB SHEET-53

UNRECORDED
FEB 25 1957

FED. ROAD DIV. NO.	STATE	FEDERAL AID PROJECT NO.	TYPE FUNDS
2	OHIO		


54
67

CUYAHOGA COUNTY
CITY OF CLEVELAND
INNER BELT FREEWAY
WEST APPROACH VIADUCT
CUY-42R-17.43




SECTION A-A CROSS FRAME K


Note:
See Sheet 46 for
connection of Beam B to
Cross Frame K.




CROSS FRAME L







SECTION B-B




SECTION E-E CANTILEVER BRACKET DETAIL




SECTION F-F




TYPICAL LATERAL CONNECTIONS




CROSS FRAME M



SECTION C-C




SECTION D-D




END CONNECTION


CONTINUOUS STRINGER CONNECTION




PLAN




SECTION G-G



SECTION H-H




SECTION J-J




SECTION K-K

TRANSVERSE STRINGER CONNECTION



SECTION L-L



END CONNECTION

GIRDER F TO I
GIRDER I TO J
GIRDER R TO Q

U. S. ROUTE 42 RELOCATION
INNER BELT FREEWAY
WEST APPROACH VIADUCT
BR. NO. CUY-42R-1750


SUPERSTRUCTURE DETAILS

CLEVELAND CUYAHOGA COUNTY OHIO


SCALE: 1/2" = 1'-0"
MADE BY: H. DATE: 2-10-56
TRCD: DATE: KANSAS CITY CLEVELAND NEW YORK
CKD: RGC, DATE: 2-14-56 914(2)WB SHEET-54

HOWARD, NEEDLES, TAMMEN & BERGENDOFF
CONSULTING ENGINEERS


**CUYAHOGA COUNTY
CITY OF CLEVELAND
INNER BELT FREEWAY
WEST APPROACH VIADUCT
CUY - 42R - 17.43**




TOP ROLLER BEARING PLATE




SECTION B-B



DISC BEARING PLATE




SECTION A-A




BOX GIRDER DEFLECTION DIAGRAM


No Scale



BRONZE BEARING DISC




REPRODUCED
FEB 25 1956




BOX GIRDER END DETAIL

Scale 1/2" = 1'-0"




SECTION G-G

Scale 1/2" = 1'-0"




END ACCESS DOOR

Scale 1/2" = 1'-0"



SECTION H-H


Scale 1/2" = 1'-0"



GIRDER CONNECTION TO BOX GIRDER


Scale 1/2" = 1'-0"

(Girder K shown, all others similar)




SECTION J-J

Scale 1/2" = 1'-0"




SECTION L-L

Scale 1/2" = 1'-0"




SECTION K-K

Scale 1/2" = 1'-0"




EXPANSION SHOE ES-1



EXPANSION SHOE ES-2

Notes (Shoes)

Rollers shall be set vertical under full dead loads at 60° F.
Machined surfaces of rollers which bear on base plates and all exposed surfaces shall be painted.
Spaces around anchor bolts in base plates shall be filled with an approved metallic filler, such as babbitt, poured in place before setting nuts. See sheet 59 for anchor bolt detail.
All contact surfaces between metal parts shall be finished as shown.
All base plates and bearing plates shall be scribed with longitudinal and transverse center lines.
Use Structural Steel Sec. M74(a) except as noted.



ROLLER AND TOOTH BAR DETAIL

Scale 6" = 1'-0"

U. S. ROUTE 42 RELOCATION
**INNER BELT FREEWAY
WEST APPROACH VIADUCT**
BR. NO. GUY - 42R - 1750













BOX GIRDER DETAILS

CLEVELAND CUYAHOGA COUNTY OHIO

SCALE 1/2" = 1'-0" unless noted
MADE DFB DATE 1-10-56
TRCD DATE
CKD WPO DATE 3-13-56

HOWARD, NEEDLES, TAMMEN & BERGENDOFF
CONSULTING ENGINEERS
KANSAS CITY CLEVELAND NEW YORK
914(2)WB SHEET- 56

CUYAHOGA COUNTY
CITY OF CLEVELAND
INNER BELT FREEWAY
WEST APPROACH VIADUCT
CUY - 42R - 17.43



Note: For Elevation of Expansion Joint at curbs see sheet 58

Note A: 5/8" x 2 1/4" bolts at about 2'-0" ctrs. Weld nuts to angle. Remove bolts within 2 hours after Pour 3 is poured. Fill holes with bituminous material.

Note: Details not shown are similar to Section D-D.

U. S. ROUTE 42 RELOCATION
INNER BELT FREEWAY
WEST APPROACH VIADUCT
BR. NO. CUY-42R-1750
EXPANSION JOINTS

CLEVELAND CUYAHOGA COUNTY OHIO


SCALE: As shown
MADE C.C.F. DATE 1-17-55
TRCD C.A.L. DATE 3-23-56
CKD R.G.C. DATE 3-9-56

HOWARD, NEEDLES, TAMMEN & BERGENDOFF
CONSULTING ENGINEERS
KANSAS CITY CLEVELAND NEW YORK
914 (2) WB SHEET-57


REVISIONS
FEB 25 1968

FED. ROAD DIV. NO.	STATE	FEDERAL AID PROJECT NO.	TYPE FUNDS	58 67
2	OHIO			


CUYAHOGA COUNTY
CITY OF CLEVELAND
INNER BELT FREEWAY
WEST APPROACH VIADUCT
CUY-42R-17.43




EXPANSION JOINT AT EXPANSION ROLLER RAMP W-1
Scale: 1/2" = 1'-0"




SECTION A-A
Scale: 1" = 1'-0"




SECTION B-B
Scale: 1" = 1'-0"




SECTION C-C
Scale: 1" = 1'-0"




EXPANSION JOINT AT ROADWAY EXPANSION ROLLER
Scale: 1/2" = 1'-0"




CURB ELEVATION
Scale: 1" = 1'-0"




SECTION D-D
Scale: 1" = 1'-0"




SECTION E-E
Scale: 1" = 1'-0"




SECTION G-G
Scale: 1" = 1'-0"




SECTION F-F
Scale: 1" = 1'-0"




SECTION H-H
Scale: 1" = 1'-0"




SECTION J-J
Scale: 1" = 1'-0"



SECTION K-K
Scale: 1" = 1'-0"




PART PLAN OF EXPANSION JOINT AT ABUTMENT W-2
Scale: 1/4" = 1'-0"




PART PLAN OF EXPANSION JOINT AT ABUTMENT W-1
Scale: 1/4" = 1'-0"

U. S. ROUTE 42 RELOCATION
INNER BELT FREEWAY
WEST APPROACH VIADUCT
BR. NO. CUY-42R-1750
EXPANSION JOINTS
CLEVELAND CUYAHOGA COUNTY OHIO
SCALE: As Shown
MADE & CHECKED DATE: 5-4-66
TRCD: DATE
CKD: DATE
HOWARD, NEEDLES, TAMMEN & BERGENDOFF
CONSULTING ENGINEERS
KANSAS CITY CLEVELAND NEW YORK
914(2)WB SHEET-58


CUYAHOGA COUNTY
CITY OF CLEVELAND
**INNER BELT FREEWAY
WEST APPROACH VIADUCT**
CUY - 42R - 17.43



E-1, E-2 AND E-3



E-4, E-5 AND E-6



R-1 AND R-2

EXPANSION SHOES
No Scale

SHOE DIMENSIONS		EXPANSION SHOES												NUMBER OF SHOES REQ'D				
		A	B	C	D	E	F	G	H	K	L	M	P	Q	T	Y		
E-1	2 1/2"	10"	2 1/2"	2"	1"	1"	3 3/4"	10 3/8"	9"	1'-7"	3 3/8"	8 3/8"	6 1/4"	1 1/2"	1 1/8"		E-1	5
E-2	3 3/8"	1'-6"	3 1/2"	2 3/4"	1 1/2"	1"	5"	1'-5 3/8"	1'-1"	2'-2"	4 3/8"	1'-0 3/8"	1 1/4"	2 1/4"	1 1/8"		E-2	2
E-3	3 3/8"	1'-8"	3 1/2"	3 1/4"	1 1/2"	1"	6"	1'-5 3/8"	1'-2"	2'-4"	4 3/8"	1'-1 3/8"	1'-0 3/8"	3"	1 1/8"		E-3	2
E-4	-	1'-6"	-	3 1/2"	-	-	5"	1'-9"	-	2'-4"	4"	1'-8"	1'-0 3/8"	3"	-		E-4	10
E-5	1'-8"	-	3 1/2"	-	-	-	6"	2'-0 1/2"	-	2'-4"	4"	1'-8"	1'-3"	3 1/2"	-		E-5	6
E-6	2'-0"	-	4"	-	-	-	7"	2'-3 3/8"	-	2'-6"	1 1/2"	1'-10"	1'-6"	3 3/8"	-		E-6	4
F-1	2 1/2"	10"	2 1/2"	2"	1"	1"	3 3/4"	10 3/8"	9"	1'-7"	3 3/8"	8 3/8"	6 1/4"	1 1/2"	1 1/8"		F-1	5
F-2	3 3/8"	1'-6"	3 1/2"	2 3/4"	1 1/2"	1"	5"	1'-5 3/8"	1'-1"	2'-2"	4 3/8"	1'-0 3/8"	1 1/4"	2 1/4"	1 1/8"		F-2	5
F-3	3 3/8"	1'-8"	3 1/2"	3 1/4"	1 1/2"	1"	6"	1'-5 3/8"	1'-2"	2'-4"	4 3/8"	1'-1 3/8"	1'-0 3/8"	3"	-		F-3	9
F-4	-	1'-6"	-	3 1/2"	-	-	5"	1'-9"	-	2'-4"	4"	1'-8"	1'-0 3/8"	3"	-		F-4	4
F-5	1'-8"	-	3 1/2"	-	-	-	6"	2'-0 1/2"	-	2'-4"	4"	1'-8"	1'-3"	3 1/2"	-		F-5	1
F-6	2'-0"	-	4"	-	-	-	7"	2'-3 3/8"	-	2'-6"	1 1/2"	1'-10"	1'-6"	3 3/8"	-		F-6	4
R-1	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-		R-1	4
R-2	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-		R-2	2

FIXED SHOES		LOCATION OF SHOES																										
		A	B	C	H	K	L	M	P	Q	T	Y	GIRDERS															
													F	G	H	I	J	K	L	M	N	O	P	Q	R	S	T	
Pier 2W-2	F-2	F-2	F-2	F-2	F-2	F-2	F-2	F-2	F-2	F-2	F-2	F-2	Pier 1-A	-	-	-	-	E-4	E-5	E-6	E-6	E-4	E-4	E-6	E-6	E-5	E-4	
Abut. W-1	-	-	-	-	-	-	-	-	-	-	-	-	Pier 2-A	F-3	F-3	-	-	F-3	F-5	F-4	F-4	F-3	F-3	F-3	F-3	F-3		
Abut. W-2	E-1	E-1	E-1	E-1	E-1	-	-	-	-	-	-	-	Pier 3-A	-	-	-	-	E-4	E-5	E-5	E-4	E-4	E-5	E-5	E-3	-		
Joint W-1	-	-	-	-	-	-	-	-	-	-	-	-	Pier 1W-1	-	-	-	-	-	-	-	-	-	-	-	-	-		
Joint W-2	B-1	-	B-2	-	-	-	-	-	-	-	-	-	Pier 1W-2	E-2	E-4	E-2	-	-	-	-	-	-	-	-	-	E-4	E-3	E-4

NOTES:

Shoes E-1, E-2, E-3, F-1 and F-2 shall be structural steel, Sec. M-7.4.

Shoes F-3, F-4, F-5 and top castings for shoes E-4 thru E-6 shall be steel castings Sec. M-7.7.

Rocker castings and base plates of shoes E-4 thru E-6 shall be high strength steel castings, A.S.T.M. A148 Grade 80-55.

Rollers and base plates for shoes R-1 and R-2 shall be steel forgings, A.S.T.M. A237 Grade 80-55, Class B.

All pins, nuts, washers, rings, pintles, and tooth bars (on shoes R-1 and R-2) shall be structural steel.

Bolts to girder flanges shall have hex heads and self locking nuts. Provide washers under heads and nuts.

Lower portions of shoes shall be centered in both directions under top portion for a temp. of 60°F.


All base plates, rockers and sole plates shall be scribed with centerlines in both directions.

All fillets on castings to be 3/8" unless shown.


Spaces around anchor bolts in base plates shall be filled with an approved metallic filler before setting nuts.

Threaded ends of pins on shoes E-4 thru E-6 and F-3 thru F-5 shall be upset, battered or welded after field assembly.

Sole plates of shoes E-1 and F-1 shall be beveled to grade of finished roadway surface at Abutments W-2 and W-1 respectively.




F-1 AND F-2




F-3, F-4 AND F-5


FIXED SHOES
No Scale




DETAIL "A"
Scale: 3"=1'-0"




DETAIL "B"
Scale: 3"=1'-0"




DETAIL "C"
Scale: 3"=1'-0"



SECTION A-A
Scale: 3"=1'-0"



DETAIL "D"
Scale: 3"=1'-0"



ANCHOR BOLT
DETAIL
No Scale

Revised - 4-10-57

U. S. ROUTE 42 RELOCATION
**INNER BELT FREEWAY
WEST APPROACH VIADUCT**
BR. NO. CUY - 42R - 1750

SHOES

CLEVELAND CUYAHOGA COUNTY OHIO

SCALE As Noted
MADE, R.O.C. DATE 1-18-56
TRCD DATE
CKD, DEB DATE 3-17-56


HOWARD, NEEDLES, TAMMEN & BERGENDOFF
CONSULTING ENGINEERS
KANSAS CITY CLEVELAND NEW YORK
914(2)WB SHEET 59

UNOFFICIAL
FEB 25 1956

FED. ROAD DIV. NO.	STATE	FEDERAL AID PROJECT NO.	TYPE FUNDS
2	OHIO		

60
67

CUYAHOGA COUNTY
CITY OF CLEVELAND
INNER BELT FREEWAY
WEST APPROACH VIADUCT
CUY - 42R - 17.43



Notes:
 For Sections A-A, B-B, C-C, D-D, E-E and F-F see Sheet 62.
 For handrail detail details see Sheet 67.
 For handrail and light pole spacing see Sheet 63.
 For additional steel under light poles see Section N-N, Sheet 62.
 For details of nose on Ramps W1 and W2 see Sheet 62.
 For top slab reinforcement see Sheet 61.
 For reinforcing steel in Ramp W2 see Sheet 64.

U. S. ROUTE 42 RELOCATION
INNER BELT FREEWAY
WEST APPROACH VIADUCT
BR. NO. CUY-42R-1750

SLAB PLAN

CLEVELAND CUYAHOGA COUNTY OHIO


SCALE AS SHOWN
 MADE I.D.D. DATE 2-8-56
 TRCD C.A.L. DATE 6-6-56
 CRD. W.P.O. DATE 3-14-56

HOWARD, NEEDLES, TAMMEN & BERGENDOFF
CONSULTING ENGINEERS
KANSAS CITY CLEVELAND NEW YORK
914(2)WB SHEET- 60


AS SHOWN
FEB 25 1956

FED. ROAD DIV. NO.	STATE	FEDERAL AID PROJECT NO.	TYPE FUNDS	61 67
2	OHIO			


CUYAHOGA COUNTY
CITY OF CLEVELAND
**INNER BELT FREEWAY
WEST APPROACH VIADUCT**
CUY - 42R - 17.43



**LOCATION OF THREADED SLEEVES
FUTURE NOSE EXTENSION ON RAMP W1**
Scale: 1" = 20' 0"




**DETAIL OF
THREADED SLEEVES**
Scale: 1" = 1' 0"
Note: Threaded sleeves and 3/4" x 1" bolts will be furnished under Item S-7, "Structural Steel."




**SLAB POURING SEQUENCE
AND ORDINATE DIMENSIONS**
Scale: 1" = 40' 0"

Notes:
All slab pours shall be complete prior to pouring any sidewalks or medians.
The Contractor may use an alternate pouring sequence, subject to the approval of the Engineer.
Pours shall extend the full width of the roadway.
Sequence and direction of pours noted thus (2)



TYPICAL SLAB CONSTRUCTION JOINT
Scale: 1 1/2" = 1' 0"

Notes:
For bottom slab reinforcing and sidewalk and parapet reinforcing see Sheet G0.
For additional reinforcing over cantilever brackets see sidewalk reinforcing.
For Sections A-A thru E-E see Sheet G2.
For nose offsets and additional slab dimensions see Sheet G3.



SLAB PLAN SHOWING TOP REINFORCEMENT
Scale: 1/8" = 1' 0"

U. S. ROUTE 42 RELOCATION
**INNER BELT FREEWAY
WEST APPROACH VIADUCT**
BR. NO. CUY - 42R - 1750

**SLAB PLAN AND
POURING SEQUENCE**
CLEVELAND CUYAHOGA COUNTY OHIO


SCALE: AS SHOWN
MADE: R.S.G. DATE: 2-3-56
TRCD: C.A.L. DATE: 6-2-56
CKD: W.P.O. DATE: 3-14-56

HOWARD, NEEDLES, TAMMEN & BERGENDOFF
CONSULTING ENGINEERS
KANSAS CITY CLEVELAND NEW YORK
914 (2)WB SHEET- 61


FED. ROAD DIV. NO.	STATE	FEDERAL AID PROJECT NO.	TYPE FUNDS	62 67
2	OHIO			

CUYAHOGA COUNTY
CITY OF CLEVELAND
**INNER BELT FREEWAY
WEST APPROACH VIADUCT**
CUY-42R-17.43


Note: "A"
1/2" Copper drain tubes at about 6'0" ctrs. as per section 5-29.08. Set to clear piers and cross frames at least 6". First drain tube at ends of bridge shall be placed within one foot of end finish.



SECTION B-B
Scale 3/8"=1'-0"




SECTION C-C
Scale 3/8"=1'-0"




SECTION D-D
Scale 3/8"=1'-0"


SECTION E-E
Scale 3/8"=1'-0"




SECTION F-F
Scale 1/2"=1'-0"




PARAPET DEFLECTION JOINT
Scale 1/2"=1'-0"




PLAN




ENDPOST PLAN




TYPICAL FLOORBEAM HAUNCH DETAIL
Scale 3/4"=1'-0"



SECTION A-A
Scale 1/2"=1'-0"




SECTION H-H



SECTION K-K

SECTION G-G

RAMP W1 NOSE DETAILS
Scale 3/8"=1'-0"



SECTION L-L

RAMP W2 NOSE DETAILS
Scale 3/8"=1'-0"

Notes:
For station location of Nose Ramp W1 and W2 see Sheet no. 63.
For Handrail and Light Pole locations see Sheet 63.
Haunches:
2 1/2" from back of angles to bottom of slab at girders 6 thru 7 at all piers.
5/8" from back of angles to bottom of slab at girder F at piers.
0" from top of rolled beam to bottom of slab at beams U thru Y at abutment W1.

U. S. ROUTE 42 RELOCATION
**INNER BELT FREEWAY
WEST APPROACH VIADUCT**
BR. NO. CUY-42R-1750

SLAB DETAILS

CLEVELAND CUYAHOGA COUNTY OHIO


SCALE As Shown
MADE I.D.D. DATE 2-8-56
TRCD. DATE 6-3-56
CRD. DATE 9-14-56

HOWARD, NEEDLES, TAMMEN & BERGENDOFF
CONSULTING ENGINEERS
KANSAS CITY CLEVELAND NEW YORK
914(2)WB SHEET 62

FED. ROAD DIV. NO.	STATE	FEDERAL AID PROJECT NO.	TYPE FUNDS
2	OHIO		

63
67

CUYAHOGA COUNTY
CITY OF CLEVELAND
INNER BELT FREEWAY
WEST APPROACH VIADUCT
CUY-42R-1743



PLAN A-A

U. S. ROUTE 42 RELOCATION
INNER BELT FREEWAY
WEST APPROACH VIADUCT
BR. NO. CUY-42R-1750

SLAB CONTOURS AND
HANDRAIL SPACING
CLEVELAND CUYAHOGA COUNTY OHIO

SCALE: 1/4" = 1'-0"
MADE: 2-22-56 DATE: 2-21-56
TRCD: J.B.M. DATE: 6-3-56
CKD: R.G.C. DATE: 3-14-56


HOWARD, NEEDLES, TAMMEN & BERGENOFF
CONSULTING ENGINEERS
KANSAS CITY CLEVELAND NEW YORK
914(2)WB SHEET 63

REVISIONS
FEB 25 1956


FED. ROAD DIV. NO.	STATE	FEDERAL AID PROJECT NO.	TYPE FUNDS
2	OHIO		

64
67


CUYAHOGA COUNTY
CITY OF CLEVELAND
INNER BELT FREEWAY
WEST APPROACH VIADUCT
CUI - 42R - 17.43




Note:
See Section N-N,
Sheet 62 for bars to
be added at light posts.




Mark	No	Length	TYPE
5501	4	6'-4"	STR
5502	4	17'-0"	STR
5503	14	4'-4"	Bent



SLAB PLAN RAMP W-2
Scale: 3/8" = 1'-0"





SECTION A-A
Scale: 3/8" = 1'-0"



SECTION B-B
Scale: 3/8" = 1'-0"

Note: Slab reinforcing may be cut in field to clear scupper.



PLAN OF NOSE AT RAMP W-2
Scale: 1/2" = 1'-0"

Notes:
For handrail and light post spacing see Sheet 63.
For handrail details see Sheet 67.
A 3/8" haunch, measured from top of rolled beam flanges to bottom of slab at & beams, has been provided at Abutment W-2 and Pier 2W-2.

U. S. ROUTE 42 RELOCATION
INNER BELT FREEWAY
WEST APPROACH VIADUCT
BR. NO. CUY-42R-1750

SLAB PLAN RAMP W-2

CLEVELAND CUYAHOGA COUNTY OHIO

SCALE: As shown
MADE WEG DATE 1-4-56
TRCD CAL DATE 4-4-56
CKD RGC DATE 3-13-56

HOWARD, NEEDLES, TAMMEN & BERGENDOFF
CONSULTING ENGINEERS
KANSAS CITY CLEVELAND NEW YORK


914 (2) WB SHEET 64

Revised 1-3-56


FED. ROAD DIV. NO.	STATE	FEDERAL AID PROJECT NO.	TYPE FUNDS
2	OHIO		

65
67


CUYAHOGA COUNTY
CITY OF CLEVELAND
INNER BELT FREEWAY
WEST APPROACH VIADUCT
CUY-42R-17.43




SCUPPER LOCATION
Scale: 1"=50'0"



TYPE "A" HANGER




SECTION C-C




TYPE "B" HANGER


PIPE HANGER DETAILS
Scale: 1 1/2"=1'0"




TYPICAL CONNECTION
6" W.I. PIPE TO 12" PIPE
Scale: 1/2"=1'0"




DOWNSPOUT CONNECTION
TO GIRDERS
Scale: 1/2"=1'0"




PIER 2A




SECTION D-D
Section E-E opposite hand



PLAN




SCUPPER CONNECTION
TO DOWNSPOUT
Scale: 1 1/2"=1'0"




SECTION THRU
GRATING FASTENING
Scale: 3"=1'0"

SECTION THRU
GRATING SUPPORT
Scale: 3"=1'0"




SECTION A-A




SECTION B-B

SCUPPER DETAILS
Scale: 1 1/2"=1'0" unless shown



PIER 1W1



PIER 1W2

DRAINAGE DETAILS AT PIER FOOTINGS
Scale: 1/2"=1'0" unless shown

Note:
For additional drainage details at piers,
see individual pier drawings.
For drainage at Abutment W2 see Sheet 38.

U. S. ROUTE 42 RELOCATION
INNER BELT FREEWAY
WEST APPROACH VIADUCT
BR. NO. CUY-42R-1750

DRAINAGE DETAILS























CLEVELAND CUYAHOGA COUNTY OHIO

SCALE: As shown
MADE RSG DATE 5-3-56
TRCD DATE
CKD ASR DATE 5-7-56

HOWARD, NEEDLES, TAMMEN & BERGENDOFF
CONSULTING ENGINEERS
KANSAS CITY CLEVELAND NEW YORK
914(2)WB SHEET 65

**CUYAHOGA COUNTY
CITY OF CLEVELAND
INNER BELT FREEWAY
WEST APPROACH VIADUCT
CUY-42R-17.43**

Note:
Luminaires to be located 6" back of Gutter Line on Ramp 'B' and Abbey Ave. as shown on Lighting Plan






**U. S. ROUTE 42 RELOCATION
INNER BELT FREEWAY
WEST APPROACH VIADUCT
BR. NO. CUY-42R-1750
LIGHTING DETAILS**

CLEVELAND CUYAHOGA COUNTY OHIO


SCALE: As shown
MADE W.E.G. DATE 2-10-56
TRCD DATE
CKO A.S.R. DATE 2-5-56

HOWARD, NEEDLES, TAMMEN & BERGENDOFF
CONSULTING ENGINEERS
KANSAS CITY CLEVELAND NEW YORK
914(2)WB SHEET 66


SCALE AS SHOWN
 HOWARD, NEEDLES, TAMMEN & BERENDORFF
 CONSULTING ENGINEERS
 MADE 1957 DATE 1-5-58
 TRCD DATE 3-18-58
 914(2)WB SHEET 67
 OHIO
HANDRAIL DETAILS
 CLEVELAND CUYAHOGA COUNTY
 BR. NO. CUY-42R-1750
**INNER BELT FREEWAY
 WEST APPROACH VIADUCT**




TYPICAL HANDRAIL DETAILS
 Scale: 3"=1'-0"



TYPICAL HANDRAIL POST



END OF HANDRAIL
 Scale 1/2"=1'-0"



HANDRAIL POST AT EXPANSION JOINT

Note (Light Pole Support):
 Before inserting aluminum tube, coat the inside of sleeve with aluminum, impregnated calking compound and after insertion form an external fillet of calking compound.

Notes:
 For aluminum refer to supplemental specification No. S-114
 Handrail shall be fabricated in lengths equal to 1 space. Bolt holes in tubes shall be 1/8" at one end. Other end shall have slotted holes 1/8" x 1" except at expansion joint where no holes are required at expansion end. Aluminum washers shall be used between steel and post base to align posts. Maximum thickness shall be 3/8". Space below post base plate shall be thoroughly calked with aluminum-impregnated calking compound. Handrail posts shall be set normal to grade and tubes shall parallel grade. Light pole supports shall be set vertical, lighting details see sheet 66.

CUYAHOGA COUNTY
 CITY OF CLEVELAND
**INNER BELT FREEWAY
 WEST APPROACH VIADUCT**
 CUY-42R-17.43

DIV. NO.	2
OHIO	
FUNDS	6