



DITCH ANALYSIS

PID : 116570 **Date :** 07/22/2025 **Project :** ERIE-US 6-CORRIDOR **Location :** Rye Beach SUP

Description : Ditch from Sta 122+00 to Sta 125+40

Designer : WK

Rainfall Area : A

Allowable Shears

	Seed:	0.40	Jute Mat:	0.45	Temporary Mat:	1.00
Permanent Mat	Type 1:	2.00	Type 2:	3.00	Type 3:	5.00
RCP	Type B:	6.00				

(*) Warning: Grade is steeper than allowable.

If value is parantheses, design parameters have been exceeded. - See user manual.

STATION BEGIN	STATION END	SIDE	LENGTH (ft.)	RADIUS WIDTH (ft.)	IN SLOPE (ft./ft.)	BACK SLOPE (ft./ft.)	GRADE (ft./ft.)	AREA (acres)	AREA SUM (acres)	RUNOFF COEFF.	CA (Sum)	PROTECT TYPE	RAIN INT. (in./hr.)	STORM FREQ. (yrs.)	MANN. COEFF.	TIME FLOW (min.)	VEL. FLOW (fps.)	SHEAR (lbs./ sq.ft.)	DESIGN FLOW (cfs.)	DEPTH FLOW (ft.)	WIDTH FLOW (ft.)
122+00	125+40	R	340.00	2.00	3.00	10.00	0.0059	0.40	0.40	0.70	0.28	Seed	3.14	5	0.030	19.90	1.11	0.08	0.89	0.23	4.97
												Seed	3.49	10	0.040	20.79	0.94	0.10	0.98	0.28	5.60