Project Scope	PID	124357	Project Name	W//Y SR UUS / UX YI						
Project Overview										
Scope Project Mgr.		Kat Wade		Initial Scope Meeting	7/1/2025					
Design Project Mgr.		Jane Cullen		Scope Version	Original					
In-House Designer(s)		Pitcher, Shelley I	<b>(</b>	Letting Type	ODOT Let					
Faring a satal Man		C	. 1	Contract Type	Standard Build					
Environmental Mgr.		ewsome, Connor		PDP Path	Path 2					
Design Responsibility		025 Programmati		File Date	1/1/2030					
Design Team		sign Engineering		Federal Aid Number	E250824					
Primary Work Cat.	Intersect	ion Improvemen	t (Safety)	County	WAY					
				City/Village	None					
Project Termini	WA	Y-57-8.91 at SR	585	Environmental Doc Type	C2					
				CFR 940 ITS Project	N/A					
Existing PID 116947 Roadway Minor Rehab (2024) Plans										
Convert signal-controlled intersection into single-lane* roundabout at SR-57 and SR-585 in Wayne County. (March 2025 Safety Application #202503D03-13)  *Possible for right/left turn lanes on some approaches. D03 will determine final roundabout lane configuration by design consultant selection (Nov 2025).										
2024 HSIP Rural Into 13 (43%) injury and superior safety and treatment. Roundal	points and decrease the severity of crashes due to lower vehicle speeds.									
					Complete?					
Action Items										

Project Scope PID 124357 Project Name WAY SR 0057 08.91
Roundabouts

CRS	WAY-5	7-8.91	Roundabout Type	9	Single Lane**
MOT Type	Det	tour			
Design Vehicle Type	WB-62*		Center Island La	Center Island Landscaping	
R/W Req'd	Yes		Т	urn Lanes?	TBD**
Survey Req'd	Yes		Ti	ruck Apron	Interior
Soil Borings Req'd	Yes		Outsi	de Curbing	Curb & Gutter
Utility Relocation Req'd	Yes		Approach	Pavement	Asphalt
Driveway Accom. Req'd	Yes			Grading	Common
Lighting	Yes			Drainage	Enclosed
Bicycles	No		Traffic Fore	ecast Type	NCHRP255
Pedestrian Accommodations	No		Circulating Lanes Cor	nfiguration	1
Major Road Approach Lanes	1**				
Minor Road Approach Lanes	1**				

<sup>\*</sup> Refer to L&D Manual for vehicle checks.

Roundabout 1 of

- > Truck Apron: 4" (minimum 3") height Type 9 with colored concrete (QC-1P with no QC/QA) to match splitter islands (not stamped, red). 8"-9" thick. Applies to the traffic side of all truck aprons.
- > Splitter Island: 100' (min); 200' (max), use 6" high curb tapered at beginning and end, broomed (NOT stamped) concrete (color red). Attempt to install straight splitter islands where possible, try to eliminate breaks for drives. Any unavoidable breaks for drives are to be depressed brushed finish splitter island, not asphaltic splitter breaks. Type 6 curb with broomed (NOT stamped) splitter island (color red) inside the curb. Type 2 curb & gutter outside curb except 3" Type 9 rolled curb at all exterior truck aprons.

<sup>\*\*</sup>D03 to determine roundabout lane configuration by the time the design consultant is selected (Nov 2025). May have consultant include northbound right turn lane and/or westbound left turn lane in design with the intent to only construct a standard single-lane roundabout.

**Project Scope** 

124357

Project Name

WAY SR 0057 08.91

> Landscaping: Follow normal landscaping guidelines for roundabouts, prefer mounded center (see WAY-57/604 PID 116212 for example). Use stone instead of grass. We have typically used a single layer of Item 204 - Geotextile Fabric but have heard that it is underperforming. Designer consider two layers of Item 204 - Geotextile Fabric or other weed control options.

- > Drainage: Replace existing storm sewer within project limits. Only replace culverts within full-depth project limits if needed. Keep open ditch if existing, enclosed if necessary. Designer to determine. Post-construction BMPs will be required on this project due to the Project EDA exceeding 1 acre. A NOI will be required on this project due to the total EDA exceeding 1 acre. The consultant shall evaluate vegetated filter strips and vegetated biofilter (if uncurbed section). Install Item 670 slope Erosion Protection Mat on slopes steeper than 3:1 (type of mat to be determined by shear stress values evaluated by the designer). Install underdrains under full depth pavement areas. Designer to verify underdrains able to be outlet properly. If not, aggregate drains will be installed.
- > Grading: Standard.

Roundabout Comments

- > Lighting: Minimum 2 per approach with illumination extending beyond the approach tapers, use LED luminaires, include with Stage 1. Follow TEM 1140-4.6.10 (Major/Collector). Roundabout lighting shall be installed according to IED DG-19-08, Design Guide for Roundabout Lighting and design lighting level and uniformity shall comply with IES DG-19-08 Table 1, which is based on functional class (FC) of intersecting roadways and pedestrian demand. For this project, use FC Major/Collector and Low Pedestrian Area. Illumination analysis should extend to approach tapers. Provide 120/240V power service, 3 wire #4 AWG (L-L-G) 2400V cable, ensure 5% voltage is not exceeded, ensure 15' clearance to overhead electric (from closest conductor). Offset all poles at least 8'-10' from the edge of pavement/face of curb. Do not place conventional pole foundations inside of a ditch. Provide a ground mounted Lighting Control Center (LCC) with concrete work pad. The LCC should be placed near a location that the maintenance bucket truck can pull off the roadway. Place a fused disconnect switch on the line side of the LCC. Also, the LCC should be at least 20' from the edge of pavement/face of curb to ensure it will not be hit by a motorist. A Pole Mounted Lighting Control Center may be acceptable over a Ground Mounted LCC if it will have better protection from the motorists. The LCC photocell should be located 2' above the LCC enclosure. If the LCC is placed behind the ditch line, place a 5' length of conduit in the ditch for the staff to traverse across. Provide 24" concrete pull boxes for 3 or more entrances/exits into a pull box. Provide a pull box on both sides of a conduit jack/bore. Include note for contractor underground marking after they take over maintenance. Include roundabout lighting note for operational lighting (temp/permanent) prior to opening the roundabout to traffic.
- > Include Plan Note for Item 630 Ground Mounted Support, No 3, As Per Plan

Page 3 of 12

Project **Project Scope** WAY SR 0057 08.91 124357 PID Name Geotechnical CRS WAY-57-8.91 0 Geotech Site 1 of Geohazard Type None **MOT Type Flaggers** (for geotechnical work) Description of Work Subgrade exploration required with half of the borings within the existing pavement area and remaining half in the proposed pavement area. Approx. 4-5 borings required. Comments As a district preference, global chemical stabilization is to be used if any stabilization is needed. **Pavement CRS** WAY-57-8.91 Vibratory Roller Permitted Yes Pavement Segment MOT No Detour Existing **Proposed** Use Simplified Pav't Design  $\rightarrow$ Pav't Cores Required Mainline Treatment Type Asphalt Asphalt No Shoulder Treatment Type  $\rightarrow$ PVD/Curb Pav't Cores Taken No Agg 2'-4'  $\rightarrow$ Paved Shoulder Width Varies\* ft Survey Required Yes  $\rightarrow$ Verify Proposed Lane Width 12' Varies\* R/W Required Yes Edge Line Location Varies\*  $\rightarrow$ Varies\* **Curbs Present** No  $\rightarrow$ Cross Slope **Varies** 0.0156 ft/ft Safety Edge No Proposed Grading Type Standard No. of Days Traffic can run on Milled Surface N/A days Proposed Pav't Treatment 100 - New Flexible Pavement Comments \*Follow L&D Manual for approach and circulating lane/shoulder widths. Proposed Full Depth: 1.5" Item 442 Asphalt Concrete Surface Course, 12.5mm, Type A (446) PG76-22M 1.75" Item 442 Asphalt Concrete Intermediate Course, 12.5mm, Type A (448) PG70-22M 6" Item 301 Asphalt Concrete Base PG64-22 6" Item 304 Aggregate Base Chemical subgrade stabilization Proposed Resurfacing if needed: 3.25" Item 254 Pavement Planning 1.5" Item 442 Asphalt Concrete Surface Course, 12.5mm, Type A (446) PG76-22M 1.75" Item 442 Asphalt Concrete Intermediate Course, 12.5mm, Type A (448) PG70-22M Safety edge on uncurbed sections with profile correction but not on curbed sections. Install underdrains under full depth pavement areas. Add 2' x 2" avg 617 with 408 prime coat on any areas of resurfacing/pavement replacement outside of the curbed area. Same for all approaches.

**Project Project Scope** 124357 WAY SR 0057 08.91 PID Name

#### **Traffic Control**

ng	Long Line Pavement Marking Type	The	rmoplastic	Lane Separator	No
Striping	Auxiliary Pavement Marking Type	The	rmoplastic	Delineators	Yes
₹.				Replace RPMs	Yes
es	Edge Line Rumble Stripes	No	Per	manent Traffic Count Station	No
Rumbles	Rumble Strips	No		Air Speed Zone Markings	No
<b>&amp;</b>	Centerline Rumble Stripes	No		Loop Detectors	No
	Transverse Rumble Strips	No			

- > Salvage signal heads and equipment (ground-mounted cabinet, meter base, controller, radar, conflict monitor, back-up battery inverter, cell modem, etc.) and return to ODOT D03 Ashland Office. Signal poles and mast arms to be disposed.
- > Use 36" warning and yield signs.
- > Use District 3 general note for flat sheet sign post stub and 3 lb u-channel posts.
- > RPM placement standard drawing (SCD TC-65.11).
- > Include edge line in the approach and exiting roadway up to yield line.
- >To prevent farm machinery from striking a sign post or light pole, for signs placed in the islands, do not place them directly across from a light pole. Stagger the placement at least 20'.
- > Splitter Island Related:
- Prefer to not install left side Yield signs in the splitter islands. Comments from other roundabouts include concerns of farm machinery knocking over signs within splitter islands. Left side Yield signs may be needed if exterior truck aprons are used due to increased offset to the right side Yield sign.
- Place route signs for exiting the roundabout in the splitter island but away from the edge of the island.
- For signs placed in the island, for the yielding stubbed post, install a 12" PVC conduit from the subbase layer to the top of the island.
- Include yellow flexible delineator at leading edge of splitter islands instead of a Keep Right sign.
- 600' no passing zone outside of the splitter islands on each approach to the roundabout.

Ma	Maintenance of Traffic (MOT)										
_	MOT Type	Detour	Feature	eature Roundab		Coordination Needed	Yes				
of	CRS	WAY-57-8.91	Duration	70	(Days)	Municipality	See Below				
E 1						Work Zone Speed Zone	No				
ltem	Disincentive	Road Closure	\$10,000/day		(Amt.)	PLCS	No				
MOT	MOT Exception	No			(Desc.)	LEO No. of Hours	0				
8	Conflict	Description			Rou	ite Dates to	o Avoid				

#### No known conflicts

- > SR 57 Detour: Use US 30, SR 94, and SR 604.
- > SR 585 Detour: Use SR 3/83, US 30, and SR 94.

Coordinate detours with Wooster, Dalton, and Marshallville.

- > Use \$10,000/day for holiday/event PN 127 disincentive. Include note that the detours are exempt from all holidays/events duirng the allowed detour duration.
- > Include temporary lighting note for operational lighting (temp/permanent) prior to opening the roundabout to traffic.

Project Classification			
CRS	Federal Aid System	<b>Functional Classification</b>	<b>Urbanized Area</b>
SR-57	Other Fed-Aide Highway	Minor Arterial	Rural (Pop < 5k)
SR-585	Other Fed-Aide Highway	Minor Arterial	Rural (Pop < 5k)

Traffic Forecast to be performed by ODOT D03 and provided to consultant.

Ρ	roject Scope	PID	124357	Project	Name	way SR 0057 08.91								
Er	vironmental													
	Environ. Category	Code	Responsib	oility	_									
	C	I	In-House		WAY-57-8.91									
	CZ	Т	OES Task Order		3-/									
	Environmental PM	С	Consultant Servi	ces	<u>}</u>									
	Connor Newsome	-	Not Applicable		≸									
<u>ie</u>	Section 106 - Scoping	g Request F	orm (*)		1									
Cultural	Phase 1 Hist./Arch. Survey Rpt. (If Auth.)													
Cu	Phase 1 Arch. Survey Report (If Auth.)													
S	Determination Reque	est Form	•											
Forms	Individual Section 4(	f) Eval.												
Ĕ	Section 6(f) Docume	ntation												
>	Ecological Exempt Fo	orm (*)												
Ecology	Level 1 Ecological Su		ts		1									
Ĕ	UNIONID Mussel Surv	ey Report												
	Sole Source Aquifer	Coordinatio	n											
	Convert signal contro	olled inters	ection into single	-lane round										
	Permit Determinatio	n Request I	Package											
	Concp. Stream/Wetl	•	-											
ts	Section 404/401 App	lications												
Permits	USACE Pre-Constr. N	otification	(PCN) Application	ns										
, Pe	Ohio EPA Isol. Wetland Permit Pre-Act. Notif. (PAN)													
Waterway	Coastguard Section 9	Applicatio	n											
ter	ACOE Section 10 Per	mit												
×a	Floodplain Permit Ap	plication												
	Floodplain Coordinat	•			1									
	Coastal Waterway Pe													
	Regulated Mat. Revie		(1)		1									
Site	Phase 1 Env. Site Ass	sess. Rpt. (I	f Auth.)											
S	Asbestos Survey/Insp	•	,											
	Ozone Analysis													
Air	MSAT Analysis													
•	PM 2.5 Analysis													
Se	Traffic Noise Analysi	s Report												
Noise	Noise Barrier Public	•	t Summary											
	Public Involvement F		,											
ij	Public Meeting Activ													
Public	Public Announce. (w		ticle, news releas	se)	ı									
_	Underserved Populat			,										

Any Known Env. Concerns (ex. historic properties on Nat. Reg., wetlands, underground storage tanks, stream reloc.)

Design consultant to provide exhibits (roundabout layout and detour plan) for PI mailers. Provide the PI exhibits to District 3 with the Stage 1 submittal. Include preliminary ROW lines on Stage 1 plans.

**Project Scope Project Name** WAY SR 0057 08.91 124357 PID Right-of-Way Feature CRS WAY-57-8.91 R/W Site 1 of Feature Type Roundabout Responsibility Task Order **Titles** Permanent & Temp Task Order R/W Type **Appraisal** Task Order Known Relocations? Maybe Appraisal Review Access Modification Reg'd? R/W Acquisition Services Task Order Maybe Estimated No. of Parcels 3-4 R/W Acquisition Cost Est. Task Order Residential/Agricultural Land Use R/W Plans Dsgn Consultant Comments Consultant should attempt to avoid right-of-way takes, if possible. Note: There is a billboard in the NW corner and an attempt should be made to avoid. Otherwise, it will be considered a relocation. Reason for Construction of roundabout will require additional R/W and temp. R/W for construction. Additional R/W Survey CRS WAY-57-8.91 Roundabout Surveyor CONSULTANT/DISTRICT 3 Asset Type

		CIND	11A1 37	0.71	Asset Type	Roundabout		Jui	VCyOI COINSOL	ANT DISTRICT S
of										
e –							Co	unt		Responsibility
Sit	_				Type 'A' Control Mo	nument	7	2	Monuments	In-House
Survey Site	ţį			Type 'B' Control Mo	nument	4	4	Monuments	In-House	
Sur	ints			Mon. Re	ecovery for Existing CL a	nd R/W	1.	.5	Miles	In-House
	Monumentation			Monum	ent Recovery for Proper	ty Lines	Ç	9	Owners	Dsgn Consultant
	on		Stake F	R/W for Acc	quisition/Utilities/Tree (	Clearing	Ç	9	Owners	Dsgn Consultant
	2	Pin New R/W Following Construction					Ç	9	Owners	Dsgn Consultant
	DG DG				Base Mapping (and Field	Verify)	6	6	Tenths of a Mile	Dsgn Consultant
	Mapping			Est. Prop	o. Lines, Tax ID, Owners	on Map	Ģ	9	Owners	Dsgn Consultant
	¥				Property Owner Noti	fication	Ģ	9	Owners	Dsgn Consultant
					Soil Boring	Staking -			Borings	Dsgn Consultant
	Торо	Inte	rsects		Road (At Grade)				Tenths of a Mile	Dsgn Consultant
	မို					l	ength	Width	1	
		То	po for		Intersection				Tenths of a Mile	Dsgn Consultant

The ODOT District Survey Department will establish the primary control network per ODOT Specification. The ODOT District Survey Department will determine the Centerline of RW and RW for all routes within the project limits (SR 57 & SR 585). The control and centerlines as determined by the District Survey Department will be held for the project. The consultant will perform the following relative to the established control network: Retrace and establish property lines for all parcels within mapping limits (approximately 9 parcels). Topographic mapping 700' from the intersection in all directions and extending 25' beyond the existing R/W or proposed conceptual work limits(whichever is greater) including all utilities per 811 markings. All working performed in Ohio County Coordinate System.

> When it comes time for ROW acquisitions, we will need an if-authorized task for ROW staking for negotiations and ROW staking for all ROW takes at the time of acquisition (includes all utilities, temps, SH, etc.). This is in addition to the permanent pinning usually included in SAFe tasks. Also include final staking for all right-of-way after acquisition complete (include all permanent, temp, and easements).

Project Scope PID 124357 Project Name WAY SR 0057 08.91
Utilities

<del>.</del>	
of	
es 1	
ijį	
当	

	Location WAY-57- Asset Roundal Name of Utility					pə	al	SUE Needed?	R/W Needed?
	Name of Utility	/	Lo	cation/Description		Buried	Aerial	SUE	§ §
Power	City of Orrville		SR 57, north leg	e on SR 57, south leg; wes g; south side of SR 585, e side of SR 585, west leg		No	Yes	No	Yes
Phone	Brightspeed		Buried on the	north and south side of S	SR 585 Y	Yes	No	Yes	Yes
Gas	Northeast Ohio G	as	Cross SR 5	85 west of the intersection	on Y	Yes	No	Yes	Maybe
Gas	OWS Acquisition	s Fo	-	& Blake; east side of SR th side of SR 585, east leg	Y	Yes	No	Yes	Maybe
Cable	City of Orrville Ca	ble	Attach	ed to the Orrville poles	ı	No	Yes	No	Yes
Comm.	Everstream	,	Attached to the	power poles, south leg a leg	and east	No	Yes	No	Yes

#### Comments Notes:

- > Use centerline of the roadway as centerline of construction- helpful to locate and coordinate with utilities. Also, use one center of the roundabout with 4 matchlines for each leg. For each stage review/feasibility study submittal, send a one-page combined P&P sheet in .PDF format.
- > Use SUE Level B performed by design consultant on all underground utilities prior to first submittal (Stage 1). District will determine location of proposed test holes. Prepare cost proposal and scope of work for up to 10 SUE test holes.
- > Designers Utilities & the highway lighting, ensure all our facilities (poles, arms, luminaires) are a minimum 15 feet from the closest distribution electric powerline conductors.
- > Discuss potential roll plot style submission for utility review so everything is together and viewable.
- >Utility relocation plan process currently under review. May be modified from existing process. Additional information will be provided as it becomes available.

	oject Scope PID	1243	Project Name	WAY :	SR 0057 08.91	
Co	ordination					
	FAA	Yes			Railroad	No
	Detour Agreement	No			Floodplain	No
rd.	Detour Coordination	Yes				
Coo	Innovative Contracting	No	B <sup>-</sup>	ike Route or Trail with	nin Project Limits	No
	Maintenance Agreement	Maybe	Assets in Mainten	ance Agreement		
	Tree Removal	No		N/A		

> Design consultant to evaluate via the FAA Notice Criteria Tool. Filings, if needed, are to be for both construction equipment and the final permanent facility (light poles, etc.)

### **Project Schedule**

Comments

**Project Schedule** 

Date		Date	
-	Field Review Date	8/1/2027	Stage 2 Plans - Submitted
7/1/2025	In-House Scope Meeting	9/1/2027	Stage 2 Plans - Complete
-	Project Initiation Package	6/1/2027	Preliminary R/W Plans - Submit
8/1/2025	Initial Project Scope Complete	7/1/2027	Preliminary R/W Review Approve
		9/1/2027	Compliance R/W Plans - Submit
		10/1/2027	Compliance R/W Plans - Approve
9/8/2025	Programmatic Date	11/1/2027	Final R/W Plans - Approved
-	Feasibility Study - Approved	12/1/2027	R/W Authorized
-	Alternative Evaluation Report - Appr.	4/1/2028	Stage 3 Plans - Submitted
-	Preferred Alternative Approval	5/1/2028	Stage 3 Plans - Complete
	Survey Deliverables Complete	9/1/2027	Environmental Doc. Approved
-	Begin In-House Detailed Design	8/1/2029	R/W Acquisition Complete
2/1/2026	Authorized Design Consultant	9/1/2029	District R/W Certification
1/1/2027	NEPA Start Date	9/1/2029	Final Tracings Submitted
6/1/2026	Pre-Stage 1 Submitted	10/1/2029	Final Tracings Complete
7/1/2026	Pre-Stage 1 - Complete	10/1/2029	Plan Package Received in C.O.
12/1/2026	Stage 1 Plans - Submitted	1/1/2030	Sale Date
1/1/2027	Stage 1 Plans - Approved	1/1/2030	Award Date
-	Waterway Permit Determination-Submit	5/1/2030	Estimated Begin Construction
	404/401 Permits Submitted	9/1/2030	Estimated End Construction

Comments Sept 2025 programmatic for design consultant.

TED Office Required Milestones - >20M Projects

Include preliminary ROW lines on Stage 1 plans. Provide the PI exhibits to District 3 with the Stage 1 submittal.

Milestone not needed for all projects

Pı	rojec	t Scope PID	124357	Project Name		WAY SR 0057 08.91					
Fu	nding										
	<del>≥</del>			Fundi	ng Source	Fundi	ng Source				
Split /	orit			Soi	Source 1		ource 2				
Spl	Pri	Name	Plan Split Code	%	Fund	%	Fund	Cost			
1	/ 1	CO CO Contr 01	01/SAF/21	100	4HJ7			\$2,900,000.00			
	Descr:	escr: Convert signal-controlled intersection into roundabout at WAY-57-8.91 (Construction Only)									

Funding Summary													
Project Phase	Funding Source / Description	Percent Fed State		Fiscal Year / Quarter	Phase Estimate								
Preliminary Engineering	Safety	100		FY2026 Q3	\$600,000.00								
Detailed Design	Safety	100		FY2028 Q2	\$100,000.00								
Right of Way Services	Safety	100		FY2028 Q2	\$30,000.00								
Right of Way Acquisition	Safety	100		FY2028 Q2	\$20,000.00								
Utilities Reimbursement	Safety	100		FY2030 Q3	\$100,000.00								
Construction Contract	Safety	100		FY2030 Q3	\$2,900,000.00								
Construction Engineering	Labor	100		FY2030 Q3	\$203,000.00								
Total					\$3,953,000.00								

Project Scope PID 124357 Project Name WAY SR 0057 08.91

See the project overview map below.



Project Scope	PID	124357	Project Name	WAY S	Y SR 0057 08.91								
Signatures and Att	endance				Approval		Field Visit	Scope Meeting					
			Signature	Date	Approve	Disapprove	On Your Own	7/1/2025					
<b>ELLIS Coordinator</b>	Heidi Mertler						-	-	-				
Environmental PM	Connor Newsome						-	-	-				
Bridge Engineer	Kent Kapustar						-	-	-				
Planning Engineer	Scott Ockunzzi						-	X	-				
Design PM	Jane Cullen						-	X	-				
Roadway Engineer	Charlie Laughrey						-	X	-				
Traffic Engineer	Julie Cichello						-	X	-				
Survey Op. Mgr.	Scott Hawkins						-	X	-				
<b>Utility Coordinator</b>	John Schafrath						-	X	-				
Real Estate Admin.	Brad Corder						-	X	-				
Design Engineer	Kenny Knapp						-	X	-				
Constr. Area Eng.	Luke Wysocki						-	-	-				
Constr. Engineer	Mike Fair						-	-	-				
Cap. Prog. Admin.	Matt Walter						-	-	-				
Rdwy. Serv. Mgr.	. Mgr. Kimberly Conklin						-	-	-				
Hwy. Mgt. Admin.	Eric Sheppard						-	Χ	-				
County Manager	Dennis Ryncarz						-	Χ	-				
Attendee	Gary Gillen		N/A	N/A	N/A	N/A	-	Χ	-				
Attendee	Carrie Whitaker		N/A	N/A	N/A	N/A	-	Χ	-				
Attendee	Adam Mellen		N/A	N/A	N/A	N/A	-	Χ	-				
Attendee	Kathryn Wade		N/A	N/A	N/A	N/A	-	Χ	-				
Attendee	Jared Feller		N/A	N/A	N/A	N/A	-	Χ	-				
Attendee	Nick Foster		N/A	N/A	N/A	N/A	-	Χ	-				
Attendee	Jerry Bantz		N/A	N/A	N/A	N/A	-	Χ	-				
Attendee	Shelley Pitcher		N/A	N/A	N/A	N/A	-	Χ	-				
Attendee	Anthony C	irigliano	N/A	N/A	N/A	N/A	-	X	-				
Attendee	Levi W	ingler	N/A	N/A	N/A	N/A	-	X	-				
							-	-	-				