



OHIO DEPARTMENT OF TRANSPORTATION

CENTRAL OFFICE • 1980 WEST BROAD STREET • COLUMBUS, OH 43223
JOHN R. KASICH, GOVERNOR • JERRY WRAY, DIRECTOR

12/12/2016

Project 160630 **Addendum No. 3**
PID No. 103632
SUM – IR 77 – 15.18
Spot Patching
Letting: December 15, 2016

Notice to all Bidders and Suppliers to please be advised of the attached Proposal Addendum.

For internet access to information referenced in this addendum, please see the ODOT web site at -> <ftp://ftp.dot.state.oh.us/pub/Contracts/Attach/SUM-103632/>

The Department utilizes Bid Express (<http://www.bidx.com>) as the official medium for electronic bid submittal. All bidders must prepare bids and submit them online via Bid Express.

Addenda amendments must be acknowledged in the miscellaneous section of the Expedite (EBS) file and all amendments loaded in order for your bid to be considered for award of this project. Bid express will not accept bids that do not have amendments incorporated. Failure to incorporate changed quantities or items in your Expedite (EBS) submissions will result in the rejection of your bid.

**Proposal Addendum
For
SUM-77-15.18; PID 103632
Project 160630**

Bid Item Changes, Additions or Deletions: Yes

Revised Bid Items:

Ref. No.	Item No.	Total Quantity	Unit	Description	Section
0019	614E18601	32	SNMT	Portable Changeable Message Sign, As Per Plan	0006

Added Bid Items:

Ref. No.	Item No.	Total Quantity	Unit	Description	Section
0100	202E11201	LS	LS	Portions Of Structure Removed, As Per Plan	0008
0101	509E10001	1305	LB	Epoxy Coated Reinforcing Steel, As Per Plan	0008
0102	509E20001	200	LB	Reinforcing Steel, Replacement Of Existing Reinforcing Steel, As Per Plan	0008
0103	510E10000	80	EACH	Dowel Holes With Nonshrink, Nonmetallic Grout	0008
0104	519E11900	7	CY	Patching Concrete Structure: Ves-Lmc (Very Early Strength Latex Modified Concrete)	0008
0105	519E60000	LS	LS	Patching Concrete Structure: Trial Batch For Ves-Lmc (Very Early Strength Latex Modified Concrete)	0008

Replace/Add Plan sheets: Yes replace sheets 1 – 13. Add sheets 14 – 21.

Remove standard construction drawing MT-104.10 dated 10/16/15 and Supplemental Specification 808 dated 1/29/16 from the title sheet, added SCD BP-2.1 & BP-2.5 to title sheet, added 1 MOT sheet and 7 structure sheets, revised concrete repair notes on sheet 4.

Answers to Prebid Questions: Yes

(The inclusion of the question(s) that accompany answer(s) in this addendum is provided for reference only and the question(s) shall not be construed as a contract modification or change.)

Q1: Under Reference number 7 Plan Page 4 is the intent to install a new 18" Prefabricated Edge Underdrains per Item 611 or is the Underdrain paid under item 605 Reference 3 6" Shallow Pipe Underdrains ?

A1: Underdrains will be 6" Shallow Pipe Underdrains. There will be no 18" Prefabricated Edge underdrains.

Q2: Please add STD BP 2.5 to the Standard drawings for this project and provide a detail for the longitudinal joints as specified in the repair quantity.

A2: We will add direction in the plan to refer to BP-2.5 for the transverse joints and to refer to BP-2.1 for the longitudinal joints.