
0



LATITUDE: 40°17'55" LONGITUDE: 83°04'25"

SCALE IN MILES

DESIGN EXCEPTIONS.

NONE

ND	CON	TACT L TVC	BOTH	SERVICE ING DAY U DIG	S
		-800	CALL -362-	2764	
OHIO		NON	-MEMB	CTION: ERS DIRECTI	
•	R GAS		DUCERS 1-801	-929-	CTIVE 0988

PLAN PREPARED BY:

OHIO DEPARTMENT OF TRANSPORTATION OFFICE OF PRODUCTION 1980 HEST BROAD STREET COLUMBUS, OHIO 43223 STATE OF OHIO

DEPARTMENT OF TRANSPORTATION

DEL-36-9.81

CITY OF DELAWARE DELAWARE COUNTY

INDEX OF SHEETS:

TITLE SHEET

SCHEMATIC PLAN

GENERAL NOTES

MAINTENANCE OF TRAFFIC

GENERAL SUMMARY

PLAN AND PROFILE - US36

PLAN AND PROFILE - LIBERTY

CULVERT DETAILS

RIGHT OF WAY

SOIL PROFILES

# PROJECT DESCRIPTION

REHABILITATION OF A 15 FT STONE ARCH STRUCTURE
UNDER US36 USING AN INSITU LINER. THE ARCH SPIRAL
WOUND RENEWAL SYSTEM WILL BE USED CONSISTING OF
A PYC LINER AND GROUTING THE ANNULAR SPACE.

PROJECT EARTH DISTURBED AREA: N/A MAINTENANCE PROJECT)
ESTIMATED CONTRACTOR EARTH DISTRIBED AREA: N/A MAINTENANCE PROJECT)
NOTICE OF INTENT EARTH DISTURBED AREA: N/A MAINTENANCE PROJECT)

# 2010 SPECIFICATIONS

THE STANDARD SPECIFICATIONS OF THE STATE OF OHIO, DEPARTMENT OF TRANSPORTATION, INCLUDING CHANGES AND SUPPLEMENTAL SPECIFICATIONS LISTED IN THE PROPOSAL SHALL GOVERN THIS IMPROVEMENT.


I HEREBY APPROVE THESE PLANS AND DECLARE THAT THE MAKING OF THIS IMPROVEMENT WILL NOT REQUIRE THE CLOSING TO TRAFFIC OF THE HIGHNAY EXCEPT FOR THE SIDE ROADS AS DESCRIBED ON SHEETS 4 AND THAT PROVISIONS FOR THE MAINTENANCE AND SAFETY OF TRAFFIC WILL BE AS SET FORTH ON THE PLANS AND ESTINATES.

DATE
CTM .
SIX TRANSPORTATION

APPROVED DIRECTOR, DEPARTMENT OF TRANSPORTATION

SUPPLEMENTAL STANDARD CONSTRUCTION DRAWINGS SPECIFICATION ~800 4/15/11 4/16/10 ENGINEERS SEAL+ 832 5/5/09 H-50.H 1/19/07 07/16/10 MT-101.80 A/17/09 17-105.10 1/16/08 SPECIAL MT-110.10 1/16/09 PROVISIONS 70-41,20 1/19/01 WATERWAY PERMIT CON DATED: 1/4/10 06/14/2010 #20100482

22



### UTILITIES

LISTED BELOW ARE ALL UTILITIES LOCATED WITHIN THE PROJECT CONSTRUCTION LIMITS TOGETHER WITH THEIR RESPECTIVE OWNERS:

ELECTRIC:	TELEPHONE:
AMERICAN ELECTRIC POWER	VERIZON
850 TECH CENTER DRIVE	<i>550 LEADER STREET</i>
GAHANNA, OH 43230-6605	MARION, OH 43302
PAUL PAXTON	CHRIS AVERY
OFFICE 614-883-6831	OFFICE 740-383-0551
FAX 614-883-6868	

GAS:	SANITARY, STORM
COLUMBIA GAS OF OHIO	CITY OF DELAWARE
3550 JOHNNY APPLESEED COURT	225 CHERRY STREET
COLUMBUS, OH 43231	DELAWARE, OH 43015
MATT COYNE	DALE FILBY
OFFICE 614-818-2107	OFFICE 740-203-196
FAX 614-365-3406	CELL 740-816-7338
	FAX 740-203-1997

CABLE:	WATER:
TIME WARNER CABLE	CITY OF DELAWARE WATER
<i>3760 INTERCHANGE DRIVE</i>	3080 US 23 NORTH
COLUMBUS, OH 43204	DELAWARE, OH 43015
RAY MAURER	RON AMBROSE
OFFICE 614-481-5262	OFFICE 740-203-1972
	FAX 740-203-1998

### WORK LIMITS

THE WORK LIMITS SHOWN ON THESE PLANS ARE FOR PHYSICAL CONSTRUCTION ONLY. PROVIDE THE INSTALLATION AND OPERA-TION OF ALL WORK ZONE TRAFFIC CONTROL AND WORK ZONE TRAFFIC CONTROL DEVICES REQUIRED BY THESE PLANS WHETHER INSIDE OR OUTSIDE THESE WORK LIMITS.

# ELEVATION DATUM

ALL ELEVATIONS ARE ORTHOMETRIC HEIGHTS USING THE NORTH AMERICAN VERTICAL DATUM OF 1988 (NAVD 88) AND THE GEOIDO3 GEOID. HORIZONTAL POSITIONS ARE BASED ON THE OHIO STATE PLANE NORTH ZONE, A LAMBERT CONFORMAL CONIC MAP PROJECTION, THE NORTH AMERICAN DATUM OF 1983 ADJUSTED TO THE NATIONAL SPATIAL REFERENCE SYSTEM OF 2007 (NAD 83 (NSRS 2007)), AND THE GRS80 ELLIPSOID.

# CLEARING AND GRUBBING

ALTHOUGH THERE ARE NO TREES OR STUMPS SPECIFICALLY MARKED FOR REMOVAL WITHIN THE LIMITS OF THE PROJECT. A LUMP SUM QUANTITY IS INCLUDED IN THE GENERAL SUMMARY FOR ITEM 201, CLEARING AND GRUBBING. ALL PROVISIONS AS SET FORTH IN THE SPECIFICATIONS UNDER THIS ITEM ARE INCLUDED IN THE LUMP SUM PRICE BID FOR ITEM 201, CLEARING AND GRUBBING.

# ITEM 607 - FENCE, TYPE CL. AS PER PLAN

THE CONTRACTOR SHALL FURNISH TEMPORARY FREE-STANDING CHAIN LINK FENCE PANELS FOR THE CONSTRUCTION STAGING AREAS AND PEDESTRAIN SAFETY. THE CONTRACTOR SHALL NOT DRILL / DRIVE POSTS TO ERECT FENCE. THE FOLLOWING ESTIMATED QUANTITY HAS BEEN INCLUDED IN THE GENERAL SUMMARY:

607, FENCE, TYPE CL, AS PER PLAN 450 FT.

### SEEDING AND MULCHING

THE FOLLOWING QUANTITIES ARE PROVIDED TO PROMOTE GROWTH AND CARE OF PERMANENT SEEDED AREAS:

659. REPAIR SEEDING AND MULCHING 300 SQ. YD

659, WATER 2 M. GAL.

SEEDING AND MULCHING SHALL BE APPLIED TO ALL AREAS OF EXPOSED SOIL BETWEEN THE RIGHT-OF-WAY LINES, AND WITHIN THE CONSTRUCTION LIMITS FOR AREAS OUTSIDE THE RIGHT-OF-WAY LINES COVERED BY WORK AGREEMENT OR SLOPE EASEMENT. QUANTITY CALCULATIONS FOR SEEDING AND MULCHING ARE BASED ON THESE LIMITS.

# REVIEW OF DRAINAGE FACILITIES

BEFORE ANY WORK IS STARTED ON THE PROJECT AND AGAIN BEFORE FINAL ACCEPTANCE BY THE STATE, REPRESENTATIVES OF THE STATE AND THE CONTRACTOR, ALONG WITH LOCAL REPRESENTATIVES, SHALL MAKE AN INSPECTION OF ALL EXISTING SEWERS WHICH ARE TO REMAIN IN SERVICE AND WHICH MAY BE AFFECTED BY THE WORK. THE CONDITION OF THE EXISTING CONDUITS AND THEIR APPURTENANCE SHALL BE DETERMINED FROM FIELD OBSERVATIONS. RECORDS OF THE INSPECTION SHALL BE KEPT IN WRITING BY THE STATE.

ALL NEW CONDUITS, INLETS, CATCH BASINS, AND MANHOLES THAT MAY BE CONSTRUCTED AS A PART OF THE PROJECT SHALL BE FREE ORF ALL FOREIGN MATTER AND IN A CLEAN CONDITION BEFORE THE PROJECT WILL BE ACCEPTED BY THE STATE.

ALL EXISTING SEWERS INSPECTED INITIALLY BY THE ABOVE MENTIONED PARTIES SHALL BE MAINTAINED AND LEFT IN A CONDITION REASONABLY COMPARABLE TO THAT DETERMINED BY THE ORIGINAL INSPECTION. ANY CHANGE IN THE CONDITION RESULTING FROM THE CONTRACTOR'S OPERATIONS SHALL BE CORRECTED BY THE CONTRACTOR TO THE SATISFACTION OF THE ENGINEER.

PAYMENT FOR ALL OPERATIONS DESCRIBED ABOVE SHALL BE INCLUDED IN THE CONTRACT PRICE FOR ITEM 603 CONDUIT. MISC.: 15' SPAN X 7' RISE ARCH SPIRAL WOUND RENEWAL SYSTEM.

# UNRECORDED STORM WATER DRAINAGE

FURNISH A CONTINUANCE FOR ALL UNRECORDED STORM WATER DRAINAGE, SUCH AS ROOF DRAINS, FOOTER DRAINS, OR YARD DRAINS, DISTURBED BY THE WORK, FURNISH EITHER AN OPEN CONTINUANCE OR AN UNOBSTRUCTED CONTINUANCE BY CONNECT-ING A CONDUIT THROUGH THE CURB OR INTO A DRAINAGE STRUCTURE. THE LOCATION, TYPE, SIZE AND GRADE OF THE NEEDED CONDUIT TO REPLACE OR EXTEND AN EXISTING DRAIN WILL BE DETERMINED BY THE ENGINEER. ALL SUCH CONTINUANCE REQUIRES A RIGHT OF WAY USE PERMIT.

THE FOLLOWING CONDUIT TYPES MAY BE USED: 707.33, 707.41 NON-PERFORATED, 707.42, 707.43, 707.45, 707.46, 707.47, 707.51. 707.52 SDR35.

THE FOLLOWING ESTIMATED QUANTITIES HAVE BEEN INCLUDED IN THE GENERAL SUMMARY FOR USE AS DIRECTED BY THE ENGINEER FOR THE WORK NOTED ABOVE:

603, 6" CONDUIT, TYPE B, FOR DRAINAGE CONNECTION 50 FT.

603, 6" CONDUIT, TYPE C, FOR DRAINAGE CONNECTION 50 FT.

# UNRECORDED ACTIVE SANITARY SEWER CONNECTIONS

FURNISH A CONTINUANCE FOR ALL UNRECORDED ACTIVE SANITARY SEWER CONNECTIONS SUCH AS SANITARY, WASTEWATER, CURTAIN/ GRADIENT DRAINS, AND FOUNDATION FLOOR DRAINS DISTURBED BY THE WORK. FURNISH AN UNOBSTRUCTED CONTINUANCE OF THE UNRECORDED ACTIVE SANITARY SEWER CONNECTIONS TO THE SATISFACTION OF THE ENGINEER. ALL SUCH CONTINUANCE REQUIRES A RIGHT OF WAY USE PERMIT. ALL SANITARY AND SANITARY WASTEWATER CONTINUANCE MAY ALSO REQUIRE A NPDES PERMIT FROM THE OHIO ENVIRONMENTAL PROTECTION AGENCY. REPORT ALL CONTINUANCE TO THE LOCAL HEALTH DEPARTMENT.

THE FOLLOWING CONDUIT TYPES MAY BE USED: 707.42, 707.43, 707.44, 707.45, 707.46, 707.47, 707.51, 707.52 SDR35, 706.01, 706.02, OR 706.08 WITH JOINTS AS PER 706.11 OR 706.12.

THE FOLLOWING ESTIMATED QUANTITIES HAVE BEEN INCLUDED IN THE GENERAL SUMMARY FOR USE AS DIRECTED BY THE ENGINEER FOR THE WORK NOTED ABOVE:

603, 8" CONDUIT, TYPE B, FOR SANITARY 50 FT.

603. 8" CONDUIT. TYPE C. FOR SANITARY 50 FT.

# AIRWAY/HIGHWAY CLEARANCE FOR AIRPORTS AND HELIPORTS

THIS PROJECT HAS BEEN IDENTIFIED AS BEING WITHIN THE IN-FLUENCE AREA OF A PUBLIC USE AIRPORT OR HELIPORT. NO TEMPORARY STRUCTURES OR CONSTRUCTION EQUIPMENT AT MAXIMUM OPERATING HEIGHT SHALL EXCEED A HEIGHT OF 167 FT. IF ANY TEMPORARY STRUCTURES OR CONSTRUCTION EQUIPMENT WILL EXCEED THIS HEIGHT. FURTHER COORDINATION WITH THE FEDERAL AVIATION ADMINISTRATION (FAA). AND ODOT OFFICE OF AVIATION, WILL BE NECESSARY PRIOR TO ERECTING SUCH TEMPORARY STRUCTURES OR OPERATING SUCH EQUIPMENT ON THE PROJECT. THE CONTRACTOR WILL BE REQUIRED TO SUBMIT FORM 7460-1 TO THE FAA. A COPY OF THE SUBMISSION AND TWO COPIES OF FORM 7460-1 SHALL BE FORWARDED TO THE ODOT OFFICE OF AVIATION. NO TEMPORARY STRUCTURES OR CONSTRUCTION EQUIPMENT SHALL EXCEED THE PERMISSIBLE HEIGHT. UNTIL A COPY OF THE FAA APPROVAL AND ODOT OFFICE OF AVIATION PERMIT HAS BEEN FURNISHED TO THE PROJECT ENGINEER.

Express Processing Center The Federal Aviation Administration Southwest Regional Office Air Traffic Airspace Branch ASW-520 2601 Meachan Blvd. Fort Worth, TX 76137-4298

Ohio Department of Transportation Office of Aviation 2829 West Dublin-Granville Road Columbus, Ohio 43235 614-387-2346

# STREAM CHANNEL EXCAVATION

THE CONTRACTOR SHALL TAKE ALL PRECAUTIONS NECESSARY TO PREVENT ANY INCIDENTAL DISCHARGES ASSOCIATED WITH THE EXCAVATION AND HAULING OF MATERIAL FROM THE STREAM CHANNEL. THIS PERTAINS TO ANY EXCAVATION OPERATIONS SUCH AS, FOUNDATION PIER OR ABUTMENT EXCAVATION, CHANNEL CLEANOUT, EXCAVATION FOR ROCK CHANNEL PROTECTION AND REMOVAL OF ANY TEMPORARY FILL ASSOCIATED WITH CONSTRUC-TION OPERATIONS.

### ENVIRONMENTAL COMMITMENT - WILLIS FIELD

THE WORKS INVOLVES LINING A STONE ARCH THAT CARRIES DELAWARE RUN UNDER THE LOCAL ROADWAY NETWORK IN THE CITY OF DELAWARE, DELAWARE COUNTY, OHIO. IN ORDER TO FACILITATE CONSTRUCTION, SEWER EASEMENTS ARE NEEDED TO PROVIDE FOR RIGHT-OF-ENTRY ACCESS. THE MAJORITY OF THE WORK AND ANY FUTURE MAINTENANCE IS TO OCCUR UNDERGROUND. THERE WILL BE NO TEMPORARY OR PERMANENT INTERFERENCE WITH THE INTENDED FUNCTIONS OR ATTRIBUTES ASSOCIATED WITH THE EXISTING RECREATIONAL FACILITY.

SHOULD THE CONTRACTOR NEED ACCESS TO THE STONE ARCH THROUGH A MANHOLE AT STA. 514+29.96 LT. FOR GROUTING NO OPERATIONS PERMANENT OR ADVERSE EFFECTS WILL OCCUR. THE CONTRACTOR WILL ONLY OCCUPY THE AREA TO DROP A GROUT LINE THROUGH THE OPENING.

WILLIS FIELD IS TO REMAIN UNAFFECTED BY THE WORK.

# WATERSHED PROTECTION

THE WORK ASSOCIATED WITH THIS PROJECT IS BEING PERFORMED WITHIN A CORRIDOR MANAGEMENT ZONE & SOURCE WATER PROTECTION AREA. IT IS ESSENTIAL THAT ALL ACTIVITIES WITH THIS WORK BE PERFORMED IN A MANNER CONSISTENT WITH BEST WATERSHED MANAGEMENT PRACTICES INCLUDING. BUT NOT LIMITED

AREAS OF DISTURBED GROUND SHALL HAVE APPROPRIATE EROSION AND SEDIMENT CONTROLS. IF HAZARDOUS/TOXIC MATERIALS INCLUDING BUT NOT LIMITED TO FUELS, OILS, BITUMEN'S PAINT, SEMILANTS, OR OTHER CHEMICALS, ARE STORED ON SITE, THEY SHOULD BE STORED IN A DOUBLE-CONTAINMENT MANNER. ALL EQUIPMENT REPAIRS, MAINTENACE, AND MECHANICAL WORK THAT COULD RESULT IN THE RELEASE OF HAZARDOUS/TOXIC MATERIALS WILL BE PERFORMED IN AN APPROPRIATELY CONTAINED AREA PREFERABLY OFF-SITE OR AN APPROPRIATE OFF-SITE FACILITY.


IN THE EVENT THAT ANY HAZARDOUS/TOXIC MATERIALS INCLUDING, BUT NOT LIMITED TO FUELS, OILS, BITUMEN'S PAINT, SEALANTS OR OTHER CHEMICALS ARE SPILLED, THE CONTRACTOR WILL IMMEDIATELY NOTIFY THE OHIO EPA @ (800)282-9378 AND THE DELCO PUBLIC WATER SYSTEM @ (800)521-6779. THE CONTRACTOR SHOULD BE PREPARED TO PROVIDE DETAILED INFORMATION RELATIVE TO THE TYPE AND QUANTITY OF MATERIAL THAT HAS BEEN SPILLED AS WELL AS THE EXACT LOCATION AND THE EXACT TIME AT WHICH THE SPILL OCCURRED. THE CONTRACTOR WILL BE SOLEY RESPONSIBLE FOR INFORMING ALL SUBCONTRACTORS AND OTHER AGENTS OF THESE RESPONSIBLITIES, PRECAUTIONS, AND PROHIBITIONS.

NO TOXIC OR HAZARDOUS MATERIALS SUCH AS SEALANTS. PAINT SOLVENTS, CLEANING AGENTS, EARTHEN MATERIALS, WASTE-WATER FUELS OR DEBRIS OF ANY KIND WILL BE DISCHARGED TO ANY STREAMS, DRAINAGE COURSES OR BODIES OF WATER. ALL ASPHALT OR CONCRETE GRINDINGS, EXCESS ASPHALTIC OR CONCRETE MATERIALS OR ANY DEBRIS GENERATED DURING RE-SURFACING OR OTHER SIMILIAR ACTIVITIES WILL NOT BE DIS-POSED OF WITHIN A FLOODPLAIN BELOW THE 100-YEAR FLOOD ELEVATION. THE CONTRACTOR WILL TAKE ALL PRECAUTIONS NECESSARY TO PREVENT LIQUIDS USED TO REPAIR, CLEAN, SEAL, OR TREAT ANY BRIDGE STRUCTURE (E.G. PAINT, SOLVENT) FROM ENTERING STREAMS, WETLANDS, OR OTHER "WATERS OF THE UNITED STATES" AND TAKE THE APPROPRIATE ACTIONS IN THE EVENT OF A RELEASE.

BEFORE THE WORK BEGINS, THE CONTRACTOR WILL SUBMIT TO THE ENGINEER THE NAMES AND TELEPHONE NUMBERS OF THE PERSON OR PERSONS WHO CAN BE CONTACTED 24 HOURS PER DAY BY THE OHIO DEPARTMENT OF TRANSPORTATION, DELAWARE COUNTY ENGINEER, AND ALL INTERESTED POLICE AGENCIES. THIS PERSON OR PERSONS IS RESPONSIBLE FOR PLACING OR REPLACING NECESSARY TRAFFIC CONTROL DEVICES IN ACCORDANCE WITH THE OHIO MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES.

THE CONTRACTOR WILL ADVISE THE ODOT DISTRICT PUBLIC INFORMATION OFFICER AT (740) 833-8349, AND THE CITY OF DELAWARE AT (740) 203-1700, SEVEN (7) DAYS PRIOR TO THE START OF CONSTRUCTION ACTIVITES. THE PROJECT ENGINEER WILL PROVIDE ASSISTANCE/CLARIFICATION FOR ANY QUESTIONS.

NOTICE OF CLOSURE SIGNS, AS DETAILED IN THESE PLANS, ARE TO BE ERECTED BY THE CONTRACTOR AT LEAST ONE WEEK IN ADVANCE OF THE SCHEDULED ROAD OR RAMP CLOSURE. THE SIGNS WILL BE ERECTED ON THE RIGHTHAND SIDE OF THE ROAD FACING TRAFFIC. THEY WILL BE PLACED SO AS NOT TO INTERFERE WITH THE VISIBILITY OF ANY OTHER TRAFFIC CONTROL SIGNS. THEY SHOULD BE ERECTED AT THE POINT OF CLOSURE.



*W20-H13-60*\* DATE OF CLOSURE

IF LIMITED CLOSURE OF ALLEYS I IS NEEDED FOR CONSTRUCTION ACTIVITIES, THE CONTRACTOR WILL USE THE PROPER CLOSURE SIGNS. THE ALLEY IS TO REOPEN AFTER DAILY CONSTRUCTION ACTIVITIES AND WILL NOT BE CLOSED OVERNIGHT. LIMIT CLOSURE OF ALLEY I TO THE SOUTHERN PORTION NEAR WILLIAM STREET.

LIMITED ACCESS OF ALLEY 2 NEAR DELAWARE RUN MAY BE AVAILABLE TO THE CONTRACTOR FOR CONSTRUCTION OPERATIONS. THE CONTRACTOR MAY NOT BLOCK THE DRIVE ACCESS TO THE REAR OF THE POST OFFICE OR POSTAL DROP BOXES. THE CONTRACTOR MUST MINIMIZE THE DISRUPTION TO POSTAL TRAFFIC. SEVERAL EMPLOYEE PARKING SPACES ADJACENT TO DELAWARE RUN MAY BE MADE AVAILABLE TO THE CONTRACTOR. SEE SHEET 2/22. THE CONTRACTOR MUST CONTACT JOSEPH SCHNEIDER, POST MASTER (740) 363-1906 TO NEGOTIATE THE USE OF THE ALLEY AND PARKING SPACES. THE CONTRACTOR WILL USE THE PROPER SIGNING WHEN CONDUCTING ANY CONSTRUCTION ACTIVITIES IN THIS AREA.

THE CONTRACTOR WILL MAINTAIN INGRESS AND EGRESS TO THE RESIDENTIAL DRIVE ALONG CATHERINE STREET UNLESS OTHERWISE NEGOTIATED WITH THE PROPERTY OWNWER.

THE EAST SIDEWALK ALONG CATHERINE STREET WILL REMAIN
OPEN FOR PEDESTRIAN TRAFFIC UNLESS THE CONSTRUCTION
ACTIVITIES PROVE TO BE A SAFETY CONCERN. THE CONTRACTOR
WILL THEN PROVIDE DETOURING PER MT-110.10.

HOURS OF CONSTRUCTION EQUIPMENT OPERATION WILL CONFORM TO ANY PERTINENT LOCAL ORDINACES THAT MAY EXIST.

ALL WORK AND TRAFFIC CONTROL DEVICES ARE TO BE IN ACCORDANCE WITH CMS 614 AND OTHER APPLICABLE PORTIONS OF THE SPECIFICATIONS, AS WELL AS THE OHIO MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES. PAYMENT FOR ALL LABOR, EQUIPMENT AND MATERIALS WILL BE INCLUDED IN THE LUMP SUM CONTRACT PRICE FOR ITEM 614, MAINTAINING TRAFFIC, UNLESS SEPARATELY ITEMIZED IN THE PLAN.

### DETOUR SIGNING

ROAD

R11-2-48

PROVIDE, MAINTAIN, AND SUBSEQUENTLY REMOVE ALL DETOUR SIGNS AND SUPPORTS. PAYMENT FOR ALL LABOR, EQUIPMENT AND MATERIALS FOR DETOUR SIGING WILL BE INCLUDED IN THE LUMP SUM BID PRICE FOR ITEM 614 - DETOUR SIGNING.

# NOTIFICATION OF CONSTRUCTION INITIATION

AT LEAST FOURTEEN DAYS PRIOR TO ANY CONSTRUCTION ACTIVITIES, THE CONTRACTOR WILL ADVISE THE DISTRICT OFFICE OF COMMUNICATIONS VIA EMAIL AT DO6.PIO@DOT.STATE.OH.US AND THE DISTRICT WORK ZONE TRAFFIC MANAGER VIA EMAIL AT DO6.MOT@DOT.STATE.OH.US OF THE ANTICIPATED START DATE OF ANY CONSTRUCTION ACTIVITIES, INCLUDING BUT NOT LIMITED TO THE PLACING OF WORK ZONE SIGNS. THE NOTIFICATION WILL ALSO INCLUDE THE PROJECT NUMBER, PID, NAME AND PHONE NUMBER OF THE CONTRACTOR, A POINT OF CONTACT AND THE ANTICIPATED IMPACT ON TRAFFIC. THE CONTRACTOR WILL IMMEDIATELY INFORM THE DISTRICT OFFICE OF COMMUNICATIONS AND THE DISTRICT WORK ZONE TRAFFIC MANAGER OF ANY AND ALL DELAYS AND/OR CHANGES REGARDING THE CONSTRUCTION INITIATION DATE.

ROAD

R11-2-48

M4-10R-48

M4-10L-48

5

ROAD CLOSED

THRU TRAFFIC

R11-4-60

CATHERINE ST

D3-1

DETOUR

M4-9R-30

# NOTIFICATION TO EMERGENCY SERVICES AND LOCAL SCHOOLS

THE CONTRACTOR IS RESPONSIBLE FOR NOTIFYING ALL LOCAL, COUNTY, STATE AND FEDERAL EMERGENCY SERVICES AND EVERY EFFECTED SCHOOL FACILITY OF ANY ANTICIPATED ROAD CLOSURES AT LEAST FOURTEEN (14) DAYS BEFORE THE CLOSURE. SPECIFICALLY, THE ROAD CLOSURE NOTICE MUST DISCLOSE I) THE EXACT PORTION OF THE ROAD TO BE CLOSED 2) THE DATE OF THE ANTICIPATED CLOSURE 3) THE DURATION OF THE CLOSURE 4) AND THE DETOUR ROUTE(S). A COPY OF THIS NOTIFICATION MUST BE PRESENTED AT THE PRECONSTRUCTION MEETING. THE CONTRACTOR IS ALSO RESPONSIBLE FOR NOTIFYING THE PROJECT ENGINEER WHEN, INCLUDING DATE AND TIME, THE NOTIFICATION IS DISTRIBUTED. A COPY OF EVERY NOTIFICATON MUST BE SENT TO ODOT COMMUNICATIONS AT DO6.PIO@STATE.OH.US.

CATHERINE ST

D3-1

DETOUR

M4-9L-30

# NOTIFICATION OF TRAFFIC RESTRICTIONS


THROUGHOUT THE DURATION OF THE PROJECT, THE CONTRACTOR
WILL NOTIFY THE PROJECT ENGINEER IN WRITING OF ALL
TRAFFIC RESTRICTIONS AND UPCOMING MAINTENANCE OF
TRAFFIC CHANGES. THE CONTRACTOR WILL ENSURE THE
WRITTEN NOTIFICATION IS SUBMITTED IN A TIMELY MANNER TO
ALLOW THE PROJECT ENGINEER TO MEET THE REQUIRED TIME
FRAMES SET FORTH IN THE TABLE BELOW. THIS NOTIFICATION
SHALL BE RECEIVED BY THE PROJECT ENGINEER PRIOR TO THE
PHYSICAL SETUP OF ANY APPLICABLE SIGNS OR MESSAGE
BOARDS.

INFORMATION SHOULD INCLUDE BUT IS NOT LIMITED TO ALL CONSTRUCTION ACTIVITIES THAT IMPACT OR INTERFERE WITH TRAFFIC AND SHOULD LIST THE SPECIFIC LOCATION, TYPE OF WORK, ROAD STATUS, DATE AND TIME OF RESTRICTION, DURATION OF RESTRICTION, NUMBER OF LANES MAINTAINED, DETOUR ROUTES IF APPLICABLE, AND ANY OTHER INFORMATION REQUESTED BY THE PROJECT ENGINEER.

		NOTIFICATION TIME FRA	AME TABLE					
	ITEM	DURATION OF CLOSURE	NOTIFICATION TO DISTRICT 6 COMMUNICATIONS OFFICE					
5446	44/2 2042	> = 2 WEEKS	14 BUSINESS DAYS PRIOR TO CLOSURE					
	RAMP AND ROAD CLOSURES	> 12 HOURS AND < 2 WEEKS	7 BUSINESS DAYS PRIOR TO CLOSURE					
		< 12 HOURS	2 BUSINESS DAYS PRIOR TO CLOSURE					
LANE	CLOSURES	> = 2 WEEKS	7 BUSINESS DAYS PRIOR TO CLOSURE					
REST	AND TRICTIONS	< 2 WEEKS	2 BUSINESS DAYS PRIOR TO CLOSURE					

ANY UNFORESEEN CONDITIONS NOT SPECIFIED IN THE PLANS REQUIRING TRAFFIC RESTRICTIONS SHALL ALSO BE REPORTED TO THE PROJECT ENGINEER USING THE NOTIFICATION TIME FRAME TABLE.


THE CONTRACTOR SHALL CONTACT MIKE BROOKOVER FROM THE CITY OF DELAWARE 14 DAYS PRIOR TO ANY STREET CLOSURES AT 740-203-1715 or mbrookover@delawareohio.net.








<u>.</u>		,	S	HEET	NUMB	ER					PARTICI 70/	PATION 30	ITEM	ITEM	GRAND	UNIT	DESCRIPTION	SEE SHEET
		3	4				9		11		ODOT	CITY	1 1 - 141	EXT.	TOTAL	——————————————————————————————————————		NO.
																	ROADWAY	
		LUMP											201	11000	LUMP		CLEARING AND GRUBBING	
		20,,,,							244		171	73	SPECIAL	20270100		FT	SPECIAL - PIPE CLEANOUT	11
		450									<i>315</i>	135	607	20001	450	FT	FENCE, TYPE CL, AS PER PLAN	3
																	EROSION CONTROL	
		300									210	90	659	14000	300	SQ YD	REPAIR SEEDING AND MULCHING	
		2									1.4	0.6	659	35000	2	M GAL	WATER	
											700	300	832	30000	1000	EACH	EROSION CONTROL	
																	DOATNACE	
																	DRAINAGE	
		50									35	15	603	00900	50		6" CONDUIT, TYPE B, FOR DRAINAGE CONNECTION	
		50									<i>35</i>	<i>15</i>	603	01100	50	FT	6" CONDUIT, TYPE C, FOR DRAINAGE CONNECTION	
		50									<i>35</i>	<i>15</i>	603	01800	50	FT	8" CONDUIT, TYPE B, FOR SANITARY	
		50									35	15	603	02000	50	FT	8" CONDUIT, TYPE C, FOR SANITARY	
							244				171	73	603	98300	244	FT	CONDUIT, MISC.: 15' X 7' ARCH SPIRAL WOUND RENEWAL SYSTEM	9
																	MAINTENANCE OF TRAFFIC	
			LUMP										614	12420	LUMP		DETOUR SIGNING	
			LUMP										614	11000	LUMP		MAINTAINING TRAFFIC	
													623 624	10000 10000	LUMP LUMP		CONSTRUCTION LAYOUT STAKES  MOBILIZATION	
																		+
																		1
																		+
								+										
	•	1			1			1	1	ļ					1			

 $\bigcirc$ 









ITEM 603 CONDUIT MISC : 15' SPAN X 7' RISE ARCH SPIRAL WOUND RENEWAL SYSTEM

### DESCRIPTION.

A. GENERAL: THE CONTRACTOR SHALL FURNISH ALL TOOLS, EQUIPMENT, MATERIALS AND SUPPLIES AND SHALL PERFORM ALL LABOR REQUIRED TO COMPLETE INSTALLATION OF THE SPIRAL WOUND HDPE OR PVC PROFILE RENEWAL PROCESS IN FULL CONFORMITY WITH THE CONTRACT DOCUMENTS.

THE SPIRAL WOUND PVC PROFILE RENEWAL PROCESS UTILIZES AN EXTRUDED POLYVINYL CHLORIDE (PVC) PROFILE STRIP OR PANEL THAT IS SPIRAL WOUND OR ERECTED INTO AN EXISTING CONDUIT (HOST PIPE). THE EXTRUDED PROFILE STRIP IS MECHANICALLY LOCKED TOGETHER BY VIRTUE OF THE PROFILE DESIGN. THE INSTALLATION SYSTEM SHALL PROVIDE PRECISE CONTROL OF THE INTERNAL DIMENSIONS OF THE NEWLY FORMED PVC CONDUIT THAT WILL ENSURE THE SPECIFIED ANNULAR GROUT SPACE IS MAINTAINED THROUGHOUT THE RENEWAL LENGTH. THE ANNULAR SPACE IS FILLED WITH A CEMENTITIOUS GROUT.

# MATERIAL.

- A. FURNISH MATERIALS CONFORMING TO THE FOLLOWING:
- 1. PVC PROFILE STRIP USED SHALL CONFORM TO ASTM F 1697 OR ASTM F 1735. THE PROFILE GEOMETRY SHALL BE COMPATIBLE WITH THE DESIGN REQUIREMENTS FOR THE RENEWED CONDUIT AND SHALL BE SUITABLE FOR INSTALLATION IN THE HOST PIPE.
- 2. ANNULUS GROUT USED SHALL CONFORM TO SS 837.03.
- 3. IF USED, THE STEEL REINFORCING STRIP SHALL CONFORM ASTM F 1697.
- B. PRODUCT HANDLING
- 1. ALL OTHER PRODUCTS REQUIRED TO COMPLETE THE SPIRAL WOUND PVC LINING RENEWAL PROCESS SHALL BE HANDLED AND STORED IN ACCORDANCE WITH THE MANUFACTURER'S INSTRUCTIONS. EACH PRODUCT SHALL BE ACCOMPANIED BY ITS RELEVANT SPECIFICATION AND MSDS INFORMATION.
- C. MATERIAL MARKING
- 1. THE PVC PROFILE STRIP SHALL BE DISTINCTLY MARKED ON ITS INSIDE SURFACE AT APPROPRIATE INTERVALS WITH A CODE NUMBER IDENTIFYING THE MANUFACTURER, PLANT, DATE OF MANUFACTURE. AND PROFILE DESIGNATION.
- 2. ALL OTHER PRODUCTS REQUIRED TO COMPLETE THE SPIRAL WOUND PVC LINING RENEWAL PROCESS SHALL BE DISTINCTLY MARKED WITH PRODUCT TYPE AND MANUFACTURER.

# REFERENCE STANDARDS.

- A. ASTM F-1697 STANDARD SPECIFICATION FOR PVC PROFILE STRIP FOR MACHINE SPIRAL WOUND LINER PIPE REHABILITATION OF EXISTING SEWERS AND CONDUIT.
- B. ASTM F-1741 STANDARD PRACTICE FOR INSTALLATION OF MACHINE SPIRAL WOUND PVC LINER PIPE REHABILITATION OF EXISTING AND CONDUITS.
- C. ASTM D-1784 STANDARD SPECIFICATION FOR RIGID PVC AND CPVC COMPOUNDS.
- D. ASTM C-109 STANDARD TEST METHOD FOR COMPRESSIVE STRENGTH OF HYDRAULIC CEMENT MORTARS (USING 2-IN. CUBE SPECIMEN)

- E. ASTM A653/A653M-06 STANDARD SPECIFICATION FOR STEEL SHEET, ZINC-COATED (GALVANIZED) OR ZINC-IRON ALLOY-COATED (GALVANNEALED) BY THE HOT-DIP PROCESS
- F. ASTM F1698-02(2008) STANDARD PRACTICE FOR INSTALLATION OF POLY(VINYL CHLORIDE) (PVC) PROFILE STRIP LINER AND CEMENTITIOUS GROUT FOR REHABILITATION OF EXISTING MAN-ENTRY SEWERS AND CONDUITS.
- G. ASTM F1735-02(2008) STANDARD SPECIFICATION FOR POLY(VINYL CHLORIDE) (PVC) PROFILE STRIP FOR PVC LINERS REHABILITATION OF EXISTING MAN-ENTRY SEWERS AND CONDUIT.

# CONTRACTOR SUBMITTALS

- A. PRIOR TO COMMENCING WITH CONSTRUCTION THE CONTRACTOR SHALL SUBMIT THE FOLLOWING TO THE ENGINEER:
- 1. DESIGN SUBMITTAL: SHOP DRAWINGS FOR THE RENEWED CONDUIT. THESE DRAWINGS SHALL ADDRESS THE PVC PROFILE DESIGNATION (GEOMETRY). GROUT THICKNESS REQUIRED. AND THE STEEL REINFORCING STRIP IF USED.
- 2. PRE-INSTALLATION VIDEO OR PHOTO SURVEY OF HOST PIPE.
- 3. DESIGN SUBMITTAL: THE DETAILS FOR THE LEVELING PAD/FOOTER THAT THE SPRIAL WOUND PVC LINING WILL ATTACH TO ALONG WITH THE TYPE OF CONNECTION.
- B. DURING CONSTRUCTION THE CONTRACTOR SHALL SUBMIT THE FOLLOWING TO THE ENGINEER:
- 1. COMPRESSIVE STRENGTH TEST RESULTS FOR ANNULUS GROUT, TESTED PER ASTM C109.
- C. WITHIN 2 WEEKS OF THE SPIRAL WOUND PROFILE BEING INSTALLED, THE CONTRACTOR SHALL SUBMIT THE FOLLOWING TO THE ENGINEER:
- 1. POST-INSTALLATION VIDEO OR PHOTO SURVEY OF THE RENEWED CONDUIT WITH A COPY SENT TO THE OFFICE OF STRUCTURAL ENGINEERING.

# **EXECUTION**

- A. SAFETY
- 1. PERFORM ALL WORK IN ACCORDANCE WITH APPLICABLE OSHA STANDARDS.
- B. PREPARATION
- 1. HOST PIPE ACCESS:
- i.UNLESS OTHERWISE SPECIFIED BY THE ENGINEER. THE CONTRACTOR MAY UTILIZE ANY OF THE EXISTING MANHOLES AND/OR CATCHBASINS IN THE PROJECT AREA AS ACCESS POINTS.
- ii.SHOULD TEMPORARY EXCAVATIONS BE NEEDED TO ACCESS THE HOST PIPE, SUCH WORK SHALL BE COORDINATED WITH THE ENGINEER. EXCAVATIONS SHALL BE SLOPED OR SHORED IN ACCORDANCE WITH ALL APPLICABLE SAFETY REGULATIONS.
- 2. CLEANING:
- i. WATER JETTING SHALL BE USED TO CLEAN AND PREPARE THE SURFACE OF THE HOST PIPE. ALL LOOSE MATERIAL, ACIDS, GREASE AND OTHER DELETERIOUS SUBSTANCES SHALL BE REMOVED DURING CLEANING. AND THE PREPARED SURFACE SHALL BE SUITABLE FOR BONDING WITH CEMENTITIOUS GROUT.

- ii.CARE WILL BE TAKEN TO NOT DISLODGE THE STONES THAT FORM THE STONE ARCH ESPECIALLY THE TOP KEY STONES.
- 3. ANY VOIDS IN THE HOST PIPE WILL BE FILLED WITH GROUT.
- 4. FLOW BYPASSING

i.WHERE REQUIRED DUE TO EXCESSIVE FLOW OR WHERE OTHERWISE DESIRABLE, THE CONTRACTOR SHALL BYPASS FLOWS AROUND THE LENGTH OF HOST PIPE DESIGNATED FOR RENEWAL.

ii.THE BYPASS SHALL BE MADE BY PLUGGING THE HOST PIPE AT AN EXISTING UPSTREAM MANHOLE AND PUMPING THE FLOW INTO A DOWNSTREAM MANHOLE, OR OTHERWISE AS APPROVED BY THE ENGINEER.

iii.FLOW INTERRUPTIONS SHALL BE COORDINATED WITH THE ENGINEER AT LEAST 14 DAYS IN ADVANCE AND WITH PROPERTY OWNERS AND BUSINESSES AT LEAST 3 DAYS IN ADVANCE.

iv.ONCE THE RENEWAL PROCESS HAS BEGUN. THE FLOW BYPASS SHALL BE MAINTAINED UNTIL THE RENEWAL PROCESS IS COMPLETE OR AS APPROVED BY THE ENGINEER.

5. PRE-INSTALLATION INSPECTION:

i.AFTER CLEANING, AND PRIOR TO INSTALLING THE PVC PROFILE, THE CONTRACTOR SHALL INSPECT THE HOST PIPE TO ENSURE THERE ARE NO EXCESSIVE VARIATIONS IN THE HOST PIPE PROFILE AND NO OBSTRUCTIONS THAT WOULD HINDER THE RENEWAL PROCESS. CONTRACTOR SHALL ALSO VERIFY THAT THE SIZING OF THE PROFILE (WOUND GEOMETRY) WILL BE SUITABLE FOR THE HOST PIPE GEOMETRY.

- ii.THE LONGITUDINAL AND RADIAL LOCATIONS OF ALL LATERAL CONNECTIONS TO THE HOST PIPE SHALL BE LOGGED FOR SUBSEQUENT REINSTATEMENT.
- iii.THE CONTRACTOR SHALL PERFORM A PRE-INSTALLATION VIDEO SURVEY OF THE HOST PIPE AS REQUIRED BY THE ENGINEER.
- C. INSTALLATION
- 1. PROFILE WINDING
- i.WINDING OF THE PVC PROFILE SHALL CONFORM TO APPROVED SUBMITTALS.
- ii.THE PVC PROFILE SHALL BE WOUND USING THE SELF-WINDING MACHINE THAT TRAVERSES DOWN THE HOST PIPE FORMING THE SPIRAL WOUND PVC LINING CONDUIT AS IT GOES ACCORDING TO ASTM F 1741 OR MANUALLY ACCORDING TO ASTM F1698. (SEE SHEET FOR NOTES AND DETAIL)
- iii.THE WINDING PROCESS SHALL BE CONTINUOUS UNTIL THE SPIRAL WOUND PVC LINING IS COMPLETE FOR THE LENGTH OF HOST PIPE TO BE RENEWED.
- 2. LEVELING PAD/FOOTER.
- (SEE SHEET FOR NOTES AND DETAIL)
- 3. ANNULUS GROUTING:
- i.ANNULUS GROUTING SHALL CONFORM TO THE CONTRACTOR'S APPROVED SUBMITTALS.

ii.AFTER THE SPIRAL WOUND PVC LINING CONDUIT HAS BEEN INSTALLED, AND BEFORE THE ANNULUS IS GROUTED, THE CONTRACTOR SHALL RESTORE SERVICE AT ALL LATERAL CONNECTIONS, FIELD CONDITIONS WILL DICTATE WHETHER SERVICE RESTORATION CAN BE DONE FROM INSIDE THE CONDUIT OR WHETHER RESTORATION WILL REQUIRE THE EXTERIOR OF THE CONDUIT AND CONNECTING PIPES TO BE EXPOSED.

iii.GROUTING SHALL BE DONE BETWEEN BULKHEADS INSTALLED AT PRE-DETERMINED DISTANCES APART ALONG THE CONDUIT.

iv.PRIOR TO GROUTING. A BRACING FRAMEWORK SHALL BE INSTALLED WHICH SHALL BE DESIGNED BY THE CONTRACTOR TO SERVE THE FOLLOWING FUNCTIONS DURING GROUTING; (A) PREVENTING FLOTATION OF THE SPIRAL WOUND PVC CONDUIT, (B) ALIGNING THE PVC CONDUIT WITHIN THE HOST PIPE SO THAT THE REQUIRED ANNULAR SPACE IS MAINTAINED BETWEEN THE PVC CONDUIT AND HOST PIPE, (C) PREVENTING EXCESSIVE DEFLECTION OR BUCKLING OF THE PVC CONDUIT.

v.VENT HOLES SHALL BE PROVIDED AT SUITABLE LOCATIONS TO PERMIT AIR TO BE EXPELLED FROM THE ANNULAR SPACE AND TO MONITOR GROUT FILL LEVELS.


vi.GROUTING MAY BE PERFORMED IN ONE OR MORE LIFTS IN ORDER TO COMPLETELY FILL THE ANNULAR SPACE.

vii.GROUT SHALL BE SAMPLED AND TESTED AS DESIGNATED BY THE ENGINEER. SAMPLE PREPARATION AND TESTING SHALL CONFORM TO ASTM C39 OR ASTM C109.

# COMPLETION OF WORK AND SITE RESTORATION

- A. ENDS OF RENEWED CONDUIT:
- 1. THE ENDS OF THE SPIRAL WOUND PVC CONDUIT SHALL BE SECURELY GROUTED IN POSITION. THE PVC CONDUIT SHALL BE SEALED TO THE HOST PIPE WITH MATERIAL CAPABLE OF ACHIEVING A WATERTIGHT SEAL. 2. THE STEP IN THE FLOW LINE AT THE ENDS OF THE RENEWED CONDUIT SHALL BE BLENDED INTO THE EXISTING FLOW LINE USING APPROPRIATE MATERIALS.
- B. ANY HOLES MADE IN THE PVC PROFILE DURING THE GROUTING OPERATION SHALL BE SEALED USING MEANS AND METHODS APPROVED BY THE ENGINEER.
- C. AT POINTS WHERE TEMPORARY EXCAVATION WAS REQUIRED FOR ACCESS TO THE HOST PIPE OR LATERAL CONNECTIONS. APPROPRIATE ENCASEMENT SHALL BE PROVIDED FOR THE EXPOSED PVC PROFILE AND/OR CONNECTING PIPES, ENCASEMENT MATERIALS MAY CONSIST OF CONCRETE, SAND SLURRY, OR OTHER SUITABLE MATERIALS AS APPROVED BY THE ENGINEER.
- D. FINAL INSPECTION AND ACCEPTANCE:
- 1. THE GROUTED IN-PLACE, SPIRAL WOUND PVC PROFILE LINING IN THE RENEWED CONDUIT SHALL BE CONTINUOUS OVER THE ENTIRE LENGTH OF AN INSTALLATION RUN AND BE FREE FROM DEFECTS SUCH AS FOREIGN INCLUSIONS, HOLES, CUTS, TEARS, AND GROUT VOIDS. THE RENEWED CONDUIT SHALL BE IMPERVIOUS AGAINST LEAKAGE OUT OF THE CONDUIT TO THE SURROUNDING GROUND OR INTO THE CONDUIT FROM THE SURROUNDING GROUND.
- 2. ANY DEFECT WHICH WILL OR POTENTIALLY COULD AFFECT THE STRUCTURAL INTEGRITY OR PERFORMANCE OF THE RENEWED CONDUIT SHALL BE REPAIRED AT THE CONTRACTOR'S EXPENSE USING MEANS AND METHODS APPROVED BY THE ENGINEER.
- 3. THE CONTRACTOR SHALL PERFORM A POST-INSTALLATION VIDEO SURVEY OF THE RENEWED CONDUIT AS REQUIRED BY THE ENGINEER.





### 2. LEVELING PAD/FOOTER.


i.THE SPIRAL WOUND PVC LINING WILL ENCOMPASS THE ENTIRE CIRCUMFERENCE OF THE STONE ARCH. THE CONTRACTOR WILL NOT CONSTRUCT THE LINING AT THE TOP OF THE EXISTING CONCRETE KNEE WALLS BUT ALONG THE BOTTOM OF THE STREAM BED ATOP THE LEVELING PAD/FOOTER.

ii.THE LEVELING PAD/FOOTER ELEVATIONS/DIMENSIONS SHOWN IN THE PLAN ARE FOR DETAIL PURPOSES. THE CONTRACTOR MAY ADJUST THE ELEVATIONS/DIMENSIONS TO ACCOMODATE THE VARIATIONS IN THE STREAM BED PROFILE TO MINIMIZE THE ROCK CUT REQUIRED FOR THE MANUFACTURE'S RECOMMENDED LEVELING PAD/FOOTING DIMENSIONS.

METHOD OF MEASUREMENT.


THE DEPARTMENT WILL MEASURE THE RELINING OF EXISTING PIPE USING SPIRAL WOUND RENEWAL SYSTEM BY THE NUMBER OF FEET (METERS) OF EXISTING PIPE RELINED.

2022 LBS - 509 EPOXY COATED REINFORCING




# BASIS OF PAYMENT.

THE PAYMENT FOR FURNISHING THE SPIRAL WOUND PVC PIPE RENEWAL SYSTEM, ANNULUS GROUT, LEVELING PAD/FOOTER, ALL REINFORCING, ALL LABOR, DEBRIS REMOVAL, INCIDENTALS AND EQUIPMENT NEEDED TO COMPLETE THIS ITEM OF WORK WILL BE MADE AT THE CONTRACT PRICE FOR ITEM 603 CONDUIT, MISC.: 15' SPAN X 7' RISE ARCH SPIRAL WOUND PIPE RENEWAL SYSTEM.




iii.IN LIEU OF KEYING INTO THE ROCK, THE CONTRACTOR MAY DOWEL INTO THE ROCK.



FOR ESTIMATING PURPOSES: 1300 LBS -509 EPOXY COATED REINFORCING 325 EACH - 510 DOWEL HOLES WITH NONSHRINK, NONMETALLIC GROUT

iv.THE MANUFACTURE MAY PROVIDE A DESIGN OTHER THAN THE ONES SHOWN IN THE PLANS PER THE CONTRACTOR SUBMITTALS - 3. SHEET 10.





# ITEM SPECIAL - PIPE CLEANOUT

THIS WORK SHALL CONSIST OF REMOVING SEDIMENT AND DEBRIS FROM THE EXISTING STRUCTURE SPECIFIED IN THE PLANS. ALL MATERIAL REMOVED SHALL BE DISPOSED OF AS PER 105.16 AND 105.17. THE STRUCTURE SHALL BE CLEANED OUT TO THE SATISFACTION OF THE ENGINEER.

CLEANOUT OF THE STRUCTURE SHALL BE PAID FOR AT THE UNIT BID PRICE FOR ITEM SPECIAL - PIPE CLEANOUT. THIS PRICE SHALL INCLUDE THE COST FOR MATERIAL, EQUIPMENT, LABOR, AND ALL INCIDENTALS REQUIRED TO COMPLETE THE CLEANOUT. THE FOLLOWING ESTIMATED QUANTITY HAS BEEN INCLUDED IN THE GENERAL SUMMARY FOR THE ABOVE NOTED WORK:

ITEM SPECIAL, PIPE CLEANOUT 244 FT.





### UTILITIES

LISTED BELOW ARE ALL UTILITIES LOCATED WITHIN THE PROJECT CONSTRUCTION LIMITS TOGETHER WITH THEIR RESPECTIVE OWNERS:

SEWERS: CITY OF DELAWARE SANITARY/STORM SEWER 225 CHERRY ST. DELAWARE, OH 43015 740-203-1961

 $\bigcirc$ 

 $\bigcirc$ 

0

 $\bigcirc$ 

CITY OF DELAWARE WATER 3080 US 23 NORTH DELAWARE. OH 43015 740-203-1972

TRAFFIC SIGNALS: CITY OF DELAWARE DEPT. OF ENGINEERING SERVICES

20 EAST WILLIAM ST. DELAWARE, OHIO 43015 740-203-1749

TELEPHONE AND FIBER OPTIC: VERIZON 550 LEADER ST. MARION. OHIO 43302

PHONE: 740-383-0551

FLECTRIC:

850 TECH CENTER DRIVE GAHANNA, OHIO 43230 PHONE: 614-883-6831

COLUMBIA GAS OF OHIO 3550 JOHNNY APPLESEED COURT COLUMBUS. OHIO 43231 PHONE: 614-818-2107

CABLE:

TIME WARNER CABLE 3760 INTERCHANGE DR. COLUMBUS, OH 43204 614-481-5262

THE LOCATION OF THE UNDERGROUND UTILITIES SHOWN ON THE PLANS ARE OBTAINED FROM THE OWNER OF THE UTILITIES AS REQUIRED BY SECTION 153.64 O.R.C.

WD = WARRANTY DEED
SH = STANDARD HIGHWAY EASEMENT
T = TEMPORARY EASEMENT

CH = CHANNEL EASEMENT U = UTILITY EASEMENT WA = WORK AGREEMENT SA = SPECIAL AGREEMENT AND WAIVER OF DAMAGES

S = SEWER EASEMENT

### STRUCTURE KEY

RESIDENTIAL

COMMERCIAL

OUT-BUILDING

### CONVENTIONAL SYMBOLS

County Line Ditch / Creek (Ex) Township Line Ditch / Creek (Pr) Section Line Or Tree Line (Ex) Corporation Line Or Property Line Symbol Center Line Break Line Symbol V Right of Way (Ex)  Right of Way (Ex)  Ditch / Creek (Ex) Ownership Hook Symbol Property Line Symbol V Tree (Pr) Tree (Pr) Tree	
Section Line — Tree Line (Ex) Ownership Hook Symbol Fence Line (Ex) — X — X — (Pr) — X — Break Line Symbol V	
Corporation Line or minima Ownership Hook Symbol Fence Line (Ex) — x — (Pr) — x — Property Line Symbol V	
Center Line ————————————————————————————————————	4
Center Line ————————————————————————————————————	12
Center Line ————————————————————————————————————	P
Right of Way (Ex) Ex R/1 Tree (Pr) 63 . Tree	
recognition of the granter of the contract of	(Ex
Right of Way (Pr) Tree (Remove) X, Sh	rut
Standard Highway Ease (Ex) Ex SH Evergreen (Ex) * , St	
Temporary Right of Way————————————————————————————————————	,
Sewer Ease. (Pr) - SW - Wetland (Pr) w , Gro	ass
General Ease. (Ex) — — — Post (Ex) O , Mailbox	( (E
Railroad ############# or	on
Guardrail (Ex)かってっての (Pr) ・・・・・・・・・・・・・・・・・・・・・・・・・・・・・・・・・・・・	W
Construction Limits — • — • — • Water Valve (Ex) & ,	Ut
Construction Limits ——• ——• —— Water Valve (Ex) $\bullet$ , Edge of Pavement (Ex) —— ——• —— Telephone Pole (Ex) $\phi$	,
Edge of Pavement (Pr) Light Pole (Ex) $\phi$	
Edge of Shoulder (Ex)	
Edge of Shoulder ( Pr)	

Z . Example . Example Example Ex) 👸 , Shrub (Ex) 🖏 ub (Remove)💥 , Stump (Remove) ss (Pr) ملك , Aerial Target ه (Ex) SMB , Mailbox (Pr) ED ne Marker (Ex)+TEL Water Meter (Ex) 🔯 Jtility Valve Unknown (Ex.) ゆ , Power Pole (Ex)  $\phi$ 

# RIGHT OF WAY LEGEND SHEET DEL-36-9.75

DELAWARE COUNTY CITY OF DELAWARE

# INDEX OF SHEETS:

LEGEND SHEET	1
CENTERLINE PLAT	2
PROPERTY MAP	3
SUMMARY OF ADD'L R/W	4-6
R/W BOUNDARY SHEETS	7-8
R/W TOPO SHEETS	9-1

### PLANS PREPARED BY:

FIRM NAME : O.D.O.T. CENTRAL OFFICE PLANS PREPARED BY: MICHAEL JAMES WARE FIELD REVIEW BY: MJW DATE COMPLETED: 12/28/09 OWNERSHIP VERIFIED BY: MJW DATE COMPLETED: 12/29/09

PROJECT DESCRIPTION

PROJECT CONTROL

REPAIR WORK TO DELAWARE RUN CULVERT

AT THE INTERSECTION OF WILLIAM ST. AND

LIBERTY ST. IN THE CITY OF DELAWARE. OH.

PROJECT ADJUSTMENT FACTOR: 0.99998968

STATE PLANE GRID:OHIO NORTH ZONE (SPC 3401) NAD83 (1995)

DATE COMPLETED: 12/29/09

I, Michael James Ware, P. S. have conducted a survey of the existing conditions for the Ohio Department of Transportation in July, 2007. The results of that survey are contained herein.

Underground utility locations are shown for informational purposes only. Though they are believed to be accurate, their location is as provided by Tampa Bay Engineering, Inc. (Project No. OH09500610), as part of a SUE contract. This information has been incorporated into the plans as a part of this project.

As a part of this project, I have reestablished the locations of the existing property lines for property takes contained herein.

As a part of this project I have established the proposed property lines, calculated the Gross Take, present roadway occupied (PRO), Net Take and Net Residue; as well as prepared the legal descriptions necessary to acquire the parcels as shown herein.

As a part of this work I have set monuments at the proposed Property corners, Section Corners and other points, as shown herein.

Any monuments to be set will be done so in accordance with OAC 4733-37 as cited below.

All of my work contained herein was conducted in accordance with Ohio Administrative Code 4733-37 commonly known as "Minimum Standards for Boundary Surveys" unless noted otherwise.

Date: 12/31/2009

The words I and my as used herein are to mean either myself or someone working under my direct supervision.

Michael James Ware, Professional Land Surveyor 8054

SURVEYORS SEAL

O

36

Ш

E070(434)

79373


A M


0

RIGHT

SHE

EGEND





O TOTAL TAKES

OWNER

O OWNERSHIPS W/ STRUCTURES INVOLVED

NO.

SHEET OWNERS RECORD AUDITOR'S RECORD

PARCEL

PAGE

BOOK

4 OWNERSHIPS

1-9 NOT USED

4 PARCELS

PARCEL

NO.

RECORD AREA - TOTAL PRO - NET TAKE = NET RESIDUE GROSS TAKE - PRO IN TAKE = NET TAKE

GROSS P.R.O. IN NET

TAKE

STRUC-

TAKE TURE

ALL AREAS IN ACRES

TAKE

TOTAL

P.R.O.

AREA

# GRANTEE:

STATE | ALL RECORD AREAS SHOWN PER AUDITOR

ALL RIGHT OF WAY ACQUIRED IN THE NAME OF THE STATE OF OHIO, DEPARTMENT OF TRANSPORTATION UNLESS OTHERWISE SHOWN.

REMARKS

0(43 07

AS ACQUIRED

BOOK PAGE

9 က

22

TYPE

FUND

NET RESIDUE

RIGHT

LEFT

1 0	NOT USED					ALE RECORD AREAS SHOWN TER ACCITOR	
							<u>୍</u> ଅ
10	MYRON NEIL SHENEFIELD	3 01	R 657 655	51943229008000 0.2200 0.0000	0.0000 0.0000	S. 32' OF INLOT 730, ALL OF INLOT 731	Ö. K
	BILLIE JOY SHENEFIELD					NO ADDITIONAL R/W REQUIRED	01 <b>6 7</b>
							. ~
11	FERGUS J. HUTCHINSON	3 Oi	R 577 138	51943229009000 0.1340 0.0000	0.0000 0.0000	INLOTS 732 AND 1724	. S
	CHRIS J. WINGET					NO ADDITIONAL R/W REQUIRED	TE JOB
				51943229010000 0.1270 0.0000	0.0000 0.0000		2 S
							STA <sup>-</sup>
12	JOHN P. NARWICZ	7,9 0	R 699 783	51943229011000 0.1380 0.0000	0.0000 0.0000	ALL OF INLOT 1725, W. 10' OF INLOT 1726	w DESIGN W REVIEW
	KAREN P. NARWICZ					NO ADDITIONAL R/W REQUIRED	× × × × × × × × × × × × × × × × × × ×
							<b>-</b>
17	NARTUA WOODDUEE	7.0	D 500 400	510.47000015000			<b>★</b>
13	MARTHA WOODRUFF			<u> </u>	0.0000 0.0000	S. HALF OF INLOT 766	+  <b>-</b>
	A.K.A. MARTHA A. WOODRUFF		V 667 802			NO ADDITIONAL R/W REQUIRED	—
							_
							<del> </del>
14-T	SCOTT SOLOMON	7,9 O	R 990 666	5 51943229014000 0.1700 0.0000	0.0111 0.0000 0.0111	TEMPORARY ACCESS	<u>رة م</u>
						0.0056 AC IN EXISTING EASEMENT	
						EASEMENT (DV 535, PG 457)	Z Z
						RIGHT-OF-ENTRY AGREEMENT (DV 535, PG 456)	
						INLOT 765	SUANO
15	PIEPER HOLDINGS, LLC	7,9	DR223 1133	3 51943229012000 0.0930 0.0000	0.0000 0.0000	E. 50' OF INLOT 1726	<u> </u>
	TILI LIV TIOLDINOS, LLO	7,0	77.223 77.33	0.0030 0.0000	0.0000 0.0000	NO ADDITIONAL R/W REQUIRED	
							A D D
16	MARY E. ALBAYATI	7,9 C	DR 36 2115	5 51943229013000 0.1450 0.0000	0.0000 0.0000	INLOT 764	+
						NO ADDITIONAL R/W REQUIRED	O
17-5	BOARD OF EDUCATION		DB 43 155		0.3044 0.0000 0.3044	INLOTS 584-588	LΩ
	OF DELAWARE OHIO		DB 43 156			0.0225 AC IN EXISTING SANITARY SEWER EASEMENT	<b>  ~</b>
			DB 44 157			SANITARY SEWER EASEMENT (DV 334, PG 85)	—
			0B 121 435 0B 120 612			INLOTS 579-580	<u> </u>
			120 סיבו סיב				ø

WD = WARRANTY DEED

BS = BILL OF SALE PRW = PROPERTY RIGHT FEE SIMPLE

SH = STANDARD HIGHWAY EASEMENT

LA = LIMITED ACCESS EASEMENT T = TEMPORARY EASEMENT

SL = SLOPE EASEMENT

S = SEWER EASEMENT

CH = CHANNEL EASEMENT

WL = FEE SIMPLE WITH LIMITATION OF ACCESS FL = FLOW EASEMENT U = UTILITY EASEMENT

A = AERIAL EASEMENT PRE = PROPERTY RIGHT

SS = SUBSURFACE EASEMENT V = IN NAME OF ANOTHER STATE AGENCY, LPA, ETC.

R = SPECIAL RESERVATION WA = WORK AGREEMENT

SA = SPECIAL AGREEMENT AND WAIVER OF DAMAGES

NOTE: ALL TEMPORARY PARCELS TO BE OF 12 MONTH DURATION.

NOTE: UNDER NO CIRCUMSTANCES ARE TEMPORARY EASEMENTS TO BE USED FOR STORAGE OF MATERIAL OR EQUIPMENT BY THE CONTRACTOR UNLESS NOTED OTHERWISE.

NOTE: ALL RECORD AREAS ARE PER AUDITOR TAX RECORDS, AND MAY DIFFER FROM DEED AREAS.

STATE

(c) = CALCULATED AREA

	1	
MJW	10/11/10	UPDATED OWNER, CHANGED 14-S TO 14-T
MJW	01/25/10	REVISED DEED REFERENCE INFO-PARCEL 17
REV. BY	DATE	DESCRIPTION
FIELD RE	VIEW BY:	MJW DATE: 12/28/09
OWNERSH	IP VERIFII	ED BY: MJW DATE: 12/29/09

DATE COMPLETED: 12/29/09

# GRANTEE:

ALL RIGHT OF WAY ACQUIRED IN THE NAME OF THE STATE OF OHIO, DEPARTMENT OF TRANSPORTATION UNLESS OTHERWISE SHOWN.

0(43 07

S

3

22

# ALL AREAS IN ACRES

PARCEL	OWNER	SHEET	OWNERS	RECORE	AUDITOR'S RI	ECORD	TOTAL	GROSS	P.R.O. IN	NET	STRUC-	NET R	ESIDUE	TYPE	REMARKS		QUIRED
NO.		NO.	воок	PAGE		AREA	P.R.O.	TAKE	TAKE	TAKE	TURE	LEFT	RIGHT	FUND		ВООК	PAGE
18	G.M.N. ENTERPRISES, LTD.	7,9	OR 262	1978	51943304002000 (	0.2470	0.0000	0.0000	0.0000	0.0000				STATE	W. HALF OF INLOT 124 NO ADDITIONAL R/W REQUIRED		
19	OHIO WESLEYAN UNIVERSITY	7,9	OR 478	341	51943304003000	3.1620	0.0000	0.0000	0.0000	0.0000					E. PART OF INLOT 125		
10	ONIO WESELTAN ONIVERSITY	7 9 0	011 410	<u> </u>	31343304003000	3.1020	0.0000	0.0000	0.0000	0.0000					NO ADDITIONAL R/W REQUIRED		
20-55	OHIO WESLEYAN UNIVERSITY	7-10	OR 473	247	51943304001000 C	0.3290	0.0000	0.0085	0.0000	0.0085					SUBSURFACE EASEMENT		
	AND TRUSTEES OF		OR 474	290											PART INLOT 125		
	OHIO WESLEYAN UNIVERSITY		OR 517	341													
21		7.10	00.507	2100	F10.47.220.00.00.00.00.00	0.0070	0.0000	0.0000	0.0000	0.0000					DADT OUTLOT 70 DADT INLOT 700		
21	DAVID M. OGLE	7-10	OR 597	2108	51943228006000 (	0.0630	0.0000	0.0000	0.0000	0.0000					PART OUTLOT 32, PART INLOT 362  NO ADDITIONAL R/W REQUIRED		
			OR 597	2130	51943228008000 C	0.0760	0.0000	0.0000	0.0000	0.0000					NO ADDITIONAL KYW REGUINED		
			OR 597	2130	51943228009000 C	0.5200	0.0000	0.0000	0.0000	0.0000							
22	L. WENDELL NUTTER	8,10	DV 570	148	51943228007000 C	0.0830	0.0000	0.0000	0.0000	0.0000					PART OUTLOT 32		
			DV 419	579											NO ADDITIONAL R/W REQUIRED		
			5.4.505														
23-SS	UNITED DAIRY FARMERS, INC.	8,10	DV 523	363	51943303007000 (	0.3270	0.0000	0.0485	0.0000	0.0485					SUBSURFACE EASEMENT INLOT 92, PART INLOTS 91, 240 AND 241		
															INLOT 32, TART INCOTS 31, 240 AND 241		
24	KPO, LLC	8,10	OR 521	570	51943303009000 1.	.0240(c)	0.0000	0.0000	0.0000	0.0000					PART OUTLOTS 236-241		
			OR 521	569	51943303021000	0.1520	0.0000	0.0000	0.0000	0.0000					LEASE TO UNITED STATES POSTAL SERVICE OR 54, PG 785		
			011 321		31343303021000	0.1020	0.0000	0.0000	0.0000	0.0000					EASEMENT (DV 536, PG 100)		
															NO ADDITIONAL R/W REQUIRED		
25	FRANCO J. OREFICE	8,10	OR 600	136	51943227010000	0.1670	0.0000	0.0000	0.0000	0.0000					S.W. PART INLOT 53		
															NO ADDITIONAL R/W REQUIRED		
26	THE THOMAS A. MITCHELL	8,10	DV541	306	51943227011000	0.1530	0.0000	0.0000	0.0000	0.0000					S.W. PART INLOT 52, S.E. PART INLOT 53		
	REVOCABLE TRUST,		OR 878	1615											NO ADDITIONAL R/W REQUIRED		
	u/d/† 12/23/08, THOMAS A. MITCHELL, TRUSTEE																
27	EODDEST VEITU SUEETS	9.10	OP 403	220	510.43303006000	0 1330	0.0000	0.0000	0.0000	0.0000					DADT INI OT OI		
21	FORREST KEITH SHEETS  MARY KATHRYN SHEETS	8,10	OR 403	220	51943303006000	0.1330	0.0000	0.0000	0.0000	0.0000					PART INLOT 91  NO ADDITIONAL R/W REQUIRED		
											+			STATE			
	n:	•						•	•	•	<u> </u>		•		•	1	•

LEGEND: WL = FEE SIMPLE WITH LIMITATION OF ACCESS FL = FLOW EASEMENT

WD = WARRANTY DEED BS = BILL OF SALE

PRW = PROPERTY RIGHT FEE SIMPLE SH = STANDARD HIGHWAY EASEMENT

SL = SLOPE EASEMENT

S = SEWER EASEMENT

CH = CHANNEL EASEMENT

LA = LIMITED ACCESS EASEMENT T = TEMPORARY EASEMENT

U = UTILITY EASEMENT A = AERIAL EASEMENT PRE = PROPERTY RIGHT

SS = SUBSURFACE EASEMENT V = IN NAME OF ANOTHER STATE AGENCY, LPA, ETC.
R = SPECIAL RESERVATION

WA = WORK AGREEMENT SA = SPECIAL AGREEMENT AND WAIVER OF DAMAGES

NOTE: ALL TEMPORARY PARCELS TO BE OF 12 MONTH DURATION.

NOTE: UNDER NO CIRCUMSTANCES ARE TEMPORARY EASEMENTS TO BE USED FOR STORAGE OF MATERIAL OR EQUIPMENT BY THE CONTRACTOR UNLESS NOTED OTHERWISE.

NOTE: ALL RECORD AREAS ARE PER AUDITOR TAX RECORDS, AND MAY DIFFER FROM DEED AREAS.

(c) = CALCULATED AREA

MJW	9/28/10	REVISED PARCEL 23-SS	
MJW		REVISED PARCELS 20-SS, 23-SS	
REV. BY	DATE	DESCRIPTION	-
FIELD RE	VIEW BY:	MJW DATE: 12/28/09	

DATE: 12/29/09

OWNERSHIP VERIFIED BY: MJW

DATE COMPLETED: 12/29/09

GROSS P.R.O. IN NET

TAKE

0.0000 | 0.0000

STRUC-

TAKE TURE

NET RESIDUE

RIGHT

LEFT

TYPE

FUND

STATE

ALL AREAS IN ACRES

TAKE

0.0000

# **GRANTEE:**

NO ADDITIONAL R/W REQUIRED

PART INLOT 91

ALL RIGHT OF WAY ACQUIRED IN THE NAME OF THE STATE OF OHIO, DEPARTMENT OF TRANSPORTATION UNLESS OTHERWISE SHOWN.

REMARKS

0(434) 07 AS ACQUIRED BOOK PAGE

37

 $\widehat{\mathbf{L}}$ 

97

Ŋ

46

0

**UMMA** 

S

0

0

S 

**O** 

9 3

OR 707 51943303004000 0.1550 0.0000 0.0000 0.0000 PART INLOTS 90 AND 91 A.J. REAL ESTATE HOLDING, L.L.C. 8,10 0.0000 ACCESS EASEMENT - OR 584 PG 1137 NO ADDITIONAL R/W REQUIRED |51943303001000|0.3240(c)| TIM DONUT U.S. LIMITED, INC. 8,10 OR 618 0.0000 0.0000 0.0000 0.0000 PART INLOTS 89 AND 90 NO ADDITIONAL R/W REQUIRED 51943303002000 0.0950 0.0000 0.0000 0.0000 0.0000 |51943303003000| 0.3220(c)| 0.0000 0.0000 0.0000 0.0000 0.0000 ROBERT P. PEOPLES 8,10 OR 986 51943303022000 0.1440 0.0000 0.0000 0.0000 S. PART INLOT 89 ESTHER P. PEOPLES NO ADDITIONAL R/W REQUIRED 0.0000 8,10 0.0000 0.0000 UNKNOWN OWNER 0.0897(c) 0.0000 DELAWARE RUN STATE WL = FEE SIMPLE WITH LIMITATION OF ACCESS FL = FLOW EASEMENT NOTE: ALL TEMPORARY PARCELS TO NOTE: ALL RECORD AREAS ARE PER AUDITOR U = UTILITY EASEMENT

SHEET OWNERS RECORD AUDITOR'S RECORD TOTAL

PARCEL

51943303005000 0.1410

AREA

P.R.O.

0.0000

PAGE

1132

PARCEL

NO.

28

SHRI, INC.

WD = WARRANTY DEED

SL = SLOPE EASEMENT

CH = CHANNEL EASEMENT

S = SEWER EASEMENT

PRW = PROPERTY RIGHT FEE SIMPLE

SH = STANDARD HIGHWAY EASEMENT

LA = LIMITED ACCESS EASEMENT T = TEMPORARY EASEMENT

BS = BILL OF SALE

OWNER

NO.

8,10

A = AERIAL EASEMENT

PRE = PROPERTY RIGHT

WA = WORK AGREEMENT

SS = SUBSURFACE EASEMENT

R = SPECIAL RESERVATION

V = IN NAME OF ANOTHER STATE AGENCY, LPA, ETC.

SA = SPECIAL AGREEMENT AND WAIVER OF DAMAGES

BOOK

OR 584


6 / 10 REV. BY DATE DESCRIPTION 18 FIELD REVIEW BY: MJW DATE: 12/28/09 DATE: 12/29/09 OWNERSHIP VERIFIED BY: MJW 22 DATE COMPLETED: 12/29/09


NOTE: UNDER NO CIRCUMSTANCES ARE TEMPORARY EASEMENTS TO BE USED FOR STORAGE OF MATERIAL OR EQUIPMENT BY THE CONTRACTOR UNLESS NOTED OTHERWISE.


BE OF 12 MONTH DURATION.


TAX RECORDS, AND MAY DIFFER FROM DEED AREAS.

(c) = CALCULATED AREA









# HISTORIC RECORDS

NO HISTORIC RECORDS WERE FOUND FOR THIS PROJECT.

# <u>GEOLOGY</u>

THE PROJECT IS LOCATED WITHIN THE CENTRAL OHIO CLAYEY TILL PLAIN WHICH IS CHARACTERIZED BY FLAT-LYING GROUND MORAINE WITH WELL DEFINED END MORAINES. THIN OVERBURDEN SOILS GENERALLY CONSISTING OF COHESIVE, HIGH CLAY CONTENT SOILS UNDERLAIN BY DEVONIAN AGED DELAWARE LIMESTONE.

# RECONNAISSANCE

A FIELD RECONNAISSANCE WAS COMPLETED ON APRIL 16, 2008 BY PERSONNEL FROM THE OFFICE OF GEOTECHNICAL ENGINEERING. THE PROJECT AREA WAS NOTED AS BEING MIXED COMMERCIAL AND URBAN RESIDENTIAL WITH HOUSES AND A PARK. THE CULVERT WAS NOTED AS BEING A THREE SIDED CONCRETE BOX AT THE INLET LEADING INTO A CUT STONE ARC WITH A CORRUGATED GALVANIZED STEEL OUTLET. THE STONE ARC, THE MAJORITY OF WHICH IS LOCATED UNDER THE ROADWAY AND COMMERCIAL BUILDINGS, IS NOTED AS BEING IN POOR CONDITION WITH SEVERAL SECTIONS OF HEAVY DETERIORATION AND SEVERAL KEY STONES MISSING. THE INLET BOX WAS NOTED AS HAVING A OVER TWO INCHES OF SHIFTING AT THE ARCH JOINT AND THE OUTLET PIPE IS NOTED AS BEING CORRODED. SEVERAL UTILITY PIPES HAVE BEEN INSTALLED THROUGH THE SIDE WALLS OF THE ARCH WITH SEVERAL ATTEMPTS TO PATCHING THE PUNCH THROUGH AREAS. PAVEMENT CONDITIONS WITHIN EXISTING SR 36 WERE NOTED AS BEING POOR WITH HEAVY SETTLEMENT WITHIN THE ROADWAY INCLUDING RUTS AND DEPRESSIONS.

# SUBSURFACE EXPLORATION

THREE (3) BORINGS WERE DRILLED ADJACENT TO THE EXISTING CULVERT. THE BORINGS WERE DRILLED WITH A TRUCK MOUNTED ROTARY DRILL RIG, USING 3 1/4-INCH I.D. HOLLOW STEM AUGERS TO ADVANCE THE BORINGS THROUGH THE SOIL. THE HAMMER SYSTEM USED WAS LAST CALIBRATED IN FEBRUARY 20, 2007, AND THE AVERAGE DRILL ROD ENERGY RATIO (ER) IS 83.4%. DISTURBED SAMPLES WERE COLLECTED IN ACCORDANCE WITH THE STANDARD PENETRATION TEST (AASHTO T206) AT 2.5 FOOT INTERVALS WITH THE OVERBURDEN SOILS. THE BORINGS WERE ADVANCED INTO BEDROCK AND SAMPLED (AASHTO T225) USING AN N SERIES WIRELINE CORE BARREL, WATER METHOD.

# EXPLORATION FINDINGS

SUBSURFACE CONDITIONS REVEALED BY THE BORINGS INDICATED THAT BORINGS B-001 AND B-002 ENCOUNTERED OVERBURDEN SOILS CONSISTING PREDOMINATELY OF GLACIAL TILL COMPRISED OF SILT AND CLAY (A-6a) IN VERY STIFF CONSISTENCY AND DAMP. B-003 ENCOUNTERED FILL BELOW THE PAVEMENT COMPRISED OF STONE FRAGMENT WITH SAND, SILT AND CLAY CONTAINING BRICK FRAGMENTS IN LOOSE COMPACTNESS AND MOIST TO ELEVATION 877.7. BELOW THIS STRATUM THE BORING ENCOUNTERED STONE FRAGMENTS WITH SAND AND SILT (A-2-4) IN LOOSE TO MEDIUM DENSE IN COMPACTNESS IN MOIST CONDITION AND SLIGHTLY TO MODERATELY ORGANIC. ALL BORINGS WERE ADVANCED INTO BEDROCK TO CONFIRM THE CONDITIONS. THE BORINGS REVEALED TOP OF ROCK RANGING BETWEEN 872.4 IN B-002 TO 870.6 IN B-003 CONSISTING OF VERY STRONG LIMESTONE IN MODERATELY WEATHERED CONDITION CONTAINING CHERT, SHALE AND CLAY SEAMS. UNIT RQD VALUES RANGED BETWEEN 32% AND 56% AND REPORTED LOSS BETWEEN 2% AND 5%. ALL BORINGS WERE TERMINATED IN THIS LAYER.


# <u>SPECIFICATIONS</u>

THIS GEOTECHNICAL EXPLORATION WAS PERFORMED IN ACCORDANCE WITH THE STATE OF OHIO, DEPARTMENT OF TRANSPORTATION, OFFICE OF GEOTECHNICAL ENGINEERING, SPECIFICATIONS FOR GEOTECHNICAL EXPLORATIONS, DATED APRIL 2008.

# AVAILABLE INFORMATION

ALL AVAILABLE SOIL AND BEDROCK INFORMATION THAT CAN BE CONVENIENTLY SHOWN ON THE GEOTECHNICAL EXPLORATION SHEETS HAS BEEN SO REPORTED. ADDITIONAL EXPLORATIONS MAY HAVE BEEN MADE TO STUDY SOME SPECIAL ASPECT OF THE PROJECT. COPIES OF THIS DATA, IF ANY, MAY BE INSPECTED IN THE DISTRICT DEPUTY DIRECTOR'S OFFICE, THE OFFICE OF GEOTECHNICAL ENGINEERING AT 1600 WEST BROAD STREET OR THE OFFICE OF STRUCTURAL ENGINEERING AT 1980 WEST BROAD STREET.

<u>LE</u>	<u>GEND</u>	ODOT	CLASS	CIEIEN
	DESCRIPTION	CLASS		
	GRAVEL AND/OR STONE FRAGS, WITH SAND & SILT	A-2-4	1	1
	GR. AND/OR ST. FRAGS. WITH SAND, SILT & CLAY	A-2-6	1	1
	SILT AND CLAY	A-6a	3	3
	CLAY	A-7-6	0	1
		TOTAL	5	6
	LIMESTONE	VISUAL		
XXXXX	PAVEMENT OR BASE = X = APPROXIMATE THICKNESS	VISUAL		
<del>-</del>	BORING LOCATION - PLAN VIEW.			
	DRIVE SAMPLE AND/OR ROCK CORE BORING PLOTTED THORIZONTAL BAR INDICATES A CHANGE IN STRATIGRAPH		L SCALE	ONLY.
WC	INDICATES WATER CONTENT IN PERCENT.			
N <sub>60</sub>	INDICATES STANDARD PENETRATION RESISTANCE NORMALIZED TO 60% DRILL ROD ENERGY RATIO.			
<i>X/Y/Z</i>	NUMBER OF BLOWS FOR STANDARD PENETRATION TEST X= NUMBER OF BLOWS FOR FIRST 6 INCHES. Y= NUMBER OF BLOWS FOR SECOND 6 INCHES. Z= NUMBER OF BLOWS FOR THIRD 6 INCHES.	(SPT):		
SS	INDICATES A SPLIT SPOON SAMPLE.			
TR	INDICATES TOP OF ROCK.			



SCALE IN MILES

1 2 3 4



# PARTICLE SIZE DEFINITIONS

12	2" 3	2.0	mm	0.42	° mm	0.07	4 mm 0.00	5 mm
BOULDERS	COBBLES	GRAVEL	COARSE	SAND	FINE	SAND	SILT	CLAY
'		No. 10	SIEVE	No. 40	SIEVE	No. 200	SIEVE	I

**RECON. -** DAN, KDB 04/16/08 **DRILLING -** KAM 07/21-22/08

DRAWN - JAG 09/09
REVIEWED - BKL 09/09

0

3

OHIO OFFI(

37

Z


<u>o</u>

0

0

Z

0



\79373ZL001.dan 04-JAN-2011 9:52AM

 $\bigcirc$ 

 $\bigcirc$ 

CALIBRATING METHOD: 3.25   ASA   ANGE   CALIBRATIO DATE   CALIBRATION AND AUTO   ASA   A	<u>DEL-36-9.75</u> RUCTURE - CULVERT	IRM / OF	DRILL RIG: CME 55 HAMMER: AUTOMATIC	55 JATIC	STA / OFFSET	F: 23+46, 9.0'		EXPLORATION ID: B-001-08	
BELEV. SPT 14 SMPL 6 REC (HP) SAMPLE GRADATION (X) AT 180.0.2 DEPTHS ROD N60 X (TSF) 1D GR (CS FS SI CL UL) GR (CS FS SI CL UL	1 <del>-</del> - 1	DRILLING METHOD: 3.25" HSA / NQ2 SAMPLING METHOD: SPT / NQ2	CALIBRATION PARA	2/20 83.4	ELEV: 880.2 COORDS: 8	\ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \	9 <b>B:</b> 2 655.	PAGE 1 of 1	
871.7 TOR 8 18 100 4.00 SS-1 24 7 10 29 30 29 1	MATERIAL		v. .2 DEPTHS	T / RE	HP SAMPLE (TSF) ID	SADATION CS FS SI	TRBRG. PL PI	WC CLASS (GI)	SNI
871.7 TOR 8	OWN SILT & CLAY,	LITTLE SAND, GLACIAL T	<del>                                     </del>	\ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \					
871.7 TOR 8 - 10				5 14 10		7 10 29	58	16 A-6a (5)	
871.7 TOR 8				5 13 10	00.	1 1 1	1	16 A-6a (V)	
### 871.7 TOR 8 = 8 = 8 = 8 = 8 = 8 = 8 = 8 = 8 = 8				8 18 10	SS SS	1 1	1	15 A-6a (V)	
— 10 — 11 — 13 — 14 — 15 — NR 98 — RC — 15 — 17 — 16 — 16 — 17 — 19 — 19 — 19 — 19 — 19 — 22 — 21 — 23 — RC — 24 — 19 — 24 — 24 — 19 — 24 — 24 — 24 — 24 — 24 — 24 — 24 — 2	RK GRAY WITH BRO)	WN. MODERATELY WEATHERED, VERY STRONG,	71.7 TOR 8 1	- 4	-SS-	1	1	1 ROCK (V)	
HIGH ANGLE FRACTURE, FRESH.  EAM.  EAM.  DRY BEFORE CORING.  MICH ANGLE FRACTURE, FRESH.  EAM.  DRY BEFORE CORING.  MICH ANGLE FRACTURE, FRESH.  EAM.  DRY BEFORE CORING.  MICH ANGLE FRACTURE, FRESH.  EAM.  EAM.  DRY BEFORE CORING.  MICH ANGLE FRACTURE, FRESH.  EAM.  EAM.  DRY BEFORE CORING.  MICH ANGLE FRACTURE BLICK BENTSMITTER DRY METHOD	RED TÓ MODERATE		0 = 2 E						
BEFORE CORING.  BEFORE CORING.  BEFORE MATERIAL STATES AND STATES AND WELLOW	ANGLE							CORE	
EAM.  EAM.  DRY BEFORE CORING.  METHODS MATERIALS DIANTITIES 3 BASS WOLF BLILS BENTONITE DRY METHOD.			17						
DRY BEFORE CORING. Methods Matebials aliantities 3 bass "half belief bentanite nby	EAM。		5.2 EOB - 24 -	<b>⊕</b>	   RC-2			CORE	
MEIHOUS, MAIEKIALS, QUANIIIES: S BAGS HOLE FLUG BENIONIIE, URI	DRY BEFOR METHODS,	S, QUANTITIES: 3 BAGS "HOLE PLUG" BENTONI	TE, DRY METHOD.						

EXPLORATION ID:  B-002-08  PAGE 1 of 1	WC CLASS (GI) IS (VISUAL)	15 A-6g (2)	14 A-6g (5)	24 A-6g (V)	6 A-7-6 (V)	CORE	C C C C C C C C C C C C C C C C C C C	- - -
FOB: 25.0 FT 808434.540 E	%) ATTRBRG. CL LL PL PI W	21 30 17 13	23 31 18 13 1		1 1			-
ET: 513+95, 5.( © US 36 8 FT (MSL) 837925.197 N,	GRADATION ( GR CS FS SI	44 6 8 21	26 4 15 32	1	1 1			- - -
STA ALIGI ELEV COOF		67 4.00 SS-1	67 2.50 SS-2	78 3.00 SS-3	42 - SS-4	91 RC-1	8.C-7.R	
ME 55 TOMATIC DATE: 2/20/ O (%): 83.4	SPT / ROD RO	9 4 6 14	5 4 13	16 32	50/1" -	~ ~ ~	2 5 8 9 5 7 8 8 9 9 7 8 9 9 9 9 9 9 9 9 9 9 9 9 9	
DRILL RIG: HAMMER: CALIBRATIGENERY RA	ELEV. 880.8 DEPTHS	- 2 K		**************************************	2.4 TOR -	9 C = C E 4 #	B55.8 FOR FOR	
DRILLING FIRM / OPERATOR: ODOT / SABO SAMPLING FIRM / LOGGER: ODOT / MCLEISH DRILLING METHOD: 3.25" HSA / NQ2 SAMPLING METHOD: SPT / NQ2	AND NOTES	"AND" GRAVEL, LITTLE SAND, GLACIAL TILL,			DERS)	AY STRONG, and clay %.		
PROJECT: DEL-36-9.75  TYPE: SIRUCTURE - CULVERT  PID: 79373 BRIDGE ID: N/A  START: 7/22/08 END: 7/22/08	MATERIAL DES HICKNESS NOT RECORDED) THICKNESS NOT RECORDED	VERY STIFF BROWN SILT & CLAY, "ANI DAMP @ 3.5': DARK BROWN, SOMF GRAVF!		@ 6.0'; MOIST	HARD GRAY CLAY, "AND" STONE FRAGN	LIMESTONE, DARK GRAY WITH BROWN. MODERATELY WEATHERED, VEI THIN BEDDED, CHERTY, SLIGHTLY FOSSILIFEROUS, CONTAINS SHALE SEAMS, FRACTURED TO MODERATELY FRACTURED; RQD 52%, LOSS 2		NOTES: HOLE DRY BEFORE CORING.

36

20 29 09 STA / OFFSET
ALIGNMENT:
ELEV: 880.7
COORDS: 8.
HP SAMPLE
(TSF) ID 707 DRILL RIG: CME 55
HAMMER: AUTOMATIC
CALIBRATION DATE: 2/2
ENERGY RATIO (%): 83
EV. | 2 တ 9 9 LIMESTONE, DARK GRAY WITH BROWN. MODERATELY WEATHERED, VERY STRONG, THIN BEDDED, CHERTY, SLIGHTLY FOSSILIFEROUS, CONTAINS SHALE AND CLAY SEAMS, FRACTURED TO MODERATELY FRACTURED; RQD 32%, LOSS 3%. TRA( DRILLING FIRM / OPERATOR: ODOT / SAMPLING FIRM / LOGGER: ODOT / M DRILLING METHOD: 3.25" HSA / NQ2 SAMPLING METHOD: SPT / NQ2 MATERIAL DESCRIPTION AND NOTES

CONCRETE (THICKNESS NOT RECORDED)

LOOSE BROWN STONE FRAGMENTS WITH SAND, SILT & CLAY, CONTAINS BRICK
FRAGMENTS, MOIST MEDIUM DENSE BROWN WITH GRAY STONE FRAGMENTS WITH SAND & CLAY, SLIGHTLY ORGANIC, MOIST @ 873.2'; LOOSE, MODERATELY ORGANIC

PROJECT: <u>DEL-36-9.75</u> TYPE: STRUCTURE - CULVERT PID: 79373 BRIDGE ID: N/A START: 7/22/08 END: 7/22/

NOTES: HOLE DRY BEFO ABANDONMENT METHODS

SEAM.

24.0'; CLAY

**©** 

SEAM.

21.47; CLAY

**©** 

# **SPECIAL PROVISIONS**

# WATERWAY PERMITS CONDITIONS

C-R-S: DEL-36-9.75

PID: 79373

Date: 01/04/10

Special Provisions / Plan Notes for DEL-36-9.75 (PID 79373)

### 1. Waterway Permit Time Restrictions:

Complete all work in streams and wetlands depicted in the plans, Special Provisions, and/or working drawings for temporary fill by 10/23/2014.

For work on streams and wetlands, the Department will consider the Contractor's submission of an extension to the waterway permit end date based on project constraints. In order to be considered, the Contractor must submit a justification to the Engineer at least two months prior to the waterway permit end date.

The Engineer will submit the request for a time extension to ODOT- Office of Environmental Services- Waterway Permits Unit (614-466-7100) for consideration and coordination with the USACE and/or Ohio EPA.

### 2. Deviations from Permitted Construction Activities

No deviation from the requirements for work in streams and wetlands depicted in the plans, Special Provisions, and/or working drawings may be made unless a modification has been submitted to ODOT and approved by the appropriate agencies (i.e., USACE, Ohio EPA, USCG, ODNR, and USFWS).

For emergency situations resulting in unanticipated impacts to streams or wetlands, provide notification (verbal or written) to the Engineer as soon as possible following discovery of the situation. Written notification to the Engineer and notification to the ODOT- Office of Environmental Services- Waterway Permits Unit must be made within 24 hours.

For non-emergency situations, notify the Engineer in writing for submission to the ODOT- Office of Environmental Services- Waterway Permits Unit (614-466-7100) for consideration and coordination with the appropriate agencies. Notification must be made at least two months prior to planned non-permitted activities. Consideration of the requested deviation is at the discretion of the Director and must be coordinated with the appropriate regulatory agencies.

### 3. In-Stream Work Restrictions

Work in the following sensitive streams is further restricted as follows

Steam Name /Description	Location	Work restriction dates (No in-stream work permitted)
Delaware Run	510+20 to 519+80	None

Examples of "fill materials" include (but are not limited to) bridge piers, abutments, bridge demolition debris, culverts, rock channel protection, scour protection, and temporary work pads. Temporary work pads can be constructed of rock or include any structures (e.g., scaffolds, ladders, barges that touch the bottom of the stream, etc).

Fills (such as temporary work pads) placed within a stream identified in the above table outside

Special Provisions / Plan Notes for DEL-36-9.75 (PID 79373)

of the work restriction dates can continue to be worked from during the work restriction dates, but cannot be expanded, removed, or otherwise modified (below ordinary high water) until once again outside of the work restriction dates.

The Engineer will submit the request for a time extension to ODOT- Office of Environmental Services- Waterway Permits Unit (614-466-7100) for consideration and coordination with the USACE and/or Ohio EPA.

### 4. Materials:

Materials utilized in or adjacent to streams and wetlands on this project for temporary or permanent fill or bank protection shall consist of suitable material free from toxic contaminants in other than trace quantities. Broken asphalt is specifically excluded.

Cadmium, chromium, arsenate (CCA), creosote, and other pressure treated lumber shall not be used in structures that are placed in wetlands and streams.

### 5. Cultural Resources

If archeological sites or human remains are discovered, cease all work in the immediate area and notify the Engineer who will immediately contact the Office of Environmental Services – Cultural Resource Section

(614-466-7100) and the Ohio Historic Preservation Office.

In the event of human remains are discovered the Engineer shall also contact the Delaware County Sherriff's Office. (740)833-2810.

### 6. Water Resource Demarcation:

All streams, wetlands, lakes, and ponds indicated on the plans shall be demarcated in the field as per SS 832 prior to site disturbance. The fence shall remain in place and be maintained throughout the construction process. Following the completion of the project, the fence and posts shall be removed.

### 7. Spill containment:

Provide and Maintain an Oil Spill Kit with a minimum capacity of 65 gallons. The Spill Kit shall contain:

- 6 3 in. X 8 ft. Oil only socks
- 4 18 in. X18 in. Oil only pillows
- 2 5 in. X 10ft. Booms
- 50 16in. X 20 in. Oil only pads
- 10- Disposable Bags
- 1- 65 Gallon drum with lid
- 25 pounds of Granular Oil Absorbent

The Oil Spill Kit shall be located within 150 feet of any equipment working in a stream or

Special Provisions / Plan Notes for DEL-36-9.75 (PID 79373)

wetland. The oil Spill Kit shall be maintained for the life of the contract. Any materials utilized during the project will be replaced within 48 hours.

All costs associated with furnishing and maintaining the above referenced spill containment kit is incidental to work.

### 8. Blasting:

State law requires notification to the Ohio Department of Natural Resources should blasting be required within or near stream channels (See ORC 1533.58 & CMS 107.09).

Notify Engineer, in writing, for submission to ODOT Office of Environmental Services – Waterway Permits Unit (614-466-7100) for coordination with the Ohio Department of Natural Resources.

### 9. Waterway Permits:

A copy of the waterway permits: RGP Part B Permit shall be kept at the work site at all times and made available to all contractors and subcontractors. The Permit is effective starting: 01/10/2011. The Permit expires: 10/23/2014

### 10. Bridge Inspection:

Prior to the removal of bridge structures, the underside must be carefully examined for the presence of birds and bats. Should any birds or bats be found roosting on the underside of the bridge, the Contractor is required to notify the Engineer for coordination with ODOT- Office of Environmental Services (614-466-7100).

### 11. Project Inspection:

Inspection of Work may include inspection by representatives of other government agencies or railroad corporations that pay a portion of the cost of the Work or regulate the Work through State and Federal law. Comments from the representatives of these agencies shall be directed to the Engineer. Please forward a copy to ODOT Office of Environmental Services. Waterway Permits Unit (614-466-7100).

### 12. Construction Completion Certification:

Upon Completion of the work, notify the Engineer. The US Army Corps of Engineers Construction Completion Certification must be completed and signed by the Engineer then forwarded to the:

### Special Provisions / Plan Notes for DEL-36-9.75 (PID 79373)

U.S. Corps of Engineers DSCC Building 10, Section 10 3990 East Broad Street Columbus, Ohio 43218

Foward a copy of the certification to ODOT Office of Environmental Services. Waterway Permits Unit.

### 13. Temporary Access Fills (Stream and River Crossings and Fills)

### **Special Provisions Notes:**

Regional General Permit (RGP) for the State of Ohio Department of Transportation

### Definitions:

### **Hydraulic Opening**

The cross sectional area allowing an unimpeded discharge equal to twice the highest monthly flow without producing a rise in the backwater above the Ordinary High Water Mark (OHWM)\*.

### Standard Temporary Discharge

The hydraulic opening providing a capacity for a discharge equal to twice the *highest monthly flow* without producing a rise in the backwater above the OHWM shall be known as the Standard Temporary Discharge. The U.S. Geologic Service publication "Techniques for estimating Selected Streamflow Characteristics of Rural Unregulated Streams in Ohio" provides equations that estimate monthly flow for Ohio Waterways These flows are also available in a web application by USGS StreamStats, (http://water.usgs.gov/osw/streamstat/ohi.html).

### **Average Monthly Flow**

The average monthly flow represents the estimated "normal" flow.

### **Temporary Access Fills (TAFs)**

In Streams and Rivers may include, but are not limited to, causeways, cofferdams (as described by other items of work), access pads, temporary bridges, etc. The Contractor will make every attempt minimize disturbance to water bodies, stream banks, stream beds, and approach sections during the construction, maintenance, and removal of the TAFs. Fording of streams and rivers is prohibited.

Construct TAFs in such a manner that will maintain flows, minimize upstream flooding, and avoid overtopping the TAF on a regular basis. TAFs shall be designed and constructed so that the hydraulic opening provides capacity for a discharge equal to twice the highest monthly flow without producing a rise in the backwater above the Ordinary High Water Mark (OHWM)\*.

Do not exceed an overall length of 250 feet measured linearly upstream to downstream.

### Requirements

Special Provisions / Plan Notes for DEL-36-9.75 (PID 79373)

21 calendar days prior to the initiation of any in-stream work, provide the Engineer with working drawings that include:

- Plan view drawing (200 scale or less) showing the location of all jurisdictional temporary fill proposed for use on the project
- Scaled Cross section and profile drawing showing the OHWM and the proposed compliant hydraulic opening.
- A description of the installation and staging of all temporary jurisdictional fill over the life of the contract.
- A description of the removal of all jurisdictional temporary fill and restoration of the channel and all areas impacted by the jurisdictional temporary fill.
- A schedule outlining the timing of the placement and removal of all TAF.
- Have an Ohio Registered Engineer prepare, sign, seal and date the working drawings. Have a second Ohio Registered Engineer check, sign, seal and date the working drawings. The preparer and checker are two different Engineers. Include the following statement on the working drawings:

"These working drawings were prepared in compliance with the terms of the Regional General Permit and all contract documents."

- Include supporting hydraulic calculations developed by the engineer(s) who sealed the working drawings.
- Do not begin instream work until the Engineer has accepted the working drawings.

If the OHWM is not shown on the plans, the Department will establish the OHWM based on the definition of OHWM (as defined in SS 832) or the peak discharge from the 2 year event, using the method described in the most current version of the Department's Location and Design Manual Volume II.

If the Contractor proposes a TAF which does not provide for the Standard Temporary Discharge (discharge equal to twice the highest monthly flow without producing a rise in the backwater), the Contractor is required to coordinate the request for the contractor's proposed TAF with the Engineer and the ODOT Office of Environmental Services (OES). The Department makes no guarantee to grant the request. The contractor's proposed TAF request will be coordinated by OES with the U.S. Army Corps of Engineers and the Ohio Environmental Protection Agency, as appropriate.

In addition to the requirements described in SS 832, supply the Engineer/OES with the following:

- 1. A plan and Profile showing the temporary access fill(s) with the OHWM.
- 2. Cross section showing the hydraulic opening and the anticipated discharge flow.
- 3. A restoration plan for the area affected by the temporary access fill(s).
- 4. A schedule outlining the timing of the placement and removal of the temporary access fill(s)

The time frame allowed for the coordination of the contractor's proposed TAF will be a minimum of 60 days. Installation of any jurisdictional fill without a 404 Permit authorized by the USACE is strictly prohibited. All direct coordination with the USACE and/or OEPA will be performed through OES.

Special Provisions / Plan Notes for DEL-36-9.75 (PID 79373)

### **Temporary Access Fills Construction and Payment**

Begin planning and installing causeways and access fills as early in construction as possible to avoid conflicts with 404/401 permits or other environmental commitments that have been included in the construction plans.

Temporary Access Fills (TAFs) in Streams and Rivers may include, but are not limited to, causeways, cofferdams, access pads, temporary bridges, etc. Make every attempt minimize disturbance to water bodies, stream banks, stream beds, and approach sections during the construction, maintenance, and removal of the TAFs. Make every attempt to minimize disturbance to water bodies during construction, maintenance and removal of the causeway and access fills. Construct the causeway and access fills as narrow as practical. Install instream conduits parallel to the stream banks. Make the causeway and access fills in shallow areas rather than deep pools where possible. Minimize clearing, grubbing, and excavation of stream banks, bed, and approach sections. Construct the causeway and access fills as to not erode stream banks or allow sediment deposits in the channel.

Prior to the initiation of any in-stream work, establish a monument upstream of proposed temporary crossing or temporary construction access fill to visually monitor the water elevation in the waterway where the fill is permitted. Maintain the monument throughout the project. Provide a visual mark on the monument that identifies the elevation 1 foot above the OHWM. If the OHWM is not shown on the plans, the Department will establish the OHWM based on the definition of OHWM (SS 832.02) or the peak discharge from the 2 year event, using the method described in the most current version of the Department's Location and Design Manual Volume II.

Ensure that the monument can be read from the bank of the waterway. Have this elevation set and certified by an Ohio Registered Surveyor.

Temporary access fills placed by the contractor above the OHWM are not subject to the 404/401 permit constraints.

Should the water elevation of the waterway, exceed the elevation 1 foot above OHWM, the Department will compensate the Contractor for repair of any resulting damage to the permitted temporary access fill up to the elevation of 1 foot above the OHWM. The Department will not pay for repair and maintenance of temporary access structures that are related to the construction access fill.

Should the water elevation of the waterway exceed the elevation shown on the monument, the Department will recognize this event as an excusable, non-compensable delay in accordance with Section 108.06 of the Construction & Materials Specifications.

All costs associated with furnishing and maintaining the above referenced monument is incidental to the work.

Construct the causeway and access fills to a water elevation at least 1 foot (0.3 m) above the OHWM. If the causeway fills more than one-third the width of the stream, then use culvert pipes to allow the movement of aquatic life. Ensure that any ponding of water behind the causeway and access fills will not damage property or threaten human health and safety.

The following minimum requirements apply to TAFs where culverts are used.

- A. Furnish culverts on the existing stream bottom.
- B. Avoid a drop in water elevation at the downstream end of the culvert.
- C. Furnish a sufficient number of culverts in addition to stream openings to providing a

### Special Provisions / Plan Notes for DEL-36-9.75 (PID 79373)

discharge equal to twice the highest monthly flow without producing a rise in the backwater above the OHWM.

D. Furnish culverts with a minimum diameter of 18 inches (0.5 m)...

For all fill and surface material placed in the channel, around the culverts, or on the surface of the causeway and access fills furnish clean, non-erodible, nontoxic dumped rock fill, Type B, C, or D, as specified in C&MS 703.19.B. Extend rock fill up the slope from original stream bank for 50 feet (10 m) to catch and remove erodible material from equipment.

When the work requiring the TAFs is complete all portions of the TAF (including all rock and culverts) will be removed in its entirety. The material will not be disposed in other waters of the US or isolated wetland. The stream bottom affected by the causeway and access fills will be restored to its preconstruction elevations. The TAF will not be paid as a separate item but will be included by the Contractor as part of the total project cost.

All environmental protection and control associated with the 404/401 permit activities are incidental to the work within the boundaries of the 404/401 permit or as otherwise identified in the 404/401 permit application.

X\Ecological\Waterway Permits\ Resources\ Special Provisions\Special Provisions condition \ Plan Notes 12-13-10.doc

DEL-36-9.81 PID: 79373

SPECIAL PROVISIONS

City of Delaware, OH Department of Planning and Community Development 1 S. Sandusky St. Delaware, OH 43015

Fees Due: \$0.00

Application Type: Flood - - Floodplain Development Permit

THIS MUST BE ON THE JOB SITE FOR ALL INSPECTIONS.

# **City of Delaware** Plan Approval

Approval Number: 20100482

Address: 123 W WILLIAM ST

Lot #: PTS 91. Subdivision: DELAWARE TOWN PLAT

Conditions:



### SPECIAL FLOOD HAZARD AREA DEVELOPMENT PERMIT APPLICATION



Permit No. 20100487

### SINGLE FAMILY \$100.00 Fee

ALL OTHER PURPOSES \$300.00 Fee

Application is hereby made for a DEVELOPMENT PERMIT as required by the Flood Plain Standards, Chapter 1150 of the City of Delaware Codified Ordinances for the development in an identified flood hazard area. All activities shall be completed in accordance with the requirements of said Standards. The development to be performed is described below and in attachments hereto. The applicant understands and agrees that:

- this permit is issued on the conditions and facts described;
- any permit may be repealed if conditions or facts change;
- permit void if the activity has not begun within 180 days of the issuance date;
- the permit will remain valid for one year from date of issuance.

Owner's Name: Ohio Department of Trans	sportation – District 6 A	ddress: 400 E. William Street	Delaware, Ohio 43015	
Parcel Number		Address		
Builder		Address		
Contact email				WHAT, week
Contact phone				
1. Location of proposed development site	e-address: Below the intersection o	f US36 (William St.) & Liberty !	<u>3t.</u>	
Legal description: refer to R/W plan sh	<u>eets</u>			
Kind of development proposed		filing largeling		
new building	existing structure			
residential non-residential	alteration addition	mining/dredging watercourse		
manufactured home	accessory	watercourse alteration		
installation	materials storage	other*	<u>X</u>	
and that once a structure meets the requirements. For floodplain man	ructure). FEMA maintains that the se definition of "new construction" a agement purposes "new construction d Insurance Rate Map issued by Fl	e "substantial improvement" de any further improvements to the ion" means structures for whice EMA for the community.	efinition applies to existing stat structure must meet "new h "start of construction" bega	tructures on construction
	is required from applicant if it has i	not been provided by FEMA.		
ADMINISTRATIVE: The following is to be (m.s.l.). The term base flood elevation me	completed by the local floodplain	administrator. All references to	elevations are in feet mean	sea level
5. Is the proposed development located X an identified floodway		th no identified floodway?		
an approximate flood	odplain fringes?	·		
NOTE: Floodway development must de	monstrate through hydrologic and le eflood elevation will result during of			
1 South Sandusky St	reet Delaware, Ohio 43015 740-20	03-1600 (v) 740-203-1699 (f) w	ww.delawareohio.net	

floodway delineation, hydrologic and hydraulic analysis is required to demonstrate not more than one foot increase at any point to the water surface elevation of the base flood.

6.	Does proposed development meet NFIP and local General Standards? N/A
	Construction materials and methods resistant to flood damageAnchored properly.
	Subdivision designed to minimize flood damage.
	Encroachments-proposed action will not obstruct flood waters.
	Proposed site grada elevation if fill or topographic alterations plannedLowest floor elevated to or above BFE.
	Lowest floor elevated to or above BPESpecific Standards? .
	Lowest floor floodproofed above BFE.
7.	Base flood elevation (100-year) at proposed site 885.9 feet m.s.l.
	Data source: FIRM Flood Insurance Rate Map, Delaware County, Ohio and Incorporated Areas
	Community-Panel No.: Panel 112 of 295, Map# 39041CO112K
	Map effective date: April 16, 2009
8.	Does the structure contain a <u>N/A</u> basement; <u>N/A</u> enclosed are used only for parking access or storage, other than basement below the lowest floor?
9.	For structures located in unnumbered A zones (no BFE available) the structure's lowest floor is <u>N/A</u> feet above the highest grade adjacent to the structure.
10.	The certified as-built elevation of the structure lowest floor is N/A feet above m.s.l.*
11. <u>NO</u>	The certified as-built floodproofed elevation of the structure's is <u>N/A</u> feet above ms.l.*  *Certificates of a registered engineer or land surveyor documenting these elevations are necessary if elevations are provided by applican
12.	The proposed development is in compliance with applicable floodplain standards.  PERMIT ISSUED ON 6.14.10
13.	The proposed development is <u>not</u> in compliance with applicable floodplain standards.  PERMIT DENIED ON
	ison:
NO	<u>FE</u> :All structures must be built with the lowest floor, including the basement, elevated or floodproofed to or above the base flood elevation (100-year) unless a variance has been granted. Only nonresidential structures may be floodproofed.
14.	The proposed development is exempt from the floodplain standards per Section of the Flood Damage Prevention Ordinance (Resolution) No
The	undersigned is either the property owner or a duly authorized agent of the property owner and do hereby verify the truth and correctness of
fact	s and information presented with this application and authorize on-site inspections by City Staff.
Owr	ner or Authorized AgentDateDateDate
Арр	roved ByDate
Plar	nning/ZoningDate
CBC	Date



# OHIO DEPARTMENT OF TRANSPORTATION

**DISTRICT 6 • INTER-OFFICE COMMUNICATION** 

June 7, 2010

TO:

David Efland, Director of Planning and Community Development

FROM:

Brian S. Tatman, Office of Planning, ODOT-District 6 (387)

SUBJECT:

DEL-36-9.75 (PID 79373) - Floodplain Permit Application

ODOT District 6 is planning to line the stone arch culvert under US 36 that carries Delaware Run through urbanized areas. The line will be installed in-situ and consists of a spiral wound profile method consisting of a PVC liner and grouting the annular space. No new right-of-way or in-stream beyond clearing debris out of the culvert is required for this project.

Per your request, enclosed you will find a document containing the No-Rise Certification, Flood Permit, and Floodplain Study outlining the final results of the HEC-RAS Analysis. The results show little change in pre/post conditions which can be expected due to lining operation location. Please let me know if this is acceptable to receive the necessary floodplain permit. Thanks!

Enclosure(s)

BST:bt



### **ENGINEERING "NO-RISE" CERTIFICATION**

This is to certify that I am a duly qualified engineer licensed to practice in the State of				
Ohio. It is to further certify that the attached technical data supports the fact that proposed				
development: DEL-36-9.81 (rehabilitation of a portion an existing stone arch) in the floodway will (Name of Development)				
not increase the Base Flood Elevations (100-year flood), floodway elevations and the				
floodway widths on <u>Delaware Run</u> at published sections in (Name of Stream)				
The Flood Insurance Study for Delaware County, Ohio (Map #39041C0112K), dated April 16, 2009 and (Name of Community)				
will not increase the Base Flood Elevations (100-year flood), floodway elevations, and floodway				
widths at unpublished cross-sections in the vicinity of the proposed development.				

		1
אנג מממגי	mark I am	33d
TIGORI	W (/ ) W	25 4

	Mathew of 6033ct	
Signature:		


Date: May 21, 2010

EMAIL: matt.cozzoli@dot.state.oh.us 614-466-3152 Phone Number:

Representing: Ohio Department of Transportation - District 6

Address: 400 E. William Street


City: Delaware State: Ohio Zip Code: 43015



**CERTIFYING SEAL OR STAMP** 

City Hall ( ) South Sandusky Street ( Delaware, Ohio 43015 ( Planning And Development@delawarenhio.or) Tel: 740.203.1600 + Fan: 740.204.1699 nwn.delawanobio.cet

# **FLOODPLAIN STUDY**



**DEL-36-9.81** 

**PID 79373** 

May 19, 2010

Prepared for:


Jerry Warner, City of Delaware Chief Building Official and Code Enforcement Officer Floodplain Administrator

**ODOT - District 6** 

Prepared by: Central Office, Office of Production

### **INTRODUCTION**

The purpose of this study is to perform a hydraulic analysis to verify that the proposed partial lining of the 15' stone arch will not result in any increase in the 100-year flood elevation. The structure lies under US36 (W William St.) within the City of Delaware, Delaware County, Ohio.



The stone arch structure was constructed in the 1800's during the early beginnings of the City of Delaware. The structure currently has a general appraisal and operational status rating of a 3A (Serious, no restriction). The structure spans Delaware Run which is a tributary of the Olentangy River. The project site lies in a designated FEMA Flood Zone where base flood elevations have been established.

1

### **HYDRAULIC DESIGN DATA**

A drainage area of 8.85 miles<sup>2</sup> (5667 acres) was hand delineated from the USGS quadrangles. A Gazetteer of Ohio Streams was used to check the delineated drainage area. The project site lies upstream near the mouth of Delaware Run. The Gazetteer lists a drainage area at the mouth of 10.1 miles<sup>2</sup> which makes the 8.85 miles<sup>2</sup> a reasonable estimate. The USGS StreamStats program was also used to delineate a drainage area of 9.24 miles<sup>2</sup>. We feel this drainage area may be a little conservatively oversized but it also a validates our original estimate.

The USGS WRI 93-4080 Regression Equations were used to calculate the flood peak discharges for the site as well as USGS StreamStats program.

The project site lies in a designated FEMA Flood Zone where base flood elevations have been established. A flood discharge was calculated from the FEMA Flood Insurance Study at the cross section near Catherine Street.

USGS WRI 93-4080 Regression Equations:

Q(25) - 1120 cfsQ(100) - 1510 cfs

StreamStats:

Q(25) - 1250 cfsQ(100) - 1650 cfs

Q(500) - 2110 cfs

Floodway Data:

Known Water Surface Elevation @ Section I, 875.3

FEMA - 2058 cfs

Below are the discharges used for the analyses and the downstream slope used for the normal depth calculations. A known starting water surface elevation was also used based upon the Floodway Data from Table 11.

flow 1: Q25 (1120 cfs), Q100 (1510 cfs), FEMA (2058 cfs) for Reach 1, slope 1.0%

flow 2: Q25 (1120 cfs), Q100 (1510 cfs), FEMA (2058 cfs) for Reach 2, slope 1.0%

flow 3: Q25 (1120 cfs), Q100 (1510 cfs), FEMA (2058 cfs) for Reach 1, slope 0.9%

flow 4: Q25 (1120 cfs), Q100 (1510 cfs), FEMA (2058 cfs) for Reach 2, slope 0.9%

flow 5: FEMA (2058 cfs) for Reach 2, Known WS elevation 875.3

$$\left\{\frac{32(0.013)^{1.5} + 23.5(0.030)^{1.5} + 23.5(0.030)^{1.5} + 22.5(0.034)^{1.5}}{101.5}\right\}0.67$$

=0.0258

= 0.0220

With the structure shape and n = 0.0258 added to the input, the existing system was analyzed to establish existing water surface elevations.

w/ structure no lining

g07, plan7, flow4: straight alignment but revised channel profile/xsections g07, plan8, flow5: straight alignment but revised channel profile/xsections, WS

Inlet @ river STA. 60+56  $Q_{100} - 884.74$  $Q_{FEMA} - 886.20$ 

QFEMA & KNOWN WS ELEVATION - 886.5

$$\left\{ \frac{32(0.013)^{1.5} + 23.5(0.030)^{1.5} + 23.5(0.012)^{1.5} + 22.5(0.034)^{1.5}}{101.5} \right\} 0.67$$

The system was analyzed again using an n = 0.0220 to account for the partial lining of the stone arch.

### w/ structure lining

g08, plan9, flow4: straight alignment but revised channel profile/xsections g08, plan10, flow5: straight alignment but revised channel profile/xsections, WS

Inlet @ river STA. 60+56  $Q_{100} - 884.73$  $Q_{\text{FEMA}} - 886.15$ 

QFEMA & KNOWN WS ELEVATION - 886.47

STA.
DEPARTMENT O
DEPARTMENT O
DIVISION OF UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY 83.07730

Project: DEL-36-9.75 Stream name: DELAWARE RUN LOCATION: DELAWARE/OSTRANDER QUAD

Geographic region = A

Recurrence	Regression	
Interval	Estimate	
(Years)	(cfs)	
2	473	
5	781	
10	1010	
25	1300	
50	1530	
100	1760	

DEL36.PKE Date: 8/15/05

warning: The regression equations used by this program tend to overestimate peak discharges for basins having approximately 30 percent or more surface-mined area. For more information, refer to page 15 of the reference report.

DEL36.PKE

Date: 8/15/05

Project: DEL-36-9.75 Stream name: DELAWARE RUN Location: DELAWARE/OSTRANDER QUADS

Geographic region = A

tributing drainage area = 8.85 square miles (5667 acres) 1 1-channel slope = (956 ft - 893 ft)/(0.75 \* (7.10 miles))Storage area = 0.53%

Recurrence	Regression
Interval	Estimate
(Years)	(cfs)
2	417
5	681
10	873
25	1120
50	1310
100	1510

Warning: The regression equations used by this program tend to overestimate peak discharges for basins having approximately 30 percent or more surface-mined area. For more information, refer to page 15 of the reference report.

Streamstats Report



# **Streamflow Statistics Report**

Date: Mon May 3 2010 08:23:32

Site Location: Ohio Latitude: 40.2994 Longitude: -83.0749 Drainage Area: 9.24 mi2

Latitude (NAD83): 40.2994 (40 17 57) Longitude (NAD83): -83.0749 (-83 04 29)

Peak Flow Basin Characteristics			
100% Peak Flow Full Model (9.24 mi2)			
Parameter	Value	Min	Max
Drainage Area (square miles)	9.24	0.01	7422
Ohio Region C Indicator 1 if in C else 0 (dimensionless)	0	0	1
Ohio Region A Indicator 1 if in A else 0 (dimensionless)	1	0	1
Stream Slope 10 and 85 Longest Flow Path (feet per mi)	10.6	1.53	674
Percent Storage from NLCD (percent)	0.91	0	25.8

100% Low Flow Lattitude LE 41.2 (9.24 mi2)			
Parameter Parameter	Value	Min	Max
Drainage Area (square miles)	9.24	0.12	7422
Percent Forest (percent)	13.1	0	99.1
Percent Storage from NLCD (percent)	0.91	0	19
Mean Annual Precipitation (inches)	36.4	34	43.2
Streamflow Variability Index (dimensionless)	0.7	0.25	1.13
Latitude of Basin Centroid (decimal degrees)	40.3257	38.68	41.2
Longitude of Basin Centroid (decimal degrees)	83.1138	80.53	84.6

Streamflow Sta	atistics				
	2	Prediction Error	Equivalent	90-Percent Pred	ction Interval
Statistic	Flow (ft <sup>3</sup> /s)	(percent)	years of record	Minimum	Maximum
PK2	484	37	2.1	268	874
PK5	781	35	3.3	449	1360
PK10	991	34	4.4	571	1720
PK25	1250	35	5.9	714	2210


Streamstats Report

Page 2 of 2

PK50	1450	37	6.8	811	2600
PK100	1650	38	7,5	903	3020
PK500	2110	42	8.6	1090	4100

Streamflow Sta	treamflow Statistics												
		Prediction Error	Equivalent	90-Percent Prediction Interval									
Statistic	Flow (ft <sup>3</sup> /s)	(percent)	years of record	Minimum	Maximum								
Q1	12.4	17											
Q2	14.8	12											
Q3	17.1	14											
Q4	15.4	11											
Q5	10.4	20											
Q6	6.3	27											
Q7	3.65	28											
Q8	2.12	37	~										
<b>Q</b> 9	1.31	44											
QA	8.81	11											
Q10	1.63	51											
Q11	4.4	38											
Q12	8.76	22											
QAH	0.59	66											
FPS25	7.67	29											
FPS50	2.69	40											
FPS75	0.9	48											

USGS OH StreamStats Page 1 of 1



of 98**2** (i) Page: 14 38








Soom Win	Viji Pan
Zeem in	Coons Out
Zoons in	XAM 1110 (1100)

FLOODING	SOURCE	The second secon	FLÓOD	WAY			ENT-ANNUAL TER SURFACT (FEET N.	E ELEVATION	
·	S	WIDTH	WIDTH REDUCED FROM	SECTION AREA	MEAN VILOCITY (FEET PER		willion.	MARRIE	Decrease
CROSS SECTION	DISTANCE'	(FEET)	PRIOR STUDY	(SQUARE FEET)	SECOND	REGULATORY	PUDODNAY	FEDODWAY	(FEET)
Deep Run									
A	315	23		89	8.4	777.8	777.8	777.9	0.1
B	1.120	168	}	182	4.1	807,8	807.8	807.8	0.0
C	2,380	34	•	83	9.0	x36.0	836.0	836,0	0.0
D	3.270	21	-	69	10.2	854.4	854.4	854.4	0.0
E	4,470	45	ŀ	88	7.1	884.0	884.0	884.0	0.0
F	5,140	35		114	5.0	\$97.9	897.9	898.5	0.6
G	5,270	39		82	7,0	901.1	901.1	901.1	0.0
) <del>-1</del>	5.580	30		. 79	7.3	905.6	905.6	905.7	0.3
Ī	6,435	Ai)	İ	368	1.6	922 6	922.6	923.8	0.2
1	6,715	50		282	19	922.6	932.6	922.9	0.3
Delaware Run									
A	438	67		384	5.3	\$62. <b>‡</b>	860.27	860.2	0.0
B	(3(3))	50		3-41	6.0	862.1	860.5	860.6	0.1
C	310	4()		314	6.5	865.8	863.8	863.8	0.0
D	1,355	60		4) (	5.0	863.9	863.9	864.7	0.8
100 100 100	1,730	22		253	8.1	867.3	867.3	867.8	0.5
IF	2.115	32		313	6.6	870,4	870.4	870.7	0.3
G	2,414	24		230	8,9	870.9	870.9	871.6	0.7
H	2,600	61		458	4.5	872.3	872.3	873.3	1.0
. 3	2.913	18	251×8.2	157	13.0	875.3	875.3	875.7	(),4
1	3.060	49	1	524	3.9	879.8	879.\$	\$80.3.	9.5
<u>K</u>	3,986	. 26	= 2058	251	8.3	885.9	885.9	886.9	1.0
Ĺ	4,106	29		269	7.6	1.388	888.1	888.1	0,0
M at above confluence w	1,422	52 *Basa	tien computed without	628 consideration of bod	3.3 water of feets fro	891.3 m Olentanev River	891.3	892.0	0.7
ne market de mes gefäule mitten ge.		·	CY MANAGEME				_ <del></del>		
			E COUNTY, C	FLOODWAY DATA					
- 1	Ar	MU INCOR	PORATED AF	KIBAS		DEEP RUN - DELAWARE RUN			

http://map1.msc.fema.gov/idms/IntraView.cgi?ROT=0&O X=1122&O Y=741&O ZM=0.500000&O SX=600&O SY=400&O DPI=200&O

4/13/201



HEC-RAS Plant Plan01 River: Delawre Run Reach: Reach1

Color   Colo	Reach	River Sta	Profile	Run Reach: H		W.S. Elev	Crit W.S.	E.G. Elev	E.G. Slope	Vel Chnl	Flow Area	Top Width	Froude # Chi
Pales			Lagran .	(cls)	(ft) 2°-	(h)	(ft)	(h)	(tun)	(fl/s)	(sq ft)	(ft)"	NY NY
Repert   620,000   FPMA	ach1	6350.000	Q25	1120.00	876.90	882.98		884.32	0.004833		120,71	19.91	0.66
Report   \$25,000   FEMA   200,00   \$76,00   \$86,13   \$88,00   \$0,005150   \$11,21   \$83,54   \$19,97   \$10,00   \$25   \$1120,00   \$76,80   \$83,87   \$86,66   \$0,005746   \$10,75   \$140,43   \$19,94   \$19,94   \$10,000   \$76,80   \$83,87   \$86,66   \$0,005746   \$10,75   \$140,43   \$19,94   \$19,94   \$10,000   \$76,80   \$85,85   \$83,87   \$86,66   \$0,005746   \$10,75   \$140,43   \$19,94   \$19,94   \$19,94   \$10,000   \$15,000   \$	ach 1	6350.000	Q100	1510.00	876.90	884.32		885.95	0.005025	10.24	147.39	19.94	
Resert   620,000   625	ach1	6350.000	FEMA	2058.00		886.13	• •	888.08	0.005130	11.21	183.54	19.97	0.65
Pascht   6200.000   1010	333		1-1-1-2							-			
	ach1	6300.000	025	1120.00	876.80	882.53		884.04	0.005701	9.84	113.87	19.91	0.72
Report   \$260.000   025			O100			883.87		885.66	0.005746	10.75	140.43	19.94	0.71
Report   \$260.000   025	achj	6300.000	FEMA	2058.00	876.80	885.85	883.72	887.82	0.005297.	11.32	195.05	86.65	0.66
Section   Sect									1		• • •		
Research   \$250,000   FEMA   2086,00   \$76,25   \$86,08   \$887,22   \$0,000865   \$4.99   \$661,96   \$296.00   \$120,00   \$76,10   \$81,00   \$76,10   \$81,00   \$	ach 1	6250.000	Q25	1120.00	876.25	882.35		883.73	0.005029	9.43	118.74	19.52	0.67
Figure 1   1990   199	مهنون استخطيط علي مراجع	6250:000	Q100	***********					ter or carrena to a	10.47	144.24	19.55	0.68
Reacht   SQC   ADD   DZS	the second of the second		FEMA						0.000886	G1 1 AW 19 8	661.96	296.09	0.27
Resent   420,000   0100			TARES OF										
Reach   G20 000   C100   C100   S10.00   876.10   886.09   885.41   887.11   0.00208   7.45   400.53   186.90	ach1	6200.000	O25	1120.00	876.10	881.83		883.43	0.006152	10.14	110.44	19.31	0.75
Fig. 2010   Color   FEMA   2088.00   876.10   886.45   883.17   887.11   0.002085   7.45   400.53   186.80													0.75
Probability   1576 050   125							883.17	to the second second			400.53		0.41
Reserve   6150000   DiDD.   DiDD.   DiDD.   S78.85   882.80   881.59   884.75   0.005091   11.22   134.86   19.55   Reserve   6150.000   FEMA   2058.00   875.85   884.42   882.90   886.75   0.005292   12.34   189.71   38.36   Reserve   3810.000   225   1120.00   875.60   881.42   881.42   882.76   0.005893   13.70   110.21   19.09   Reserve   6150.000   FEMA   2058.00   875.60   881.42   881.42   884.32   0.008893   13.70   110.21   19.09   Reserve   6150.000   FEMA   2058.00   875.60   882.76   886.37   882.76   886.32   0.009161   15.17   136.62   19.15   19.09   Reserve   6150.000   Cito									,				
Reserve   6150000   DiDN.   DiDN.   DiDN.   S78.85   882.80   B1.59   B84.75   DiDN.	ach 1	6150 000	IQ25	1120.00	875.85	881.56		883.16	0.004856	10.14	110.40	19.49	0.75
February		حصيب بدنند ب عثب					881.59						0.75
Reserved   120,000   120   1120,000   875,60   886,37   886,37   882,78   0.008585   1.241   90,22   19,03	Transfer or August 1971					** * * * * * ** ** **		protect of the company which is			**** *** ***********		0.75
Reach   \$10,000   \$10,000   \$10,000   \$10,000   \$75,60   \$81,42   \$81,42   \$84,53   \$0,008093   \$13,70   \$10,21   \$19,09   \$10,600   \$	4 - 00 - 1		STATE OF										
Reach   \$100,000   \$100,000   \$100,000   \$150,000   \$75,600   \$892,75   \$82,75   \$882,75   \$886,32   \$0,009151   \$15,17   \$135,62   \$19,15   \$100,000   \$150,000   \$74,30   \$892,75   \$892,75   \$892,75   \$891,71   \$0,000806   \$12,80   \$888,86   \$18,02   \$100,000   \$150,000   \$74,30   \$893,32   \$893,32   \$893,32   \$0,009175   \$13,96   \$108,17   \$18,04   \$1866,17   \$150,000   \$150,000   \$74,30   \$893,32   \$893,32   \$893,32   \$0,009175   \$13,96   \$108,17   \$18,04   \$1866,17   \$100,000   \$150,00   \$874,30   \$891,71   \$885,41   \$0,009175   \$13,96   \$108,17   \$18,04   \$1866,17   \$150,00   \$150,00   \$150,00   \$874,30   \$891,71   \$885,41   \$0,009542   \$15,43   \$133,41   \$18,07   \$1866,17   \$150,00   \$150,00   \$150,00   \$865,70   \$874,30   \$875,31   \$876,60   \$0,004617   \$9,10   \$165,93   \$26,93   \$1666,10   \$150,00   \$885,70   \$876,60   \$0,004617   \$9,10   \$165,93   \$26,93   \$1666,10	achd	6100,000	025	1120.00	875 60	880.37	880.37	882.76	0.008585	12.41	90.22	19.03	1.00
Feebra   5400,000   FEMA   2058,00   875.50   882.76   882.75   886.32   0.009161   15.17   135.62   19.15     Regish   699,096   976   1120,00   674.30   879.24   879.24   881.71   0.008806   12.80   88.86   18.02     Regish   599,090   1200   1510.00   674.30   890.32   880.32   883.34   0.009175   13.96   108.17   18.04     Regish   599,090   1200   1510.00   687.30   881.71   885.41   0.009542   15.43   133.41   18.07     Regish   590,000   1226   1120.00   686.70   874.39   876.37   0.003967   7.93   141.20   226.91     Regish   590,000   1200   1510.00   886.70   875.31   876.60   0.004617   9.10   165.93   228.93     Regish   529,000   1200   1510.00   886.70   875.31   876.60   0.004617   9.10   165.93   228.74   61.83     Regish   529,000   1200   1200   1510.00   886.70   876.76   874.79   878.20   0.004124   9.75   228.74   61.83     Regish   529,000   1200   1310.00   886.35   873.65   873.10   674.97   0.006869   9.25   121.13   30.66     Regish   529,000   1200   1310.00   886.35   874.79   876.23   0.005849   9.60   157.33   32.42     Regish   529,000   1200   1310.00   886.35   874.79   876.23   0.005849   9.60   157.33   32.42     Regish   529,000   1200   1310.00   886.35   874.59   872.71   874.54   0.009642   10.18   109.97   29.28     Regish   529,000   1200   1310.00   868.35   874.55   873.59   875.50   0.006853   9.46   159.61   33.10     Regish   516,000   1000   1310.00   868.30   877.06   877.76   877.76   0.002685   6.23   402.62   131.21     Regish   516,000   1000   1510.00   867.20   873.47   874.01   0.00238   8.04   202.20   67.09     Regish   516,000   1000   1510.00   867.20   873.48   873.87   0.001605   5.28   337.32   97.47     Regish   516,000   1000   1510.00   867.70   873.48   873.87   0.001605   5.28   337.32   97.47     Regish   500,000   1000   1510.00   866.70   873.48   873.87   0.001607   5.28   337.32   97.47     Regish   500,000   1000   1510.00   866.50   877.48   873.89   0.001301   5.28   337.12   97.47     Regish   500,000   1000   1510.00   866.50   873.4									** ******	to a state of the second part have g			1.00
Reach									per con market continues against				1.00
Reach		ERIOT (											
Reach	ach 1	6056.000	626	1120.00	874.30	879.24	879.24	881.71	0.008806	12.60	88.86	18.02	1.00
Reacht	- Lating Landson	4										A TO JOHN BERGE TO THE REPORT OF THE PARTY O	1.00
Feech													1.00
Seach   S20,000   Q100   1510.00   868.70   875.31   876.60   0.004517   9.10   165.93   26.93	7 10.5	Herend de	ASSESS.								- 17124		
Seach   S20,000   Q100   1510.00   868.70   875.31   876.60   0.004517   9.10   165.93   26.93	ach 1	5320.000	iQ25	1120.00	868.70	874.39		875.37	0.003987	7.93	141,20	26,91	0.61
February					THE RESERVE THE PERSONNEL PROPERTY IN					the sailer or service and service			0.65
Figschi   \$756,000   Q25   1120.00   868.35   873.65   873.10   674.97   0.005895   9.25   121.13   30.66     Figschi   \$256,000   FEMA   2058.00   868.35   876.86   877.81   0.002851   8.20   295.66   90.13     Figschi   \$250,000   FEMA   2058.00   868.35   876.86   877.81   0.002851   8.20   295.66   90.13     Figschi   \$200,000   Q25   1120.00   868.30   872.93   872.71   874.54   0.009542   10.18   109.97   29.28     Figschi   \$200,000   PEMA   2058.00   868.30   874.53   873.59   875.92   0.006053   9.46   159.61   33.10     Figschi   \$200,000   FEMA   2058.00   868.30   877.06   877.56   0.002056   6.23   402.62   131.21     Figschi   \$150,000   \$25   1120.00   867.20   873.47   874.01   0.002338   6.04   202.20   67.09     Figschi   \$150,000   \$150,00   867.20   873.47   874.01   0.002338   6.04   202.20   67.09     Figschi   \$150,000   \$150,00   867.20   873.47   874.01   0.002338   6.04   202.20   67.09     Figschi   \$150,000   \$100   1510.00   867.20   873.47   874.31   0.000630   4.45   595.62   155.47     Figschi   \$100,000   \$25   1120.00   866.70   873.48   873.87   0.001687   5.00   223.81   49.20     Figschi   \$100,000   \$150   1510.00   866.70   873.48   873.87   0.001687   5.00   223.81   49.20     Figschi   \$100,000   \$150   1510.00   866.70   873.48   873.87   0.001687   5.00   223.81   49.20     Figschi   \$100,000   \$150   1510.00   866.50   871.17   871.17   873.49   0.01255   4.88   324.10   96.15     Figschi   \$060,000   \$150   1510.00   866.50   872.19   872.19   875.03   0.012574   13.52   111.88   19.68     Figschi   \$060,000   \$150   1510.00   866.50   872.19   872.19   875.03   0.012574   13.52   111.88   19.68     Figschi   \$060,000   \$25   1120.00   866.50   873.48   873.48   876.98   0.013053   15.02   137.12   20.47     Figschi   \$060,000   \$25   1120.00   866.50   873.48   873.48   876.98   0.013053   15.02   137.12   20.47     Figschi   \$060,000   \$25   1120.00   866.50   873.48   873.48   876.98   0.013053   15.02   137.12   20.47     Figschi   \$060,000   \$25   1120.00   86							874.79		the of sevent construction of the sevent construction of				0.62
Search   S	10.021732	Angel Marie	LANCE OF THE STREET										
Search   Section   Secti	achd	5250.000 W	025	1120.00	868.35	873.65	873.10	674.97	0.006895	9.25	121.13	30.66	0.82
Fig.													0.77
Reach1   \$200.000   Q25   1120.00   868.30   872.93   872.71   874.54   0.009542   10.18   109.97   29.28   826.11   \$200.000   Q100   1510.00   868.30   874.53   873.59   875.92   0.006053   9.46   159.61   33.10   150.00   150.00   868.30   877.06   877.56   0.002058   6.23   402.62   131.21   150.00   868.30   877.06   877.56   0.002058   6.23   402.62   131.21   150.00   869.20   873.47   874.01   0.002338   6.04   202.20   67.09   866.51   \$155.000   Q100   1510.00   867.20   875.11   875.49   0.001301   5.28   337.32   97.47   874.01   0.002338   6.04   202.20   67.09   866.51   \$155.000   Q100   1510.00   867.20   877.19   877.43   0.000630   4.45   595.62   155.47   150.00   868.20   877.19   877.43   0.000630   4.45   595.62   155.47   150.00   866.70   875.48   873.87   0.001687   5.00   223.81   49.20   868.21   5100.000   FEMA   2058.00   866.70   875.06   875.42   0.001255   4.88   324.10   96.15   866.20   876.00   877.15   877.39   0.000630   4.20   575.98   186.23   886.21   6060.000   Q25   1120.00   866.50   871.17   871.17   873.49   0.012279   12.24   91.47   19.65   866.21   866.21   866.20   875.42   875.03   0.012574   13.52   111.68   19.68   16.623		The state of the s	FEMA						0.002851				0.55
Reach	STATE OF	<b>第111</b> 11	I COLUMN										
Reach	ach 1	5200 000	Q25	1120.00	868.30	872.93	872.71	874.54	0.009542	10.18	109.97	29.28	0.93
February			Q100:						0.006053				0.76
Reacht         \$150,000         CZ5         \$1120,00         867,20         873,47         874,01         0.002338         6.04         202,20         67,09           Reacht         \$150,000         \$000         \$1510,00         867,20         875,11         875,49         0.001301         5.28         337,32         97,47           Reacht         \$550,000         FENA         2058,00         867,20         877,19         877,43         0.000630         4.45         595,62         155,47           Reacht         \$100,000         \$25         \$120,00         866,70         873,48         873,87         0.001687         5.00         223,81         49.20           Reacht         \$100,000         \$1510,00         866,70         875,96         875,42         0.001255         4.88         324,10         96.15           Feacht         \$100,000         \$66,70         877,15         877,39         0.000630         4.20         575,98         186,23           Reacht         \$650,000         \$25         \$120,00         866,50         871,17         871,17         873,49         0.012279         \$12,24         91,47         19.65           Reacht         \$650,000         \$150,00         866,50 <td></td> <td></td> <td>FEMA</td> <td>2058.00</td> <td></td> <td>Annual Street or Personal Printers and Publishers</td> <td></td> <td>877.56</td> <td>0.002058</td> <td>6.23</td> <td>402.62</td> <td>131.21</td> <td>0.46</td>			FEMA	2058.00		Annual Street or Personal Printers and Publishers		877.56	0.002058	6.23	402.62	131.21	0.46
Reacht         \$150,000         \$150,000         \$1510,00         \$67.20         \$75.11         \$75.49         \$0.001301         \$28         \$37.32         \$97.47           \$68e011         \$550000         \$FEMA         \$2058.00         \$67.20         \$77.19         \$877.43         \$0.000630         \$4.45         \$595.62         \$155.47           \$68e011         \$100.000         \$625         \$1120.00         \$666.70         \$73.48         \$873.87         \$0.001687         \$5.00         \$223.81         \$49.20           \$68e013         \$150.000         \$66.70         \$75.96         \$875.42         \$0.001255         \$4.86         \$324.10         \$96.15           \$6e013         \$1500000         \$FEMA         \$2058.00         \$866.70         \$877.15         \$877.39         \$0.000630         \$4.20         \$75.98         \$166.23           \$6e261         \$660.000         \$025         \$1120.00         \$866.50         \$871.17         \$871.17         \$873.49         \$0.012279         \$12.24         \$91.47         \$19.65           \$6e261         \$660.000         \$665.00         \$872.19         \$872.19         \$875.00         \$0.012574         \$13.52         \$111.68         \$19.66           \$6e361         \$665.00 </td <td>201222</td> <td></td> <td>T-12-7-18</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td>· — — — — — — — — — — — — — — — — — — —</td>	201222		T-12-7-18										· — — — — — — — — — — — — — — — — — — —
Reach1   5500000   FEMA   2058.00   867.20   877.19   877.43   0.000630   4.45   595.62   155.47     Reach1   5100.000   G25   1120.00   866.70   873.48   873.87   0.001687   5.00   223.81   49.20     Reach1   5100.000   G100   1510.00   866.70   875.06   875.42   0.001255   4.88   324.10   96.15     Reach1   5100.000   FEMA   2058.00   866.70   877.15   877.39   0.000630   4.20   575.98   166.23     Reach1   5600.000   G100   1510.00   866.50   871.17   871.17   873.49   0.012279   12.24   91.47   19.65     Reach1   5050.000   G100   1510.00   866.50   872.19   872.19   875.03   0.012574   13.52   111.68   19.68     Reach1   5050.000   FEMA   2058.00   866.50   873.48   873.48   876.98   0.013053   15.02   137.12   20.47     Reach1   5050.000   O25   1120.00   865.90   870.65   870.36   872.63   0.010005   11.29   99.16   20.94     Reach1   5000.000   O25   1120.00   865.90   870.65   870.36   872.63   0.010005   11.29   99.16   20.94     Reach1   5000.000   O25   1120.00   865.90   871.74   871.34   874.12   0.010003   12.38   121.99   20.97		5150:000	Q25 1	1120.00	867.20	873.47		874.01	0.002338	6.04	202.20	67.09	0.49
Reach 5100 000 G25 1120.00 866.70 873.48 873.87 0.001687 5.00 223.81 49.20 866.70 875.06 875.42 0.001255 4.88 324.10 96.15 875.01 5100 000 FEMA 2058.00 866.70 877.15 877.39 0.000630 4.20 575.98 166.23 875.06 875.06 875.06 875.06 875.00 0.00255 4.88 324.10 96.15 877.15 877.39 0.000630 4.20 575.98 166.23 875.00 000 00000 0000 0000 0000 0000 0000	ach1	5150,000 **	Q100 :::::	1510.00	867.20	875.11		875.49	0.001301	5.28	337.32	97.47	0.38
Resolt         \$100,000         G25         1120,00         \$66,70         873,48         873,87         0.001687         5.00         223,81         49,20           Resolt         \$100,000         1510,00         866,70         875,06         875,42         0.001255         4,88         324,10         96,15           Resolt         \$100,000         FEMA         2058,00         866,70         877,15         877,39         0.000630         4,20         575,98         186,23           Resolt         \$605,009         Q25         1120,00         866,50         871,17         871,17         873,49         0.012279         12,24         91,47         19,65           Resolt         \$505,000         \$010         1510,00         866,50         872,19         872,19         875,03         0.012574         13,52         111,68         19,58           Resolt         \$6500,000         \$66,50         873,48         873,48         876,98         0.013053         15,02         137,12         20,47           Resolt         \$500,000         \$025         1120,00         865,50         870,65         870,36         872,63         0.010005         11,29         99,16         20,94           Resolt	acht - (a)	5150:000	FEMA	2058.00	867.20	877.19		877.43	0.000630	4.45	595.62	155.47	0.28
Real/11         \$100,000         \$1510,00         \$66.70         \$75.06         \$75.42         \$0.001255         \$4.88         \$324.10         \$96.15           Real/11         \$100,0000         FEMA         \$2058.00         \$66.70         \$77.15         \$77.39         \$0.000530         \$4.20         \$75.98         \$166.23           Real/11         \$605,000         \$025         \$1120.00         \$866.50         \$71.17         \$873.49         \$0.012279         \$12.24         \$91.47         \$19.65           Real/11         \$050,000         \$01.00         \$1510.00         \$866.50         \$72.19         \$75.03         \$0.012574         \$13.52         \$11.68         \$19.68           \$665.13         \$600,000         \$66.50         \$73.48         \$73.48         \$76.98         \$0.013053         \$15.02         \$137.12         \$20.47           \$62671         \$600,000         \$025         \$1120.00         \$865.50         \$70.65         \$70.36         \$872.63         \$0.010005         \$11.29         \$9.16         \$20.94           \$62671         \$500,000         \$025         \$1120.00         \$865.90         \$71.74         \$71.34         \$74.12         \$0.010003         \$12.38         \$121.99         \$20.97	100												
Réacht         5100000         FEMA         2058.00         866.70         877.15         877.39         0.000630         4.20         575.98         166.23           Réacht         6050.090         Q25         1120.00         866.50         871.17         871.17         873.49         0.012279         12.24         91.47         19.65           Réacht         5050.000         G100         1510.00         866.50         872.19         875.03         0.012574         13.52         111.68         19.68           Réacht         2058.00         866.50         873.48         873.48         876.98         0.013053         15.02         137.12         20.47           Réacht         5000.000         Q25         1120.00         865.90         870.65         870.36         872.63         0.010005         11.29         99.16         20.94           Réacht         5000.000         Q25         1510.00         865.90         871.74         871.34         874.12         0.010003         12.38         121.99         20.97	ackte it-	5400.000	G25 7	1120.00	866.70	873.48		873.87	0.001687	5.00	223.81	49.20	0.41
Reach1         5656,000         O25         1120,00         866,50         871,17         871,17         873,49         0.012279         12,24         91,47         19,65           Reach1         5050,000         O100         1510,00         866,50         872,19         872,19         875,03         0.012574         13,52         111,68         19,68           Reach1         5050,000         FEMA         2058,00         866,50         873,48         873,48         876,98         0.013053         15,02         137,12         20,47           Reach1         5000,000         Q25         1120,00         865,90         870,65         870,36         872,63         0.010005         11,29         99,16         20,94           Reach1         5000,000         Q25         1510,00         865,90         871,74         871,34         874,12         0.010003         12,38         121,99         20,97	0013	5100,000	Q100	1510.00	866.70	875.06		875.42	0.001255	4.88	324.10	96.15	0.36
Reach1         5050000         ClCD         1510.00         866.50         872.19         872.19         875.03         0.012574         13.52         111.68         19.68           Reach1         5050000         FEMA         2058.00         886.50         873.48         873.48         876.98         0.013053         15.02         137.12         20.47           Reach1         5000000         D25         1120.00         865.90         870.65         870.36         872.63         0.010005         11.29         99.16         20.94           Reach1         5000000         Q39         1510.00         865.90         871.74         871.34         874.12         0.010003         12.38         121.99         20.97	achii.	5100.000	FEMA	2058.00	866.70	877.15		877.39	0.000630	4.20	575.98	166.23	0.27
Reach1         5050000         ClCD         1510.00         866.50         872.19         872.19         875.03         0.012574         13.52         111.68         19.68           Reach1         5050000         FEMA         2058.00         886.50         873.48         873.48         876.98         0.013053         15.02         137.12         20.47           Reach1         5000000         D25         1120.00         865.90         870.65         870.36         872.63         0.010005         11.29         99.16         20.94           Reach1         5000000         Q39         1510.00         865.90         871.74         871.34         874.12         0.010003         12.38         121.99         20.97	Section 19		1:20:35										
Reacht 5050:00B FEMA 2058:00 866.50 873.48 873.48 876.98 0.013053 15.02 137.12 20.47  Reacht 5000:000 Q25 1120.00 865.90 870.65 870.36 872.63 0.010005 11.29 99.16 20.94  Reacht 5000:000 Q190 1510.00 865.90 871.74 871.34 874.12 0.010003 12.38 121.99 20.97													1.00
Reach) 5000000 Q25 1120.00 865.90 870.65 870.36 872.63 0.010005 11.29 99.16 20.94 Reach) 5000000 Q180 1510.00 865.90 871.74 871.34 874.12 0.010003 12.38 121.99 20.97	-			1510.00	866.50	872.19		875.03	0.012574	13.52	111.68	Mark at any 2 of the same to be seen	1.00
Reach 5000,000 G190 ; 5 1510.00 865.90 871.74 871.34 874.12 0.010003 12.38 121.99 20.97	achi 💝 🛚	5050:000	FEMA	2058.00	866.50	873.48	873.48	876.98	0.013053	15.02	137.12	20.47	1.00
Reach 5000-000 G180 ; 5 1510.00 865.90 871.74 871.34 874.12 0.010003 12.38 121.99 20.97	5:000	Marie Control	12038 CA										
	TO COVER THE LAND OF THE	7,00	O253	1120.00	865.90	870.65	870.36	872.63		11.29	99.18		0.91
	ach i	5000.000	Q100 t; **	1510.00	865.90	871.74	871.34		0.010003	12.38	121,99	20.97	0.90
Re301 5000 000 FEMA 2058.00 865.90 873.16 872.60 876.01 0.010005 13.55 151.91 21.01	ach1	5000.000	FEMA	2058.00	865.90	873.16	872.60	876.01	0.010005	13.55	151.91	21.01	0.89

HEC-RAS Plan: Plan02 River: Delawere Run Reach: Reach2

Reach	River Sta	Profile	Q Total	Min Ch El	W.S. Elev	Crit W.S.	E.G. Elev	E.G. Slope	Vel Chri	Flow Area	Jop Width	Froude # Chi
			(cfs)	(ft)	(ft)	(ft)	(fi)	(IVII)	(ft/s)	(sq fi)	(ft)	
Reach2	6350.000	025	1120.00	876.90	882.98		884.32	0.004833	9.28	120.71	19.91	0.66
Reach2	6350.000	O100	1510.00	876.90	884.32		885.95	0.005025	10.24	147.39	19.94	0.66
Reach2	6350.000	FEMA	2058.00	876.90	886.13		888.08	0.005130	11.21	183.54	19.97	0.65
Reach2	6300.000	025	1120.00	876.80	882.53		884.04	0.005701	9.84	113.87	19.91	0.72
Reach2	6300.000	Q100	1510.00	876.80	883.87		885.66	0.005746	10.75	140.43	19.94	
Reach2	6300.000	FÈMA	2058.00	876.80	885.85	883.72	887.82	0.005297	11.32	195.05		
Reach2	6250.000	.025	1120.00	876.25	882.35		883,73	0.005029	9.43	118.74	19.52	0.67
Reach2	6250.000	0100	1510.00	876.25	883.66	٠,	885.36	0.005313	10.47	144.24	19.55	
Reach2	6250.000	FEMA	2058.00	876.25	886.98		887.22	0.000886	4.99	661.96		form the contract of the contr
Reach2	6200.000	025	1120.00	876.10	881.83		883.43	0.006152	10.14	110.44	19.31	0.75
Reach2	6200.000	O100	1510.00	876.10	883.09		885.04	0.006420	11.22	134.60	19.34	
Reach2	6200.000	FEMA	2058.00	876.10	886.45	883.17	887.11	0.002089	7.45	400.53	***	
	0200.000		2030.00	0,0,10,	500.45	000.17	. 007.11	0.002003			100.50	0.41
Reach2	6150.000	Q25	1120.00	875.85	881.56		883.16	0.004856	10.14	110.40	19.49	0.75
Reach2	6150.000	Q100	1510.00	875.85	882.80	881.59	884.75	0.005061,	11.22	134.58		All a seminar una
Reach2	16150.000	FÉMA	2058.00	875.85	884.42	882.90	886.78	0.005229	12.34	169.71	39.36	
	6400.000	000	4400.00	075.00	000.27	880.37	100.76	nooneoel				
Reach2 Reach2	6100,000	O25 O100	1120.00 1510.00	875.60 875.60	880.37 881.42	881.42	882.76 884.33	0.008585	12.41 13.70	90.22 110.21		
Reach2	6100.000	FEMA	2058.00	875.60	882.75	882.75	886.32	0.009161	15.17	135.62	19.09 19.15	1.00 1.00
Self-unitering	P. L.			070.00		002170	000.01	4.505101	10.17	100.02	15.13	1.00
Reach2	6056.000	O25	1120.00	874.30	879.24	879.24	881.71;	0.008806	12.60	88.86	18.02	1.00
Reach2	6056.000	Q100	1510.00	874.30	880.32	880.32	883.34	0.009175	13.96	108.17	18.04	1.00
Reach2	6056:000	FEMA	2058.00	874.30	881.71	881.71	885.41	0.009542	15.43	133,41	18.07	1.00
Reach2	5320.000	O26	1120.00	868.70	874.39	<del> </del>	875.37	0.003987	7.93	141.20	26.91	0.61
Reach2	5320,000	Q100	1510.00	868.70	875.31		876.60	0.003507	9.10	165.93	26.93	0.65
Reach2		FEMA	2058.00	868.70	876.76	874.79	878.20	0.004124	9.75	228.74	61.83	0.62
- 14 mm												
Reach2	5250,000	Q25	1120.00	868.35	873.65	873.10	874.97	0.006895	9.25	121.13	30.66	0.82
Reach2	5250.000	Q100	1510.00	868.35	874.79		876.23	0.005849	9.60	157.33	32.42	0.77
Reach2	5250:000	FEMA	2058.00	868.35	876.86		877.81	0.002851	8.20	295.56	90.13	0.55
Reach2	5200.000	O25	1120.00	868.30	872.93	972.71	874.54	0.009542	10.18	109.97	29.28	0.93
Reach2	5200.000	Q100	1510.00	868.30	874.53	873.59	875.92	0.005542	9.46	159.61	33.10	
Reach2	5200.000	FEMA	2058.00	868.30	877.06		877.56	0.002058	6.23	402.62	131.21	0.46
Reach2		Q25	1120.00	867.20	873.47		874.01	0.002338	6.04	202.20	67.09	
Reach2	5150.000	Q100	1510.00	867.20	875.11		875.49	0.001301	5.28	337.32	97.47	0.38
Reach2	5150.000	FEMA.	2058.00	867.20	877.19		877.43	0.000630	4.45	595.62	155.47	0.28
Reach2	5100.000	O25	1120.00	866.70	873.48	· seriori meneral	873.87	0.001687	5.00	223.81	49.20	0.41
Reach2	5100.000	G100	1510.00	866.70	875.06		875.42	0.001255	4.88	324.10	96.15	I'm a reason was about the same of
Reach2	5100.000	FEMA	2058.00	866.70	877.15		877.39	0.000630	4.20	575.98	166.23	0.27
100000000000000000000000000000000000000	S. 22.											
		Q25 Q100	1120.00	866.50	871.17	871.17	873.49	0.012279	12.24	91.47	19.65	1.00
Reach2	5050.000 5050.000	FEMA	1510.00 2058.00	866.50 866.50	872.19 873.48	872.19 873.48	875.03 876.98	0.012574	13.52	111.68	19.68	1.00
Tracitz	TOUGH TOU	COUNT	£000.00	300.50	013.46	0/3.48	0/0.98	0.013033	15.02	137.12	20.47	1.00
Reach2.	5000.000	C)25	1120.00	865.90	870.65	870.36	872.63	0.010005	11.29	99.18	20.94	0.91
Reach2	5000.000	O100	1510.00	865.90	871.74	871.34	874.12	0.010003	12.38	121.99	20.97	0.90
		FEMA	2058.00	865.90	873.16	872.60	876.01	0.010005	13.55	151.91	21.01	0.89
THE RESERVE OF THE PARTY OF THE PARTY.	e annual services and the services of the serv					, ,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,						

Reach	River Sta	Profile	O Total	Min Ch El	W.S. Elev	Cnt W.S.	E.G. Elev	E.G. Slope . I	Vel Chnl	Flow Area	Top Width	Froude # Ch!
		T The state of	(cfs)	(ft)	(ft)	(ft):	(ft)	(ft/ft)	(ft/s)	(sq ft)	(ft)	
Reach1	6350.000	Q25	1120.00	876.90	882.98	:	884.32	0.004830,	9.28	120.73	19.91	0.66
Reach1	6350.000	Q100	1510.00	876.90	884.32		885,95	0.005025	10.24	147.39	19.94	0.66
Reach1	6350.000	FEMA	2058.00	876.90	886.04		888.03	0.005274	11.33	181.67	19.97	0,66
Reach1	6300.000	Q25	1120.00	876.80	882.54	,	884.04	0.005696	9.83	113.91	19.91	0.72
Reach1	6300:000	Q100	1510.00	876.80	883.87		885.66	0.005746	10.75.	140.43	19.94	0.71
Reach1	6300.000	FEMA	2058.00	876.80	885.57	•	887.73	0.005881	11.79	174.48	19.98	0.70
		Action of the second						The committee is				,
Reach1	6250:000	Q25	1120.00	876.25	882.35	•	883.73	0.005024	9.43	118.78	19.52	0.67
Reach1	6250.000	O100	1510.00	876.25	883.66	•	885.36	0.005313	10.47	144.24	19.55	0.68
Reach1	6250.000	FEMA	2058.00	876.25	885.33		887.43	0.005660	11.63	176.88	19.58	0.68
											,	
Reachi	6200.000	025	1120.00	876.10	881.84		883.43	0.006141	10.13	110.52	19.31	0.75
Reach1	6200.000	Q100	1510.00	876.10	883.08		885.04	0.006421	11.22	134.60	19.34	0.75
Reach1	6200.000	FEMA	2058.00	876.10	884.69		887.09	0.006752	12.42	165.66	19.37	0.75
		li de la compansión de la		24		;					1.4.2	:
Reach1	6150.000	025	1120.00	875.85	881.56	الريو بيوح	883.16	0.004856	10.14	110.40	19.49	the second second
Reach1	6150.000	Q100	1510.00	875.85	882.80	881.59	884.75	0.005061	11.22	134,57	19.55	0.75
Reach1	6150.000	FEMA	2058.00	875.85	884.39	882.90	886.78	0.005297	12.41	165.85	19.63	0.75
Réach1	6100.000	O25	1120.00	875.60	880.37,	880.37	882.76	0.008586	12.41	90.22	19.03	1.00
Reach1	6100.000	Q100	1510.00	875.60	881.42	881.42	884.33	0.008807	13.70	110,22	19.09	1.00
ReachI	6100.000	FEMA	2058.00	875.60;	882.75	882.75	886.32	0.009161	15.17	135.62	19.15	
Reach1	6056:000	Q25	1120.00	874.30	879.25	879.25	881.71	0.008806	12.60	88.86	18.02	1.00
Reach1	6056.000	Q100	1510.00	874.30	880.33	880.33	883.34	0.009100	13.92	108.49	18.04	1.00
Reacht	6056.000	FEMA .	2058.00	874.30	881.71	881.71	885.41	0.009542	15.43	133.41	18.07	
And the state of	English Areas				1							
Reach1,	5320.000	Q25	1120.00	868.70	874.41		875.38	0.003953	7.91	141.61	26.91	0.61
Reach1	5320.000	Q100	1510.00	868.70	875.37		876.63	0.004395	9.02	167.48	26.93	0.64
Reach1 🌣	5320,000	FEMA	2058.00	868.70	876.80	874.79	878.21	0.004051	9.69	230.92	62.72	0.62
							<u>.</u>					
Reach1	5250.000	025.	1120.00	868.35	873.58	873.03	874.98	0.007021	9.46	118.33	29.12	0.83
Reach1	5250,000	O300	1510.00	868.35	874.77		876.25	0.006111	9.76	154.70	32.24	0.79
Reach1	5250,000	FEMA	2058.00	868.35	876.89		877.84	0.002862	8.21	296.64	91.99	0.55
Reach1	5200,000	025	1120.00	868.30	872.93	872.71	874.54	0.009542	10.18	109.97	29.28	0.93
Reach1	5200.000	Q100	1510.00	868.30	874.53		875.92	0.006032	9.45	159.81	33.11	0.76
Reach1.07	5200,000	FEMA	2058.00	868.30	877.04		877.59	0.002216	6.45	388.75	130.97	0,48
930E (44.1.1.1	المالم المعامل والمالية	descriptions										
Reach), 🕠	5150.000:	Q25	1120.00	867.20	873.47		874.01	0.002338	6.04	202.20	67.09	0.49
Reach1	5150.000	Q100	1510.00	867.20	875.12		875.49	0.001299	5.28	337.51	97.51	
Reach1	5150.000**	FEMA	2058.00	867.20	877.20		877.44	0.000624	4.44	598.28	156.00	0.27
	900											
Reach1	5100.000	Ö25	1120.00	866.70	873.48		873.87	0.001687	5.00	223.81	49.20	
Reach!	5100.000	Q100	1510.00	866.70	875.05		875.43	0.001294	4.95	305.20	54.62	0.37
Reacht	5100.000	FEMA	2058.00	866.70	877.10		877.40	0.000745	4.54	516.13	135.49	0.29
Reacht	5050:000	O25	1120.00	866.50	871,17	871.17	873.49	0.042220	40.04	04.47	19.65	
Reach1	5050.000	Q100	1510.00	866.50	871.17	872.19	875.03	0.012279	12.24 13.52	91.47	19.68	
Reach1/	5050.000	FEMA	2058.00	866.50	872.19 873.48	872.19 873.48	876.98	0.012574	15.02		20.47	
	Nunci i versione	Caranta (Sec.	2000.00	300,001	373.40	0/3.40		0.010003	10.02	137.12	20.47	1.00
Reach1	5000.000	O25	1120.00	865.90	870.65	870.36	872.63	0.010005	11.29	99.18	20.94	0.91

1120.00

1510.00

Reach1 5000.000 C25 Reach1 5000.000 G100 Reach1 45000.000 FEMA

865.90

865.90

865.90

870.65 870.36 871.74 871.34 873.16 872.59

20.97

121.99

11.29

12.38

13.55

0.010005

0.010003

872.63

874.12

876.01

1.00

1.00

0.91

Řeách2 5000.000 Q25

Reach2# 5000.000 O100

Reach2 5000,000 FEMA

1120.00

1510.00

2058.00

870.65

871.74

873.16

865.90

865.90

865.90

870.36

871.34

872.59

872.63

874.12

876.01

0.010003

0.010020

12,38

13.55

121.99

151.84

HEC-RAS Plan: Plan 04 River: Delaware Run Reach: Reach2 Reach: River Stat : Profile O Total Min Ch El W.S. Elev Chi W.S. E.G. Elev E.G. Stope Vel Chn! Flow Area Top Width Froude # Chl. (ft) (ft) (sq ft) (ft) 882.98 6350.000 Q100 1510.00 876.90 884.32 885.95 0.005025 10.24 147.39 0.66 Reach2 876.90 886.04 888.03 0.005274 11.33 181.67 Reach2 6350.000 FEMA 0.66 6300.000 Q25 1120.00 876.80 882.54 884.04 0 005696 9.83 113.91 Reach2 6300.000 1510.00 876.80 863.87 885.66 0.005746 10.75 140.43 19.94 Reach2 6300.000 FEMA 2058.00 876.80 885.57 887.73 0.005881 11.79 174.48 Reach2 6250.000 Q25 1120.00 876.25 882.35 883.73 0.005024 9.43 118.78 6250.000 Q100 1510.00 876.25 883.66 885.36 0.005313. 10.47 144.24 19.55 0.68 Reach2 6250.000 FEMA 2058.00 876.25 885.33 887.43 0.005660 11.63 176.88 Reach2 6200,000 Q25 1120.00 876.10 881.84 883.43 0.006141 10.13 110.52 0.75 6200.000 Q100 1510.00 876.10 863.08 885.04 0.006421-11.22 134.60 19.34 0.75 Reach2 6200.000 FEMA 2058.00 875.10 884 69 887.09 0.006752 12.42 165.66 19.37 Reach2 6150,000 025 Reach2 6150,000 0100 0.75 1120.00 875.85 881.56 883.16 0.004856 10.14 110.40 19.49 1510.00 875.85 882.80 881.59 884.75 0.005061, 11.22 134.57 19.55 0.75 Reach2 6150.000 FEMA 2058.00 875.85 884.39 882.90 886.78 0.005297. 12.41, 165.85 Reach2 6100,000 025 Reach2 6100,000 Q100 1120.00 875.60 880.37 880.37 882.76 0.008586 12.41 90.22 19.03 1510.00 875.60 881.42 881.42 884.33 0.008807 13.70 110.22 19.09 Reach2 8100,000 FEMA 2058.00 875.60; 882.75 882.75 886.32 0.009161 15.17 135.62, Reach2 6056:000 025 Reach2 6056:000 0100 879.25 12.60 1120.00 874.30 879.25 881.71 1908800.0 88.86 18 02 1.00 880.33 0.009100 1510.00 874.30 880.33 883.34 13.92 108.49 18.04 1.00 Reach2 5056 000 FEMA 2058.00 874.30 881.71 881.71 885.41 0.009542 15.43 133.41; 18.07 Reach2 5320,000: 025 Reach2 5320,000 30100 Reach2 5320,000 FEMA 874.41 0.003953 141.61 1120.00 868.70 875.38 7.91 26.91 0.61 875.37 876.63 0.004395 9.02 167.48 1510.00 868.70 26.93 0.64 2058.00 868.70 876.80 874.79 878.21 0.004051 230.92 62.72 0.62 Reach2 5250 000 Q25 Reach2 5250 000 0100 873.58 873.03 874.98 0.007021 29.12 1120.00 9.46 9.76 118.33 868.35 0.83 1510.00 876.25 0.006111 154.70 868.35 874.77 32.24 0.79 Reach2: 5250:000 // FEMA 876.89 0.002862 296.64 868.35 877.84 8.21 91.99 2058.00 0.55 5200.000 868.30 872.93 872.71 1120.00 0.009542 109.97 29.28 Reach2 Reach2 22 5200,000 Q100 868.30 874.53 875.92 0.006032 9.45 1510.00 159.81 33.11 0.76 5200 000 FEMA 877.04 0.002216 130.97 2058.00 868.30 877.59 388.75 0.48 Reach2 5150,000 Q25 Reach2 5150,000 0100 1120.00 867.20 873.47 874.01 0.002338 6.04 202.20 1510.00 867.20 875.12 875.49 0.001299 5.28 337.51 97.51 2058.00 867.20 877.20 877.44 0.000624 4.44 598.28 156.00 0.27 1120.00 866 70 873.48 873.87 0.001687 5.00 223.81 49.20 0.41 Reach2 5100.000 Q100 Heach2 5100.000 FEMA 1510.00 866,70 875.05 875 43 0.001294 4.95 305.20 54.62 0.37 2058.00 866.70 877.10 877.40 0.000745 4.54 516.13 135.49 0.29 866.50 871.17 871.17 873.49 0.012279 Reach2 5050.000 Q25 1120.00 12.24 91.47 19.65 1.00 13.52 19.68 Reach2 5050,000 Q100 1510.00 866.50 872.19 872.19 875.03 0.012574 111.68 1.00 5050 000 FEMA 20.47 1.00 2058.00 866.50 873.48 873.48 876.98 0.013053 15.02 137.12

0.91

0.90

0.89

20.97

21.01

Reach	River Sta	Profile	Q Total	Min Ch El	W,S. Elev	- Cnt W.S.	E.G. Elev	E:G. Slope	Vel Chril	Flow Area	Top Width	Froude # Chi
VE THE		1	(cis)	(fi)	(ft)	(ft) j	(ft) .	(f)/ft)	(fVs)	(sq ft)	(ft)	
Reach1	6350.000	Q25	1120.00	876.90	882.42		884.04	0.006368	10.22	109.54	19.90	0.7
Reach1.	6350.000	O100	1510.00	876.90	883.68		885.63	0.006458	11.21	134.67	19.92	0.70
Reach1	635D.000	FEMA	2058.00	876.90	885.35		887.68	0.006528	12.26	167.92	19.96	0.74
Reach1	6300.000	O25	1120.00	876.57	882.12		883.72	0.006269	10.17	110.14	19.91	0.76
Reach1	6300.000	Q100	1510.00	876.57	883.36		885.31	0.006429	11.19	134.88	19.93	0.70
Reach1	6300.000	FEMA	2058.00	876.57	885.02		887.35	0.006523	12.25	167.96	19.97	0.7
Reach1	6250,000	Q25	1120,00	876.25	881.24.	880.93	883.31	0.008953	11.55	97.00	19.50	0.9
Reach1 **	6250.000	Q100	1510.00	876.25	882.51	881.96	884.90	0.008496	12.39.	121.86	19.53,	0.8
Reach1	6250,000	FEMA	2058.00	876.25	884.22		886.95	0.008068	13.26	155.22	19.56	0.83
Reach1	6200.000	O25	1120.00	875.75	880.74	880.46	882.85	0.009194	11.67	95.95	19.30	0.9
Reach1	6200.000	Q100	1510.00	875.75	882.09	881.50	884.47	0.008407	12.36	122.20	19.32	0.87
Reach1	6200.000	FEMA	2058.00	875.75	883.83		886.54	0.007987	13.22	155.73	19.36	0.82
Reach1	6150.000	O25	1120.00	875.25	880.54		882.40	0.006058	10.96	102.17	19.45	0.8
Réach1.	6150.000	Q100	1510.00	875.25	881.92		884,05	0.005670	11.69	129.21	19.51	0.80
Reach1	6150.000	FEMA	2058.00	875.25	883.67		886.13	0.005525	12.60	163.31	19.60	0.7
reach1	6100.000	Q25	1120.00	874.75	880.34	879.52	882.08	0.005449	10.59	105.75	19.05	0.79
keach1	6100.000	O100	1510.00	874.75	881.71	880.57	883.74	0.005322	11.44	131.96	19.11	0.7
(éach1	6100.000	FEMA	2058.00	874.75	883,43	881.90	885.85	0.005382	12.49	164.81	19.19	0.7
Reach1	6056.000	025	1120.00	874.30	879.25	879.25	881.71	0.008805	12.60	88.87	18,02	1.00
Reach1.	6056.000	0100	1510.00	874.30	880.32	880.32	883.34	0.009175	13.96	108.17	18.04	1.00
Reach1	6056.000	FEMA	2058.00	874,30	881.71	881.71	885.41	0.009542	15.43	133.41	18.07	1.00
Reach1	5320.000	025	1120.00	868.70	874.28		875.30	0.004252	8.11	138.16	26.91	0.63
teach 1.	5320.000	Q100	1510.00	868.70	875.17		876.52	0.004836	9,32	162.07	26.93	0.67
Reachi	15320.000	FEMA	2058.00	868.70	876.53	874.79	878.11	0.004628	10.16	215.18	55.92	0.66
englass.		Jan Salva V			***************************************							OF CONTROLS A WAR
teach 1, a	5250.000	025	1120.00	868.20	872.98	872.91	874.79	0.010028	10.77	103.96	27.59	0.96
Reach)	5250.000	Q100	1510.00	868.20	874.43		876.08	0.007089	10.31	146.44	31.34	0.84
teach1	5250 000	FEMA	2058.00	868.20	876.59		877.69	0.003384	8.74	272.53	86.51	0.60
reach111	5200.000	Q25	1120.00	867.70	873.04		874.22	0.006009	8.71	128.57	29.99	0.74
each1	5200.000	Q100	1510.00	867.70	874.48	873.04	875.65	0.004654	8.67	174.17	33.18	0.67
each1	5200.000	FEMA	2058.00	867.70	876.81		877.40	0.002251	6.64	374.42	124.85	0.48
each1.3	(6150.000	Q25	1120.00	867.20	873.22		873.85	0.002835	6.46	186.16	62.52	0.5
Reach1	5)60 000	Q100	1510.00	867.20	874.88		875.31	0.001531	5.61	314.52	93.05	0.41
each1	5150.000	FEMA	2058.00	867.20	876.98		877.24	0.000716	4.67	563.44	148.89	0.2
each1	\$100,000	Q25	1120.00	866.70	873.24		873.68	0.001958	5.28	212.28	48.38	0.44
leach1	5100.000	Q100	1510.00	866.70	874.81		875.23	0.001455	5.16	292.55	53.81	0.39
leach1	5100:000	FEMA	2058.00	866.70	876.86		877.20	0.000860	4.78	484.03	129.48	0.3
leach1	5050:000	C25	1120.00	866.30	871.06	870.97	873.30	0.011628	12.02	93.20	19.65	0.9
each1	5050:000	Q100°	1510.00	866.30	872.12	871.99	874.84	0.011843	13.24	114.06	19.67	0.9
each1	5050.000	FEMA	2058.00	866.30	873.52	873.26	876.79	0.011901	14.53	141.72	20.63	0.9
each1	5000 000	O25	1120.00	865.90	870.82	870.36	872.67	0.009005	10.89	102.83	20,95	0.87
each4	5000.000	0100	1510.00	865.90	871.96	871.34	874.17	0.009001	11.93	126.59	20.98	0.8
and the second second	4000.000	EENAA	2058.00	926.00	973 44	972 BD	978.00	0.000004	13.04	157 79	21.01	

876.09 0.009004

157.78

0.86 0.84

865.90

873.44

872.60

2058.00

Reach1 15000.000 FEMA

HEC-RAS Plan: Plan 06 River: Delaware Run Reach: Reach2 
 Beach
 River Sta
 Profile
 O Total
 Min Ch El.
 WS. Elev
 Crit W.S.
 E.G. Elev
 E.G. Slope
 Vel Chnl
 Flow Area
 Top Width
 Froude # Chl

 (cfs)
 (ft)
 (ft)
 (ft)
 (ft)
 (ft)
 (ft/45)
 (ft/45)
 (ft/5)
 (ft)
 1120.00 10.22 109.54 Reach2 6350.000 1510.00 876.90 883.68 885.63 0.006458 11.21 134.67 19.92 0.76 Reach2 885.35 887.68 0.006528 12.26 167.92 19.96 0.74 Reach2 Reach2 1120.00 876.57 882.12 883.72 0.006269 10.17 110 14 19 91 0.76 Reach2 1510.00 876.57 883.36 885.31 0.006429 11.19 134.88 19.93 0.76 876.57 885.02 887.35 0.006523 12.25 167.96 19.97 0.74 6300.000 Reach2 11.55 97.00 1120.00 876.25 881.24 880.93 883.31 0.008953 19.50 0.91 6250.000 1510.00 876.25 882.51 881.96 884.90 0.008496 12.39 121,86 19.53 0.87 Reach2 2058.00 876.25 884.22 886.95 0.008068 13.26 155.22 19.56 0.83 6250.000 Reach2 11.67 6200.000 1120.00 875.75 880.74 880.46 882.85 0.009194 95.95 19.30 0.92 Reach2 6200.000 Q100 1510.00 875.75 882.09 881.50 884.47 0.008407 12.36 122.20 19.32 0.87 Reach2 6200.000 FEMA 2058.00 875.75 883.83 886.54 0.007987 13.22 155.73 19.36 0.82 882.40 0.006058 10.96 102.17 19.45 6150.000 O25 1120.00 875.25 880.54 0.84 11.69 6150.000 Q100 1510.00 875.25 881.92 884.05: 0.005670 129.21 19.51 0.80 Reach2 6150:000 FEMA 2058.00 875.25 883.67 886.13 0.005525 12.60 163.31: 19.60 0.77 10.59 882.08 0.005449 0.79 6100.000 Q25, 879.52 105.75 19.05 1120.00 874.75 880.34 11.44 0.77 Reach2: 6100.000 Q100 1510.00 874.75 881.71 880.57 883.74 0.005322 131.96 19.11: 0.75 0.005382 12.49 Reach2 6100.000 FEMA 2058.00 874.75 883.43 881.90 885.85 164.81 19.19 Reach2 6856.000 Q25 Reach2 6056.000 Q100 12.60 1.00 18.02 1120.00 874.30 879.25 879.25 881.71 0.008805 88.87 13.96 1.00 883.34 0.009175 108,17 18.04 1510.00 874.30 880.32 880.32 881.71 885.41 0.009542 15.43 133.41 18.07 1.00 Reach2: 6056:000 FEMA 2058.00 874.30 881.71 Reach2 5320 000 Q25 875.30 0.63 874.28 0.004252 8.11 138,16 26.91 1120 009 868.70 876.52 0.004836 9.32 162.07 0.67 875.17 868.70 Reach2 5320,000 Q100 1510.00 874.79 10.16 0.66 878.11 0.004628 215.18 55.92 Reack2 5320.000 FEMA 876.53 2058.00 868.70 0.010028 Reach2 5250.000 Q25 872.91. 10.77 103.96 872.98 1120.00 868.20 Reach2 874.43 876.0B 146.44 31.34 0.84 5250.000 \Q100 1510.00 868.20 877.69 0.003384 8.74 272.53 0.60 868,20 876.59 Reach2 2058.00 5250,000 FEMA 873.04 874.22 8.71 128.57 Reach2 5200.000 Q25 1120.00 1510.00 875.65 0.004654 8.67 174.17 33.18 0.67 Reach2 5200.000 Reach2 ( 5200:000 FEMA 867.70 876.81 877.40 0.002251 6.64 374.42 124.85 0.48 2058.00 Reach2 5150.000 Q25 867.20 873.22 873.85 0.002835 6.46 186.16 62.52 0.53 Reach2 5150:000 Q100 1510.00 867.20 874.88 875.31 0.001531 5.61 314.52 93.05 0.41 Reach2 - 5150.000 FEMA 2058.00 867.20 876.98 877.24 0.000716 4.67 563,44 148,89 0.29 Reach2 5100.000 Q25 0.001958 873.66 1120.00 866.70 873.24 212.28 0.39 875.23 0.001455 5.16 292.55 53.81 Reach2 5100.000 Q100 1510.00 866.70 874.81 4.78 0.31 877.20 484.03 129.48 Reach2' 5300.000 FEMA 2058.00 866.70 876.86 0.000860 Reach2 5050 000 025 873.30 870.97 1120.00 866.30 871.06 0.97 872.12 871.99 874.84 0.011843 13.24 114.06 19.67 Reach2 - 15050,000 Q100 1510.00 865.30 0.95 873.26 876.79 Reach2 5050 000 FEMA 2058.00 866,30 873.52 
 Reach2
 5000.006
 Q25

 Reach2
 5000.000
 Q100

 Reach2
 5000.000
 FEMA
 865.90 870.82 870.36 872.67 0.87

1120.00

1510.00

2058.00

865.90

871.96

871.34

874.17

11.93

126.59

0.86

HEC-RAS Plan: Plan07 River: Delaware Run Reach: Reach2 Reach River Sta | Profile | O Joial | Min Ch El W.S. Elev | Crit W.S. | E.G. Elev | E.G. Slope | Vel Chril | Flow Area | Top Width | Froude # Chi (ft) (ft) · (ft) (ft) 134.16 6350.000 0.003591 6350.000 0100 1510.00 876.90 885.35 886.61 0.003509 8.99 168.01 19.96 0.55 6350.000 FEMA 2058.00 876-90 888.31 0.004597 10.76 191.21 19.98 Reach2 6300,000 025 1120.00 876.57 883.53 884.55 0.003305 8.10 138.20 19 94 0.54 Reach2 6300.000 0100 1510.00 876.57 885.22 886.42 0.003289 8.78 172.06 19.97 0.53 Reach2 6300,000 FEMA 2058.00 876.57 886.33 888.07 0.004415 10.60 194.10 19.99 0.60 Reach2 6250.000 025 1120.00 876.25 883.37 884.38 0.003267 8.08 138.54 10.54 0.54 Reach2 6250.000 0100 1510.00 876.25 885.05 886.25 0.003313. 8.81 171.47 19.58 0.52 Reach2 6250.000 FEMA 2058.00 876.25 886.03 883.27 887.84 0.004634: 10.80 190.60 19.60 0.61 7.72 Reach2 6200 000 O25 1120.00 875.75 883 27 884.20 0.002875 145.03 19 35 0.50 Reach2 6200.000 O100 1510.00 875.75 884.95 886.07 0.003023 B.51 177.39 19.38 0.50 Reach2 6200,000 FEMA 2058.00 875,75 885.86 882.81 887.59 0.004358 10.55 195.07 19.40 0.59 Reach2. 6150.000 Q25 1120.00 884.05 0.001890 7.23 154.90 19.58 875.25 883.24 0.45 Reach2 Reach2 6150.000 Q100 1510.00 875.25 884.91 885.91 0.002047 8.05 187.61 19 66 0.46 6150,000 FEMA 2058.00: 875.25 885.79 882.30 887.36 0.003001 10.04 205.07 19.70 0.55 Reach2 6100.000 Q25 1120.00 874.75 874.75 19.18 0.001720 160.23 0.43 883.19 883.95 6.99 Reach2 6100.000 Q100 Reach2 6100.000 FEMA 1510.00 884.84 885.80 0.001926 7.87 191.97 19.26 0.44 881.92 874.75 887.20 9.88 33.08 2058.00 885.68 0.002874 208.74 0.53 Réačh2 5056.000 025 Reach2 5056.000 0100 18.10 874.30 874.30 874.30 1120.00 883.09 879.25 883.87. 0.001780 7.08 158.27 0.42 1510.00 884.74 880.32 7.95 7.33 99.93 885,71 0.001952; 205,84 0.43 Reach2 6056.000 FEMA 2058.00 886.20 886.85 0.001393 476.62 311.77 0.38 Reach2 5588 Reach2 5320,000 Q25 Culvert ..... 874.28 875.30 0.004252 8.11 138.16 26.91 1120.00 868.70 0.63 Resch2 5320,000 Q100 Reach2 5320,000 FEMA 1510.00 868.70 875.17 876.52 0.004836 9.32 162.07 26.93 0.67 868.70 874.79 2058.00 0.004628 55.92 0.66 876.53 878.11 10.16 215.18 Reach2 5250.000 025 Reach2 5250.000 0100 868.20 872.91 0.98 872.98 874.79 103.96 1510.00 868.20 876.08 0.007089 146.44 0.84 reach2 5250,000 FEMA 2058.00 868.20 877.69 0.003384 8.74 272.53 0.60 876.59 Reach2 5200.000 Q25 0.74 1120.00 867.70 29.99 873.04 874.22 0.006009 8 71 128.57 5200,000 Q100 5200,000 FEMA 1510.00 867.70 874.48 873.04 875.65 0.004654 8.67 174.17 33.18 0.67 Reach2 ... 2058.00 867,70 876.81 877.40 0.002251 6.64 374.42 124.85 Reach2: 5150,000 aC25 1120.00 867.20 0.53 873.22 873.85 0.002835 6.46 186.16 62.52 Reach2 5150:000 G100 Reach2 5150:000 FEMA 1510 00 867.20 874.88 875.31 0.001531 5.61 314 52 93.05 0.41 2058.00 867.20 876.98 877.24 0.000716 4.67 563.44 148.89 0.29 Reach2 5100:000 025 Reach2 5100:000 0100 Reach2 5100:000 FEMA 1120.00 212.28 873.24 0.44 866.70 873.68 0.001958 5.28 48.38 866.70 866.70 875.23 1510.00 0.001455 874.81 5.16 4.78 292.55 53.81 0.39 484.03 129.48 2058.00 876.86 877.20 0.000860 0.31

871.06

872,12

873.52

871.96

1510.00

2058.00

1120.00

1510.00

866.30

866.30

865.90

870.97

871.99

873.26

870.36

871.35

873.30

0.011842

0.011901

874.84

876.79

872.67

874.17

12.02

13.24

14.53

114.07

102.83

19.67

20.63

0.97

0.97

0.95

0.86

Reach2 5050.000 025

Reach2: 5050,000 0100 Reach2: 5050,000 FEMA

5000.000

5000.000

Q100

Reach2 Reach2 Reach2

Reach	River S	ta Profile	Q Total	Min Ch El	W.S. Elev	Crit W.S.	E.G. Elev	E.G. Slope	Vel Chri	Flow Area	Top Width	Froude # Ch!
	Aliasi.		(cfs)	(ft)	(ft)	(fl)	(ft)	(ft/ft)	(fVs)	(sq.ft)	(fi)	
Reach2	6350.000	FEMA	2058.00	876.90	886.72		888.44	0.004342	10.54	195.33	19.98	0.59
Reach2	6300,000	PEMA	2058.00	876.57	886.55		888.22	0.004159	10.37	198.50	20.00	0.58
Reach2	6250.000	FEMA	2058.00	876.25	866.28	883.27	888.00	0.004319	10.52	195.66	28.30	0.59
Reach2	6200,000	FEMA	2058-00	875.75	886.12	882.81	887.76	0.004060	10.28	200.28	23.71	0.56
Reach2	6150.000	FEMA	2058.00	875.25	886.16	882.30	887.52	0.002566	9.48	258.42	200.94	0.51
Reach2	6100.000	FEMA	2058.00	874.75	885.95	881.92	887.38	0.002621	9.60	224.30	80.26	0.51
Reach2	6056:000	FEMA	2058.00	874.30	886.59	881 71	887.01	0.000955	6.21	605.21	337.64	0.31
Reach2	5688		Culvert									
Reach2	5320.000	FEMA	2058-00	868.70	876.81	874.79	878.22	0.004033	9.68	231.48	62.95	0.62
Reach2	5250.000	FEMA	2058.00	868.20	876.93		877.84	0.002711	8.05	303.08	92.75	0.54
Reach2	5200.000	FEMA	2058.00	867.70	877.12		877.60	0.001801	6.05	414.87	132.27	0.43
Reach2	5150.000	FEMA	2058.00	867.20	877.24		877.47	0.000610	4.40	604.03	157.14	0.27
Reach2	5100.000	FEMA	2058.00	866.70	877.14		877.43	0.000728	4.51	521.39	136.45	0.29
Reach2	5050.000	FEMA .	2058.00	866.30	874.97		877.16	0.006666	11.95	176.93	27.90	0.72
Reach2	5000.000	FEMA	2058.00	865.90	875.30	872.61,	876.67	0.003793	9.72	264.97	139.15	0.56

Profile O Total Min.Ch.El W.S. Elev Crit W.S. E.G. Elev E.G. Slope Vel Chnl Flow Area Top Width Froude # Chl (ft/ft) (fi/s) (cfs) ...(fi) (ft) (ft) (ft) (ft) 6350.000 0.003604 6350.000 1510.00 876.90 885.35 886.60 0.003516 8.99 167.90 19.96 6350.000 2058.00 876.90 688.30 0.004622 10.78 190.82 19.98 6300.000 1120.00 876.57 883.52 884.54 0.003317 8.12 138.01 19.94 0.54 Reach2 6300.000 Q100 1510.00 876.57 885.22 886.41 0.003295 8.78 171,94 19.97 0.53 6300.000 FEMA 2058.00 876.57 886.31 888.06 0.004440 10.63 193.69 19.99 Reach2 6250.000 1120.00 876.25 883.36 884.37 0.003280 8.10 138.35 19.54 0.54 6250.000 1510.00 876.25 885.04 886.25 0.003320 8.81 171.34 19.58 0.52 6250.000 2058.00 876.25 886.00 883.27 887.82 0.004663 10.82 190.16 19.60 0.61 7.73 Reach2 6200.000 Q25 1120.00 875.75 883.26 884.19 0.002886 144.82 19.35 0.50 Reach2 6200.000 Q100 1510.00 875.75 884.94 886.07 0.003028 8.52 177.27 19.38 0.50 Reach2 6200,000 FEMA 2058.00 875.75 885.83 882.81 887.57 0.004386 10.58, 194.60 19.39 0.59 884.04 19.58 Reach2 6150:000 O25 1120.00 875.25 883.23 0.001897 7.24 154.69 0.45 Reach2 6150.000 Q100 1510.00: 875.25 884.90 885.91 0.002051 8.05 187.48 19.66 0.46 Reach2 6150.000 FEMA 882.30 2058.00 875.25 885.77 887.34 0.003020 10.06 204.58 19.70. 0.55 0.43 Reach2 6100 000 Q25 1120.00 0.001726 160.02 874.75 883.18 883.94 7.00! 19,18 Reach2 874.75 6100:000 - 10100 1510.00<sup>1</sup> B84.83 885.79 0.001930 7.87 191.84 19.26 0.44 Reach2 6100,000 FEMA 881.92 2058.00 874.75 885.65 887.18 0.002897 9.91 207.93 28.59 0.53 18.10 Reach2 6056.000 1120.00 874.30 883.08 879.25 883.86 0.001786 7.09 158.07 0.42 Reach2 ... 6056.000 Q100 1510.00 874.30 884.73 880.32 0.001959 7.96 204.97 885.71 98.25 0.44 2058.00 Reach2 6056.000 FEMA 874.30 886:15 881.71 886.84 0.001455 7.47 462.05 308.70 0.38 ..... Reach2 5688 Culver . ... .. ... . . . Reach23 5320,000 1120.00 868.70 874.28 26.91 0.63 875.30 0.004252 138.16 Reach2 5320,000 Q100 Reach2 5320,000 FEMA 1510.00 868.70 875.17 876.52 0.004836 0.67 9.32 162.07 26.93 2058.00 868.70 874.79 878.11 876.53 0.004628 55.92 0.66 10.16 215.18 Reach2 , 5250:000 1120.00 868.20 872.98 874.79 103.96 27.59 0.98 872.91 0.010028 Reach2 5250.000 Q100 Reach2 5250.000 FEMA 868.20 874.43 10.31 0.84 2058.00 868.20 877.69 0.003384 8.74 272.53 0.60 876.59 86.51 Reach2 5200,000 Q25 Reach2 5200,000 Q100 874.22 1120.00 867.70 873.04 0.006009 128.57 29.99 1510.00 867.70 874.48 873.04 875.65 0.004654 8.67 174.17 0.67 0.48 Beach2 3 5200.008 - FEMA 2058.00 867.70 876.81 0.002251 6.64 374.42 124.85 Reach2 5150,000 025 0.53 1120.00 867,20 873.22 873.85 0.002835 6.46 186,16 62,52 Reach2 5150.000 Q100 Reach2 5150.000 FEMA 1510.00 867.20 874.88 875,31 0.001531 5.61 314.52 93.05 0.41 5150 000 FEMA 2058.00 867.20 876.98 877.24 0.000716 4.67 563.44 148.89 0.29 Beach2 5100 000 × Q25 1120.00 873.24 873.68 0.001958 212.28 48.38 0.44 Reach? 5100,000 G100 Reach? 5100,000 FEMA 866.70 5.28 866.70 1510.00 874.B1 875.23 0.001455 292.55 53.81 0.39 0.31 2058.00 866.70 876.86 877.20 0.000860 4.78 484.03 129.48 Reach2 5050 000 Q25 871.06 870.97 873.30 19.65 0.97 0.011628 12.02 93.20 Reach2 5050,000 0100/ Reach2 5050,000 FEMA 866.30 874.84 1510.00 872.12 871.99 0.011842 13.24 114.07 19.67 0.97 2058.00 866.30 873.52 873.26 876.79 0.011901 14.53 141.72 20,63 0.95 Reach2 5000.000 Q25 1120.00 5000.000 0100 5000.000 FEMA 1510.00 865.90 871.96 871.35 874.17 0.009001 128.59 0.86

HEC-RAS Plan: Plan 10 River: Delaware Run Reach; Reach2 Profile: FEMA

Reach	River Sta	Profile	Q Total	Min Ch El	W.S. Elev.	Cnt W.S.	E.G. Elev	E.G. Slope	INT. THE OR OLD THE WAY PROPERTY !	Flow Area	and the second section of the second section of the	Service State of Other services and the services
	11. A.		(cfs)	(ft)	(ħ)	(ft)	(ft)	(tvti)	(fVs)	(sq fi)	(ft)	
Reach2	6350.000	FEMA	2058.00	876.90	886.63		888.39	0.004452	10.64	193.51	19.98	0.60
Reach2	630D.000	FEMA	2058.00	876.57	886.45		888.15	0.004269	10.47	196.56	19.99	0.59
Reach2	6250.000	FEMA	2058.00	876.25	886.17	883.27	887.93	0.004455	10.64	193.43	19.60	0.60
Reach2	6200.000	FEMA	2058.00	875.75	686.01	882.81	887.69	0.004188	10.39	198.02	19.40	0.57
Reach2	6150.000	FEMA	2058.00	875.25	885.96	882.30	887.47	0.002838	9.85	220,77	187.62	0.53
Reach2	6100:000	FEMA	2058.00	874.75	885.85	881.92	887.32	0.002715	9.71	217.14	63.09	0.52
Reach2	6056.000	FEMA	2058.00	874.30	886.47	881.71	886.95	0.001078	6.55	563.49	329.47	0.33
Reach2	5688		Culvert									
Reach2	5320.000	FEMA	2058.00	868.70	876.81	874.79	878.22	0.004033	9.68	231.48	62.95	0.62
Reach2	5250.000	FEMA	2058.00	868.20	876.93		877.84	0.002711	8.05	303.08	92.75	0.54
Reach2	5200.000	FEMA	2058.00	867.70	877, 12		877.60	0.001801	6.05	414.87	132.27	0.43
Reach2	5150.000	FEMA :	2058.00	867.20.	877.24	1	877.47	0.000610	4,40	604.03	157.14	0.27
Reach2	5100.000	FEMA	2058.00	866.70	877.14		877.43	0.000728	4.51	521.39	136.45	0.29
Reach2	5050,000	FEMA	2058.00	866.30	874.97		877.16	0.006666	11.95	176.93	27.90	0.72
Reach2	5000.000	FEMA	2058.00	865.90	875.30	872.61	876.67	0.003793	9.72	264.97	139.15	0.56