

# Structure Foundation Exploration

## Brent Spence Bridge Replacement

Interstate 71/Interstate 75

Cincinnati, Ohio/Covington, Kentucky

Project No. N1105070

March 11, 2011



### Prepared for:

Parsons Brinckerhoff, Inc.  
Cincinnati, Ohio

### Prepared by:



Cincinnati, Ohio

Offices Nationwide  
Employee-Owned

Established in 1965  
terracon.com

# Terracon

Geotechnical   ■   Environmental   ■   Construction Materials   ■   Facilities

March 11, 2011



Parsons Brinckerhoff  
312 Elm Street, Suite 2500  
Cincinnati, Ohio 45202

Attn: Mr. Duane F. Phelps, P.E.  
P: 513-639-2138  
F: 513-421-1040  
E: phelpsd@pbworld.com

**Re: Geotechnical Engineering Report  
Proposed Brent Spence Bridge Replacement  
Interstate 71/Interstate 75 Corridor  
Cincinnati, Ohio- Covington, Kentucky  
HCN/Terracon Project No.: N1105070**

Dear Mr. Phelps:

H.C. Nutting, a Terracon Company (HCN) has completed the geotechnical engineering services for the above referenced project. This report presents the findings of the subsurface exploration and provides geotechnical and foundation recommendations regarding the proposed Brent Spence Bridge Replacement project.

We appreciate the opportunity to be of service to you on this exciting project. If you have any questions concerning this report, or if we may be of further service, please contact us.

Sincerely,  
**H.C. Nutting, a Terracon Company**

A blue ink signature of David W. Westendorf.

David W. Westendorf, P.E.  
Senior Staff Geotechnical Engineer

A blue ink signature of Aaron J. Muck.

Aaron J. Muck, P.E.  
Senior Associate/Department Manager

A blue ink signature of Swaminathan Srinivasan.  

Swaminathan Srinivasan, P.E.  
Senior Vice President/Division Manager



H.C. Nutting, a Terracon Company 611 Lunken Park Drive Cincinnati, Ohio 45226  
P [513] 321 5816 F [513] 321 0294 www.terracon.com

Geotechnical

Environmental

Construction Materials

Facilities

## TABLE OF CONTENTS

	Page
<b>EXECUTIVE SUMMARY</b> .....	<b>i</b>
<b>ACRONYMS</b> .....	<b>ii</b>
<b>1.0 INTRODUCTION</b> .....	<b>1</b>
<b>2.0 GEOLOGY AND OBSERVATIONS</b> .....	<b>2</b>
2.1 General Overburden Geology of Southwest Ohio/Northern Kentucky .....	3
2.2 General Bedrock Geology of Southwest Ohio/Northern Kentucky .....	4
2.3 General Seismic Geology of Project Area .....	4
<b>3.0 EXPLORATION</b> .....	<b>6</b>
3.1 Test Borings .....	6
3.2 Geophysical Testing .....	8
3.3 Environmental Screening .....	9
3.4 Laboratory Testing .....	9
3.5 Previous Geotechnical Studies .....	10
<b>4.0 FINDINGS</b> .....	<b>11</b>
4.1 Ohio- Land Borings (L-1, L-1A, L-2, L-2A, L-3, and L-3A) .....	11
4.2 River Borings (R-1, R-2, R-2A, R-3, R-4, R-5, R-6, R-7, R-8) .....	15
4.3 Kentucky- Land Borings (L-4, L-5, L-6, L-7) .....	18
4.4 Groundwater .....	22
4.5 Shear Wave Velocity Profiles .....	23
4.6 Previous Geotechnical Studies .....	23
<b>5.0 ANALYSIS AND RECOMMENDATIONS</b> .....	<b>24</b>
5.1 Foundation Discussion .....	24
5.2 Drilled Shafts .....	25
5.2.1 Design Parameters .....	26
5.2.1.1 Axial Loading .....	26
5.2.1.2 Group Effects – Axial Loading .....	29
5.2.1.3 Group Effects – Lateral Loading .....	30
5.2.1.4 Uplift Design .....	30
5.2.1.5 Downdrag .....	31
5.2.2 Scour Considerations .....	31
5.2.3 Drilled Shaft- Cofferdams .....	31
5.2.4 Drilled Shaft – Construction Considerations .....	32
5.2.4.1 General Discussion .....	32
5.2.4.2 Drilled Shaft Installation .....	32
5.2.4.3 Rock Socket Sidewall Disturbance .....	36
5.2.4.4 Additional Comments/Considerations .....	36
5.2.5 Drilled Shaft – Quality Control .....	36
5.2.5.1 Integrity Testing .....	37
5.2.5.2 Load Testing .....	37
5.3 Driven Piles .....	39

5.3.1 Driven Piles- Design.....	39
5.3.2 Construction Considerations .....	41
5.4 Seismic Considerations .....	42
5.4.1 Essential Structure Parameters.....	43
5.4.2 Critical Structure Parameters .....	44
<b>6.0 GENERAL COMMENTS .....</b>	<b>45</b>

**Appendix A – Field Exploration**

Exhibit A-1	Site Vicinity Map
Exhibit A-2	Test Boring Location Plan
Exhibit A-3	Geotechnical Summary Sheet- Ohio - Land
Exhibit A-4	Geotechnical Summary Sheet- Ohio - River
Exhibit A-5	Geotechnical Summary Sheet- Kentucky- River
Exhibit A-6	Geotechnical Summary Sheet- Kentucky- Land
Exhibit A-7	Subsurface Profile
Boring Logs/Photos	Test Boring Logs L-1 to L-7, L-1A, L-3A, R-1 to R-8, R-2A and Rock Core Photographs
Exhibit A-8	Existing Brent Spence Bridge Test Boring Logs (1958)
Exhibit A-9	Queensgate Alignment Test Boring Logs (2007)
Exhibit A-10	Environmental Screening Results
Exhibit A-11	GeoVision Suspension Logging Report
Exhibit A-12	Photo Science Geospatial Solutions Report

**Appendix B – Laboratory Testing**

Exhibit B-1	Laboratory Test Results (Sieve, Hydrometer, Atterberg Limits, Moisture)
Exhibit B-2	Triaxial Testing Results
Exhibit B-3	Consolidation Testing Results
Exhibit B-4	Unconfined Compressive Strength Testing Results & Figures
Exhibit B-5	Point Load Testing Results
Exhibit B-6	Elastic Modulus Testing Results
Exhibit B-7	Slake Durability Testing Results

**Appendix C – Supporting Documents**

Exhibit C-1	ODOT Classification
Exhibit C-2	Drilled Shaft Base & Shaft Resistance Calculations
Exhibit C-3	Driven Pile Calculations (DRIVEN & GRLWEAP)

## EXECUTIVE SUMMARY

This summary should be used in conjunction with the entire report for design purposes. It should be recognized that details were not included or fully developed in this section, and the report must be read in its entirety for a comprehensive understanding of the items contained herein. The following provides a brief summary of our exploration, findings, and recommendations.

- This report is intended for use in the bridge foundations only. Grading and earthwork related issues, roadway and embankment design/construction have not been finalized and are not discussed in this report.
- Nineteen (19) test borings were performed for the project; nine (9) test borings were performed in the river with the remaining borings performed on land in Ohio and Kentucky. All borings extended to bedrock with approximately 40 to 80 feet of rock coring performed at each location. The test borings encountered primarily granular overburden soils (both fill and natural) overlying limestone and shale bedrock.
- Geophysical testing consisting of PS Suspension Logging was performed in three (3) of the test borings (L-1, L-4, R-2A) by GeoVision Geophysical Services. The purpose of the geophysical testing was to acquire site specific shear wave velocities and compressional wave velocities as a function of depth to aid in seismic design.
- Given the subsurface conditions and the preliminary design plans provided by Parsons Brinckerhoff, drilled shafts are indicated for the bridge pier foundations. Driven (CIP) piles, H-piles, and drilled shafts could be considered for the approach spans and abutments located on land. Design parameters for drilled shafts and driven piles are provided.
- Several types of cofferdams (if needed) could be considered for the proposed construction; braced, cellular, or double-walled sheet piles. The designer should consider hydrostatic, soil, current, waves, and ice load as well as construction loading. Accidental loading, such as due to a ship strike, and seismic loading may also need to be considered.
- Quality control is critical to the success of the deep foundation system performance. Quality control of drilled shafts can be divided into three categories; diligent inspection, integrity testing and load testing. Besides installation quality control, we recommend both integrity and load testing be included in the specifications for the proposed bridge foundations.

This summary should be used in conjunction with the entire report for design purposes. It should be recognized that details were not included or fully developed in this section, and the report must be read in its entirety for a comprehensive understanding of the items contained herein. The section titled **GENERAL COMMENTS** should be read for an understanding of the report limitations.

## Geotechnical Engineering Report

Brent Spence Bridge Replacement ■ Cincinnati, Ohio-Covington, Kentucky

March 11, 2011 ■ HCN/Terracon Project No. N1105070



## ACRONYMS

AASHTO – American Association of State Highway Transportation Officials

ATH – Ambient Temperature Headspace

BSB – Brent Spence Bridge

CEUS – Central and Eastern U.S. Seismic Zone

CIP - Cast-in-place concrete piles

CSL – Crosshole Sonic Logging

CT – Crosshole tomography

DHC – Downhole Camera

FHWA – Federal Highway Administration

FID – Flame ionization detector

GGL - Gamma-Gamma logging

KYTC – Kentucky Transportation Cabinet

LRFD – Load and Resistance Factor Design

NHI – National Highway Institute

ODOT – Ohio Department of Transportation

PB- Parsons Brinckerhoff

PSI – Photo Science, Inc.

REC - Recovery

RMR – Rock mass rating

RQD - Rock Quality Designation

RTK – Real time kinematics

SDI – Slake Durability Index

SID – Shaft Inspection Device

SPT – Standard Penetration Test

USGS – U.S. Geological Survey

VOC – Volatile organic compounds

WOH – Weight of hammer

**GEOTECHNICAL ENGINEERING REPORT  
BRENT SPENCE BRIDGE REPLACEMENT  
INTERSTATE 71 / INTERSTATE 75  
CINCINNATI, OHIO-COVINGTON, KENTUCKY  
Terracon Project No. N1105070  
March 11, 2011**

## **1.0 INTRODUCTION**

A geotechnical study has been performed for the proposed Brent Spence Bridge (BSB) replacement project by H.C. Nutting, a Terracon Company (HCN) in support of the ongoing design efforts by Parsons Brinckerhoff (PB), the Kentucky Transportation Cabinet (KYTC), and the Ohio Department of Transportation (ODOT). This report includes a description of the field activities, a summary of the encountered subsurface conditions, laboratory test results, and foundation recommendations, along with construction considerations and recommended quality control testing during the project construction phase. Exhibit A-1 in the Appendix provides a general overview map of the project location.

Nineteen (19) test borings were performed for the project; nine (9) test borings were performed in the river with the remaining borings performed on land in Ohio and Kentucky. Each of the test borings was extended to bedrock with approximately 40 to 80 feet of rock coring being performed at each location. Limited environmental screening was performed on soil samples during drilling activities. Shear wave velocity testing was completed at three (3) locations, one (1) within the Ohio River and the remaining two (2) on land. The Suspension P-S velocity logging method was used to measure the seismic wave velocity profiles.

Two (2) previous geotechnical reports were performed by HCN for the BSB replacement project; the 2005 Red Flag study and the 2007 Queensgate alignment study. Six (6) borings were performed as part of the 2007 study. In addition, HCN performed 12 borings for the existing bridge in 1958. These borings have been reviewed as part of this study and have been included in the Appendix.

The existing Brent Spence Bridge links Cincinnati, Ohio and Covington, Kentucky and carries Interstate 75 and Interstate 71 traffic over the Ohio River. The proposed replacement bridge will be located immediately west (downriver) of the existing bridge. At the time this report is being published, three (3) alternatives are being considered for the proposed replacement bridge. The alternatives consist of a tied arch bridge (alternative 1), a two tower cable-stayed bridge (alternative 3), and a single tower cable-stayed bridge (alternative 6). All three (3) alternatives have a main span length of 1,000 to 1,023 feet with the main span piers located near each shore. The roadway will consist of a double-deck truss with six (6) lanes of traffic in each direction as well as shoulders.



Drilled shaft foundations with pier caps extending from the mud line to the waterline are proposed for the bridge replacement. The preliminary drawings provided by PB indicate that minimum 8-foot diameter drilled shafts are anticipated. The following table summarizes the proposed bridge foundations.

**Table 1, Summary of Proposed Bridge Types**

<b>Bridge Alternative</b>	<b>River Pier Cap Length (feet)</b>	<b>River Pier Cap Width (feet)</b>	<b>Drilled Shaft Spacing (feet)</b>	<b>Number of Drilled Shafts</b>
Tied Arch (Alt. 1)	328	88	24	52
Two Tower Cable-Stayed (Alt. 3)	236	116	20	72
Single Tower Cable-Stayed (Alt. 6)	356	136	20	126

This report focuses on bridge foundations only. Final grading schemes and alignments have not been finalized during this phase of study. Therefore, grading and earthwork related recommendations, along with roadway and embankment design and construction considerations are not discussed further in this report

The following sections include a description of the geology, field activities, encountered subsurface conditions, laboratory test results, and recommendations for drilled pier and driven pile capacities/construction/quality control for the proposed bridge.

## **2.0 GEOLOGY AND OBSERVATIONS**

Currently, the proposed bridge alignment is occupied by a Duke Energy Facility and Substation on the Ohio side of the river. The riverbank is brush and tree covered and relatively steep (approximately 1.5 to 2H:1V). The Kentucky riverbank, also brush and tree covered, extends gradually up from the river's edge to the toe of the levee protecting Covington, Kentucky. On the southern side of the levee, the area is occupied by several small businesses and parking lots.

An overview of the geology in the project area is briefly described below. The subject area lies near the southern extent of the historic glacial progression/regression, which has resulted in a notably variable geology across the region. The general overburden geology is discussed, followed by the bedrock geology in the region. An overview of the seismic geology of the region is also provided. The geology of the region is based on various published and on-line resources and maps, in conjunction with our experience in the general project area.



## **2.1 General Overburden Geology of Southwest Ohio/Northern Kentucky**

An estimated two million years before present time, the first major ice sheet arrived in Southwest Ohio and Northern Kentucky. At the time, the northwesterly-flowing Teays River flowed across West Virginia and entered Ohio near Portsmouth. This ancestral river occurred along with several tributaries, including the north-flowing Licking River. The valleys at that time were only about 150 feet deep, compared with 400 feet deep today.

Between an estimated 1.2 and 2 million years ago, the Kansan and Nebraskan glaciers advanced into Cincinnati and the Northern Kentucky area. At that time, the north-flowing Teays Age Licking River was dammed by the snout of the glacial ice, resulting in deposition of lake clays within the valleys. The base elevation of the lake-filled valley was about elevation 650 feet.

In time, the lake waters rose and eventually overflowed a divide near Madison, Indiana. The glacial meltwaters caused elevated water flow through the new drainage system westward, near Hamilton, Ohio and southwesterly toward Ross and Harrison, Ohio, Lawrenceburg, Indiana, and on to Louisville, Kentucky. The water flow eroded a deep and wide channel, termed the Deep Stage Ohio. The valley bottom was deepened well below today's Ohio, Little Miami, and Great Miami Rivers to about elevation 380 feet.

The Teays Age Licking River abandoned its former course and shifted somewhat westerly, cutting its Deep Stage valley where the present day Licking River occurs. However, in Deep Stage time, the Licking River did not terminate at its present day mouth location. Instead, it continued northerly across the basin of present day downtown Cincinnati, west of Great American Ball Park and northward to what is now called the Mill Creek Valley to join the Deep Stage Ohio River near Norwood, Ohio.

The Illinoian Age glacier then advanced into southwest Ohio about 400,000 years ago. This glacier did not reach Northern Kentucky. The ice dammed the north flowing Deep Stage Ohio River, forming a lake, which extended towards Portsmouth and well into the Deep Stage Licking valley to the south. The resulting deposition above the valley bottom consisted of Deep Stage gravels topped by Illinoian lakebed silts and clays. The lake filled and eventually spilled over directly west from Cincinnati. A new valley was now cut through Anderson Ferry, Saylor Park, and on to North Bend, Ohio. This process created the present day course of the Ohio River. Also occurring at this time, the Illinoian glacier continued to creep southwesterly and deposited till on top of the lake clays.

Over the next 300,000 years, well after the Illinoian glacier retreated, extensive weathering and erosion took place. New valleys were carved by streams, within the partially filled former valleys. The last glacial advance began about 70,000 years ago. This glacier, called the

## Geotechnical Engineering Report

Brent Spence Bridge Replacement ■ Cincinnati, Ohio-Covington, Kentucky

March 11, 2011 ■ HCN/Terracon Project No. N1105070



Wisconsin glacier, retreated slightly and then re-advanced into Northern Hamilton County, Ohio about 18,000 years ago. This glacier left till and then granular outwash from its meltwaters. Subsequent stream erosion has cut terraces into this outwash along many of the valleys.

## 2.2 General Bedrock Geology of Southwest Ohio/Northern Kentucky

During the Ordovician Period (444 to 448 million years ago), Southwest Ohio, Northern Kentucky and Eastern Indiana was largely covered with a shallow saltwater sea. This environment encouraged the growth of organisms and the precipitation of calcium carbonate that became the dominant source of the calcareous material in the deposits along the sea floor. In the Late Ordovician Period, collisions of eastern North America with ancestral Europe, Africa, and South America caused an upward bulge of the area and formed what is known as the Cincinnati Arch. The Cincinnati Arch is a gentle, wide structure with bedrock inclinations typically less than 1 degree.

Primarily two formations of bedrock are located within the limits of the project and the maximum depth explored; the lower portions of the Point Pleasant Formation and the upper portions of the Lexington Limestone Formation. The Point Pleasant Formation, deposited during the Middle Ordovician, is approximately 90 to 110 feet thick with an upper elevation of approximately 420 feet in Southwestern Ohio. The Point Pleasant Formation consists of interbedded dark argillaceous limestone, brown to black calcareous shales and fossiliferous layers. The amount of limestone increases with depth in this formation. The Point Pleasant Formation is typically more thickly bedded than the underlying Lexington Limestone Formation and contains appreciably more shale.

The Point Pleasant is underlain by the Lexington Limestone, deposited in the Middle Ordovician, which is approximately 100 feet thick in the Tri-State region. The Lexington Limestone is generally light- to medium-gray limestone. Fossiliferous and argillaceous seams are encountered throughout the formation. Interbeds of shale are encountered in this formation, primarily in the upper portions of the formation.

## 2.3 General Seismic Geology of Project Area

Plate tectonic theories do not adequately explain the mechanisms associated with intra-plate earthquakes such as those which occur in this area. To our knowledge, there are no mapped faults within the project site area. Further, there are no mapped faults which have experienced surface displacement due to seismic activity during the Holocene Epoch (past 11,000 years) within 100 miles of the project site. The closest mapped fault with such movement is the New Madrid Seismic Zone, which is about 200 miles southwest of the site.

A preliminary seismic hazard analysis was performed for the proposed bridge corridor. The steps for the analysis generally include the identification of the seismic sources capable of

## Geotechnical Engineering Report

Brent Spence Bridge Replacement ■ Cincinnati, Ohio-Covington, Kentucky

March 11, 2011 ■ HCN/Terracon Project No. N1105070



strong motions at the project site, evaluation of the seismic potential for each capable source, and evaluation of the intensity of the design ground motions at the project site.

For this preliminary analysis, the evaluation of the intensity of ground motions was accomplished using U.S. Geological Survey (USGS) published information regarding the seismic hazard for the Central and Eastern United States. This information for the project site is strongly influenced by the New Madrid Seismic Zone in southeastern Missouri. To a lesser degree, historical local seismicity of Ohio, Kentucky and Indiana contribute to the seismic hazard as well. The USGS Internet website seismic hazard mapping tools were used to estimate the potential ground motions for the project site corridor. For the purposes of this analysis, the design event evaluated was an earthquake whose ground motions have a 2 percent probability of exceedance in 50 years (equivalent to a 10 percent probability of exceedance in 250 years, or a recurrence interval of 2475 years). This is consistent with the classification of the Brent Spence Bridge as a “critical structure.”

The USGS mapping evaluation uses a database that considers the contribution of all recorded earthquakes that may influence the project site area. The coordinates at the Ohio River were entered to obtain peak ground accelerations and spectral accelerations at the soil-bedrock interface. The following table summarizes the information obtained for each of the locations for the design event:

**Table 2, Preliminary Seismic Hazard Data – Ohio River**

Criteria	Accel (g)	Site-Source Mean Event		Site-Source Modal Event		Relative Contribution		CEUS Source Mean Event	
		M	D (km)	M	D (km)	NMSZ (%)	CEUS (%)	M	D (km)
PGA	0.080	6.21	150	7.7	455	14	86	5.94	100
0.2 sec SA	0.179	6.42	183	7.7	455	18	82	6.13	125
0.3 sec SA	0.156	6.73	237	7.7	455	28	72	6.33	150
1.0 sec SA	0.076	7.25	357	7.7	455	51	48	6.74	240

Notes: Accel.=acceleration value, M=earthquake magnitude, D=distance, NMSZ= New Madrid Seismic Zone, CEUS=Central and Eastern US Seismic Zone, PGA = peak ground accelerations, SA = spectral accelerations

The primary conclusions that may be derived from the information presented above are:

- The relative contribution of the New Madrid Seismic Zone is limited except for the spectral accelerations predicted at a period of 1.0 second.
- The relative contribution of the random seismicity of the Central and Eastern U.S. Seismic Zone (CEUS) appear to be higher for spectral accelerations at the other selected periods and for the peak ground acceleration.

These observations suggest that seismic site response analyses should be performed using a series of several time histories that represent the smaller magnitude earthquakes of the CEUS and at least one time history that represents the New Madrid Zone event.

## **3.0 EXPLORATION**

The exploration performed for this study consisted of a geotechnical test boring program. The test borings were supplemented by environmental screening during our drilling activities at each of the test boring locations and geophysical testing at three (3) selected test boring locations. In addition, the collected soil and rock core samples were subjected to an extensive laboratory testing program, which is further discussed below.

### **3.1 Test Borings**

Nineteen (19) soil borings were performed for this project. Nine (9) of the borings were performed within the Ohio River (R-1 to R-8), six (6) were performed on land in Ohio (L-1 to L-3A), and the remaining four (4) on land in Kentucky (L-4 to L-7). See Exhibit A-2 in the Appendix for a boring location plan.

The boring locations were laid out on-site by PhotoScience Geospatial Solutions. Based on a summary report (Exhibit A-12) provided by PhotoScience Geospatial Solutions, a two-person RTK (real time kinematics) GPS crew was mobilized to the site. The crew was equipped with dual-frequency Trimble 5700 Base, Trimble R8 Rover GPS units, and Trimble TRIMMARK 3 Radio, to establish horizontal and vertical control values for the boring locations. The crew used BSB/PSI's control monuments 11 and 12 as base known positions. Both RTK and traditional surveying techniques were used in locating the borings. Each of the river borings were located with a TOPCON GTS223 Total Station by making use of two control points set by RTK near the river's edge. The elevation of the top of the barge was recorded for each of the river borings. When allowable, boring locations on land were located by direct RTK occupation. If the boring location wasn't suitable for direct occupation, a pair of control points were established nearby and then located with the total station.

The borings were drilled with truck and ATV-mounted rotary drill rigs using continuous flight hollow-stem augers to advance the boreholes. The drill rig was placed on a barge to drill the borings located within the Ohio River. The barge was anchored at the boring locations using spuds located at the barge corners. Barge coordination and permitting was performed by HCN. Samples of the soil encountered in the borings were obtained using the split-barrel sampling procedures. Relatively undisturbed samples were obtained by pushing Shelby Tubes into primarily cohesive soils.

## Geotechnical Engineering Report

Brent Spence Bridge Replacement ■ Cincinnati, Ohio-Covington, Kentucky

March 11, 2011 ■ HCN/Terracon Project No. N1105070



In the split barrel sampling procedure, the number of blows required to advance a standard 2 inch O.D. split barrel sampler the last 12 inches of the typical total 18 inch penetration by means of a rope and cathead manual safety hammer with a free fall of 30 inches, is the standard penetration resistance value (SPT-N). For this project, a calibrated automatic SPT hammer was used to advance the split-barrel sampler in the borings performed on this site. A greater efficiency is typically achieved with the automatic hammer compared to the conventional safety hammer operated with a cathead and rope. This SPT N-value is used to estimate the in-situ relative density of cohesionless soils and consistency of cohesive soils.

Published correlations between the SPT values and soil properties are based on the lower efficiency cathead and rope method. This higher efficiency affects the standard penetration resistance blow count (N) value by generally increasing the penetration per hammer blow over what would be obtained by using the cathead and rope method. The effect of the automatic hammer's efficiency has been considered for the test boring performed.  $N_{60}$  values have been provided on the boring logs.

Rock coring was performed using wireline NQ and HQ size, double-tube core barrels per ASTM D2113. Water was added during coring to cool the bit and clear the cuttings. The rock coring was performed to explore the characteristics and quality of the bedrock. Recovery (REC) and rock quality designation (RQD) values were measured in the field and confirmed in the laboratory for each core run. Recovery is the length of core recovered as a percentage of the core run. RQD is the sum of pieces of solid core that are 4 inches or longer in length measured along the centerline of the core, divided by the length of the core run. Rock core fractures and breaks due to rock coring and retrieval methods were not included in the determination of RQD. Following the measurement of the recovery and RQD, the samples were placed in wooden boxes and wrapped with plastic and aluminum foil to help maintain the integrity and natural moisture content. Photographs were taken of the rock core in the laboratory and have been included in the Appendix following each boring log.

The soil samples were tagged for identification, sealed to reduce moisture loss, and taken to our laboratory for further examination, testing, and classification. Information provided on the boring logs attached to this report includes soil descriptions, consistency evaluations, boring depths, sampling intervals, and groundwater conditions. The borings were backfilled with cement-bentonite grout prior to the drill crew leaving the site.

A field log of each boring was prepared by the drill crew. These logs included visual classifications of the materials encountered during drilling as well as the driller's interpretation of the subsurface conditions between samples. Final boring logs included with this report represent the engineer's review of obtained soil samples, driller's field logs, and include modifications based on laboratory tests of the samples.

All borings were backfilled after their completion and patched at surface (if located within the existing paved areas). Excess auger cuttings were disposed of on the site. The borings were

backfilled with a bentonite-cement grout. Details of the backfill materials are included on each boring log.

### **3.2 Geophysical Testing**

Geophysical testing consisting of PS Suspension Logging was performed in three (3) of the test borings (L-1, L-4, R-2A) by GeoVision Geophysical Services. The borings were cored a minimum of an additional 15 feet and cased with 3-inch-diameter PVC pipe for the geophysical testing. Installation of the casing at R-2A encountered an obstruction along the sidewall at 139 feet, which was approximately 50 feet above the total boring depth. The casing was abandoned and grouted in place. The river location was grouted below the mudline and then broken off.

The purpose of the geophysical testing was to acquire compressional (P) wave velocities and shear wave ( $S_H$ ) velocities as a function of depth. In geophysical testing, a dynamic or vibratory force applied to soil or rock results in wave propagation outward from the source in all directions through that soil and/or rock. In general, three wave types are generated in soil and rock (compressional, shear and Rayleigh waves). A P-wave is a dilational wave that displaces soil or rock particles parallel to the direction of the wavefront and has the highest velocity of the three wave types. An  $S_H$ -wave is a distortional wave that displaces soil or rock particles perpendicular to the direction of the wavefront and has a relatively lower wave velocity as compared to the P-wave. For the purposes of this study, the Rayleigh wave is not relevant.

Suspension soil velocity measurements were performed in all borings using the PS suspension logging system, manufactured by OYO Corporation. This system directly determines the average velocity of a 3.3-foot-high segment of the soil column surrounding the boring of interest by measuring the elapsed time between arrivals of a wave propagating upward through the soil column. The receivers that detect the wave, and the source that generates the wave, are moved as a unit in the boring producing relatively constant amplitude signals at all depths.

The entire probe is suspended in the boring by the cable, therefore, source motion is not coupled directly to the borehole walls; rather, the source motion creates a horizontally propagating impulsive pressure wave in the fluid filling in the boring and surrounding the source. This pressure wave is converted to P- and  $S_H$ -waves in the surrounding soil and rock as it impinges upon the wall of the boring. These waves propagate through the soil and rock surrounding the boring, causing pressure waves to be generated in the fluid surrounding the receivers as the soil waves pass their location.

At each measurement depth the measurement sequence of two opposite horizontal records and one vertical record was performed, and the gains were adjusted as required. The data from each depth were viewed on the computer display, checked, and recorded on disk before moving to the next depth.

## Geotechnical Engineering Report

Brent Spence Bridge Replacement ■ Cincinnati, Ohio-Covington, Kentucky

March 11, 2011 ■ HCN/Terracon Project No. N1105070



Following data collection, the data was analyzed by GeoVision using the program PSLOG and the results were plotted in Excel. The results of the analysis and further details on the testing and analysis are included in the GeoVision report provided in the Appendix (Exhibit A-11).

### 3.3 Environmental Screening

All samples were screened for volatile organic vapors associated with petroleum products using the Ambient Temperature Headspace (ATH) method. Screening of soil samples was performed with a Foxboro Toxic Vapor Analyzer (TVA) 1000B flame ionization detector (FID). Vapors are measured as present in the soil sample jar head space, which may be a different concentration than the concentration measured in the soil. The FID yields readings of ionizable vapors in parts per million vapor by volume (ppm v/v) present in the soil relative to ambient air and the calibration gas (methane in air). The FID was factory calibrated to methane in air.

The ATH screening method consists of splitting a soil sample and placing it into new, clean jars with lids. One of the split soil samples from each sampling interval is vigorously shaken to aid in releasing organic compounds and allowed to stabilize. The lid of the sample jar is slightly opened, and the organic vapors in the headspace of the sample jar are then screened with the FID. In the event that FID readings above detection limits were observed, an activated charcoal filter tip fitted to the FID was used to screen the soil samples a second time to identify and quantify the presence of ionizable methane and ethane. Methane and ethane are naturally occurring soil gases typically resulting from the decay of organic matter within the soils. FID readings obtained with the charcoal filter tip represent readings of ionizable methane and/or ethane in ppm v/v. A summary of the screening results is provided in Exhibit A-10 in the Appendix.

In summary, elevated readings, particularly in the river borings, generally appeared to be attributable to the presence of methane and organics. However, elevated readings occurring in fill materials are likely partially attributable to something else. The significance of any of the elevated readings is not really determinable at this point since chemical analysis of the collected samples was not performed and is beyond our scope. Based on the overall field screening readings, visual observations, and general lack of odors, it appears unlikely that the samples at the test boring locations are significantly environmentally impacted. It should be noted however, that the presence of heavy metals cannot be determined unless further environmentally-specific exploration and analysis is performed.

### 3.4 Laboratory Testing

Selected samples were tested in the laboratory to evaluate the engineering properties of the soil and rock. Laboratory testing included:

## Geotechnical Engineering Report

Brent Spence Bridge Replacement ■ Cincinnati, Ohio-Covington, Kentucky  
March 11, 2011 ■ HCN/Terracon Project No. N1105070



- Soil Samples
  - Natural Moisture Content (T265/D2216)
  - Atterberg (Liquid/Plastic) Limits (T89/T90/D4318)
  - Organic Content/Loss-on-Ignition (T267/D2974)
  - Sieve/Hydrometer Analysis (T88/D422)
  - Consolidation Testing (T216/D2435)
  - Triaxial Testing (T296/D2850)
- Bedrock Samples
  - Unconfined Compressive Strength (D7012 Method C)
  - Elastic Modulus (D7012 Method D)
  - Point Load Strength (D5731)
  - Slake Durability Index (D4644)

A factory-calibrated hand penetrometer was used to estimate the approximate unconfined compressive strength of cohesive soil samples. The calibrated hand penetrometer has been correlated with unconfined compression tests and provides a better estimate of soil consistency than visual examination alone. The elastic modulus testing was performed by the Earth Mechanics Institute and the Colorado School of Mines. The remaining soil and rock testing was performed by HCN.

Descriptive classifications of the soil and rock are indicated on the boring logs and are in accordance with ODOT Specifications for Geotechnical Explorations (SGE). Classification was performed by both visual examination and laboratory test results. The test results are provided on the boring logs and included in summary tables in Appendix B of this report.

### 3.5 Previous Geotechnical Studies

Two (2) previous geotechnical reports were performed by H.C. Nutting for the Brent Spence Bridge replacement project; the 2005 Red Flag Study and the 2007 Queensgate alignment study. No borings were performed for the Red Flag Study. Six (6) borings were performed as part of the 2007 study along the proposed Queensgate alignment located approximately 800 to 1200 feet west of the existing bridge. Borings for this study were performed in Kentucky, Ohio, and the Ohio River. The borings ranged in depth from 75 to 121 feet with a minimum of 45 feet of rock core performed at each location. Limited environmental screening was performed at the time of drilling. The boring location plan and boring logs from these borings have been included in Appendix A of this report.

In addition to the 2007 borings, HCN performed 12 borings for the existing Brent Spence Bridge in 1958. Two (2) borings were performed at each abutment in Ohio and Kentucky. Four (4) borings were performed at each pier location in the river. The borings ranged in depth from 79 to 116.5 feet. Rock coring was performed at each of the eight (8) borings located in the river. The boring logs and location plan have been included in Appendix A of this report.



## **4.0 FINDINGS**

In general the test borings encountered primarily granular soils (both fill and natural) overlying limestone and shale bedrock. The proposed bridge project has been separated into four (4) segments for this report: 1) Ohio-Land, 2) Ohio-River, 3) Kentucky-River, and 4) Kentucky-Land. Due to the generally similar materials encountered in the river borings, the Ohio and Kentucky sides have combined in this section. Detailed borings logs and photographs of the rock core, as well as geotechnical summary sheets (Exhibits A-3 to A-6), are included in the Appendix. The following sections provide generalized descriptions for each area of the project.

### **4.1 Ohio- Land Borings (L-1, L-1A, L-2, L-2A, L-3, and L-3A)**

#### ***Existing Fill***

Vacuum extraction was performed in the upper 4 to 10 feet of each boring in this area to expose possible existing utility conflicts with the test borings. Below the vacuum excavation, existing fill was encountered in the test borings. The fill material consisted of silt, sandy silt, sand, sand and gravel, and rock fragments (A-4b, A-4a, A-3, A-3a, A-1-b, and A-1-a). Variable amounts of brick fragments, concrete, cinders, and occasional organics (topsoil, wood/fibrous material, and/or decayed matter) were observed in the fill materials. Boring L-2 also includes A-6(b) and A-7-6 fill soils. The thickness of fill ranged from approximately 5 feet in L-1 to 60 feet in L-2 near the bank of the Ohio River. It is our understanding that the existing fill in the Duke Energy property is known to be environmentally impacted and will be remediated in-place or excavated and replaced. The areal extent and depth of the removal is unknown at this time.

The consistency of the existing fill ranged from very soft to soft for the cohesive fill and very loose to loose for the granular fill. Blow counts (N-values) in the existing fill ranged from weight-of-hammer (WOH) to as high as 53 blows per foot (bpf). The average N-value was 11 bpf in the fill. N-values in the fill may not be representative of the actual density/stiffness due to obstructions and its non-uniform composition. Moisture contents of both predominantly cohesive and granular materials varied greatly in the fill, ranging from 9% to 65%.

#### ***Natural Overburden Soils***

Cohesive soils were encountered in the upper portions of the overburden in this area. The cohesive soils consisted primarily of silt with occasional clay and silt layers. A large percentage of sand and gravel was also present in these soils. The cohesive overburden soils were generally medium stiff to stiff in consistency. Underlying the natural cohesive soils, the overburden soils consisted primarily of gravel and stone fragments with sand, sandy silt, silt, and fine sand (A-1-a, A-1-b, A-4a, A-4b, and A-3). These soils were deposited as alluvial soils by the Ohio River, and as glacial outwash in the deeper profile. The consistency of the overburden soils was generally loose to dense with occasional very loose or very dense zones. Typically, the overburden soils became increasingly dense with depth. Blow counts in the overburden soils varied from WOH to over 100 bpf, with an average N-value of 36. The higher

## Geotechnical Engineering Report

Brent Spence Bridge Replacement ■ Cincinnati, Ohio-Covington, Kentucky

March 11, 2011 ■ HCN/Terracon Project No. N1105070



blow counts were encountered just above the bedrock surface or in zones with higher percentages of gravel and rock fragments. Cobbles, boulders, and large rock fragments are likely to be encountered erratically throughout the natural soils and in particular just above the bedrock surface.

### **Bedrock**

Bedrock was encountered in this area at an average elevation of 371 feet. A summary of the depth to bedrock in the test borings is provided in the following table.

**Table 3, Summary of Encountered Bedrock – Ohio Land**

Test Boring	Surface Elevation (ft.)	Approximate River Depth (ft.)	Approximate Depth to Bedrock (ft.) <sup>(1)</sup>	Approximate Bedrock Elevation (ft.) <sup>(2)</sup>
L-1	493.5	-	127.0	366.5
L-1A	491.5	-	121.0	370.5
L-2	496.3	-	115.0	381.3
L-2A	494.5	-	128.5	366.0
L-3	458.7	15.0	88.2	370.5
L-3A	496.1	-	125.0	371.1

(1) The depth to rock indicated in this table is for estimation purposes. Actual depth to rock may vary, as determined by construction conditions and as approved by the engineer based on the encountered field conditions.

(2) Up to 15 feet of variation in the bedrock elevation was observed. We recommend additional test borings be performed during the project design and construction phases to better define the rock surface.

The bedrock consisted primarily of limestone and shale. Interbedded limestone and shale was also encountered primarily in the upper portions of the bedrock. The percentage of limestone in the interbedded zones ranged from approximately 70% to 80%. The percentage of limestone typically increased with depth which is consistent with the gradual transition from the Point Pleasant Formation, which has as much as 50% shale, to the Lexington Limestone Formation, which is primarily limestone. Fossiliferous and argillaceous limestone seams were noted in the bedrock. The thickness of shale seams/layers in the interbedded limestone and shale ranged from approximately 8 inches to less than ¼ inch. Limestone layers ranged from thin partings to 3 feet in thickness, with a typical thickness of approximately 3 to 6 inches.

Rock Quality Designation (RQD) values for the Ohio-Land borings averaged 46% with values generally increasing with depth (see Figure 1). The RQD values ranged from 0% to 100%. The Recovery (REC) values ranged from 40% to 100%, with an average of 97%. The measured RQD and recovery values are summarized in the figure below.

# Geotechnical Engineering Report

Brent Spence Bridge Replacement ■ Cincinnati, Ohio-Covington, Kentucky

March 11, 2011 ■ HCN/Terracon Project No. N1105070




Figure 1, Bedrock RQD/REC Summary – Ohio Land

The overall average unconfined compressive strength ( $q_u$ ) was 10,938 pounds per square inch (psi) for the Ohio-Land portion. Lower values were seen in samples with shale and argillaceous limestone seams while the higher values were measured in predominately limestone samples. Additionally, lower strength values were observed in the shale samples with generally high moisture contents (See Figure 3). Elastic modulus testing was also performed on select limestone samples. An average elastic modulus of 8,608 kips per square inch (ksi) was observed in this testing (see Exhibit B-6). See Figure 2 below for a summary of the unconfined strengths versus elevation.





Figure 2, Bedrock Unconfined Strength Summary – Ohio Land

**Geotechnical Engineering Report**


Brent Spence Bridge Replacement ■ Cincinnati, Ohio-Covington, Kentucky

March 11, 2011 ■ HCN/Terracon Project No. N1105070



**Figure 3, Unconfined Compressive Strength vs. Moisture Content – Ohio Land**

Slake durability testing was performed on shale samples to evaluate potential deterioration in the presence of water. Values less than 60% are generally considered susceptible to degradation. The average value was about 77% for this portion of the project. One sample, located at an elevation of 347.2 feet in boring L-2A, had a value less than 60%. The slake durability tests are summarized in Figure 4.



**Figure 4, Bedrock Slake Durability Index Summary – Ohio Land**

## 4.2 River Borings (R-1, R-2, R-2A, R-3, R-4, R-5, R-6, R-7, R-8)

### **Natural Overburden Soils**

The borings located within the Ohio River near both the Ohio side (R-1, R-2, R-2A, R-3, and R-4) and Kentucky side (R-5, R-6, R-7, and R-8) encountered predominately granular soils overlying the shale and limestone bedrock. On the Kentucky side, approximately 12 to 30 feet of predominately cohesive soils were encountered above the granular soils. The total thickness of overburden soils ranged from about 51 to 84 feet.

The granular soils encountered in the river borings consisted primarily of sand and gravel (A-1 and A-1-b) as well as occasional fine sand (A-3). These granular soils were mostly medium dense in the upper zones grading with depth, to dense and very dense. The cohesive soils encountered in the upper portions of the Kentucky borings consisted of a mixture of silt and clay soils (A-4, A-6, and A-7-6). The consistency of these soils ranged from soft to medium stiff.

Blow counts in the overburden soils ranged from WOH to over 100 bpf. The higher blow counts were encountered just above the bedrock surface or in zones with higher percentages of gravel, cobbles, and rock fragments. Cobbles, boulders, and large rock fragments are likely to be encountered erratically throughout the soil profile particularly just above the bedrock surface. The average blow count was 24 bpf in the river borings. Natural moisture contents in the overburden soils ranged from about 6% to 49%.

### **Bedrock**

Bedrock was encountered on average at elevation 372 feet in the river. This corresponds to a depth of about 84 feet below the normal pool level (456.36 feet) of the Ohio River. The bedrock consisted of primarily limestone, with interbedded limestone and shale being encountered in the upper portions of the borings. A summary of the encountered depth to bedrock is provided in the following table.

**Table 4, Summary of Encountered Bedrock – Ohio River**

Test Boring	Surface Elevation (ft.)	Approximate River Depth (ft.)	Approximate Depth to Bedrock (ft.) <sup>(1)</sup>	Approximate Bedrock Elevation (ft.)
R-1	458.0	32.0	87.0	371.0
R-2	458.1	29.0	87.0	371.1
R-2A	457.6	29.0	88.0	369.6
R-3	458.0	28.0	86.5	371.5
R-4	458.0	30.5	86.5	371.5
R-5	458.6	16.0	85.0	373.6
R-6	457.0	-	84.0	373.0
R-7	458.5	21.0	82.5	376.0
R-8	455.7	-	80.0	375.7

(1) The depth to rock indicated in this table is for estimation purposes. Actual depth to rock may vary, as determined by construction conditions and as approved by the engineer based on the encountered field conditions.

## Geotechnical Engineering Report


Brent Spence Bridge Replacement ■ Cincinnati, Ohio-Covington, Kentucky

March 11, 2011 ■ HCN/Terracon Project No. N1105070



Fossiliferous and argillaceous seams were noted in the bedrock. The percentage of limestone in the interbedded layers ranged from approximately 70% to 80%. The percentage of limestone typically increased with depth. Shale seams and layers within the interbedded limestone and shale typically ranged in thickness from thin partings to 6 inches. Limestone layers ranged from thin partings to 3 feet or more in thickness, with a typical thickness of approximately 4 to 8 inches.

Rock Quality Designation values for the Ohio River borings averaged about 76% on the Ohio side of the river and 77% on the Kentucky side of the river. In both areas the RQD generally increased with depth. The RQD values in the river ranged from 0% to 100% while the rock core recovery values ranged from about 50% to 100%, with an average of about 97%. The figure below summarizes the RQD and Rock Core Recovery of samples obtained within the Ohio River.




**Figure 5, Bedrock RQD/REC Summary – Ohio River**

Unconfined compressive strength ( $q_u$ ) testing resulted in an overall average strength of 11,268 psi on the Ohio side of the river and 11,044 psi on the Kentucky side. Higher strengths were seen in the samples that were primarily limestone while the lower strengths were seen in primarily shale samples. Also, lower strengths were correlated with shale samples with a higher natural moisture content (see Figure 7). Elastic modulus testing was also performed on select limestone samples. Elastic modulus testing yielded an average elastic modulus of 7,787 and 7,794 ksi for the Ohio and Kentucky sides, respectively (see Exhibit B-6). A summary of the unconfined compressive strength on tested rock core samples is shown in the figure below.


# Geotechnical Engineering Report

Brent Spence Bridge Replacement ■ Cincinnati, Ohio-Covington, Kentucky

March 11, 2011 ■ HCN/Terracon Project No. N1105070




**Figure 6, Bedrock Unconfined Strength Summary – Ohio River**



**Figure 7, Unconfined Compressive Strength vs. Moisture Content – Ohio River**

Slake durability testing was performed on shale samples to evaluate potential deterioration in the presence of water. Values less than 60% are generally considered susceptible to degradation. The average value was 76% for this portion of the project. A total of four (4) shale samples located in borings L-5 and L-6 had a value less than 60%. These values ranged from 36% to 59% and all were in samples above elevation 360 ft., which was within about 10 feet of the bedrock surface.



**Figure 8, Slake Durability Index Summary – Ohio River**

### 4.3 Kentucky- Land Borings (L-4, L-5, L-6, L-7)

#### **Existing Fill**

Vacuum extraction was performed at L-5, L-6, and L-7 to expose possible underground utility conflicts; vacuum extraction was not performed at L-4 located between the levee and the riverfront. Fill material was encountered to depths of about 10 to 25 feet below existing grade. Fill was not encountered in boring L-6; however, it is likely some fill is present within the depth that was vacuum excavated. The fill consisted of silt, sandy silt, and silt and clay (A-4a, A-4b, A-6a, and A-6b) as well as sand, sand and gravel, and rock fragments (A-1-b). Evidence of fill included slag, wood, organics (topsoil, wood/fibrous material, and/or decayed matter), and concrete fragments.

The consistency of the existing fill was generally very loose to loose in the granular fill and medium stiff to stiff in the cohesive fill. Blow counts ranged from 1 to 18 bpf, with an average of 9 bpf. Natural moisture contents in both the granular and cohesive portions of the fill ranged from 17% to 38%.

#### **Natural Overburden Soils**

Overlying the thick granular layers at borings L-5, L-6, and L-7, the natural overburden was typically stiff silty clay (A-6a) and medium dense to dense silt or sandy silt (A-4a and A-4b). These layers were approximately 20 feet thick at borings L-5 and L-7, but were about 72.5 feet thick at boring L-6 where no fill was encountered. At boring L-4, located between the levee and the riverfront, the zone consisted of about 20 feet of soft gray clay (A-7-6).



## Geotechnical Engineering Report

Brent Spence Bridge Replacement ■ Cincinnati, Ohio-Covington, Kentucky

March 11, 2011 ■ HCN/Terracon Project No. N1105070



Underlying these soils was mostly sand (A-3) underlain by varying amounts of gravel and gravel with sand (A-1-a and A-1-b). These layers were medium dense in the top layers grading with depth to dense and very dense. Cobbles, boulders, and large rock fragments are likely to be encountered erratically throughout the soil profile particularly just above the bedrock surface. Blow counts in the natural overburden soils ranged from 3 to over 100 bpf. The average value was 46.

### **Bedrock**

Bedrock was encountered on average at about elevation 372 feet in this area. The bedrock consisted of primarily limestone as well as interbedded limestone and shale in the upper portions of the bedrock. Occasional fossiliferous and argillaceous seams were present in the limestone. The percentage of limestone in the interbedded layers ranged from approximately 70% to 80%. The percentage of limestone typically increased with depth. The thickness of shale seams/layers in the interbedded limestone and shale ranged from approximately 8 inches to less than ¼ inch. Limestone layers ranged from thin partings to 3 feet in thickness with a typical thickness of approximately 3 to 6 inches. A summary of the depth to bedrock is provided in the following table.

**Table 5, Summary of Encountered Bedrock – Kentucky Land**

Test Boring	Surface Elevation (ft.)	Approximate Depth to Bedrock (ft.) <sup>(1)</sup>	Approximate Bedrock Elevation (ft.)
L-4	480.0	104.0	376.0
L-5	486.3	107.0	379.3
L-6	485.7	108.5	377.2
L-7	484.4	100.0	384.4


(1) The depth to rock indicated in this table is for estimation purposes. Actual depth to rock may vary, as determined by construction conditions and as approved by the engineer based on the encountered field conditions.

Rock Quality Designation values for the Kentucky-Land borings averaged about 53% and ranged from about 0% to 92%. Rock core recovery values ranged from about 17% to 100%, with an average of about 53%. The figure below summarizes the RQD and Rock Core Recovery for samples obtained in the land borings in Kentucky.

**Geotechnical Engineering Report**


Brent Spence Bridge Replacement ■ Cincinnati, Ohio-Covington, Kentucky

March 11, 2011 ■ HCN/Terracon Project No. N1105070



**Figure 9, Bedrock RQD/REC Summary – Kentucky Land**

The overall average unconfined compressive strength ( $q_u$ ) was 11,989 psi for the Kentucky portion of the project. Figure 6 shows a summary of the unconfined compressive strength test results. Compressive strengths were generally greater in shale samples with lower moisture contents (figure 11) and those samples consisting primarily of limestone. In addition to the strength testing, elastic modulus testing was performed on select limestone samples. The average elastic modulus in this area was 9,104 ksi (see Exhibit B-6).




**Figure 10, Bedrock Unconfined Strength Summary – Kentucky Land**

**Geotechnical Engineering Report**


Brent Spence Bridge Replacement ■ Cincinnati, Ohio-Covington, Kentucky

March 11, 2011 ■ HCN/Terracon Project No. N1105070



**Figure 11, Unconfined Compressive Strength vs. Moisture Content– Kentucky Land**

Slake durability testing was performed on several samples in the Kentucky-Land portion of the project. Values less than 60% are generally considered susceptible to degradation. The average value for this area was 63.3%. Five (5) of the eight (8) samples in this area have slake durability indexes of less than 60%.



**Figure 12, Slake Durability Index Summary– Kentucky Land**

## 4.4 Groundwater

Groundwater observations were made during drilling. Water level readings are not considered reliable since water was introduced to the borehole during rock coring operations and in granular soils to prevent heave into the augers. Long-term (24-hour) water level observations were not made since the test borings were backfilled immediately upon completion for safety reasons. The groundwater levels measured during drilling may not accurately represent the prevailing groundwater levels at the test boring locations. The groundwater in the boreholes requires sufficient time to stabilize and reach the static groundwater level. To obtain long-term groundwater measurements, it is necessary to install water level observation wells or piezometers.

Perched water may be encountered at higher elevations within the existing fill and at the fill/natural interface. The long-term groundwater levels are influenced by amount of precipitation, degree of surface runoff, and primarily the water level in the Ohio River.

The Ohio River, forming the border between Ohio and Kentucky, is about 1,300 feet wide at the existing Brent Spence Bridge location. The normal pool elevation of the Ohio River in the area of the bridge is about 456 feet. On the Kentucky side of the Ohio River, the nearest tributary is the Licking River, which is located about 1 mile to the east of the existing I-71/I-75 roadway. In Ohio, the nearest tributary is the Mill Creek, which is located about  $\frac{1}{2}$  to  $\frac{3}{4}$  of a mile to the west of the existing roadway. The USGS map indicates several smaller water features, including lakes, ponds, and manmade ponds/reservoirs.

Water drainage in the corridor study area is generally achieved by diverting water towards the Ohio River and/or adjacent connecting streams. Due to the relatively large watershed that the Ohio River covers upstream to the north and east, periodic flooding is generally common in low-lying areas along the Ohio River in the Cincinnati/Covington area. The following flood information was obtained from the Louisville District U.S. Army Corp of Engineers for the project location:

- Normal pool – Elevation 456.36 feet
- Ordinary High Water Mark – Elevation 468.5 feet
- 100 Year Flood – Elevation 497.10 feet
- 500 Year Flood – Elevation 512 feet

The river level ranged in elevation from a low of 455.1 feet to a high of 465.9 feet during drilling (5/17/2010 to 9/4/2010). At the time the borings located in the river were drilled (6/29/2010 to 9/4/2010), the river elevation ranged between about 455 and 456 feet.

## 4.5 Shear Wave Velocity Profiles

The results of the PS Suspension Logging at test borings (L-1, L-4, and R-2A) were evaluated for the AASHTO seismic Site Class in accordance with AASHTO LRFD 2010 Section 3.10.3.1. The shear wave velocity results for each boring are included in Appendix A as Exhibit A-11. The interval shear wave velocity values were used to calculate the average shear wave velocity of the upper 100 feet. The approach described in Method A of Table C3.10.3.1-1 was used to obtain the following results:

Location	V <sub>s</sub> (feet/second)	Site Class
L-1	754	D
L-4	940	D
R-2A	2565	B (C <sup>1</sup> )

Note: 1. Defaults to C since rock is more than 10 feet below bottom of pile cap.

## 4.6 Previous Geotechnical Studies

Soil borings were performed by H.C. Nutting for both the existing Brent Spence Bridge (1958 study) and the Queensgate alignment (2007 study). The results of these test boring programs were generally consistent with the borings performed for this study. The major differences are the lack of overburden soils in the river and the depth to bedrock is shallower by approximately 50 feet along the Queensgate alignment.

The overburden soils encountered in the 1958 borings consisted of existing fill overlying primarily granular soils. The existing fill consisted of sandy clay, silty clay, sand, gravel, and cinders. Various amounts of brick fragments and organic material were also encountered throughout the fill. Underlying the fill the natural soils were primarily granular consisting of sand and gravel. Silty and sandy clay was also encountered, mostly in the upper 10 to 20 feet of the natural overburden soils. Bedrock was encountered in these borings at elevations ranging from 371 to 375.2 at the river pier locations, 379 to 381 feet at the Ohio abutment, and 382 to 387 feet at the Kentucky abutment. The bedrock encountered consisted of interbedded limestone and shale.

Six (6) borings were performed in 2007 to investigate the subsurface conditions for the proposed Queensgate alignment located approximately 800 to 1200 feet west of the existing bridge. The overburden soils encountered in the land borings were generally consistent with the borings performed for this study. Existing fill consisting of both cohesive and granular soils as well as cinders, brick fragments, and organics was encountered in the borings located on land in Ohio and Kentucky. The natural soils underlying the fill were primarily cohesive in the Kentucky borings and granular in Ohio. The major difference between the 2007 borings and the borings performed in 1958 and 2010 is the lack of overburden soils in the river and the shallower depth

## Geotechnical Engineering Report

Brent Spence Bridge Replacement ■ Cincinnati, Ohio-Covington, Kentucky

March 11, 2011 ■ HCN/Terracon Project No. N1105070



to bedrock. At the two (2) borings performed in the river along the Queensgate alignment only 0.5 feet of overburden soils (sand and gravel) were encountered overlying the bedrock. The bedrock at this location was approximately 50 feet higher than at the existing bridge location. This difference in bedrock elevations is consistent with the geology of the area with the existing bridge located within the ancient Deep Stage Licking River.

## 5.0 ANALYSIS AND RECOMMENDATIONS

The following text provides foundation recommendations for the proposed Brent Spence Bridge project. Details regarding construction considerations and field testing of the foundations are also provided. The provided foundation recommendations and construction considerations are each critical to bridge foundation design and should not be viewed independently. Grading and earthwork plans, along with roadway and embankment alignments have not been finalized at this time. Therefore, details beyond the proposed bridge foundations are not discussed in this report.

Based on review of various foundation types, construction practices, and major river crossing projects, it is our opinion that drilled shafts are an effective and cost-practical foundation for bridge support at both the interior (river) pier and abutment (land) locations. In consideration of the structure type, loads and constructability, it appears that drilled shafts are the preferred foundation choice for this project.

Driven pile types have been considered as a feasible foundation alternative. Both H-piles and CIP piles have been evaluated for the bridge abutments and approach spans. H-piles driven to bedrock have been considered for the river foundations and additional discussion is provided in section 5.3.

The following sections further develop these foundation recommendations. Following the foundation recommendations, detailed discussions regarding quality control during construction and field testing are provided. A well-conceived field testing program and strict quality control during construction are considered part of the foundation design process and are essential to the long-term performance of the foundation system.

### 5.1 Foundation Discussion

Tower foundations like those expected for the proposed bridge require large compressive, uplift, lateral, and overturning moment capacities. A general subsurface profile of the bridge alignment consists of overburden soils, primarily granular, overlying unweathered shale and limestone bedrock. Based on the limited number of borings, the bedrock surface on the Ohio land side varied by up to 15 feet. Bedrock elevation variation within the Ohio River was typically less than 3 feet. On the Kentucky land side, bedrock elevation varied nearly 10 feet between the test boring locations. We recommend additional test borings be performed during the

## Geotechnical Engineering Report

Brent Spence Bridge Replacement ■ Cincinnati, Ohio-Covington, Kentucky

March 11, 2011 ■ HCN/Terracon Project No. N1105070



project design and construction phases to better define the bedrock surface. The general profile at the project site is considered suitable for consideration of both driven pile and drilled shaft foundation types.

Driven piles could consist of steel pipe piles (CIP) or H-piles. Steel piles can provide high-strength, they are easy to handle, and are capable of carrying large loads to deep loading bearing strata. For depths greater than about 60 feet, splicing of the piles is usually required to achieve the design length. Driven steel piles do not produce excavation spoils requiring disposal. A common problem with driven steel piles is deviation from vertical (lack of plumbness) and loss of load capacity when driving through soils with cobbles, rock fragments, or into an uneven bedrock surface. In addition, battered piles may be required to provide the lateral capacities required for the tower foundations. Driven steel piles could be considered for the bridge particularly on the portions over land. Preliminary design recommendations have been provided for driven piles at the abutment locations on land. If driven piles are deemed viable, further analysis could be performed and detailed recommendations developed.

Drilled shafts consist of cast-in-place, reinforced concrete piers socketed into the bedrock. Drilled shafts are a common type of construction in the area and are familiar to contractors. Drilled shafts allow for a reduction in the pile cap size and the overall number of foundation elements compared to driven piles. The construction of drilled shafts would require steel permanent casing, possible use of slurry, as well as the disposal of the excavated spoils. Drilled shafts are the recommended option for the proposed bridge foundations in the river and can also be used for the land foundations.

### 5.2 Drilled Shafts

The bridge structure can be supported on a cast-in-place drilled shaft foundation that is sufficiently embedded into shale and limestone bedrock. Drilled shaft performance is strongly related to the effectiveness of the construction technique in preserving the integrity of the bearing materials and ensuring the structural integrity of the reinforced concrete shaft element. The typical construction sequence is anticipated to consist of the following components:

- Install a temporary casing through water and upper overburden soils,
- Using polymer slurry, drill through the overburden soils,
- Place permanent casing into the upper shale bedrock,
- Excavate the bedrock socket under polymer fluid to the design tip elevation,
- Roughen the sidewall bedrock surface to remove any slick or decomposed material,
- Thoroughly clean out the shaft base,
- Place steel reinforcement and concrete

The following sections discuss design recommendations along with certain aspects of the construction sequence for drilled shafts, as they relate to design.

## **5.2.1 Design Parameters**

Given the subsurface conditions and the provided preliminary concept design, drilled shafts are recommended for the bridge foundations. Design parameters for both axial end bearing and side resistance for rock socketed drilled shafts are provided. Shafts will also need to be evaluated for lateral resistance which may control rock socket embedment depths. Strain compatibility when using side and end bearing would need to be evaluated as well as group settlement, as part of final design when the drill shaft geometry and layout are finalized.

### **5.2.1.1 Axial Loading**

The drilled shaft design parameters for axial loading were developed based on the test borings, detailed review of rock cores, laboratory testing, and review of published literature. Design of the drilled shafts can include both base resistance and side resistance in the bedrock. An estimate of the total scour should be performed to determine what side resistance is available from the overburden soils. The load-displacement relationship (strain compatibility) between base and side resistance should be considered in the design since the maximum side resistance typically occurs at a lower displacement than the maximum base resistance.

Reasons cited in published literature for neglecting side resistance of rock sockets include; (1) possibility of strain-softening behavior of the sidewall interface (2) possibility of degradation of material in the borehole wall in argillaceous rock, (3) uncertainty regarding the roughness of the sidewall. Site specific laboratory testing has not been performed to determine load-deformation behavior on the rock/concrete interface. Based on published literature on similar bedrock material as those encountered for this project, strain softening is not commonly observed and therefore strain compatibility should not be a factor in combining side resistance and base resistance. This tendency is likely related to the dilatency of the shaft/rock interface. Field load testing along with careful quality control during construction to confirm sidewall conditions should be performed to confirm and justify our assumption that side resistance can be used in combination with base resistance. Laboratory testing can also be performed in addition to field testing if strain softening is a concern.

Based on the subsurface data collected during field exploration, drilled shafts would be socketed within the Point Pleasant formation or the much deeper Lexington Limestone formation. A detailed discussion of the bedrock geology, bedrock characteristics and strength properties has been presented before. The Point Pleasant formation consists of interbedded limestone and shale. The amount of limestone increases with depth in this formation. The unconfined compressive strengths obtained from intact rock core samples yielded average values of 8,000 to 10,000 psi. However, significant variability was observed with the standard deviation being about 3200 psi. The rock core in the upper 30 ft. exhibited RQD values being less than 50% in many locations. The shale samples were brittle and at many locations could not be tested as they were easily broken and a sufficient length of sample was not available for testing. Considering the low RQD values, rock core recovery, careful review of the rock core, presence of thin soft zones of shale (which could not be tested) and the variability across the site, the unconfined compressive strength ( $q_{u \text{ design}}$ ) suggested for use in design has been



## Geotechnical Engineering Report

Brent Spence Bridge Replacement ■ Cincinnati, Ohio-Covington, Kentucky

March 11, 2011 ■ HCN/Terracon Project No. N1105070



selected to be lower than average tested values. The selected  $q_{u \text{ design}}$  value also considers the disturbance and constructability considerations which has a significant impact on design performance of drilled shafts.

The Lexington Limestone is more competent than the Point Pleasant formation. However, this typically occurs 50 to 60 feet below the top of encountered bedrock. Review of the rock core and laboratory testing data indicates that higher base and side resistance is likely available within this formation. However, considering the depth of rock socket needed to bear within the formation, we do not think it will be cost effective to design shafts bearing within this formation.

Using AASHTO LRFD design procedures, the ultimate capacities of the drilled shafts were determined based on unconfined compressive strength of the intact rock and the rock mass rating (RMR). The elastic modulus used in design has been reduced to two-thirds of the average measured value to account for the shale in the rock mass. Most of the elastic modulus tests were performed on limestone specimens. The bridge project was broken into four areas (Ohio-Land, Ohio-River, Kentucky-River, and Kentucky-Land) and recommended values are given for each area. A summary of the recommended values is provided in the following table. Calculations for these values are provided in Exhibit C-2 in the appendix.

**Table 6, Drilled Shaft Design Input Values**

Location	Avg. RQD (%) (upper 30 ft.)	Avg. Unconfined Compressive Strength Used In Design ( $q_u$ , psi)	Design Elastic Modulus ( $E_i$ , ksi) (upper 30 ft.)
Ohio-Land	38%	4,000	6,043
Ohio-River	67%	4,800	5,311
Kentucky-River	59%	4,800	4,757
Kentucky-Land	49%	4,000	6,073

**Table 7, Drilled Shaft Design Parameters**

Location	Rock Mass Rating (RMR)		Rock Mass Modulus ( $E_m$ , ksi)	Nominal Shaft Resistance ( $q_s$ , ksf)			Nominal Base Resistance* ( $q_p$ , ksf)
				Rock	<	Concrete	
Ohio-Land	42	III (Fair Rock)	1,220	14.3		22.7	350
Ohio-River	57	III (Fair Rock)	1,627	17.7		22.7	350
Kentucky-River	57	III (Fair Rock)	1,627	17.9		22.7	350
Kentucky-Land	42	III (Fair Rock)	1,220	14.3		22.7	350

\*Values reported are limiting values (see discussion)

The nominal base resistance is computed using the empirical relationship (FHWA-NH1-10-016):

$$q_{bN} = N^*_{CR} \cdot q_u$$

$N^*_{CR}$  = empirical bearing capacity factor for rock

$q_u$  = unconfined compressive strength of rock

$q_{bN}$  = nominal base resistance

Based on various research studies,  $N^*_{CR} = 2.5$  is recommended for design when the following conditions are met:

- The shaft is bearing on rock that is either massive or tightly jointed
- No solution cavities or voids exist beneath the base
- A clean base can be achieved and verified using conventional clean-out equipment

The empirical factor  $N^*_{CR}$  can vary and be as low as 0.4 if there are joints and discontinuities in the rock mass. O-cell testing data (1995) of the Maysville New US 62/68 Ohio River Bridge on the Point Pleasant Formation bedrock indicated that ultimate end bearing was 160 tsf at 1.0 inch of base movement. A description of O-cell testing is provided in section 5.2.5.2. Displacements required to mobilize the base resistance are related to shaft diameter. The design guidelines for geotechnical strength are based on limiting the displacement at nominal resistance to 2.5% of diameter, considering that larger diameter shafts will be used. We have limited the nominal base resistance to 350 ksf to satisfy the above discussed criterion. Also, for loads greater than 350 ksf, large creep movements are likely. The limiting of base resistance also appears reasonable considering the need to ensure strain compatibility between side resistance and end bearing and limiting the overall foundation movement to less than 1.0 inch. The bridge structure may be able to tolerate settlements greater than 1.0 inch and the tolerable settlement (total and differential) will need to be determined jointly by the geotechnical and structural engineer. Project specific load testing will be performed to help determine load displacement data and modify design values, as needed.

Additional axial design considerations include:

- Minimum rock socket the greater of 1.5B or 10 feet.
- Per AASHTO section 10.8.3.5.6 and table 10.5.5.2.4-1, resistance factors for axial compression and uplift (socket resistance), considering static load testing is performed, are 0.7 and 0.6, respectively. If applied to a single shaft supporting a bridge pier, then the resistance factors should be reduced by 20 percent (per AASHTO section 10.5.5.2.4).
- Overburden should not be considered to contribute axial capacity due to strain compatibility considerations.
- The base capacity may be limited by allowable shaft movement.

The drilled shafts are expected to be subjected to lateral loads and should be designed accordingly. The shaft lengths should be designed such that the lateral deflections are acceptable due to the anticipated lateral loads. Non-linear p-y analyses can be used to estimate the shear and moment along the length of the shaft. The following table provides recommended LPILE parameters to be used for static lateral analysis of the drilled shafts.

**Table 8, Recommended Soil Parameters for Single Lateral Pier (LPILE) Static Analysis**

Soil Type	Moist Unit Weight of Soil - $\gamma$ (pcf)	Buoyant Unit Weight - $\gamma$ (pcf)	LPILE P-y Modulus - k (pci)	Internal Angle of Friction - $\phi$ (°)	Undrained Shear Strength - Su (psf)	Uniaxial Compressive Strength - $q_u$ (psi)	Strain Parameter - $\epsilon_{50}$ or $k_{rm}$
Cohesive Existing Fill (stiff to very stiff) <sup>1</sup>	120	57.6	500	--	2,000	--	0.007
Granular Existing Fill (medium dense to dense) <sup>2</sup>	120	57.6	50	32	--	--	--
Granular Natural Soil (loose to medium dense) <sup>2</sup>	125 <sup>2</sup>	62.6	80	33	--	--	--
Granular Natural Soil (dense to very dense) <sup>2</sup>	130 <sup>2</sup>	67.6	100	36	--	--	--
Cohesive Natural Soils (medium stiff to stiff) <sup>1</sup>	125	62.6	300	--	750	--	0.01
Cohesive Natural Soils (very stiff) <sup>1</sup>	125	62.6	750	--	3,000	--	0.006
Limestone Bedrock <sup>3</sup>	165	102.6	--	--	--	10,000	0.0005

<sup>1</sup> - Anticipated to be modeled as "stiff clay without free water"

<sup>2</sup> - Anticipated to be modeled as "sand (Reese)"

<sup>3</sup> - Use a modulus of elasticity value of  $8 \times 10^6$  psi for limestone bedrock

The parameters provided in the above table are considered to be "initial" parameters under static loading. The basis of the lateral analyses is soil-structure interaction, and the behavior of the soil is non-linear depending on the loading conditions and the stiffness of the structural element. The reaction/resistance of the soil is dependent on the movement of the structure and hence the input soil properties are not fundamental properties of the soil. Therefore, lateral analysis is an iterative process based on an initial set of soil parameters that may need to be adjusted depending on the initial results and engineering judgment. HCN/Terracon requests the opportunity to review and comment, as necessary, on the lateral analysis results.

### 5.2.1.2 Group Effects – Axial Loading

Considering that all the drilled shafts will be socketed a sufficient distance in competent bedrock and because the strength of the bedrock is anticipated to be greater than the strength of the



shaft/rock interface, group effects are generally not expected to control design. Superposition of stresses from adjacent drilled shafts may result in increased deformations of group of shafts relative to that of single shafts, however, settlement of drilled shafts founded on bedrock are anticipated to be small and group effects should be minimal. A more detailed analysis of shaft groups will be needed once the shaft diameter, spacing, loading and bedrock embedments have been finalized.

Drilled shafts which develop their capacity from a combination of side resistance and end bearing should be installed with a minimum center-to-center spacing of 2.5 times the shaft diameter. No reduction in individual axial shaft capacity is needed for this spacing. Adjacent shafts should not be constructed on the same day. If the drilled shafts are spaced closer than 2.5D, then further evaluation to determine group effects will be needed.

**5.2.1.3 Group Effects – Lateral Loading**

The lateral resistance in the scour zone (computed by the design team) should be neglected. When laterally loaded drilled shafts are used in closely spaced groups, a given shaft will deflect further under a given system of loads that if loaded when the neighboring shafts are not present, and bending stresses will be greater. It is therefore recommended to consider group effects due to loading when shaft spacing is less than about six diameters in any direction. A “p-multiplier” to accommodate the group effects can be considered. For group effects, then “Pm” factor provided in this table can be used.

**Table 9, Recommended P-Multiplier, P<sub>M</sub>, Values for Design by Row Position**

Pile Spacing (c-c)	Design P-multiplier, P <sub>M</sub>			
	3D	4D	5D	≥6D
Lead row	0.7	0.85	1.0	1.0
2 <sup>nd</sup> Row	0.5	0.65	0.85	1.0
3 <sup>rd</sup> and Higher Rows	0.35	0.5	0.7	1.0

FBPIER, a computer program capable of considering coupled effects of the drilled shafts and pier cap in addition to much more complex three-dimensional group configurations, three-dimensional loading conditions, and GROUP in 2-D and 3-D should be utilized for analyses of pier groups.

**5.2.1.4 Uplift Design**

The drilled shafts can be subject to uplift loads. The uplift nominal unit side resistance are the same for uplift and compression. However, a lower resistance factor is recommended for uplift than axial compression. The recommended resistance factors for uplift are typically 0.10 less than those for compression.

### **5.2.1.5 Downdrag**

The effects of downdrag should be evaluated as part of the final drilled shaft design. The relative settlement of the soil to the shaft as a function of time and depth must be known in order to determine the magnitude of downdrag. For preliminary considerations, downdrag is not expected to be a significant factor for the river foundations. However, once the grading and bridge foundation details, including installation procedures have been determined, evaluation of downdrag should be performed. The effects of the change in river levels under normal pool and flood conditions will also need to be considered during final design.

### **5.2.2 Scour Considerations**

Bridge scour is the loss of soil by erosion due to flowing water around bridge supports. Scour analysis is being performed by the design team. We would anticipate that the majority of the overburden soils are susceptible to scour. Axial capacity within the overburden soils have been neglected to account for scour, strain compatibility, and other constructability considerations. Effects of scour that must be taken into account for drilled shaft design (FHWA-NHI-10-016) include (1) changes in subsurface stress, (2) reduced embedment and therefore changes in axial and lateral resistances, and (3) possible changes in the structural response and resulting foundation force effects. AASHTO Specifications also require evaluation of bridge foundations for two scour conditions (1) design flood scour condition for foundation strength and service limit state and (2) check flood scour condition for extreme limit state.

Scour should include the general scour and channel construction scour plus local scour immediately around the bridge piers. The effects of the existing Brent Spence Bridge piers relative to scour development should also be considered in the analysis.

The minimum rock sockets for drilled shafts should be designed below the maximum (predicted design) scour elevation in bedrock. Generally, we would anticipate that the limestone and shale bedrock is not erodible. A final determination of the erodibility of shale bedrock would need to be made after detailed scour analyses by the design team. In addition, the estimated scour depths should be considered in the lateral load analysis.

### **5.2.3 Drilled Shaft- Cofferdams**

Construction of the drilled shafts located in the river can be performed in cofferdams. A cofferdam is a temporary structure designed to keep water and/or soil out of the excavation in which a bridge pier or other structure is built. Sheet piling is driven around the work site, seal concrete is placed into the bottom, and the water is pumped out. The concrete seal course is used to seal off the water, resist its pressure, and also can be used to act as a slab to brace against the inward movement of the sheet piles.

Several types of cofferdams could be considered for the proposed construction; braced, cellular, or double-walled sheet piles. The proposed cofferdam will experience several loading conditions. The designer should consider hydrostatic, soil, current, waves, and ice load as well

as construction loading. Accidental loading, such as due to a ship strike, and seismic loading may also need to be considered.

As an alternative to a traditional cofferdam the shafts could be installed from a temporary trestle. Then the footing forms would be assembled above the water level and lowered around the shafts to the required level. A tremie seal is then placed, the form dewatered, the shafts cut off at the desired level, and the footing placed. It is our understanding that this option was used successfully on the Audubon Bridge over the Mississippi River in Louisiana. This method can accommodate a wide fluctuation in river levels and may be less costly than cofferdams.

## **5.2.4 Drilled Shaft – Construction Considerations**

### **5.2.4.1 General Discussion**

Drilled shaft construction generally falls into three (3) categories based on the method of construction. These include the dry method, the casing method, and the wet method. Selection of the appropriate method is dependent on the subsurface conditions at a site and is typically the contractor's responsibility to select the appropriate method. Based on the drilled shaft construction extending into bedrock to achieve the desired capacities at locations within the river or in close proximity to the river, we do not anticipate dry construction methods will be feasible. Wet construction methods, including utilization of casing, in combination with drilling slurry, is anticipated at the river and land abutment locations. The following sections further develop feasible construction methods, provide criteria for drilled shaft construction, and address other relevant construction considerations.

Random miscellaneous fill, both manmade and river debris, are anticipated along the river banks. Such deposits may consist of, but not be limited to, abandoned utilities, boulders, foundations, tree trunks, wood, concrete slabs, etc. Dense sands and gravel were encountered in lower portions of the overburden soils. Cobbles and boulders may be encountered in the outwash deposits, which may cause difficulties during drilled shaft construction. Based on discussions with the project team, we understand that the existing fill on the Ohio landside within the existing West End Duke Energy Substation will be environmentally remediated. If the remediation effort includes removal and replacement of the existing fill soils, then the majority of obstructions are anticipated to be removed; however, in-place remediation efforts will not alleviate the presence of the possible obstructions and variable fill. At the time of this report, such environmental remediation evaluation and efforts have not been completed. The presence of the variable fill and associated environmental concerns at all locations should be further evaluated during the final study.

### **5.2.4.2 Drilled Shaft Installation**

Construction of a drilled shaft requires boring a hole of a specified diameter and depth and then backfilling the hole with reinforced concrete. The selection of equipment and procedures for constructing drilled shafts is a function of the shaft dimensions, the subsoil conditions, and the

## Geotechnical Engineering Report

Brent Spence Bridge Replacement ■ Cincinnati, Ohio-Covington, Kentucky

March 11, 2011 ■ HCN/Terracon Project No. N1105070



groundwater characteristics. Consequently, the design and performance of drilled shafts can be significantly influenced by the equipment and construction procedures used for construction and also by method of placement and properties of concrete. Construction procedures and methods are of paramount importance to the success of the drilled shaft installation at this project site.

Drilled shaft contractors who participate on this project should be required to demonstrate that they have suitable equipment for this project, and adequate experience in the construction of drilled shafts of the required size and depth, and with similar subsurface conditions. A detailed installation plan along with equipment and methods should be submitted by the contractor for review and approval by the design team.

The installation of the drilled shaft is critical to the successful performance of the shaft. Extending the drilled shaft to the proper depth and careful preparation of the borehole are critical during the drilled shaft construction process. Although construction techniques and methodologies may vary between contractors, the following criteria are considered minimal in the design and construction of the drilled shaft foundations. Project specifications must be developed that present all requirements for drilled shaft construction and address the specific requirements for the project.

- 1) It is recommended that the approximate top of rock and design bottom elevation be shown for each drilled shaft on the plans, with these elevations being determined using the test borings and lateral and axial load analyses. The “minimum lengths” should be based on lateral load requirements, while “estimated lengths” would reflect axial resistance requirements and will be verified by load tests. Minimum lengths should be based on lateral load requirements, while estimated lengths would reflect axial resistance requirements and will be verified by load tests. The final bearing elevation should be determined by inspection of each shaft hole in the field by qualified geotechnical personnel. We recommend additional test borings be performed during the design phase of the project to better define the rock surface due to variations encountered in the borings performed for this study.
- 2) The specifications should be clear that the design bottom of the drilled shaft elevations shown on the plans is for estimation purposes only. Actual determination of the top of rock and bottom elevation will be made from examination of materials brought to the surface on the drilling tools by the project geotechnical engineer. As an additional quality control measure, pre-coring at drilled shaft locations could be performed to assess bedrock quality and conditions.
- 3) The specifications should require that no concrete be placed until the dimensions, bottom elevation, bearing socket depth, and excavation for each shaft has been observed and is to the satisfaction of the geotechnical engineer. A Shaft Inspection Device (SID), mini-SID, or Downhole Camera System (DHC) could be employed for inspection of the drilled shafts prior to concrete placement. This will allow for visual

## Geotechnical Engineering Report

Brent Spence Bridge Replacement ■ Cincinnati, Ohio-Covington, Kentucky

March 11, 2011 ■ HCN/Terracon Project No. N1105070



inspection of the bottom conditions. The mini-SID is a camera, lights, and feelers gauges housed in a steel bell. The bell is pressurized with dry nitrogen as it is lowered in the slurry to keep camera free of slurry. Once at the bottom, water jets are used to clear the lens to expose the shaft bottom for camera inspection.

- 4) Sonic caliper testing should be performed after the shaft base has been cleaned to determine and confirm as-built dimensions and compare them to the planned design dimensions. At a minimum, sonic caliper testing should be performed on technique and test shafts, and some selected production shafts.
- 5) Due to the random nature of the fill at the abutments, and the presence of outwash sand and groundwater, full length temporary steel casing should be used and be available on-site to prevent shaft collapse during drilling and concrete placement. The specifications should state that casings be required to stabilize loose or caving materials, or to seal off any water-bearing zones. A concrete core barrel or other suitable tool should also be available on site, if an obstruction within the fill or in the cobble/boulder zone immediately above the bedrock cannot be penetrated with the drilled shaft equipment.
- 6) The permanent casing should be strong enough to withstand handling stresses, withstand the pressures of concrete and of the surrounding earth and groundwater, and to prevent water seepage.
- 7) A permanent steel casing seated within the upper shale bedrock is recommended for the river drilled shafts. The permanent steel casings provide additional strength, abrasion protection, ductility, and confinement for the bending stresses in the drilled shafts and facilitate construction by providing a stable environment in which to construct rock sockets. If the permanent casing is used for structural support, consideration must be given to corrosion of the steel. Also, the full structural capacity cannot be assumed within a certain development length at the top and bottom of the casing. The casing will provide confinement, and may allow a reduction in the spiral or hoop reinforcement, particularly if large shear reinforcement is found to be necessary. They can also assist in avoiding any significant issues with bottom cleanout or entrapped debris.

If the permanent casing is used for structural support, consideration must be given to corrosion potential of the steel. The structural design should evaluate the effectiveness of the casing to resist bending moment as the full structural capacity cannot be assumed within a certain development length at the top and bottom of the casing. The casing will provide confinement and may allow a reduction in the shear reinforcement.

- 8) If water exists in amounts greater than three inches in depth or enters at a rate of more than twelve inches per hour then the shaft excavation should be filled with slurry. A positive head of slurry or concrete, relative to water trapped outside the casing, must always be maintained within the casing to reduce the risk of water and/or soil from



## Geotechnical Engineering Report

Brent Spence Bridge Replacement ■ Cincinnati, Ohio-Covington, Kentucky

March 11, 2011 ■ HCN/Terracon Project No. N1105070



infiltrating into the shaft and contaminating the concrete. An improper head balance could potentially cause water and/or soil to flow into the shaft and compromise the concrete integrity.

- 9) It is recommended that the contractor have appropriate equipment on site to facilitate excavation through variable fill and cobble/boulder zones. The contractor should prepare attachments for the drill rig, such as but not limited to, a rock auger and/or core barrel, attachments to break up the hard loam with rock fragments, and a muck/cleanout bucket to clean the bottom of the shaft effectively. The drill rig should have adequate torque and downpressure to facilitate drilling or coring through the variable materials and very dense/hard zone.
- 10) Concrete placement should be continuous and the discharge end should allow the discharged concrete to flow freely in all directions. If concrete placement is interrupted, the water on top of the concrete and all surficial concrete that has become contaminated with water must be completely removed to fresh concrete prior to final concrete placement to complete the drilled shaft. Shaft excavations should not be left open for an extended period of time.
- 11) Crosshole Sonic Logging (CSL) testing should be performed on every production drilled shaft as well as the technique and test shafts. The use of CSL testing will confirm adequate structural integrity of the shafts. A minimum of six (6) inspection tubes measuring 2 inches in diameter should be installed to facilitate CSL testing; however, the actual number of inspection tubes is dependent on shaft diameter. More detail is provided in section 5.2.5.1.
- 12) Due to the urban nature of the surrounding site, and close proximity of the existing bridge and other structures, a preconstruction survey should be performed prior to construction. We recommend that vibration monitoring be performed along the existing bridge during casing installation using vibratory methods. Vibration monitoring should also be considered during construction near sensitive structures and/or underground features.

Due to the potential risk of variable groundwater conditions within the granular zones, full length permanent steel casing will be required to seal off water bearing and saturated granular zones during drilling. We recommend polymer slurry or other type of heavier slurry (bentonite is not recommended) be added to the drilled hole throughout the entire drilled shaft excavation to resist hydraulic head and prevent collapse of side walls.

The bridge test borings encountered wet primarily granular soils overlying the bedrock. For the river borings the use of permanent casing and/or drilling slurry will be necessary for prevention of caving-in of these wet and granular soils and to produce a seal along the soil-rock contact to

minimize infiltration of groundwater into the socket. In addition, permanent casing provides confinement and will increase the flexural stiffness and capacity.

#### **5.2.4.3 Rock Socket Sidewall Disturbance**

The drilled shafts will be socketed into the underlying bedrock and develop their capacity based on a combination of end bearing and side friction. The condition of the sidewalls of the shaft within the rock socket is critical to the capacity of the drilled shaft. Based on the test borings and recovered bedrock at the land and river boring locations, the predominant bedrock profile consists of shale and/or limestone. Therefore, careful consideration should be given to the construction technique and participation of an experienced contractor. It is recommended that artificial roughening of the rock sockets through use of grooving tools or other measures be used during final pass.

A roughened bedrock sidewall at the concrete-bedrock interface is preferred since increased side resistance develops as opposed to a smooth surface. Smearing of the shale/argillaceous zones in the presence of even minor amounts of water seepage can cause the surface of the rock to become softened. Softening of the sidewall or the creation of a smooth sidewall during drilling can reduce side friction by greater than 50 percent. This effect should be considered during assessment of the contractor's proposed drilled shaft construction method.

#### **5.2.4.4 Additional Comments/Considerations**

The slake durability test provides an index for rock that will weather and degrade rapidly by measurement of the physical breakdown of a rock sample after a series of wet/dry cycles with mechanical agitation by tumbling in a drum. Rock with slake durability index less than 60% are considered prone to rapid deterioration and formation of "smear zones" when the borehole well is exposed to water.

Slake durability testing was performed on portions of the shale bedrock. The SDI (slake durability index) ranged from about 40 to 98 percent – averaging about 73 percent. The effect of drilling fluid on maintaining the integrity of the shale during construction has been documented in several studies. These studies showed the use of polymer slurry during SDI testing showed a markedly improved value and is preferred for use during drilling of the rock socket. Additional slake durability testing using riverwater and potential slurry mixes should be performed during the final study or prior to construction to further evaluate the impact that the drilling fluid has on the shale.

#### **5.2.5 Drilled Shaft – Quality Control**

The performance of a drilled shaft is dependent on the structural strength, geotechnical strength, deformation properties of the soil and rock, pile-soil/rock interaction, and the applied loads. Quality control is critical to the success of the deep foundation system performance. Quality control of drilled shafts can be divided into three categories; diligent inspection, integrity

testing and load testing. We recommend both integrity and load testing be included in the specifications for the proposed bridge foundations.

### **5.2.5.1 Integrity Testing**

Integrity Testing should be employed to assess the structural integrity of the drilled shafts. This testing evaluates the concrete quality, method of placement, construction method, and workmanship. Several methods can be employed including cross-hole sonic logging (CSL), crosshole tomography (CT), and gamma-gamma logging (GGL).

Crosshole sonic logging (CSL) is currently the most commonly used method for quality assurance of drilled shaft concrete. This method provides little indication of concrete soundness outside the cage. The method requires steel (preferred) or plastic tubes installed in the drilled shaft and tied to the rebar cage. One CSL tube should be placed for each foot of shaft diameter. After the shaft is drilled the cage is lowered into the hole and the concrete is placed. The tubes are filled with water as an intermediate medium. After curing for several days, a sound source and receiver are lowered, maintaining a consistent elevation between source and sensor. A signal generator generates a sonic pulse from the emitter which is recorded by the sensor. Relative energy, waveform and differential time are recorded, and logged. This procedure is repeated at regular intervals throughout the shaft and then mapped. The graphs from the various combinations of access tubes are compared and a qualitative idea of the soundness of the concrete throughout the shaft can be established.

Gamma-gamma logging (GGL) can also be performed for evaluation of the drilled shafts. Gamma-gamma logging uses the same principles as nuclear density testing commonly employed in construction. GGL is performed within PVC inspection tubes cast into the shaft during construction. The tubes can also be used for CSL testing. The gamma-gamma probe, which consists of a radioactive source and gamma photon detector separated by a length of shielded material, is lowered and raised within the tubes. During the test, gamma particles are emitted into the concrete surrounding the PVC tube. Some of the gamma particles are scattered back to the detector in the instrument. GGL is performed continuously along the shaft length with gamma count rates collected at set intervals. Multiple inspection tubes, placed around the interior of the steel reinforcing cage, are provided within a pile to obtain a representative sample of the shaft. Typically, one inspection tube per 0.3 meter (1 foot) of shaft diameter is used.

Considering the high loads supported by the drilled shafts, it is recommended that 100% of the shafts be tested using crosshole sonic logging. Crosshole tomography should also be used to develop two and three-dimensional images of signal velocities and assist in quality assurance of drilled shaft concrete. Crosshole tomography testing should be performed when CSL testing indicates significant anomalies are present.

### **5.2.5.2 Load Testing**

As a means to demonstrate the installation plan and to verify the adequacy of the construction methods, tools and quality control/assurance procedures, test shafts should be constructed

## Geotechnical Engineering Report

Brent Spence Bridge Replacement ■ Cincinnati, Ohio-Covington, Kentucky

March 11, 2011 ■ HCN/Terracon Project No. N1105070



consistent with the planned procedures for production shafts. The test shafts can be used to provide site-specific measurement of axial performance under the as-built conditions.

Site-specific field loading tests offer the potential to improve accuracy of the predictions of performance and reliability of the constructed foundations. Load testing can provide information on base resistance, side resistance (total and as a function of depth), and load versus displacement relationships. Both axial and lateral resistance can be determined using the appropriate type of load tests. Because site-specific field loading tests reduces some of the variability associated with predicting performance, the use of large resistance factors are justified when loading tests are performed. Per AASHTO section 10.8.3.5.6 and table 10.5.5.2.4-1, resistance factors for axial compression and uplift (socket resistance), considering static load testing is performed, are 0.7 and 0.6, respectively. If applied to a single shaft supporting a bridge pier, then the resistance factors should be reduced by 20 percent (per AASHTO section 10.5.5.2.4). The AASHTO guidelines in section 10.8.3.5.6 should be adhered to when developing the load testing program.

We recommend axial pier load testing be performed for the proposed bridge foundations. Lateral load testing should also be considered based on the design loads compared to the calculated lateral resistance and pier head movement under the design loads.

Axial pier load testing can be performed using static or dynamic methods. Static load testing generally involves the application of the load through the use of a reaction frame anchored by four or more piers. With the large loads expected for the proposed bridge foundations this method may be costly and difficult to perform, particularly for drilled shafts located in the river. Another method that has been successfully used for large diameter shafts and should be considered here is the Osterberg Cell (O-Cell). The Osterberg Cell consists of a sacrificial hydraulic jack(s) attached to the base of the reinforcing cage and placed in the drilled shaft. After the concrete has cured to a specified strength, the cell is pressurized and load is applied bi-directionally; upward against side friction and downwards against the base friction. Instrumentation including tell-tales and strain gages are used to measure deformation and movement of the shaft. The advantages of employing Osterberg testing versus traditional load testing is no reaction frame is required, higher applied loads can usually be applied, and the side and base resistance components are directly measured.

Considering the size of the project and subsurface variations, a minimum of four (4) load tests is recommended. One (1) test should be performed at each of the river piers and at least one (1) at the Ohio approach structures and at least one (1) at the Kentucky approach structures. The load test locations should be selected based on the loading conditions and evaluation of bedrock conditions. It is recommended that the technique shaft(s) be installed prior to the installation of the load test shafts to allow for an assessment, and if necessary, modifications of the contractor's proposed means and methods of drilled shaft construction before starting work on any of the load test shafts. Once load capacities are finalized and construction means/methods are established, a detailed load testing program can be developed.

Where the design of the foundation is controlled by considerations of lateral loading and significant cost savings are possible with an aggressive design model it may be appropriate to consider lateral load tests to validate or improve the design models. As with the axial testing, both static and dynamic methods can be considered. Static methods typically involve using a hydraulic jack to push two adjacent shafts apart. Load cells and displacement gages are placed between the shafts to measure the applied load and lateral deflection of the shaft head. Dynamic lateral load testing can be performed using the Statnamic system applied horizontally to the shaft head. This method can apply loads 1,000 tons or greater and may be more appropriate for considering impact loading such as vessels or ice. Lateral load testing of single piers or group of piers can be performed.

## **5.3 Driven Piles**

### **5.3.1 Driven Piles- Design**

Driven H-piles to rock were considered for the pier locations in the river. The overburden profile is primarily granular in nature. During drilling some large size gravel and cobbles were also noted in the granular profile. There is an approximate average of a 6 to 10 foot thick cobble/boulder zone above bedrock along the entire bridge alignment. Based on our experience and preliminary driveability analyses, H-piles will not be able to be driven to bedrock. Significant pile damage (even with pile points) is likely. Refusal within the cobble layer is likely at variable depths. We do not recommend that H-piles tip in the cobble zone due to long-term creep/settlement concerns and the reliability of mobilizing end bearing within the highly variable cobble zone. Potential scour, lateral loads, buckling potential of piles in the scour zone, the large number of piles in the pile groups, and the size of the pile cap are some other factors that should also be considered.

Pipe piles filled with concrete (CIP piles) or H-piles could be considered only for support of the approach span piers located on land. We have performed a preliminary analysis to evaluate the load capacity and driveability of 14 and 16 inch diameter CIP piles and HP14x73 piles. The piles develop their capacity through a combination of skin friction and end bearing. Per the 2007 ODOT Bridge Design Manual, 14 inch diameter CIP piles (0.25 inch thickness) can be designed for a Nominal Bearing Value,  $R_{ndr}$ , of 390 kips while 16 inch diameter CIP piles (0.375 inch thickness) can be designed for 450 kips. HP14x73 piles can be designed for a Nominal Bearing Value of 440 kips.

Using the laboratory testing results and the test boring data, DRIVEN software was used to evaluate the pile capacities. A representative boring was chosen for both the Ohio (L-2A) and Kentucky (L-5) portion of the project for this preliminary analysis. Final driven pile design should consider borings at each approach pier location due to variations in the subsurface conditions. In addition, factors such as settlement/fill placement and pre-drilling through debris in the existing fill would need to be considered in the final design.

**Geotechnical Engineering Report**

Brent Spence Bridge Replacement ■ Cincinnati, Ohio-Covington, Kentucky

March 11, 2011 ■ HCN/Terracon Project No. N1105070



Based on the DRIVEN analysis, we estimate that the maximum  $R_{ndr}$  value of 390 kips (14-inch pile), 450 kips (16-inch pile), and 440 kips (HP14x73) can be achieved on the Ohio and Kentucky land portions of the project at the following elevations. These values do not account for any predrilling, negative skin friction or potential scour effects. Negative skin friction will need to be considered if settlement of the soils may occur. In addition, if debris is encountered within the existing fill, then pre-drilling for the pile may be required. If pre-drilling is performed, then adjustments would be required to the design pile length. Final analyses should also consider remediation efforts within the Duke Energy facility on the Ohio land side. A resistance factor ( $\phi_{dyn}$ ) of 0.7 should be applied for piles installed per ODOT CMS Items 507 and 523. The minimum pile spacing should be 3 pile diameters such that a group efficiency of 1.0 can be used in axial design.

**Table 10, Preliminary Driven Pile Recommendations**

Location	Pile Dimensions/Type	$R_{ndr}$ (kips) <sup>1</sup>	Estimated Pile Tip Elevation (feet)
Ohio Abutment (L-2A)	14 inch/CIP	390	401
Ohio Abutment (L-2A)	16 inch/CIP	450	407
Ohio Abutment (L-2A)	HP14x73	440	401
Kentucky Abutment (L-5)	14 inch/CIP	390	408
Kentucky Abutment (L-5)	16 inch/CIP	450	411
Kentucky Abutment (L-5)	HP14x73	440	405

<sup>1</sup> Confirm by restriking piles

A driveability analysis of these piles was performed using GRLWEAP. The analysis shows that driving of both the 14 and 16 inch CIP piles and the HP14x73 piles is feasible to the recommended tip elevation. GRLWEAP software performs wave equation analysis to assess the ability of the proposed pile driving system to install the piles to the required capacity and desired depth within the allowable driving stresses prior to driving piles in the field. The preliminary analysis was performed using the ICE 40-S model hammer.

The pile driving contractor should provide data for the proposed pile driving system prior to commencement of production piles. WAVE Equation analyses should be utilized to assess the ability of the proposed pile driving system to install the piles to the required capacity and desired depth within the allowable driving stresses prior to driving piles in the field. Approval of the proposed driving system (by the engineer) should be required prior to any field load testing program.

The preliminary calculations and results performed using DRIVEN and GRLWEAP have been included in Appendix C of this report.

### **5.3.2 Construction Considerations**

Driven piles for bridge support at the abutments should be installed to depths as required to mobilize design capacities. The capacity of each individual pile should be confirmed during driving using established criteria based on pile load testing. The use of dynamic formulas is a helpful guide but becomes increasingly limited in such soil profiles **and is not recommended for use to establish the production pile driving criteria.**

Prior to installing production piles, a load testing program should be undertaken. This program should involve both dynamic testing during test pile driving, and static pile load tests. Specifically, we recommend the following:

1. Using data provided by the pile driving contractor, use the WAVE Equation analyses (such as GRLWEAP) to assess the ability of the proposed driving system to install piles as to the required capacity and desired penetration depth within the allowable driving stresses. Approval of the proposed driving system (by the Engineer) should be required prior to any field load testing program.
2. Dynamic pile testing is recommended on the piles on which static load tests are performed. The indicator (test) pile testing should be performed to monitor hammer and drive system performance, assess pile installation stresses and integrity, as well as to evaluate pile capacity. It is suggested that dynamic testing be performed during both initial and restrike driving. The testing during initial driving is primarily to monitor drive system performance and driving stresses. Dynamic testing during restrike is recommended since it yields a better indication of long-term pile capacity. The dynamic load test data should be analyzed using CAPWAP analyses to determine the actual pile capacity. The final production pile driving criteria and final driving system approval will be based on CAPWAP test results.
3. Static loading testing should also be performed per ODOT guidelines. The load testing program should be reviewed by the geotechnical engineer prior to implementing the load testing program to allow for modifications. It is recommended that at least two static pile load (compression) tests for each design capacity be performed on both the Ohio and Kentucky sides of the river. If significant uplift loads are present, the uplift load test(s) should also be performed. Lateral load test(s) may also be needed if large lateral loads are anticipated and based on computed load deflection response.
4. It is recommended that the piles which are statically load tested be restruck with dynamic testing within 48 hours after completion of the static load test so that a correlation between static and dynamic test results can be obtained for reference across the site. The restrike driving sequence should be performed with a warmed up hammer and shall consist of striking the piles for 50 blows or until the pile

## Geotechnical Engineering Report

Brent Spence Bridge Replacement ■ Cincinnati, Ohio-Covington, Kentucky

March 11, 2011 ■ HCN/Terracon Project No. N1105070



penetrates an additional 3 inches, whichever occurs first. Also, CAPWAP analyses of the dynamic pile testing data should be performed on the data obtained from the end of the initial driving and the beginning of restrike of indicator piles. CAPWAP is an analytical method that combines field measured data with wave equation type procedures to predict the pile's static bearing capacity and resistance distribution.

5. Perform dynamic load testing on the first two production piles and about 5 percent of all piles during installation. The production pile driving criteria may continually need to be modified based on the results of these dynamic tests.

The bridge foundation piles should be spaced at least a distance of 3 times the pile width/diameter dimension. This spacing is to eliminate group effects for axially loaded piles. For laterally loaded vertical piles, detailed analyses (such as LPILE and/or GROUP) will be needed to assess pile spacing effects. Additional details regarding spacing are discussed in the drilled shaft section of this report.

The program GROUP was developed to compute the distribution of loads (vertical, lateral, and bending moment) from the pile cap to piles in a symmetrical group. The program also computes deflection, translation, and settlement of the cap. The program generates internally the nonlinear response of the soil, in the form of t-z curves for axial loading and p-y curves for lateral loading. The equations of equilibrium are satisfied, and compatibility is achieved between pile movement and soil response, and between the movement of the cap and pile head movement. Once the pile configurations, pile head fixity, and lateral loads are known, detailed lateral load analyses for pile groups can be performed.

Settlement of pile groups will need to be evaluated once the pile group geometry and loading has been finalized. Downdrag should also be included (if applicable).

Due to the urban nature of the surrounding site, and close proximity of the existing bridge and other structures, a preconstruction survey should be performed prior to construction. We recommend that vibration monitoring be performed along the existing bridge during pile driving. Vibration monitoring should also be considered during construction near sensitive structures and/or underground features.

### 5.4 Seismic Considerations

We based our approach for the seismic considerations on the following documents:

- AASHTO LRFD Bridge Design Specifications
- AASHTO Guide Specifications for LRFD Seismic Bridge Design
- Recommended LRFD Guidelines for the Seismic Design of Highway Bridges (MCEER/ATC-49)





The AASHTO documents specify designing for the life safety performance objective considering a seismic hazard corresponding to a seven percent probability of exceedance in 75 years (return period of approximately 1,000 years) for an “essential” structure. Life safety for this design event is taken to imply that the bridge has a low probability of collapse, but may suffer significant damage. “Critical” structures (bridges) must remain open to all traffic after the design earthquake and be usable by emergency vehicles and for security/defense purposes immediately after a large earthquake, e.g., a 2500-yr return period event.

**5.4.1 Essential Structure Parameters (AASHTO 7% PE in 75 years – 1,000 return period)**

If it is determined by the project stakeholders that this bridge design should be considered an “essential” structure, the following ground motion parameters would be used. Considering the 1.0-second spectral acceleration of 0.048g on bedrock for the AASHTO 7% PE in 75 years, and a seismic Site Class D for the overall bridge alignment based on shear wave velocity measurements, under Article 3.10.6 of AASHTO LRFD Bridge Design Specifications, the bridge should be assigned to Seismic Zone 1. Liquefaction evaluation is not required for structures located in Seismic Zone 1.

Code Used	Site Classification
2010 AASHTO LRFD Bridge Design Specifications (AASHTO) <sup>1</sup>	D <sup>2</sup>

1. In general accordance with the 2010 AASHTO LRFD Bridge Design Specifications, Table 3.10.3.1-1 AASHTO Site Class is based on the characteristics of the upper 100 feet of the subsurface profile.
2. The 2010 AASHTO LRFD Bridge Design Specifications (2010 AASHTO) requires a site soil profile determination extending a depth of 100 feet for seismic site classification. Terracon used borehole geophysical logging (Suspension PS Velocity Measurements) as included in Exhibit A-11. The Site Class is based upon the subsurface conditions encountered on the project site and the average shear wave velocity of 847 feet/second derived from our seismic survey data at Locations L-1 and L-4).

Ground Motion Parameter	Value (g) <sup>1</sup>
PGA	0.048
S <sub>s</sub>	0.111
S <sub>1</sub>	0.047
A <sub>s</sub>	0.077
S <sub>DS</sub>	0.177
S <sub>D1</sub>	0.113

1. Latitude 39.0888 and Longitude -84.5233 degrees (AASHTO Spectrum 7% PE in 75 years)
2.  $F_{pga} = 1.60$  from Table 3.10.3.2-1
3.  $F_a = 1.60$  from Table 3.10.3.2-2
4.  $F_v = 2.40$  from Table 3.10.3.2-3



**5.4.2 Critical Structure Parameters (2% PE in 50 years - 2,475-year return period)**

If it is determined by the project stakeholders that this bridge design should be considered an “critical” structure, the following seismic guidelines will apply. Considering the 1.0-second spectral acceleration of 0.076g on bedrock identified in Section 2.3 above, and a seismic Site Class D for the overall bridge alignment based on shear wave velocity measurements, under Article 3.10.6 of AASHTO LRFD Bridge Design Specifications, the bridge should be assigned to Seismic Zone 2. Under Article 10.5.4.1, “where loose to very loose saturated sands are within the subsurface soil profile such that liquefaction of these soils could impact the stability of the structure, the potential for liquefaction in Seismic Zone 2 should be considered.” The AASHTO Commentary (p.10-32) indicates that for Seismic Zone 2, this is only required if  $A_s$  is 0.15g or greater. Under these specifications, a liquefaction evaluation is not required. The following ground motion parameters would be applied if it determined that this is a “critical” structure.

Code Used	Site Classification
2010 AASHTO LRFD Bridge Design Specifications (AASHTO) <sup>1</sup>	D <sup>2</sup>

1. In general accordance with the 2010 AASHTO LRFD Bridge Design Specifications, Table 3.10.3.1-1 AASHTO Site Class is based on the characteristics of the upper 100 feet of the subsurface profile.
2. The 2010 AASHTO LRFD Bridge Design Specifications (2010 AASHTO) requires a site soil profile determination extending a depth of 100 feet for seismic site classification. Terracon used borehole geophysical logging (Suspension PS Velocity Measurements) as included in Exhibit A-11. The Site Class is based upon the subsurface conditions encountered on the project site and the average shear wave velocity of 847 feet/second derived from our seismic survey data at Locations L-1 and L-2.

Ground Motion Parameter	Value (g) <sup>1</sup>
PGA	0.080
$S_s$	0.178
$S_1$	0.076
$A_s$	0.128
$S_{DS}$	0.285
$S_{D1}$	0.182

1. Latitude 39.0888 and Longitude -84.5233 degrees (NEHRP Spectrum 2% PE in 50 years)
2.  $F_{pga} = 1.60$  from Table 3.10.3.2-1
3.  $F_a = 1.60$  from Table 3.10.3.2-2
4.  $F_v = 2.40$  from Table 3.10.3.2-3

As noted in Section 4.5, the river pier locations have a distinctly different stratigraphic section than the river banks that will result in different behavior under seismic loads than the abutments. The AASHTO site class and response spectrum approach does not consider such differences

## Geotechnical Engineering Report

Brent Spence Bridge Replacement ■ Cincinnati, Ohio-Covington, Kentucky

March 11, 2011 ■ HCN/Terracon Project No. N1105070



explicitly. Site response analyses should be considered to evaluate the seismic demand on the bridges structural elements and possibly develop time histories for input at each of the abutment and pier locations.

## 6.0 GENERAL COMMENTS

HCN/Terracon should be retained to review the final design plans and specifications so comments can be made regarding interpretation and implementation of our geotechnical recommendations in the design and specifications. HCN/Terracon also should be retained to provide observation and testing services during grading, excavation, foundation construction and other earth-related construction phases of the project.

The analysis and recommendations presented in this report are based upon the data obtained from the borings performed at the indicated locations and from other information discussed in this report. This report does not reflect variations that may occur between borings, across the site, or due to the modifying effects of weather. The nature and extent of such variations may not become evident until during or after construction. If variations appear, we should be immediately notified so that further evaluation and supplemental recommendations can be provided.

The scope of services for this project does not include either specifically or by implication any environmental or biological (e.g., mold, fungi, bacteria) assessment of the site or identification or prevention of pollutants, hazardous materials or conditions. If the owner is concerned about the potential for such contamination or pollution, other studies should be undertaken.

This report has been prepared for the exclusive use of our client for specific application to the project discussed and has been prepared in accordance with generally accepted geotechnical engineering practices. No warranties, either expressed or implied, are intended or made. Site safety, excavation support, and dewatering requirements are the responsibility of others. In the event that changes in the nature, design, or location of the project as outlined in this report are planned, the conclusions and recommendations contained in this report shall not be considered valid unless Terracon reviews the changes and either verifies or modifies the conclusions of this report in writing.

**Geotechnical Engineering Report**

Brent Spence Bridge Replacement ■ Cincinnati, Ohio-Covington, Kentucky  
March 11, 2011 ■ HCN/Terracon Project No. N1105070



**APPENDIX A**  
**FIELD EXPLORATION**

**Geotechnical Engineering Report**

Brent Spence Bridge Replacement ■ Cincinnati, Ohio-Covington, Kentucky

March 11, 2011 ■ HCN/Terracon Project No. N1105070



**FIGURES**



Proposed Brent Spence Bridge Replacement





DIAGRAM IS FOR GENERAL LOCATION ONLY, AND IS NOT INTENDED FOR CONSTRUCTION PURPOSES

Project Manager:	AJM	Project No.	N1105070
Drawn by:	DWW	Scale:	As Shown
Checked by:	AJM	File Name:	A1
Approved by:	AJM	Date:	11/30/2010

611 Lunken Park Drive Cincinnati, Ohio 45226  
 PH. (513) 321-5816 FAX. (513) 321-0294

SITE VICINITY MAP  
 PROPOSED BRENT SPENCE BRIDGE  
 REPLACEMENT  
 PARSONS BRINCKERHOFF  
 CINCINNATI, OHIO – COVINGTON, KENTUCKY

Exhibit  
**A-1**



REV.	DATE	BY	DESCRIPTION


**TEST BORING LOCATION PLAN**  
 PROPOSED BRENT SPENCE BRIDGE REPLACEMENT  
**PARSONS BRINCKERHOFF**  
 CINCINNATI, OHIO - COVINGTON, KENTUCKY

**A Terracon COMPANY**  
 611 LUNKEN PARK DRIVE  
 CINCINNATI, OHIO 45226  
 PH. (513) 321-8816 FAX. (513) 321-4540

**EXHIBIT A-2**

DESIGNED BY:	DW
DRAWN BY:	KM
APPVD. BY:	DW
SCALE:	1"=200'
DATE:	12/01/2010
JOB NO.:	N1105070
ACAD NO.:	EXHIBIT A-2.DGN
SHEET NO.:	A-2

# OHIO - LAND BORINGS



REV.	DATE	BY	DESCRIPTION

SUMMARY OF GEOTECHNICAL DATA  
 PROPOSED BRENT SPENCE BRIDGE REPLACEMENT  
**PARSONS BRINCKERHOFF**  
 CINCINNATI, OHIO - COVINGTON, KENTUCKY



**A Terracon COMPANY**  
 CINCINNATI, OHIO 45226  
 PH. (513) 321-5816  
 FAX. (513) 321-4540  
 611 LUNKEN PARK DRIVE

**EXHIBIT A-3**

DESIGNED BY:	DW
DRAWN BY:	KM
APPVD. BY:	DW
SCALE:	1"=50' H
DATE:	12/01/2010
JOB NO.:	N1105070
ACAD NO.:	EXHIBIT A-3.DGN
SHEET NO.:	A-3



# OHIO - RIVER BORINGS



REV.	DATE	BY	DESCRIPTION


SUMMARY OF GEOTECHNICAL DATA  
 PROPOSED BRENT SPENCE BRIDGE REPLACEMENT  
**PARSONS BRINCKERHOFF**  
 CINCINNATI, OHIO - COVINGTON, KENTUCKY

**Terracon COMPANY**  
 CINCINNATI, OHIO 45226  
 PH. (513) 321-5616 FAX. (513) 321-4540

EXHIBIT A-4

DESIGNED BY:	DW
DRAWN BY:	KM
APPVD. BY:	DW
SCALE:	1"=50' H
DATE:	12/01/2010
JOB NO.:	N1105070
ACAD NO.:	EXHIBIT A-4.DGN
SHEET NO.:	A-4

# KENTUCKY - RIVER BORINGS



REV.	DATE	BY	DESCRIPTION


**SUMMARY OF GEOTECHNICAL DATA**  
 PROPOSED BRENT SPENCE BRIDGE REPLACEMENT  
**PARSONS BRINCKERHOFF**  
 CINCINNATI, OHIO - COVINGTON, KENTUCKY

**FCN**  
**A Terracon COMPANY**  
 CINCINNATI, OHIO 45226  
 PH. (513) 321-4540  
 FAX. (513) 321-4540

**EXHIBIT A-5**

DESIGNED BY:	DW
DRAWN BY:	KM
APPVD. BY:	DW
SCALE:	1"=50' H
DATE:	12/01/2010
JOB NO.:	N1105070
ACAD NO.:	EXHIBIT A-5.DGN
SHEET NO.:	A-5

KENTUCKY - LAND BORINGS




DESCRIPTION	
REV.	DATE
BY	

SUMMARY OF GEOTECHNICAL DATA  
 PROPOSED BRENT SPENCE BRIDGE REPLACEMENT  
**PARSONS BRINCKERHOFF**  
 CINCINNATI, OHIO - COVINGTON, KENTUCKY

**FCN**  
 A Terracon COMPANY  
 CINCINNATI, OHIO 45226  
 611 LUNKEN PARK DRIVE  
 PH: (513) 321-5816  
 FAX: (513) 321-4540

**EXHIBIT A-6**  
 DESIGNED BY: DW  
 DRAWN BY: KM  
 APPVD. BY: DW  
 SCALE: 1"=50' H  
 DATE: 12/01/2010  
 JOB NO.: N1105070  
 ACAD NO.: EXHIBIT A-6.DGN  
 SHEET NO.: A-6



**LEGEND**

- EXISTING FILL
- FINE SAND
- SILT AND CLAY
- GRAVEL AND SAND
- POINT PLEASANT FORMATION
- LEXINGTON LIMESTONE FORMATION

NOTE:  
TRANSITION FROM POINT PLEASANT TO LEXINGTON LIMESTONE FORMATION IS GRADUAL AND NOT SUDDEN AS DEPICTED HERE.

**GENERALIZED SUBSURFACE PROFILE**

NOTE:  
DIAGRAM IS FOR GENERAL ILLUSTRATION PURPOSES ONLY AND IS NOT INTENDED FOR CONSTRUCTION PURPOSES. THE STRATIFICATION HAS BEEN INTERPOLATED AND VARIATIONS SHOULD BE EXPECTED.

REV.	DATE	BY	DESCRIPTION

**SUBSURFACE PROFILE**  
**PROPOSED BRENT SPENCE BRIDGE REPLACEMENT**  
**PARSONS BRINCKERHOFF**  
 CINCINNATI, OHIO - COVINGTON, KENTUCKY

**FCN**  
**A Terracon COMPANY**  
 CINCINNATI, OHIO 45226  
 611 LUNKEN PARK DRIVE  
 PH. (513) 321-3816  
 FAX. (513) 321-4540

EXHIBIT A-7	
DESIGNED BY:	DW
DRAWN BY:	KM
APPVD. BY:	DW
SCALE:	1"=300'H
DATE:	12/03/2010
JOB NO.:	N1105070
ACAD NO.:	EXHIBIT A-7.DWG
SHEET NO.:	A-7

**Geotechnical Engineering Report**

Brent Spence Bridge Replacement ■ Cincinnati, Ohio-Covington, Kentucky  
March 11, 2011 ■ HCN/Terracon Project No. N1105070



**TEST BORING LOGS &  
ROCK CORE PHOTOGRAPHS**

PROJECT: BRENT SPENCE BRIDGE	DRILLING FIRM / OPERATOR: HCN / JJ	DRILL RIG: CME 550X ATV- 9333	STATION / OFFSET: 23+99.9, 84.1 RT	EXPLORATION ID: L-1
TYPE: BRIDGE REPLACEMENT	SAMPLING FIRM / LOGGER: HCN / DWW	HAMMER: CME AUTOMATIC	ALIGNMENT: PROPOSED BSB	
PID: 75119 BR ID:	DRILLING METHOD: 3.25" HSA / NQ	CALIBRATION DATE: 2/4/10	ELEVATION: 494.6 (MSL) EOB: 182.5 ft.	PAGE 1 OF 3
START: 7/16/10 END: 7/20/10	SAMPLING METHOD: SPT / ST / NQ	ENERGY RATIO (%): 67.1	COORD: 39.093833610, -84.522929480	

MATERIAL DESCRIPTION AND NOTES	ELEV.	DEPTHS	SPT/ RQD	N <sub>60</sub>	REC (%)	SAMPLE ID	HP (tsf)	GRADATION (%)					ATTERBERG				DOT CLASS (G)	HOLE SEALED	
								GR	CS	FS	SI	CL	LL	PL	PI	WC			
ASPHALT PRE-DRILLED (VACUUM EXCAVATED)	494.6 494.2	1 2 3 4 5																	
VERY STIFF, BROWN, SANDY SILT, TRACE TO LITTLE GRAVEL, LITTLE CLAY, TRACE CONCRETE AND BRICK (FILL), WET	488.6	6	2	1	2	33	SS-1	-	-	-	-	-	-	-	-	-	17	A-4a (V)	
		7	1	1		33	SS-2	-	17	5	27	36	15	27	17	10	30	A-4a (3)	
		10	3	4	5	10	100	SS-3	2.50	0	0	36	47	17	24	16	8	19	A-4a (6)
		13				100	ST-4	-	-	-	-	-	-	-	-	-	-	20	A-4a (V)
		14	2	3	3	7	100	SS-5	1.50	0	0	24	56	20	27	17	10	22	A-4b (8)
MEDIUM STIFF TO STIFF, BROWN, SILT, LITTLE CLAY, SOME SAND, TRACE ORGANICS, LOI=1.6% (17.5), MOIST	480.6	18	2	3	3	7	100	SS-6	0.50	-	-	-	-	-	-	-	23	A-4b (V)	
		20	2	3	3	7	100	SS-7	0.75	0	0	43	41	16	20	18	2	21	A-4a (4)
		25	2	3	4	8	100	SS-8	1.00	-	-	-	-	-	-	-	19	A-4a (V)	
MEDIUM STIFF, BROWN, SANDY SILT, LITTLE CLAY, SOME SAND SEAMS, MOIST	474.6	30	2	4	5	10	100	SS-9	1.00	0	1	36	45	18	23	17	6	19	A-4a (6)
		35	3	5	5	11	100	SS-10	0.50	-	-	-	-	-	-	-	28	A-4a (V)	
		40	4	4	5	10	100	SS-11	-	38	19	17	19	7	24	16	8	15	A-2-4 (0)
LOOSE TO MEDIUM DENSE, BROWN, SANDY SILT, LITTLE CLAY, WET	464.6	44																	
		45	25	28	19	53	100	SS-12	-	61	20	11	6	2	NP	NP	NP	10	A-1-a (0)
LOOSE, BROWN, GRAVEL AND STONE FRAGMENTS WITH SAND AND SILT, TRACE CLAY, WET	454.6	50	20	18	15	37	33	SS-13	-	-	-	-	-	-	-	-	15	A-3a (V)	
		55	5	6	12	20	67	SS-14	-	11	32	39	14	4	NP	NP	NP	16	A-3a (0)
VERY DENSE, BROWN, GRAVEL AND STONE FRAGMENTS, SOME SAND, TRACE SILT, TRACE CLAY, WET	449.6	56																	
		57																	
MEDIUM DENSE TO DENSE, BROWN, COARSE AND FINE SAND, LITTLE GRAVEL, LITTLE SILT, TRACE CLAY, WET	444.6	58																	
		59																	

STANDARD ODOT SOIL BORING LOG (11 X 17) - OH DOT.GDT - 3/9/11 10:06 - N:\PROJECTS\2010\N1105070\GINT\ODOT LOGS.GPJ

MATERIAL DESCRIPTION AND NOTES	ELEV.	DEPTHS	SPT/RQD	N <sub>60</sub>	REC (%)	SAMPLE ID	HP (tsf)	GRADATION (%)					ATTERBERG			WC	ODOT CLASS (G)	HOLE SEALED
								GR	CS	FS	SI	CL	LL	PL	PI			
MEDIUM DENSE TO DENSE, BROWN, <b>COARSE AND FINE SAND</b> , LITTLE GRAVEL, LITTLE SILT, TRACE CLAY, WET (continued)	434.6	61	9 9	20	78	SS-15	-	-	-	-	-	-	-	-	-	-	19	A-3a (V)
		62																
		63																
		64																
		65																
		66	20 18 15	37	67	SS-16	-	6	27	54	9	4	NP	NP	NP		19	A-3a (0)
		67																
		68																
		69																
		70	16 17 21	42	67	SS-17	-	-	-	-	-	-	-	-	-	-	11	A-3a (V)
DENSE, BROWN, <b>GRAVEL AND STONE FRAGMENTS WITH SAND</b> , TRACE SILT, TRACE CLAY, WET	419.6	75	15 17 11	31	100	SS-18	-	32	20	38	7	3	NP	NP	NP		15	A-1-b (0)
		76																
		77																
		78																
		79																
		80	24 17 16	37	100	SS-19	-	-	-	-	-	-	-	-	-	-	59	A-1-b (V)
		81																
		82																
		83																
		84																
MEDIUM DENSE, BROWN, <b>FINE SAND</b> , SOME COARSE SAND, TRACE SILT, TRACE CLAY, WET	409.6	85	14 13 14	30	67	SS-20	-	0	21	71	4	4	NP	NP	NP		22	A-3 (0)
		86																
		87																
		88																
		89																
		90	13 12 13	28	67	SS-21	-	-	-	-	-	-	-	-	-	-	11	A-3 (V)
		91																
		92																
		93																
		94																
MEDIUM DENSE TO DENSE, BROWN, <b>GRAVEL AND STONE FRAGMENTS WITH SAND</b> , TRACE SILT, TRACE CLAY, VERY DENSE BELOW 100', WET	399.6	95	11 11 12	26	83	SS-22	-	47	26	20	5	2	NP	NP	NP		11	A-1-b (0)
		96																
		97																
		98																
		99																
		100	17 33 34	75	100	SS-23	-	-	-	-	-	-	-	-	-	-	23	A-1-b (V)
		101																
		102																
		103																
		104																
DENSE TO VERY DENSE, BROWN, <b>GRAVEL AND STONE FRAGMENTS</b> , SOME SAND, TRACE SILT, TRACE CLAY, WET	389.6	105	15 18 20	42	67	SS-24	-	-	-	-	-	-	-	-	-		23	A-1-a (V)
		106																
		107																
		108																
		109																
		110	19 23 24	53	56	SS-25	-	58	21	13	7	1	NP	NP	NP		12	A-1-a (0)
		111																
		112																
		113																
		114																
VERY DENSE, BROWN, <b>GRAVEL AND STONE FRAGMENTS WITH SAND</b> , TRACE SILT, TRACE CLAY, WET	374.6	115	20 23 40	70	33	SS-26	-	-	-	-	-	-	-	-	-		10	A-1-a (V)
		116																
		117																
		118																
		119																
		120	10 16 31	53	44	SS-27	-	11	52	29	7	1	NP	NP	NP		15	A-1-b (0)
		121																

STANDARD ODOT SOIL BORING LOG (11 X 17) - OH.DOT.GDT - 3/9/11 10:06 - N:\PROJECTS\1010\1105070\GINT\ODOT LOGS.GPJ

MATERIAL DESCRIPTION AND NOTES	ELEV.	DEPTH	SPT/ RQD	N <sub>60</sub>	REC (%)	SAMPLE ID	HP (tsf)	GRADATION (%)					ATTERBERG				HOLE SEALED		
								GR	CS	FS	SI	CL	LL	PL	PI	WC			
VERY DENSE, BROWN, GRAVEL AND STONE FRAGMENTS WITH SAND, TRACE SILT, TRACE CLAY, WET (continued)	372.7	123																	
		124																	
		125	30 37 50/3"	-	80	SS-28	-	-	-	-	-	-	-	-	-	10	A-1-b (V)		
<b>INTERBEDDED LIMESTONE (80%) AND SHALE (20%);</b> LIMESTONE, GRAY, SLIGHTLY WEATHERED, STRONG, THIN BEDDED, CRYSTALLINE, FOSSILIFEROUS SEAMS, FRACTURED, LOSS 10%, RQD 39%; SHALE, GRAY, SLIGHTLY WEATHERED, WEAK, LAMINATED, FISSILE, FRACTURED  LS @129.9'-130.3' QU=10982 PSI SH @ 137.1' SDI = 68.0 LS @ 139.5' POINT LOAD = 14651 PSI LS @142.7'-143.2' QU=9375 PSI LS @ 145.0' POINT LOAD = 15893 PSI SH @ 147.7' SDI = 67.3 LS @150.7'-151.3' QU=21926 PSI LS @153.5'-154' QU=12023 PSI LS @156'-157' QU=10166 PSI SH @ 157.0' SDI = 67.8 LS/SH @162.5'-163' QU=8652 PSI.	367.6	TR																	
	127																		
	128		29		86	NQ-1												CORE	
	129																		
	130																		
	131																		
	132																		
	133		0		40	NQ-2													CORE
	134																		
	135																		
	136																		
	137																		
	138		20		80	NQ-3													CORE
	139																		
	140																		
	141																		
	142																		
	143		52		100	NQ-4													CORE
	144																		
145																			
146																			
147																			
148		20		100	NQ-5													CORE	
149																			
150																			
151																			
152																			
153		54		100	NQ-6													CORE	
154																			
155																			
156																			
157																			
158		48		100	NQ-7													CORE	
159																			
160																			
161																			
162																			
163		64		100	NQ-8													CORE	
164																			
165																			
166		60		98	NQ-9													CORE	
167	327.3																		
BLANK DRILLED FOR SEISMIC TESTING																			
		312.1	EOB																

STANDARD ODOT SOIL BORING LOG (11 X 17) - OH.DOT.GDT - 3/9/11 10:06 - N:\PROJECTS\2010\1105070\GINT\ODOT LOGS.GPJ

NOTES: WATER USED BELOW 6 FT. FOR DRILLING/ROCK CORING PURPOSES. 3 INCH PVC CASING PLACED FROM SURFACE TO 182.5 FEET. CASING BROKE DURING ATTEMPTED REMOVAL AND WA  
 ABANDONMENT METHODS, MATERIALS, QUANTITIES: BACKFILLED WITH BENTONITE GROUT (13 BAGS CEMENT/2 BAGS BENTONITE)






BORING NO.: L-1  
 CORE BOX NO.: 1 OF 3  
 DEPTH (ft.): 127.0-145.5  
 ELEVATION (ft.): 366.46  
 1/NQ: 127.0' – 130.5'; REC. 86%, RQD 29%  
 2/NQ: 130.5' – 135.5'; REC. 40%, RQD 0%  
 3/NQ: 135.5' – 140.5'; REC. 80%, RQD 20%  
 4/NQ: 140.5' – 145.5'; REC. 100%, RQD 52%



BORING NO.: L-1  
 CORE BOX NO.: 2 OF 3  
 DEPTH (ft.): 145.5-160.5  
 ELEVATION (ft.): 347.96  
 5/NQ: 145.5' – 150.5'; REC. 100%, RQD 20%  
 6/NQ: 150.5' – 155.5'; REC. 100%, RQD 54%  
 7/NQ: 155.5' – 160.5'; REC. 100%, RQD 48%



BORING NO.: L-1  
 CORE BOX NO.: 3 OF 3  
 DEPTH (ft.): 160.5-167.3  
 ELEVATION (ft.): 332.96  
 8/NQ: 160.5' – 165.5'; REC. 100%, RQD 64%  
 9/NQ: 165.5' – 167.3'; REC. 100%, RQD 61%

Project Mngr.: AJM	PN: N1105070	 611 LUNKEN PARK DRIVE CINCINNATI, OHIO 45226	<b>ROCK CORE PHOTOGRAPHS</b>	BORING
Drawn By: TCF	Scale: As Shown		BRENT SPENCE BRIDGE REPLACEMENT PARSONS BRINCKERHOFF CINCINNATI, OHIO	L-1
Chkd By: DWW	File No. Core A			
Approved By: AJM	Date: 9-3-10			

PROJECT: BRENT SPENCE BRIDGE TYPE: BRIDGE REPLACEMENT PID: 75119 BR ID: START: 7/29/10 END: 8/1/10		DRILLING FIRM / OPERATOR: HCN / JJ SAMPLING FIRM / LOGGER: HCN / DRK/DWW DRILLING METHOD: 3.25" HSA / NQ SAMPLING METHOD: SPT / ST / NQ		DRILL RIG: CME 550X ATV- 9333 HAMMER: CME AUTOMATIC CALIBRATION DATE: 2/4/10 ENERGY RATIO (%): 67.1		STATION / OFFSET: 25+58.6, 50.9 RT ALIGNMENT: PROPOSED BSB ELEVATION: 489.7 (MSL) EOB: 163.0 ft. COORD: 39.094153260, -84.522842640		EXPLORATION ID: L-1A PAGE 1 OF 3												
MATERIAL DESCRIPTION AND NOTES		ELEV.	DEPTHS	SPT/ RQD	N <sub>60</sub>	REC (%)	SAMPLE ID	HP (tsf)	GRADATION (%)					ATTERBERG				WC	DOT CLASS (GI)	HOLE SEALED
PRE-DRILLED (VACUUM EXCAVATED)		489.7	1-4						GR	CS	FS	SI	CL	LL	FL	FI				
MEDIUM STIFF TO STIFF, BROWN, SANDY SILT, LITTLE CLAY, MOIST		484.7	5-7	2 2 3	6	100	SS-1	0.50	-	-	-	-	-	-	-	-	29	A-4a (V)		
		479.7	8-9	3 4 5	10	100	SS-2	1.50	0	0	32	49	19	26	16	10	19	A-4a (7)		
LOOSE, BROWN, SILT, SOME SAND, LITTLE CLAY, MOIST		474.7	10-12	2 2 3	6	100	SS-3	1.50	0	2	28	52	18	24	16	8	20	A-4b (7)		
		474.7	13-14			75	ST-4	-	-	-	-	-	-	-	-	-	22	A-4b (V)		
LOOSE, GRAY AND BROWN, SANDY SILT, LITTLE CLAY, MOIST		472.2	15-16	3 2 3	6	100	SS-5	-	0	2	48	39	11	NP	NP	NP	22	A-4a (3)		
STIFF, BROWN, SILT, SOME FINE SAND, LITTLE CLAY, MOIST		472.2	17-19	3 3 4	8	100	SS-6	1.75	-	-	-	-	-	-	-	-	21	A-4b (V)		
		472.2	20-21	3 3 3	7	100	SS-7	1.50	0	0	30	51	19	25	16	9	22	A-4b (7)		
		472.2	24-25			100	ST-8	1.25	-	-	-	-	-	-	-	-	21	A-4b (V)		
		472.2	26-27	2 4 7	12	100	SS-9	1.00	-	-	-	-	-	-	-	-	25	A-4b (V)		
		472.2	30-31	2 2 2	4	100	SS-10	-	0	0	15	63	22	28	18	10	29	A-4b (8)		
		472.2	35-36	3 3 3	7	100	SS-11	-	0	0	30	54	16	27	20	7	26	A-4b (7)		
LOOSE, GRAY, SILT, SOME FINE SAND, LITTLE CLAY, MOIST		454.7	35-39																	
VERY DENSE, BROWN, GRAVEL AND STONE FRAGMENTS, SOME SAND, TRACE SILT, TRACE CLAY, WET		449.7	40-41	17 21 32	59	100	SS-12	-	53	25	9	9	4	NP	NP	NP	8	A-1-a (0)		
MEDIUM DENSE TO DENSE, BROWN, COARSE AND FINE SAND, LITTLE SILT, TRACE TO LITTLE GRAVEL, TRACE CLAY, WET		444.7	45-46	6 8 5	15	100	SS-13	-	19	27	37	13	4	NP	NP	NP	18	A-3a (0)		
		444.7	50-51	6 7 8	17	100	SS-14	-	1	22	59	13	5	NP	NP	NP	22	A-3a (0)		
		429.7	56-57	14 14 14	31	100	SS-15	-	-	-	-	-	-	-	-	-	18	A-3a (V)		

MATERIAL DESCRIPTION AND NOTES	ELEV. 429.7	DEPTHS	SPT/ RQD	N <sub>60</sub>	REC (%)	SAMPLE ID	HP (tsf)	GRADATION (%)					ATTERBERG			WC	ODOT CLASS (G)	HOLE SEALED
								GR	CS	FS	SI	CL	LL	PL	PI			
MEDIUM DENSE TO DENSE, BROWN, GRAVEL AND STONE FRAGMENTS WITH SAND AND SILT, TRACE CLAY, WET			8 10 12	25	100	SS-16	-	22	13	34	21	10	NP	NP	NP	21	A-2-4 (0)	
		61																
		62																
		63																
		64																
		65	12 16 17	37	100	SS-17	-	-	-	-	-	-	-	-	-	17	A-2-4 (V)	
		66																
		67																
		68																
		69																
	419.7	70	13 14 19	37	100	SS-18	-	3	32	57	4	4	NP	NP	NP	20	A-3 (0)	
		71																
		72																
		73																
		74																
		75	11 15 15	34	100	SS-19	-	-	-	-	-	-	-	-	-	14	A-3 (V)	
		76																
		77																
		78																
		79																
		80	8 13 15	31	100	SS-20	-	7	28	56	5	4	NP	NP	NP	19	A-3 (0)	
		81																
		82																
		83																
		84																
		85	14 13 15	31	100	SS-21	-	-	-	-	-	-	-	-	-	21	A-3 (V)	
		86																
		87																
		88																
		89																
	399.7	90	16 10 10	22	56	SS-22	-	38	21	34	4	3	NP	NP	NP	14	A-1-b (0)	
		91																
		92																
		93																
		94																
		95	10 22 18	45	100	SS-23	-	-	-	-	-	-	-	-	-	20	A-1-b (V)	
		96																
		97																
		98																
		99																
		100	15 23 15	42	100	SS-24	-	32	31	28	6	3	NP	NP	NP	15	A-1-b (0)	
		101																
		102																
		103																
		104																
		105	16 17 21	42	100	SS-25	-	-	-	-	-	-	-	-	-	16	A-1-b (V)	
		106																
		107																
		108																
		109																
		110	10 11 18	32	67	SS-26	-	43	35	16	4	2	NP	NP	NP	9	A-1-b (0)	
		111																
		112																
		113																
		114																
	374.7	115	43 30 25	62	100	SS-27	-	-	-	-	-	-	-	-	-	8	A-1-a (V)	
		116																
		117																
		118																
		119																
	368.7	120	20 48 50/1"	-	92	SS-28	-	74	7	12	5	2	NP	NP	NP	9	A-1-a (0)	
		121																
		TR																

STANDARD ODOT SOIL BORING LOG (11 X 17) - OH DOT.GDT - 3/9/11 10:06 - N:\PROJECTS\2010\1105070\GINT\ODOT LOGS.GPJ

MATERIAL DESCRIPTION AND NOTES	ELEV. 367.8	DEPTHS	SPT/ RQD	N <sub>60</sub>	REC (%)	SAMPLE ID	HP (tsf)	GRADATION (%)					ATTERBERG				ODOT CLASS (G)	HOLE SEALED
								GR	CS	FS	SI	CL	LL	PL	PI	WC		
<b>INTERBEDDED LIMESTONE (80%) AND SHALE (20%);</b> <b>LIMESTONE</b> , GRAY, SLIGHTLY WEATHERED, STRONG, THIN BEDDED, ARGILLACEOUS, MODERATELY FRACTURED, LOSS 0%, RQD 36%; <b>SHALE</b> , GRAY, SLIGHTLY WEATHERED, VERY WEAK TO WEAK, LAMINATED, LS @123.1'-123.7' QU=10192 PSI  LS @132.3'-132.8' QU=13597 PSI LS @ 140.1' POINT LOAD = 9157 PSI LS @ 152.6' POINT LOAD = 12346 PSI LS @ 154.5' POINT LOAD = 11932 PSI. <i>(continued)</i>	367.8	123																
			124															
			125	16		100	NQ-1											CORE
			126															
			127															
			128															
			129															
			130	44		100	NQ-2											CORE
			131															
			132															
			133															
			134															
		135	24		100	NQ-3											CORE	
		136																
		137																
		138																
		139																
		140	60		100	NQ-4											CORE	
		141																
		142																
	346.7	143																
<b>LIMESTONE</b> , GRAY, UNWEATHERED, MODERATELY STRONG TO STRONG, THIN BEDDED, ARGILLACEOUS, SHALE PARTINGS, LOSS 0%, RQD 67%  LS @143'-143.5' QU=5891 PSI LS @150.7'-151.1' QU=13391 PSI.		144																
			145	66		100	NQ-5											CORE
			146															
			147															
			148															
			149															
		150	68		100	NQ-6											CORE	
		151																
		152																
	336.7	153																
<b>LIMESTONE</b> , GRAY, UNWEATHERED, MODERATELY STRONG, THIN BEDDED, FOSSILIFEROUS, ARGILLACEOUS SEAMS, LOSS 0%, RQD 86%  LS @160'-160.5' QU=4409 PSI.		154																
			155	76		100	NQ-7											CORE
			156															
			157															
			158															
		159																
		160	96		100	NQ-8											CORE	
		161																
		162																
	326.7	163																
		EOB																

STANDARD ODOT SOIL BORING LOG (11 X 17) - OH.DOT.GDT - 3/9/11 10:06 - N:\PROJECTS\2010\1105070\GINT\ODOT LOGS.GPJ


NOTES: WATER USED BELOW 40 FT. FOR DRILLING/ROCK CORING PURPOSES.  
 ABANDONMENT METHODS, MATERIALS, QUANTITIES: BACKFILLED WITH BENTONITE GROUT (15 BAGS CEMENT/2 BAGS BENTONITE)




BORING NO.: L- 1A  
 CORE BOX NO.: 1 OF 3  
 DEPTH (ft.): 123.0-138.0  
 ELEVATION (ft.): 368.45  
 1/NQ: 123.0' – 128.0'; REC. 100%, RQD 16%  
 2/NQ: 128.0' – 133.0'; REC. 100%, RQD 44%  
 3/NQ: 133.0 – 138.0'; REC. 100%, RQD 24%



BORING NO.: L- 1A  
 CORE BOX NO.: 2 OF 3  
 DEPTH (ft.): 138.0 – 153.0  
 ELEVATION (ft.): 353.45  
 4/NQ: 138.0' – 143.0'; REC. 100%, RQD 60%  
 5/NQ: 143.0'-148.0'; REC. 100%, RQD 66%  
 6/NQ: 148.0' – 153.0'; REC. 100%, RQD 68%



BORING NO.: L- 1A  
 CORE BOX NO.: 3 OF 3  
 DEPTH (ft.): 153.0 – 163.0  
 ELEVATION (ft.): 333.45  
 7/NQ: 153.0' – 158.0'; REC. 100%, RQD 76%  
 8/NQ: 158.0' – 163.0'; REC. 100%, RQD 96%

Project Mngr.: AJM	PN. N1105070	 611 LUNKEN PARK DRIVE CINCINNATI, OHIO 45226	ROCK CORE PHOTOGRAPHS	BORING
Drawn By: TCF	Scale: As Shown		BRENT SPENCE BRIDGE REPLACEMENT PARSONS BRINCKERHOFF CINCINNATI, OHIO	L-1A
Chkd By: DWW	File No. Core A			
Approved By: AJM	Date: 9-3-10			

PROJECT: BRENT SPENCE BRIDGE		DRILLING FIRM / OPERATOR: HCN / JM		DRILL RIG: DIEDRICH D-50		STATION / OFFSET: 21+82.9, 54.9 LT		EXPLORATION ID												
TYPE: BRIDGE REPLACEMENT		SAMPLING FIRM / LOGGER: HCN / DRK/DWW		HAMMER: CME AUTOMATIC		ALIGNMENT: PROPOSED BSB		L-2												
PID: 75119 BR ID:		DRILLING METHOD: 3.25" HSA / NQ		CALIBRATION DATE: 9/9/10		ELEVATION: 496.3 (MSL) EOB: 168.5 ft.		PAGE												
START: 5/28/10 END: 6/1/10		SAMPLING METHOD: SPT / ST / NQ		ENERGY RATIO (%): 83.7		COORD: 39.093247060, -84.523175560		1 OF 3												
MATERIAL DESCRIPTION AND NOTES		ELEV.	DEPTH	SPT/RQD	N <sub>60</sub>	REC (%)	SAMPLE ID	HP (tsf)	GRADATION (%)					ATTERBERG				ODOT CLASS (GI)	HOLE SEALED	
				GR	CS	FS	SI	CL	LL	FL	FI	WC								
PRE-DRILLED (VACUUM EXCAVATION)		496.3	1-9																	
VERY LOOSE TO LOOSE, BLACK, GRAVEL AND STONE FRAGMENTS WITH SAND, SOME CINDERS, TRACE BRICK FRAGMENTS (FILL), MOIST TO WET		486.3	10-21	2 1 2	4	67	SS-1	-	-	-	-	-	-	-	-	-	-	-	-	A-1-b (V)
			13-14	1 1 1	3	67	SS-2	-	-	-	-	-	-	-	-	-	-	-	-	A-1-b (V)
			15-16	3 4 3	10	100	SS-3	-	-	-	-	-	-	-	-	-	-	-	35	A-1-b (V)
			18-19	2 1 1	3	67	SS-4	-	-	-	-	-	-	-	-	-	-	-	37	A-1-b (V)
			20-21	2 3 4	10	67	SS-5	-	-	-	-	-	-	-	-	-	-	-	34	A-1-b (V)
VERY LOOSE, BROWN, SANDY SILT, TRACE GRAVEL (FILL), WET		471.3	25-26	WOR 2 2	6	100	SS-6	-	-	-	-	-	-	-	-	-	-	-	40	A-4a (V)
MEDIUM STIFF, BROWN, SILTY CLAY, SOME SAND, SOME GRAVEL AND BRICK FRAGMENTS, (FILL), MOIST		466.3	30-31	3 2 1	4	100	SS-7	1.00	26	23	10	21	20	35	17	18	16			A-6b (3)
SOFT, GRAY AND BROWN, CLAY, AND SILT, TRACE FINE SAND, (FILL), MOIST		461.3	35-36	2 1	-	67	SS-8	-	-	-	-	-	-	-	-	-	-	-	30	A-7-6 (V)
			40-41	2 1 2	4	100	SS-9	-	0	0	8	60	32	48	29	19	38			A-7-6 (13)
			45-46			78	ST-10	-	-	-	-	-	-	-	-	-	-	-	36	A-7-6 (V)
VERY DENSE, BLACK, GRAVEL AND STONE FRAGMENTS WITH SAND, SOME CINDERS, LITTLE BRICK FRAGMENTS (FILL), WET		449.8	47-48	16 24 14	53	67	SS-11	-	-	-	-	-	-	-	-	-	-	-	32	A-1-b (V)
LOOSE, GRAY AND BROWN, SILT, TRACE FINE SAND, TRACE ORGANICS (FILL), WET		446.3	50-51	3 2 3	7	67	SS-12	-	-	-	-	-	-	-	-	-	-	-	24	A-4b (V)
MEDIUM DENSE, GRAY, GRAVEL AND STONE FRAGMENTS, (FILL), WET		441.3	55-56	4 4 4	11	11	SS-13	-	-	-	-	-	-	-	-	-	-	-	-	A-1-a (V)
		436.3	59																	

STANDARD ODOT SOIL BORING LOG (11 X 17) - OH DOT.GDT - 3/9/11 10:06 N:\PROJECTS\2010\1105070\GINT\ODOT LOGS.GPJ

MATERIAL DESCRIPTION AND NOTES	ELEV. 436.3	DEPTHS	SPT/ RQD	N <sub>60</sub>	REC (%)	SAMPLE ID	HP (tsf)	GRADATION (%)					ATTERBERG			WC	ODOT CLASS (G)	HOLE SEALED	
								GR	CS	FS	SI	CL	LL	PL	PI				
LOOSE TO MEDIUM DENSE, BROWN, <b>GRAVEL AND STONE FRAGMENTS WITH SAND</b> , TRACE SILT, TRACE CLAY, WET	436.3	61	2 3 4	10	67	SS-14	-	-	-	-	-	-	-	-	-	-	22	A-1-b (V)	
		62																	
		63																	
		64																	
		65																	
		66	WOH 1 WOH	1	67	SS-15	-	8	45	38	6	3	NP	NP	NP	25	A-1-b (0)		
		67																	
		68																	
		69																	
		70																	
		71	14 8 5	18	11	SS-16	-	-	-	-	-	-	-	-	-	-	-	-	A-1-b (V)
		72																	
		73																	
		74																	
75	6 8 6	20	28	SS-17	-	-	-	-	-	-	-	-	-	-	-	-	A-3 (V)		
76																			
77																			
78																			
79																			
80	8 16 18	47	0	SS-18	-	-	-	-	-	-	-	-	-	-	-	-	A-3 (V)		
81																			
82																			
83																			
84																			
85	6 10 13	32	11	SS-19	-	-	-	-	-	-	-	-	-	-	-	-	A-3 (V)		
86																			
87																			
88																			
89																			
90	8 10 11	29	28	SS-20	-	-	-	-	-	-	-	-	-	-	-	32	A-3 (V)		
91																			
92																			
93																			
94																			
95	12 13 14	38	67	SS-21	-	3	34	54	6	3	NP	NP	NP	20	A-3 (0)				
96																			
97																			
98																			
99																			
100	13 14 14	39	56	SS-22	-	-	-	-	-	-	-	-	-	-	-	15	A-3a (V)		
101																			
102																			
103																			
104																			
105	8 8 7	21	11	SS-23	-	-	-	-	-	-	-	-	-	-	-	8	A-3a (V)		
106																			
107																			
108																			
109																			
110	13 8 8	22	67	SS-24	-	-	-	-	-	-	-	-	-	-	-	19	A-1-b (V)		
111																			
112																			
113																			
114																			
115	23 33 42	105	67	SS-25	-	-	-	-	-	-	-	-	-	-	-	-	Rock (V)		
116																			
117																			
118																			
119																			
120	50/5"	-	100	SS-26	-	-	-	-	-	-	-	-	-	-	-	-	Rock (V)		
121																			

STANDARD ODOT SOIL BORING LOG (11 X 17) - OH.DOT.GDT - 3/9/11 10:06 - N:\PROJECTS\2010\1105070\GINT\ODOT LOGS.GPJ


MATERIAL DESCRIPTION AND NOTES	ELEV. 374.4	DEPTHS	SPT/ RQD	N <sub>60</sub>	REC (%)	SAMPLE ID	HP (tsf)	GRADATION (%)					ATTERBERG				HOLE SEALED	
								GR	CS	FS	SI	CL	LL	PL	PI	WC		ODOT CLASS (G)
<b>INTERBEDDED LIMESTONE (75%) AND SHALE (25%);</b> <b>LIMESTONE</b> , LIGHT GRAY, UNWEATHERED, STRONG, THIN BEDDED, FOSSILIFEROUS, ARGILLACEOUS, MODERATELY FRACTURED, LOSS=7%, RQD=18%; <b>SHALE</b> , GRAY, UNWEATHERED TO HIGHLY WEATHERED, MODERATELY STRONG, LAMINATED, MODERATELY FRACTURED  LS @126.7'-127' QU=12810 PSI LS @130'-130.7' QU=11050 PSI SH @ 133' SDI = 89.9 LS @137'-137.5' QU=12131 PSI SH @ 143.5' SDI = 91.4 LS @144'-144.5' QU=15486 PSI SH @ 148.2' SDI = 88.2 SH @148.2'-148.5' QU=4162 PSI LS @153'-153.5' QU=9710 PSI LS @154.5'-155' QU=10865 PSI LS @158.5'-158.9' QU=8892 PSI LS @163.6'-164' QU=6246 PSI LS @165.1'-165.4' QU=10715 PSI. (continued)		123																
		124																
		125																
		126	16	80	NQ-1													CORE
		127																
		128																
		129																
		130																
		131	30	93	NQ-2													CORE
		132																
	133																	
	134																	
	135																	
	136	16	100	NQ-3													CORE	
	137																	
	138																	
	139																	
	140																	
	141	0	93	NQ-4													CORE	
	142																	
	143																	
	144																	
	145																	
	146	18	100	NQ-5													CORE	
	147																	
	148																	
	149																	
	150																	
	151	30	97	NQ-6													CORE	
	152																	
	153																	
	154																	
	155																	
	156	29	98	NQ-7													CORE	
	157																	
	158																	
	159																	
	160																	
	161	14	100	NQ-8													CORE	
	162																	
	163																	
	164																	
	165																	
	166	7	100	NQ-9													CORE	
	167																	
	168																	
	327.8	EOB																

STANDARD ODOT SOIL BORING LOG (11 X 17) - OH.DOT.GDT - 3/9/11 10:06 - N:\PROJECTS\2010\1105070\GINT\ODOT LOGS.GPJ

NOTES: WATER USED BELOW THE SURFACE FOR DRILLING/ROCK CORING PURPOSES. WATER NOTED AT 52 FT. AFTER 24 HRS.

ABANDONMENT METHODS, MATERIALS, QUANTITIES: BACKFILLED WITH BENTONITE GROUT (13 BAGS CEMENT/2 BAGS BENTONITE)






BORING NO.: L-2  
 CORE BOX NO.: 1 OF 4  
 DEPTH (ft.): 124.0-143.5  
 ELEVATION (ft.): 372.26  
 1/NQ: 124.0' – 128.5'; REC. 80%, RQD 16%  
 2/NQ: 128.5' – 133.5'; REC. 94%, RQD 30%  
 3/NQ: 133.5' – 138.5'; REC. 100%, RQD 16%  
 4/NQ: 138.5' – 143.5'; REC. 94%, RQD 0%




BORING NO.: L-2  
 CORE BOX NO.: 2 OF 4  
 DEPTH (ft.): 143.5-148.5  
 ELEVATION (ft.): 352.76  
 5/NQ: 143.5' – 148.5'; REC. 100%, RQD 18%



BORING NO.: L-2  
 CORE BOX NO.: 3 OF 4  
 DEPTH (ft.): 148.5-163.5  
 ELEVATION (ft.): 347.76  
 6/NQ: 148.5' – 153.3'; REC. 96%, RQD 30%  
 7/NQ: 153.5' – 158.5'; REC. 98%, RQD 29%  
 8/NQ: 158.5' – 163.5'; REC. 100%, RQD 14%



BORING NO.: L-2  
 CORE BOX NO.: 4 OF 4  
 DEPTH (ft.): 163.5-168.5  
 ELEVATION (ft.): 332.76  
 9/NQ: 163.5' – 168.5'; REC. 100%, RQD 7%

Project Mngr.: AJM	PN: N1105070	 611 LUNKEN PARK DRIVE CINCINNATI, OHIO 45226	ROCK CORE PHOTOGRAPHS	BORING  L-2
Drawn By: TCF	Scale: As Shown		BRENT SPENCE BRIDGE REPLACEMENT PARSONS BRINCKERHOFF CINCINNATI, OHIO	
Chkd By: DWW	File No. Core A			
Approved By: AJM	Date: 9-3-10			

PROJECT: BRENT SPENCE BRIDGE	DRILLING FIRM / OPERATOR: HCN / JM	DRILL RIG: DIEDRICH D-50	STATION / OFFSET: 22+98.5, 50.0 RT	EXPLORATION ID: L-2A
TYPE: BRIDGE REPLACEMENT	SAMPLING FIRM / LOGGER: HCN / DRK/DWW	HAMMER: CME AUTOMATIC	ALIGNMENT: PROPOSED BSB	PAGE 1 OF 3
PID: 75119 BR ID:	DRILLING METHOD: 3.25" HSA / NQ	CALIBRATION DATE: 9/9/10	ELEVATION: 494.5 (MSL) EOB: 169.0 ft.	
START: 7/12/10 END: 7/15/10	SAMPLING METHOD: SPT / ST / NQ	ENERGY RATIO (%): 83.7	COORD: 39.093551680, -84.522788620	

MATERIAL DESCRIPTION AND NOTES	ELEV.	DEPTHS	SPT/RQD	N <sub>60</sub>	REC (%)	SAMPLE ID	HP (tsf)	GRADATION (%)					ATTERBERG				WC	DOT CLASS (G)	HOLE SEALED
								GR	CS	FS	SI	CL	LL	PL	FI				
PREDRILLED (VACUUM EXCAVATED)	494.5	1																	
LOOSE TO MEDIUM DENSE, GRAY AND BROWN, <b>FINE SAND</b> , TRACE GRAVEL, TRACE SILT AND ORGANICS, LITTLE BRICK FRAGMENTS, TRACE CLAY, (FILL), MOIST	491.5	3	7																
		4	11	29	56	SS-1	-	1	35	54	6	4	NP	NP	NP	9	A-3 (0)		
		5	13																
		6	16	45	56	SS-2	-	-	-	-	-	-	-	-	-	9	A-3 (V)		
		8	11	22	100	SS-3	-	-	-	-	-	-	-	-	-	46	A-3 (V)		
		10	3	7	100	SS-4	-	-	-	-	-	-	-	-	-	22	A-3 (V)		
		11	3	2	7	100	SS-4	-	-	-	-	-	-	-	-	22	A-3 (V)		
		12																	
LOOSE TO MEDIUM DENSE, GRAY, <b>SILT</b> , AND SAND, LITTLE CLAY, TRACE BRICK FRAGMENTS, TRACE ORGANICS, (FILL), LOI=4.9% (18')	482.0	13	4	6	100	SS-5	-	-	-	-	-	-	-	-	15	A-4b (V)			
		14	2	2	6	100	SS-5	-	-	-	-	-	-	-	15	A-4b (V)			
		15	3	6	100	SS-6	-	-	-	-	-	-	-	-	14	A-4b (V)			
		16	2	2	6	100	SS-6	-	-	-	-	-	-	-	14	A-4b (V)			
		18		79	ST-7	-	0	0	38	50	12	NP	NP	NP	33	A-4b (5)			
		20	4	8	100	SS-8	-	-	-	-	-	-	-	-	24	A-4b (V)			
		21	3	3	8	100	SS-8	-	-	-	-	-	-	-	24	A-4b (V)			
		22																	
LOOSE TO MEDIUM DENSE, GRAY, <b>GRAVEL AND STONE FRAGMENTS WITH SAND</b> , TRACE SILT, TRACE CLAY, MOIST	464.5	25	2	11	100	SS-9	-	-	-	-	-	-	-	-	29	A-4b (V)			
		26	3	5	11	100	SS-9	-	-	-	-	-	-	-	29	A-4b (V)			
		27																	
		28																	
		29																	
		30	2	7	100	SS-10	-	-	-	-	-	-	-	-	44	A-1-b (V)			
		31	2	3	7	100	SS-10	-	-	-	-	-	-	-	44	A-1-b (V)			
		32																	
LOOSE TO MEDIUM DENSE, BROWN, <b>GRAVEL AND STONE FRAGMENTS WITH SAND</b> , TRACE SILT, TRACE CLAY, WET	453.0	35	3	17	67	SS-11	-	48	24	16	9	3	NP	NP	NP	13	A-1-b (0)		
		36	6	6	17	67	SS-11	-	48	24	16	9	3	NP	NP	NP	13	A-1-b (0)	
		37																	
		38																	
		39																	
		40		0	ST-12	-	-	-	-	-	-	-	-	-	-	-	A-1-b (V)		
		41																	
		42	2	10	33	SS-13	-	-	-	-	-	-	-	-	22	A-1-b (V)			
	434.5	43	3	4	10	33	SS-13	-	-	-	-	-	-	-	22	A-1-b (V)			
		44																	
		45	5	24	56	SS-14	-	-	-	-	-	-	-	8	A-1-b (V)				
		46	7	10	24	56	SS-14	-	-	-	-	-	-	8	A-1-b (V)				
		47																	
		48																	
		49																	
		50	5	21	89	SS-15	-	31	30	26	9	4	NP	NP	NP	15	A-1-b (0)		
51	7	8	21	89	SS-15	-	31	30	26	9	4	NP	NP	NP	15	A-1-b (0)			
52																			
53																			
54																			
55	6	21	100	SS-16	-	-	-	-	-	-	-	-	17	A-1-b (V)					
56	6	9	21	100	SS-16	-	-	-	-	-	-	-	17	A-1-b (V)					
57																			
58																			
59																			

STANDARD ODOT SOIL BORING LOG (11 X 17) - OH.DOT.GDT - 3/9/11 10:06 - N:\PROJECTS\2010\1105070\GINT\ODOT LOGS.GPJ

MATERIAL DESCRIPTION AND NOTES	ELEV.	DEPTHS	SPT/RQD	N <sub>60</sub>	REC (%)	SAMPLE ID	HP (tsf)	GRADATION (%)					ATTERBERG			WC	ODOT CLASS (G)	HOLE SEALED	
								GR	CS	FS	SI	CL	LL	PL	PI				
DENSE, BROWN, FINE SAND, TRACE GRAVEL, TRACE SILT, TRACE CLAY, WET	434.5	61	7 12 10	31	100	SS-17	-	-	-	-	-	-	-	-	-	-	15	A-3 (V)	
		62																	
		63																	
		64																	
		65																	
		66																	
		67																	
		68																	
		69																	
		70																	
VERY DENSE, BROWN, GRAVEL AND STONE FRAGMENTS WITH SAND, TRACE SILT, TRACE CLAY	419.5	71	10 13 15	39	100	SS-19	-	1	35	54	6	4	NP	NP	NP	19	A-3 (0)		
		72																	
		73																	
		74																	
		75																	
		76																	
		77																	
		78																	
		79																	
		80																	
DENSE TO VERY DENSE, BROWN, GRAVEL AND STONE FRAGMENTS, AND SAND, TRACE SILT, TRACE CLAY, WET	414.5	81	11 16 21	52	67	SS-21	-	-	-	-	-	-	-	-	-	10	A-1-a (V)		
		82																	
		83																	
		84																	
		85																	
		86																	
		87																	
		88																	
		89																	
		90																	
DENSE, BROWN, GRAVEL AND STONE FRAGMENTS WITH SAND, TRACE SILT, TRACE CLAY	399.5	91	12 14 26	56	100	SS-23	-	-	-	-	-	-	-	-	-	22	A-1-a (V)		
		92																	
		93																	
		94																	
		95																	
		96																	
		97																	
		98																	
		99																	
		100																	
DENSE, BROWN, GRAVEL AND STONE FRAGMENTS WITH SAND, TRACE SILT, TRACE CLAY	389.5	101	11 11 20	43	67	SS-25	-	-	-	-	-	-	-	-	-	10	A-1-b (V)		
		102																	
		103																	
		104																	
		105																	
		106																	
		107																	
		108																	
		109																	
		110																	
VERY DENSE, BROWN, COARSE AND FINE SAND, TRACE GRAVEL, TRACE SILT, TRACE CLAY, WET	389.5	111	20 30 42	100	100	SS-27	-	-	-	-	-	-	-	-	-	23	A-3a (V)		
		112																	
		113																	
		114																	
		115																	
		116																	
		117																	
		118																	
		119																	
		120																	
VERY DENSE, BROWN, GRAVEL AND STONE FRAGMENTS, AND SAND, TRACE SILT, TRACE CLAY, WET	379.5	121	19 56 40	134	100	SS-29	-	-	-	-	-	-	-	-	-	7	A-1-a (V)		
		122																	
		123																	
		124																	

STANDARD ODOT SOIL BORING LOG (11 X 17) - OH DOT.GDT - 3/9/11 10:06 - N:\PROJECTS\2010\1105070\GINT\ODOT LOGS.GPJ

MATERIAL DESCRIPTION AND NOTES	ELEV.	DEPTHS	SPT/RQD	N <sub>60</sub>	REC (%)	SAMPLE ID	HP (tsf)	GRADATION (%)					ATTERBERG				HOLE SEALED	
								GR	CS	FS	SI	CL	LL	PL	PI	WC		ODOT CLASS (G)
VERY DENSE, BROWN, GRAVEL AND STONE FRAGMENTS, AND SAND, TRACE SILT, TRACE CLAY, WET (continued)	372.6																	
		123																
		124																
		125	20	-	100	SS-30	-	-	-	-	-	-	-	-	-	7	A-1-a (V)	
		126	50/2"															
		127																
		128																
INTERBEDDED LIMESTONE (70%) AND SHALE (30%); LIMESTONE, LIGHT GRAY, MODERATELY TO SLIGHTLY WEATHERED, STRONG, THIN BEDDED, FOSSILIFEROUS; SHALE, GRAY, MODERATELY WEATHERED, WEAK, VERY THIN TO THIN BEDDED, LOSS 1%, RQD 34%	366.0	TR																
LS @130.1'-130.5' QU=8084 PSI		129																
LS @131.5'-132.2' QU=8782 PSI		130	10		93	NQ-1												CORE
SH @137'-137.4' QU=1861 PSI		131																
SH @ 138.1' SDI = 75.3		132																
LS @ 142.5' POINT LOAD = 12131 PSI		133																
SH @ 147.3' SDI = 40.1		134	30		100	NQ-2												CORE
LS @150.9'-151.4' QU=16544 PSI.		135																
		136																
		137																
		138																
		139	48		100	NQ-3												CORE
		140																
		141																
		142																
		143																
		144	42		100	NQ-4												CORE
		145																
		146																
		147																
		148																
		149	40		100	NQ-5												CORE
		150																
		151																
		152																
		153																
		154	24		98	NQ-6												CORE
		155																
		156																
LIMESTONE, LIGHT GRAY, UNWEATHERED TO SLIGHTLY WEATHERED, STRONG, THIN BEDDED, FOSSILIFEROUS, TRACE SHALE PARTINGS TO SEAMS, LOSS 1%, RQD 73%	338.0																	
LS @157.8'-158.3' QU=8566 PSI		157																
LS @ 165.2' POINT LOAD = 13547 PSI.		158																
		159	52		100	NQ-7												CORE
		160																
		161																
		162																
		163																
		164	80		98	NQ-8												CORE
		165																
		166																
		167																
		168	100		100	NQ-9												CORE
		169																
	325.5	EOB																

STANDARD ODOT SOIL BORING LOG (11 X 17) - OH DOT.GDT - 3/9/11 10:06 - N:\PROJECTS\2010\1105070\GINT\ODOT LOGS.GPJ

NOTES: WATER USED BELOW 40 FT. FOR DRILLING/ROCK CORING PURPOSES.  
 ABANDONMENT METHODS, MATERIALS, QUANTITIES: BACKFILLED WITH BENTONITE GROUT (14 BAGS CEMENT/2.5 BAGS BENTONITE)




BORING NO.: L- 2A  
 CORE BOX NO.: 1 OF 3  
 DEPTH (ft.): 128.5-146.5  
 ELEVATION (ft.): 366  
 1/NQ: 128.5' – 131.5'; REC. 93%, RQD 10%  
 2/NQ: 131.5' – 136.5'; REC. 100%, RQD 30%  
 3/NQ: 136.5' – 141.5'; REC. 100%, RQD 48%  
 4/NQ: 141.5' – 146.5'; REC. 100%, RQD 42%



BORING NO.: L- 2A  
 CORE BOX NO.: 2 OF 3  
 DEPTH (ft.): 146.5-161.5  
 ELEVATION (ft.): 348  
 5/NQ: 146.5' – 151.5'; REC. 100%, RQD 42%  
 6/NQ: 151.5' – 156.5'; REC. 98%, RQD 24%  
 7/NQ: 156.5' – 161.5'; REC. 100%, RQD 52%



BORING NO.: L- 2A  
 CORE BOX NO.: 3 OF 3  
 DEPTH (ft.): 161.5-169.0  
 ELEVATION (ft.): 328  
 8/NQ: 161.5' – 166.5'; REC. 98%, RQD 80%  
 9/NQ: 166.5' – 169.0'; REC. 100%, RQD 100%

Project Mngr.: AJM	PN: N1105070	 611 LUNKEN PARK DRIVE CINCINNATI, OHIO 45226	<b>ROCK CORE PHOTOGRAPHS</b>	BORING <b>L-2A</b>
Drawn By: TCF	Scale: As Shown		BRENT SPENCE BRIDGE REPLACEMENT PARSONS BRINCKERHOFF CINCINNATI, OHIO	
Chkd By: DWW	File No. Core A			
Approved By: AJM	Date: 9-3-10			

MATERIAL DESCRIPTION AND NOTES	ELEV.	DEPTHS	SPT/RQD	N <sub>60</sub>	REC (%)	SAMPLE ID	HP (tsf)	GRADATION (%)					ATTERBERG				WC	DOT CLASS (GI)	HOLE SEALED
								GR	CS	FS	SI	CL	LL	PL	PI				
WATER (OHIO RIVER)	458.7	1-14																	
VERY LOOSE TO LOOSE, DARK BROWN, GRAVEL AND/OR STONE FRAGMENTS WITH SAND, TRACE SILT, TRACE CLAY, CONCRETE FRAGMENTS FROM 15'-21', (FILL), WET	443.7	15-21	50/0"	-		SS-1	-	-	-	-	-	-	-	-	-	-	-	A-1-b (V)	
		21-22	1	2	3	6	22	SS-2	-	-	-	-	-	-	-	-	-	29	A-1-b (V)
		22-23	1	2	1	4	67	SS-3	-	29	36	24	6	5	NP	NP	NP	26	A-1-b (0)
		23-24	2	1	1	3	0	SS-4	-	-	-	-	-	-	-	-	-	-	A-1-b (V)
		24-25																	
		25-26																	
		26-27																	
		27-28	1	0	1	1	0	SS-5	-	-	-	-	-	-	-	-	-	-	A-1-b (V)
		28-29																	
		29-30	8	16	16	41	28	SS-6	-	-	-	-	-	-	-	-	-	8	A-1-b (V)
	427.2	30-31	4	4	4	10	100	SS-7	-	6	26	63	3	2	NP	NP	NP	-	A-3 (0)
LOOSE, BROWN, FINE SAND, TRACE GRAVEL, TRACE SILT, TRACE CLAY, WET		31-32	4	4	4	10	22	SS-8	-	-	-	-	-	-	-	-	-	52	A-3 (V)
		32-33																	
		33-34																	
		34-35																	
		35-36	3	4	4	10	56	SS-9	-	1	39	56	2	2	NP	NP	NP	25	A-3 (0)
		36-37																	
		37-38																	
		38-39																	
		39-40																	
		40-41																	
		41-42																	
		42-43																	
		43-44																	
		44-45	10	8	9	22	11	SS-10	-	-	-	-	-	-	-	-	-	5	A-1-a (V)
MEDIUM DENSE, BROWN, GRAVEL AND STONE FRAGMENTS, SOME SAND, TRACE SILT, TRACE CLAY, WET		45-46																	
		46-47																	
		47-48																	
		48-49																	
		49-50	10	11	11	28	67	SS-11	-	61	14	16	7	2	NP	NP	NP	10	A-1-a (0)
		50-51																	
		51-52																	
		52-53																	
		53-54																	
		54-55																	
		55-56	8	6	8	18	67	SS-12	-	4	32	54	6	4	NP	NP	NP	24	A-3 (0)
MEDIUM DENSE, BROWN, FINE SAND, TRACE TO LITTLE GRAVEL, TRACE SILT, TRACE CLAY, WET		56-57																	
		57-58																	
		58-59																	

MATERIAL DESCRIPTION AND NOTES	ELEV.	DEPTHS	SPT/RQD	N <sub>60</sub>	REC (%)	SAMPLE ID	HP (tsf)	GRADATION (%)					ATTERBERG			WC	ODOT CLASS (G)	HOLE SEALED
								GR	CS	FS	SI	CL	LL	PL	PI			
MEDIUM DENSE, BROWN, FINE SAND, TRACE TO LITTLE GRAVEL, TRACE SILT, TRACE CLAY, WET (continued)	398.7	61	5 9 11	25	67	SS-13	-	11	28	55	4	2	NP	NP	NP	21	A-3 (0)	
MEDIUM DENSE TO DENSE, BROWN, GRAVEL AND STONE FRAGMENTS WITH SAND, TRACE SILT, TRACE CLAY, WET	393.7	65	16 9 10	24	67	SS-14	-	27	36	29	5	3	NP	NP	NP	15	A-1-b (0)	
		70	11 9 9	23	67	SS-15	-	21	58	15	3	3	NP	NP	NP	16	A-1-b (0)	
		75	8 9 12	27	67	SS-16	-	9	52	33	4	2	NP	NP	NP	19	A-1-b (0)	
MEDIUM DENSE TO DENSE, BROWN, GRAVEL AND STONE FRAGMENTS WITH SAND, AUGERED FROM 80' TO 88.2', AUGER REFUSAL AT 88.2', WET	378.7	80	50/0"	-	-	SS-17	-	-	-	-	-	-	-	-	-	-	A-1-b (V)	
LIMESTONE, GRAY, UNWEATHERED TO SLIGHTLY WEATHERED, STRONG, THIN BEDDED, ARGILLACEOUS, THIN SHALE SEAMS, LOSS 3%, RQD 51%	370.5	88																
LS @ 93.1' POINT LOAD = 9195 PSI		89	0		100	NQ-1												CORE
LS/SH @ 97.6'-98' QU=3277 PSI		91																
LS @ 100.2'-100.4' QU=12940 PSI		92																
LS @ 103.8'-104.4' QU=13314 PSI		93	62		92	NQ-2												CORE
LS @ 113.2'-114.2' QU=21169 PSI		94																
		95																
LS @ 117.6' POINT LOAD = 11786 PSI.		96																
		97																
		98	60		96	NQ-3												CORE
		99																
		100																
		101																
		102																
		103	78		98	NQ-4												CORE
		104																
		105																
		106																
		107																
		108	56		100	NQ-5												CORE
		109																
		110																
		111																
		112																
		113	34		96	NQ-6												CORE
		114																
		115																
		116																
		117																
		118	36		100	NQ-7												CORE
		119																
		120																
		121																

MATERIAL DESCRIPTION AND NOTES	ELEV. 336.8	DEPTHS	SPT/ RQD	N <sub>60</sub>	REC (%)	SAMPLE ID	HP (tsf)	GRADATION (%)					ATTERBERG				ODOT CLASS (G)	HOLE SEALED	
								GR	CS	FS	SI	CL	LL	PL	PI	WC			
<b>LIMESTONE</b> , GRAY, UNWEATHERED, STRONG, THIN BEDDED, ARGILLACEOUS, THIN SHALE PARTINGS, FOSSILIFEROUS SEAMS, LOSS 2%, RQD 74%  LS/SH @121.2'-121.8' QU=6704 PSI LS @121.8'-122.8' QU=13540 PSI LS/SH @124.6'-125.2' QU= 3954 PSI LS @ 137.2' POINT LOAD = 10439 PSI LS @145.2'-146.2' QU=11537 PSI LS/SH @145.6'-146.1' QU=9434 PSI LS @ 147.8' POINT LOAD = 10434 PSI LS @158.7'-160.2' QU=17189 PSI LS @162.8'-163.3' QU=12114 PSI LS @164.5'-165.2' QU=15115 PSI. (continued)		123	84		100	NQ-8											CORE		
		124																	
		125																	
		126																	
		127																	
		128		94		100	NQ-9												CORE
		129																	
		130																	
		131																	
		132																	
		133		86		100	NQ-10												CORE
		134																	
		135																	
		136																	
		137																	
		138		70		100	NQ-11												CORE
		139																	
	140																		
	141																		
	142																		
	143		62		98	NQ-12												CORE	
	144																		
	145																		
	146																		
	147																		
	148		64		100	NQ-13												CORE	
	149																		
	150																		
	151																		
	152																		
	153		34		92	NQ-14												CORE	
	154																		
	155																		
	156																		
	157																		
	158		62		90	NQ-15												CORE	
	159																		
	160																		
	161																		
	162																		
	163		100		100	NQ-16												CORE	
	164																		
	165																		
	166																		
	167		93		100	NQ-17												CORE	
	168																		
	290.5																	EOB	

STANDARD ODOT SOIL BORING LOG (11 X 17) - OH.DOT.GDT - 3/9/11 10:06 - N:\PROJECTS\2010\N1105070\GINT\ODOT LOGS.GPJ

NOTES: WATER USED BELOW 88 FT. FOR ROCK CORING PURPOSES.

ABANDONMENT METHODS, MATERIALS, QUANTITIES: BACKFILLED WITH BENTONITE GROUT (12 BAGS CEMENT/1.5 BAGS BENTONITE)






BORING NO.: L- 3  
 CORE BOX NO.: 1 OF 6  
 DEPTH (ft.): 88.2-105.2  
 ELEVATION (ft.): 370.46  
 1/NQ: 88.2' – 90.2'; REC. 100%, RQD 0%  
 2/NQ: 90.2' – 95.2'; REC. 92%, RQD 62%  
 3/NQ: 95.2' – 100.7'; REC. 87%, RQD 55%  
 4/NQ: 100.7' – 105.2'; REC. 100%, RQD 87%




BORING NO.: L- 3  
 CORE BOX NO.: 2 OF 6  
 DEPTH (ft.): 105.2-120.2  
 ELEVATION (ft.): 353.46  
 5/NQ: 105.2' – 110.2'; REC. 100%, RQD 56%  
 6/NQ: 110.2' – 115.2'; REC. 96%, RQD 34%  
 7/NQ: 115.2' – 120.2'; REC. 100%, RQD 36%




BORING NO.: L- 3  
 CORE BOX NO.: 3 OF 6  
 DEPTH (ft.): 120.2-135.2  
 ELEVATION (ft.): 338.46  
 8/NQ: 120.2' – 125.2'; REC. 100%, RQD 84%  
 9/NQ: 125.2' – 130.2'; REC. 100%, RQD 94%  
 10/NQ: 130.2' – 135.2'; REC. 100%, RQD 86%


Project Mngr.: AJM	PN: N1105070	 611 LUNKEN PARK DRIVE CINCINNATI, OHIO 45226	<b>ROCK CORE PHOTOGRAPHS</b>	BORING
Drawn By: TCF	Scale: As Shown		BRENT SPENCE BRIDGE REPLACEMENT PARSONS BRINCKERHOFF CINCINNATI, OHIO	L-3
Chkd By: DWW	File No. Core A			
Approved By: AJM	Date: 9-3-10			




BORING NO.: L- 3  
 CORE BOX NO.: 4 OF 6  
 DEPTH (ft.): 135.2-150.2  
 ELEVATION (ft.): 323.46  
 11/NQ: 135.2' – 140.2'; REC. 100%, RQD 70%  
 12/NQ: 140.2' – 145.2'; REC. 98%, RQD 62%  
 13/NQ: 145.2' – 150.2'; REC. 100%, RQD 64%



BORING NO.: L- 3  
 CORE BOX NO.: 5 OF 6  
 DEPTH (ft.): 150.2-160.2  
 ELEVATION (ft.): 308.46  
 14/NQ: 150.2' – 155.2'; REC. 92%, RQD 34%  
 15/NQ: 155.2' – 160.2'; REC. 90%, RQD 62%  
 16/NQ: 160.2' – 165.2'; REC. 100%, RQD 100%



BORING NO.: L- 3  
 CORE BOX NO.: 6 OF 6  
 DEPTH (ft.): 160.2-168.2  
 ELEVATION (ft.): 298.46  
 17/NQ: 165.2' – 165.2"; REC. 100%, RQD 93%

Project Mngr.: AJM	PN: N1105070	 611 LUNKEN PARK DRIVE CINCINNATI, OHIO 45226	<b>ROCK CORE PHOTOGRAPHS</b>	BORING
Drawn By: TCF	Scale: As Shown		BRENT SPENCE BRIDGE REPLACEMENT PARSONS BRINCKERHOFF CINCINNATI, OHIO	L-3
Chkd By: DWW	File No. Core A			
Approved By: AJM	Date: 9-3-10			

PROJECT: BRENT SPENCE BRIDGE	DRILLING FIRM / OPERATOR: HCN / JM	DRILL RIG: DIEDRICH D-50	STATION / OFFSET: 20+86.5, 55.1 LT	EXPLORATION ID: L-3A
TYPE: BRIDGE REPLACEMENT	SAMPLING FIRM / LOGGER: HCN / DRK/DWW	HAMMER: CME AUTOMATIC	ALIGNMENT: PROPOSED BSB	
PID: 75119 BR ID:	DRILLING METHOD: 3.25" HSA / NQ	CALIBRATION DATE: 9/9/10	ELEVATION: 496.1 (MSL) EOB: 165.0 ft.	PAGE 1 OF 3
START: 5/17/10 END: 5/20/10	SAMPLING METHOD: SPT / NQ	ENERGY RATIO (%): 83.7	COORD: 39.092603170, -84.522993590	

MATERIAL DESCRIPTION AND NOTES	ELEV.	DEPTHS	SPT/RQD	N <sub>60</sub>	REC (%)	SAMPLE ID	HP (tsf)	GRADATION (%)					ATTERBERG				WC	ODOT CLASS (G)	HOLE SEALED
								GR	CS	FS	SI	CL	LL	PL	PI	WC			
PRE-DRILLED (VACUUM EXCAVATION)	496.1	1-6																	
LOOSE TO MEDIUM DENSE, BLACK, GRAVEL AND/OR STONE FRAGMENTS WITH SAND, LITTLE CINDERS, TRACE BRICK FRAGMENTS, TRACE SILT, TRACE CLAY, (FILL), VERY LOOSE FROM 30' TO 40', MOIST TO WET	489.1	7-8	3 4	2	8	67	SS-1	-	-	-	-	-	-	-	-	-	-	25	A-1-b (V)
		9-10	1 3	4	10	100	SS-2	-	-	-	-	-	-	-	-	-	-	22	A-1-b (V)
		11-13	2 5	7	17	67	SS-3	-	-	-	-	-	-	-	-	-	-	36	A-1-b (V)
		14-16	2 3	4	10	100	SS-4	-	-	-	-	-	-	-	-	-	-	39	A-1-b (V)
		17-18	2 2	2	6	100	SS-5	-	49	24	16	7	4	NP	NP	NP	65	A-1-b (0)	
		19-21	1 2	2	6	100	SS-6	-	-	-	-	-	-	-	-	-	-	40	A-1-b (V)
		22-24																	
		25-26	1 1	3	6	44	SS-7	-	-	-	-	-	-	-	-	-	-	43	A-1-b (V)
		27-29																	
		30-31	2 1	2	4	100	SS-8	-	25	32	25	9	9	NP	NP	NP	62	A-1-b (0)	
		32-34																	
		35-36	1 1	2	4	100	SS-9	-	-	-	-	-	-	-	-	-	-	47	A-1-b (V)
		37-39																	
VERY LOOSE TO LOOSE, GRAY, COARSE AND FINE SAND, TRACE SILT AND WOOD FRAGMENTS, (FILL), WET	456.1	40-41	1 1	1	3	44	SS-10	2.00	-	-	-	-	-	-	-	-	86	A-3a (V)	
		42-44																	
	45-46	3 3	3	8	100	SS-11	-	-	-	-	-	-	-	-	-	-	29	A-3a (V)	
	47-49																		
STIFF, LIGHT BROWN, SANDY SILT, SOME CLAY, TRACE TO SOME GRAVEL, MOIST	446.1	50-51	9 7	5	17	44	SS-12	1.50	17	17	22	24	20	26	17	9	27	A-4a (2)	
		52-54																	
		55-56	2 4	4	8	0	SS-13	-	-	-	-	-	-	-	-	-	18	A-4a (V)	
	57-59																		
	436.1																		

STANDARD ODOT SOIL BORING LOG (11 X 17) - OH DOT.GDT - 3/9/11 10:06 - N:\PROJECTS\2010\1105070\GINT\ODOT LOGS.GPJ

MATERIAL DESCRIPTION AND NOTES	ELEV.	DEPTHS	SPT/ RQD	N <sub>60</sub>	REC (%)	SAMPLE ID	HP (tsf)	GRADATION (%)					ATTERBERG			WC	ODOT CLASS (G)	HOLE SEALED	
								GR	CS	FS	SI	CL	LL	PL	PI				
VERY STIFF, BLACK AND BROWN, COARSE AND FINE SAND, SOME WOOD FRAGMENTS, WET	436.1	61	5 4 4	11	100	SS-14	2.25	-	-	-	-	-	-	-	-	29	A-3a (V)		
		62																	
		63																	
		64																	
MEDIUM DENSE TO DENSE, BROWN AND GRAY, FINE SAND, AND COARSE SAND, TRACE SILT, TRACE CLAY, TRACE GRAVEL, WET	431.1	65	6 4 4	11	100	SS-15	-	-	-	-	-	-	-	-	-	29	A-3 (V)		
		66																	
		67																	
		68																	
		69																	
		70																	
		71	5 8 8	22	100	SS-16	-	-	-	-	-	-	-	-	-	18	A-3 (V)		
		72																	
		73																	
		74																	
		75	5 7 11	25	100	SS-17	-	7	38	45	5	5	NP	NP	NP	20	A-3 (0)		
	406.1	76																	
		77																	
		78																	
		79																	
		80																	
		81	11 15 14	40	100	SS-18	-	-	-	-	-	-	-	-	-	19	A-3 (V)		
		82																	
		83																	
		84																	
		85																	
		86	10 12 11	32	100	SS-19	-	-	-	-	-	-	-	-	-	14	A-3 (V)		
	401.1	87																	
		88																	
		89																	
		90																	
		91	10 18 24	59	100	SS-20	-	-	-	-	-	-	-	-	-	24	A-4b (V)		
		92																	
		93																	
		94																	
		95																	
		96	22 25 25	70	100	SS-21	-	-	-	-	-	-	-	-	-	18	A-3 (V)		
			391.1	97															
98																			
99																			
100																			
101	8 16 16			45	0	SS-22	-	-	-	-	-	-	-	-	-	-	A-3 (V)		
102																			
103																			
104																			
105																			
106	19 9 11			28	100	SS-23	-	39	33	23	2	3	NP	NP	NP	18	A-1-b (0)		
	376.1			107															
		108																	
		109																	
		110																	
		111	18 12 10	31	67	SS-24	-	-	-	-	-	-	-	-	-	14	A-1-b (V)		
		112																	
		113																	
		114																	
		115																	
		116	13 13 12	35	100	SS-25	-	-	-	-	-	-	-	-	-	17	A-1-b (V)		
		117																	
118																			
119																			
120																			
121	49 49 50/5"	-	106	SS-26	-	59	17	17	4	3	NP	NP	NP	12	A-1-a (0)				

MATERIAL DESCRIPTION AND NOTES	ELEV.	DEPTHS	SPT/RQD	N <sub>60</sub>	REC (%)	SAMPLE ID	HP (tsf)	GRADATION (%)					ATTERBERG				WC	ODOT CLASS (G)	HOLE SEALED
								GR	CS	FS	SI	CL	LL	PL	PI				
VERY DENSE, BROWN, GRAVEL AND STONE FRAGMENTS, SOME SAND, TRACE SILT, TRACE CLAY, WET (continued)	374.2		37 42 11	74	100	SS-27	-	-	-	-	-	-	-	-	-	-	20	A-1-a (V)	
INTERBEDDED LIMESTONE (75%) AND SHALE (25%); LIMESTONE, GRAY, UNWEATHERED, VERY STRONG, THIN BEDDED, FOSSILIFEROUS, ARGILLACEOUS, LOSS 2%, RQD 39%, MODERATELY FRACTURED; SHALE, GRAY, UNWEATHERED TO HIGHLY WEATHERED, WEAK TO SLIGHTLY STRONG, LAMINATED, SH @ 126.5'-126.75' QU=570 PSI SH @ 134.25' SDI = 85.3 LS @ 134.6' POINT LOAD = 14846 PSI SH @ 142.3'-142.5' QU=4272 PSI SH @ 150.5' SDI = 97.7 LS @ 152.75' POINT LOAD = 12976 PSI LS @ 155'-155.5' QU=16975 PSI SH @ 157.7'-158' QU=2759 PSI.	371.1	TR	60/2'	-	100	SS-28	-	-	-	-	-	-	-	-	-	-	-	Rock (V)	
				31	83	NQ-1												CORE	
				25	100	NQ-2												CORE	
				35	100	NQ-3												CORE	
				40	100	NQ-4												CORE	
				50	100	NQ-5												CORE	
				40	100	NQ-6												CORE	
				66	100	NQ-7												CORE	
				22	100	NQ-8												CORE	
	331.1	EOB																	

STANDARD ODOT SOIL BORING LOG (11 X 17) - OH.DOT.GDT - 3/9/11 10:06 - N:\PROJECTS\2010\1105070\GINT\ODOT LOGS.GPJ

NOTES: WATER USED AT 126 FT. FOR ROCK CORING PURPOSES. WATER NOTED AT 38 FT. AFTER 24 HRS.

ABANDONMENT METHODS, MATERIALS, QUANTITIES: BACKFILLED WITH BENTONITE GROUT (13 BAGS CEMENT/2 BAGS BENTONITE)




BORING NO.: L-3A  
 STA. OFFSET  
 CORE BOX NO.: 1 OF 3  
 DEPTH (ft.): 126.2-140.0  
 ELEVATION (ft.): 369.85  
 1/NQ: 126.2' – 130.0'; REC. 84%, RQD 32%  
 2/NQ: 130.0 – 135.0'; REC. 100%, RQD 25%  
 3/NQ: 135.0 – 140.0'; REC. 100%, RQD 35%



BORING NO.: L-3A  
 STA. OFFSET  
 CORE BOX NO.: 2 OF 3  
 DEPTH (ft.): 140.0-155.0  
 ELEVATION (ft.): 356.05  
 4/NQ: 140.0' – 145.0'; REC. 100%, RQD 50%  
 5/NQ: 145.0' – 150.0'; REC. 100%, RQD 50%  
 6/NQ: 150.0' – 155.0'; REC. 100%, RQD 40%



BORING NO.: L-3A  
 STA. OFFSET  
 CORE BOX NO.: 3 OF 3  
 DEPTH (ft.): 155.5-165.0  
 ELEVATION (ft.): 341.05  
 7/NQ: 155.0' – 160.0'; REC. 100%, RQD 66%  
 8/NQ: 160.0'-165.0'; REC. 100%, RQD 22%

Project Mngr.: AJM	PN: N1105070	 611 LUNKEN PARK DRIVE CINCINNATI, OHIO 45226	<b>ROCK CORE PHOTOGRAPHS</b>	BORING <b>L-3A</b>
Drawn By: TCF	Scale: As Shown		BRENT SPENCE BRIDGE REPLACEMENT PARSONS BRINCKERHOFF CINCINNATI, OHIO	
Chkd By: DWW	File No. Core B			
Approved By: AJM	Date: 9-8-10			

MATERIAL DESCRIPTION AND NOTES	ELEV.	DEPTHS	SPT/RQD	N <sub>60</sub>	REC (%)	SAMPLE ID	HP (tsf)	GRADATION (%)					ATTERBERG			WC	ODOT CLASS (GI)	HOLE SEALED		
								GR	CS	FS	SI	CL	LL	PL	PI					
MEDIUM STIFF, BROWN AND GRAY, SILT AND CLAY, AND SAND, TRACE SHALE FRAGMENTS, WOOD, ORGANICS, AND GRAVEL (FILL), MOIST	480.0	1	3	4	10	78	SS-1	1.50	-	-	-	-	-	-	-	-	-	38	A-6a (V)	
		2																		
		3	4	6	6	17	89	SS-2	2.00	-	-	-	-	-	-	-	-	19	A-6a (V)	
		4																		
		5																		
		6	3	5	6	15	100	SS-3	2.25	-	-	-	-	-	-	-	-	-	26	A-6a (V)
		7																		
		8	3	4	9	18	67	SS-4	2.00	10	24	18	31	17	35	24	11	27	A-6a (3)	
		9																		
		10																		
		11	2	3	1	6	6	SS-5	2.50	-	-	-	-	-	-	-	-	-	13	A-6a (V)
VERY LOOSE TO LOOSE, DARK BROWN, GRAVEL AND STONE FRAGMENTS WITH SAND, TRACE SILT, SLAG, AND ORGANICS, (FILL), WET	467.5	12																		
		13	12	2	2	6	33	SS-6	-	-	-	-	-	-	-	-	-	18	A-1-b (V)	
		14																		
		15	3	1	2	4	0	SS-7	-	-	-	-	-	-	-	-	-	-	-	A-1-b (V)
		16																		
		17																		
		18	2	2	2	6	22	SS-8	-	-	-	-	-	-	-	-	-	24	A-1-b (V)	
		19																		
		20	3	2	3	7	39	SS-9	-	-	-	-	-	-	-	-	-	28	A-1-b (V)	
		21																		
		SOFT, GRAY, CLAY, AND SILT, TRACE ORGANICS AND SAND, LOI=5.4% (25'), MOIST	455.0	22																
23																				
24																				
25	2			2	2	6	67	SS-10	1.25	0	0	2	62	36	50	29	21	44	A-7-6 (14)	
26																				
27																				
28																				
29																				
30																				
31								83	ST-11	1.50	0	0	1	62	37	46	25	21	37	A-7-6 (14)
32																				
33	2	1	3	6	6	SS-12	1.00	-	-	-	-	-	-	-	-	-	44	A-7-6 (V)		
34																				
35																				
36	1	2	3	7	100	SS-13	1.50	-	-	-	-	-	-	-	-	-	32	A-7-6 (V)		
37																				
38																				
39																				
40																				
41	3	4	3	10	72	SS-14	-	-	-	-	-	-	-	-	-	-	24	A-7-6 (V)		
42																				
43																				
44																				
45																				
46	7	8	6	20	28	SS-15	-	-	-	-	-	-	-	-	-	-	7	A-1-b (V)		
47																				
48																				
49																				
50																				
51	11	15	17	45	56	SS-16	-	-	-	-	-	-	-	-	-	-	10	A-1-b (V)		
52																				
53																				
54																				
55																				
56	17	14	14	39	56	SS-17	-	54	9	27	7	3	NP	NP	NP	12	A-1-b (0)			
57																				
58																				
59																				

MATERIAL DESCRIPTION AND NOTES	ELEV.	DEPTHS	SPT/RQD	N <sub>60</sub>	REC (%)	SAMPLE ID	HP (tsf)	GRADATION (%)					ATTERBERG			WC	ODOT CLASS (G)	HOLE SEALED	
								GR	CS	FS	SI	CL	LL	PL	PI				
MEDIUM DENSE TO DENSE, BROWN, GRAVEL AND STONE FRAGMENTS WITH SAND, TRACE SILT, TRACE CLAY, VERY DENSE AT 65', WET (continued)	420.0	61	18 15 16	43	33	SS-18	-	-	-	-	-	-	-	-	-	-	14	A-1-b (V)	
		62																	
		63																	
		64																	
		65																	
		66			40 31 34	91	33	SS-19	-	-	-	-	-	-	-	-	-	7	A-1-b (V)
		67																	
		68																	
		69																	
		70	410.0																
DENSE TO VERY DENSE, BROWN, GRAVEL AND STONE FRAGMENTS, AND SAND, TRACE SILT, TRACE CLAY, WET	410.0	71	9 17 18	49	67	SS-20	-	56	25	13	3	3	NP	NP	NP	11	A-1-a (0)		
		72																	
		73																	
		74																	
		75																	
		76			11 19 20	54	56	SS-21	-	-	-	-	-	-	-	-	10	A-1-a (V)	
		77																	
		78																	
		79																	
		80	400.0																
DENSE TO VERY DENSE, BROWN TRACE GRAY, GRAVEL AND STONE FRAGMENTS WITH SAND, TRACE SILT, TRACE CLAY, MEDIUM DENSE AT 80', WET	400.0	81	9 11 10	29	67	SS-22	-	20	63	11	3	3	NP	NP	NP	18	A-1-b (0)		
		82																	
		83																	
		84																	
		85																	
		86			9 18 17	49	6	SS-23	-	-	-	-	-	-	-	-	15	A-1-b (V)	
		87																	
		88																	
		89																	
		90																	
VERY DENSE, GRAY, STONE FRAGMENTS WITH SAND, LIMESTONE FRAGMENTS, WET	388.0	91	31 26 45	99	67	SS-24	-	-	-	-	-	-	-	-	-	6	A-1-b (V)		
		92																	
		93																	
		94																	
		95			34 100/3"	-	67	SS-25	-	-	-	-	-	-	-	-	-	A-1-b (V)	
		96																	
		97																	
		98																	
		99																	
		100			100/1"	-	0	SS-26	-	-	-	-	-	-	-	-	11	A-1-b (V)	
INTERBEDDED LIMESTONE (75%) AND SHALE (25%); LIMESTONE, GRAY, UNWEATHERED TO SLIGHTLY WEATHERED, STRONG, THIN BEDDED, ARGILLACEOUS, FOSSILIFEROUS SEAMS, FRACTURED, LOSS 11%, RQD 12%; SHALE, GRAY, SLIGHTLY WEATHERED, WEAK, LAMINATED, FISSILE, SH @ 108.5' SDI = 59.2 LS @ 116'-116.5' QU=13646 PSI LS @ 120.4'-120.9' QU=12705 PSI LS @ 127.5'-128' QU=17130 PSI LS @ 132.4' POINT LOAD = 11696 PSI LS @ 140.5'-141' QU=13056 PSI LS @ 143'-143.5' QU=12509 PSI LS @ 141.4' POINT LOAD = 11853 PSI.	376.0	104																	
		105																	
		106			0		17	NQ-1										CORE	
		107																	
		108																	
		109																	
		110																	
		111																	
		112					12	90	NQ-2									CORE	
		113																	
114																			
115																			
116																			
117																			
118																			
119																			
120																			
121																			

STANDARD ODOT SOIL BORING LOG (11 X 17) - OH DOT GDT - 3/9/11 10:07 - N:\PROJECTS\2010\110507\GINT\ODOT LOGS.GPJ



MATERIAL DESCRIPTION AND NOTES	ELEV. 358.1	DEPTHS	SPT/ RQD	N <sub>60</sub>	REC (%)	SAMPLE ID	HP (tsf)	GRADATION (%)					ATTERBERG				ODOT CLASS (G)	HOLE SEALED
								GR	CS	FS	SI	CL	LL	PL	PI	WC		
<b>INTERBEDDED LIMESTONE (75%) AND SHALE (25%);</b> LIMESTONE, GRAY, UNWEATHERED TO SLIGHTLY WEATHERED, STRONG, THIN BEDDED, ARGILLACEOUS, FOSSILIFEROUS SEAMS, FRACTURED, LOSS 11%, RQD 12%; SHALE, GRAY, SLIGHTLY WEATHERED, WEAK, LAMINATED, FISSILE, SH @ 108.5' SDI = 59.2  LS @ 116'-116.5' QU=13646 PSI  LS @ 120.4'-120.9' QU=12705 PSI  LS @ 127.5'-128' QU=17130 PSI  LS @ 132.4' POINT LOAD = 11696 PSI  LS @ 140.5'-141' QU=13056 PSI  LS @ 143'-143.5' QU=12509 PSI  LS @ 141.4' POINT LOAD = 11853 PSI. (continued)		123	20		98	NQ-3										CORE		
		124																
		125																
		126																
		127		50		100	NQ-4										CORE	
		128																
	129																	
	130																	
	131																	
	132																	
	133		0		94	NQ-5										CORE		
	134																	
	135																	
	136																	
	137																	
	138																	
	139																	
	140																	
	141																	
	142																	
	143		21		94	NQ-6										CORE		
	144																	
	145																	
	146																	
	147																	
	148	332.0																
BLANK DRILLED FOR SEISMIC TESTING		149																
		150																
		151																
		152																
		153																
		154																
		155																
		156																
		157																
		158																
		159	321.0															

EOB

STANDARD ODOT SOIL BORING LOG (11 X 17) - OH.DOT.GDT - 3/9/11 10:07 - N:\PROJECTS\2010\N1105070\GINT\ODOT LOGS.GPJ

NOTES: WATER USED IN DRILLING AT THE SURFACE. WATER NOTED AT 32 FT. AFTER 24 HRS. 3 INCH PVC CASING INSTALLED FROM SURFACE TO 159 FEET. CASING BROKE DURING REMOVAL AN ABANDONMENT METHODS, MATERIALS, QUANTITIES: BACKFILLED WITH BENTONITE GROUT (12 BAGS CEMENT/1.5 BAGS BENTONITE)




BORING NO.: L-4  
 CORE BOX NO.: 1 OF 3  
 DEPTH (ft.): 104.0-127.0  
 ELEVATION (ft.): 375.97  
 1/NQ: 104.0'-107.0'; REC. 17%, RQD 0%  
 2/NQ: 107.0'-117.0'; REC. 90%, RQD 12%  
 3/NQ: 117.0'-127.0'; REC. 98%, RQD 20%



BORING NO.: L-4  
 CORE BOX NO.: 2 OF 3  
 DEPTH (ft.): 127.0-138.0  
 ELEVATION (ft.): 352.97  
 4/NQ: 127.0'-128.0'; REC. 100%, RQD 50%  
 5/NQ: 128.0'-138.0'; REC. 99%, RQD 0%



BORING NO.: L-4  
 CORE BOX NO.: 3 OF 3  
 DEPTH (ft.): 138.0-148.0  
 ELEVATION (ft.): 341.97  
 6/NQ: 138.0'-148.0'; REC. 94%, RQD 21%

Project Mngr.: AJM	PN: N1105070	 611 LUNKEN PARK DRIVE CINCINNATI, OHIO 45226	<b>ROCK CORE PHOTOGRAPHS</b>	BORING  <b>L-4</b>
Drawn By: TCF	Scale: As Shown		BRENT SPENCE BRIDGE REPLACEMENT PARSONS BRINCKERHOFF CINCINNATI, OHIO	
Chkd By: DWW	File No. Core B			
Approved By: AJM	Date: 9-8-10			

MATERIAL DESCRIPTION AND NOTES	ELEV.	DEPTHS	SPT/RQD	N <sub>60</sub>	REC (%)	SAMPLE ID	HP (tsf)	GRADATION (%)					ATTERBERG				WC	DOT CLASS (G)	HOLE SEALED
								GR	CS	FS	SI	CL	LL	PL	PI	WC			
ASPHALT PAVEMENT PRE-DRILLED (VACUUM EXCAVATED)	486.3 485.9	1-4																	
MEDIUM STIFF TO STIFF, BROWN AND GRAY, SILT AND CLAY, LITTLE SAND, TRACE ORGANICS, TRACE ROCK FRAGMENTS, (FILL), MOIST	481.3	5-23	5	100	SS-1	1.00	-	-	-	-	-	-	-	-	-	-	38	A-6a (V)	
		8	2	3	10	100	SS-2	1.00	-	-	-	-	-	-	-	-	20	A-6a (V)	
		11	3	5	7	13	67	SS-3	1.75	-	-	-	-	-	-	-	21	A-6a (V)	
		13	4	8	8	18	100	SS-4	2.00	-	-	-	-	-	-	-	17	A-6a (V)	
		16	4	4	4	9	100	SS-5	2.00	-	-	-	-	-	-	-	26	A-6a (V)	
		18	2	3	5	9	100	SS-6	-	-	-	-	-	-	-	-	-	A-6a (V)	
		21	2	2	3	6	100	SS-7	1.50	-	-	-	-	-	-	-	23	A-6a (V)	
		24				83	ST-8	-	0	0	16	46	38	29	17	12	25	A-6a (9)	
STIFF, BROWN, TRACE GRAY, SILTY CLAY, TRACE FINE SAND, MOIST	461.3	25-34	2	2	3	6	100	SS-9	2.00	-	-	-	-	-	-	-	22	A-6b (V)	
		31	2	2	2	4	100	SS-10	1.75	-	-	-	-	-	-	-	27	A-6b (V)	
MEDIUM DENSE, GRAY, SANDY SILT, TRACE GRAVEL, VERY LOOSE AT 35', MOIST TO WET	451.3	35-44	2	2	2	4	100	SS-11	-	-	-	-	-	-	-	-	27	A-4a (V)	
		39				100	ST-12	2.50	0	0	21	48	31	29	19	10	31	A-4a (8)	
		41	10	13	15	31	100	SS-13	-	-	-	-	-	-	-	-	28	A-4a (V)	
MEDIUM DENSE, BROWN, COARSE AND FINE SAND, LITTLE GRAVEL, TRACE SILT, TRACE CLAY, CLAY SEAM AT 50', VERY DENSE AT 60', WET	441.3	45-59	4	5	6	12	56	SS-14	-	-	-	-	-	-	-	-	13	A-3a (V)	
		51	16	7	20	30	100	SS-15	-	-	-	-	-	-	-	-	18	A-3a (V)	
		56	22	20	20	45	100	SS-16	-	-	-	-	-	-	-	-	8	A-3a (V)	

MATERIAL DESCRIPTION AND NOTES	ELEV. 426.3	DEPTHS	SPT/ RQD	N <sub>60</sub>	REC (%)	SAMPLE ID	HP (tsf)	GRADATION (%)					ATTERBERG			WC	DOT CLASS (G)	HOLE SEALED	
								GR	CS	FS	SI	CL	LL	PL	PI				
MEDIUM DENSE, BROWN, <b>COARSE AND FINE SAND</b> , LITTLE GRAVEL, TRACE SILT, TRACE CLAY, CLAY SEAM AT 50', VERY DENSE AT 60', WET (continued)	426.3	61	12 26 27	59	100	SS-17	-	-	-	-	-	-	-	-	-	14	A-3a (V)		
		62																	
		63																	
		64																	
		65																	
		66		16 23 21	49	67	SS-18	-	-	-	-	-	-	-	-	-	11		A-3a (V)
		67																	
		68																	
		69																	
		70																	
		71		13 14 17	35	67	SS-19	-	-	-	-	-	-	-	-	-	11		A-3a (V)
		72																	
		73																	
DENSE TO VERY DENSE, BROWN, <b>GRAVEL AND STONE FRAGMENTS</b> , SOME SAND, TRACE SILT, TRACE CLAY, WET	411.3	74																	
		75																	
		76		23 37 40	86	100	SS-20	-	56	17	17	7	3	NP	NP	NP	12	A-1-a (0)	
		77																	
		78																	
		79																	
		80																	
		81		18 24 23	53	67	SS-21	-	-	-	-	-	-	-	-	-	10	A-1-a (V)	
		82																	
		83																	
		84																	
VERY DENSE, GRAY AND BROWN, <b>GRAVEL AND STONE FRAGMENTS WITH SAND</b> , TRACE SILT, TRACE COBBLES, TRACE CLAY, WET	396.3	85																	
		86		16 20 22	47	100	SS-22	-	-	-	-	-	-	-	-	9	A-1-a (V)		
		87																	
		88																	
		89																	
		90																	
		91		57 65 50	129	100	SS-23	-	-	-	-	-	-	-	-	-	10	A-1-b (V)	
		92																	
		93																	
		94																	
		95																	
INTERBEDDED LIMESTONE (75%) AND SHALE (25%); <b>LIMESTONE</b> , GRAY, UNWEATHERED TO SLIGHTLY WEATHERED, STRONG, THIN BEDDED, FOSSILIFEROUS, LOSS 0%, RQD 39%; <b>SHALE</b> , GRAY, MODERATELY TO SLIGHTLY WEATHERED, VERY WEAK TO WEAK, LAMINATED, FISSILE, SH @ 109' SDI = 50.9 LS/SH @113.5'-114' QU=6755 PSI SH @ 118.5' SDI = 48.1 LS @120.2'-120.6' QU=10888 PSI.	379.3	96																	
		97																	
		98																	
		99																	
		100																	
		101		39 100/4"	-	100	SS-25	-	-	-	-	-	-	-	-	-	-	A-1-b (V)	
		102																	
		103																	
		104																	
		105																	
		106		100/3"	-	133	SS-26	-	-	-	-	-	-	-	-	-	-	A-1-b (V)	
CORE	TR	107																	
		108																	
		109																	
		110		32		100	NQ-1											CORE	
		111																	
		112																	
		113																	
CORE		114																	
		115		46		100	NQ-2											CORE	
		116																	
		117																	
		118																	
CORE		119																	
		120		38		100	NQ-3											CORE	
		121																	
		122																	

MATERIAL DESCRIPTION AND NOTES	ELEV. 364.4	DEPTHS	SPT/ RQD	N <sub>60</sub>	REC (%)	SAMPLE ID	HP (tsf)	GRADATION (%)					ATTERBERG				ODOT CLASS (G)	HOLE SEALED	
								GR	CS	FS	SI	CL	LL	PL	PI	WC			
<b>LIMESTONE</b> , GRAY, UNWEATHERED, STRONG, THIN BEDDED, FOSSILIFEROUS, ARGILLACEOUS, TRACE SHALE PARTINGS TO SEAMS, NOTED CALCITE FILLED VUGS; LOSS 0%, RQD=64%  LS @ 122.7' POINT LOAD = 14712 PSI  LS/SH @130.3'-131' QU=6755 PSI  LS/SH @133.3'-133.8' QU=8455 PSI  LS @137.3'-138' QU=20794 PSI  LS @ 143.5' POINT LOAD = 144 PSI.	364.3	123	48		100	NQ-4												CORE	
		124																	125
		126	127	58		100	NQ-5												CORE
		128	129																
		130	131	62		100	NQ-6												CORE
		132	133																
		134	135	66		100	NQ-7												CORE
		136	137																
	138	139	84		100	NQ-8												CORE	
	140	141																	
	142	143																	
	144	145																	
	146	147																	
	339.3	EOB																	


STANDARD ODOT SOIL BORING LOG (11 X 17) - OH.DOT.GDT - 3/9/11 10:07 - N:\PROJECTS\2010\1105070\GINT\ODOT LOGS.GPJ

NOTES: WATER USED BELOW 45 FT. FOR DRILLING/ROCK CORING PURPOSES.

ABANDONMENT METHODS, MATERIALS, QUANTITIES: BACKFILLED WITH BENTONITE GROUT (11 BAGS CEMENT/1.5 BAGS BENTONITE)




BORING NO.: L- 5  
 CORE BOX NO.: 1 OF 3  
 DEPTH (ft.): 107.0-122.0  
 ELEVATION (ft.): 379.33  
 1/NQ: 107.0'-112.0'; REC. 100%, RQD 32%  
 2/NQ: 112.0'-117.0'; REC. 100%, RQD 46%  
 3/NQ: 117.0'-122.0'; REC. 100%, RQD 38%



BORING NO.: L- 5  
 CORE BOX NO.: 2 OF 3  
 DEPTH (ft.): 122.0-135.0  
 ELEVATION (ft.): 364.33  
 4/NQ: 122.0'-127.0'; REC. 100%, RQD 48%  
 5/NQ: 127.0'-132.0'; REC. 100%, RQD 58%  
 6/NQ: 132.0'-137.0'; REC. 100%, RQD 62%



BORING NO.: L- 5  
 CORE BOX NO.: 3 OF 3  
 DEPTH (ft.): 135.0-147.0  
 ELEVATION (ft.): 351.33  
 7/NQ: 137.0'-142.0'; REC. 100%, RQD 66%  
 8/NQ: 142.0'-147.0'; REC. 100%, RQD 84%

Project Mngr.: AJM	PN: N1105070	 611 LUNKEN PARK DRIVE CINCINNATI, OHIO 45226	<b>ROCK CORE PHOTOGRAPHS</b>	BORING
Drawn By: TCF	Scale: As Shown		BRENT SPENCE BRIDGE REPLACEMENT PARSONS BRINCKERHOFF CINCINNATI, OHIO	L-5
Chkd By: DWW	File No. Core B			
Approved By: AJM	Date: 9-8-10			

PROJECT: BRENT SPENCE BRIDGE		DRILLING FIRM / OPERATOR: HCN / JM		DRILL RIG: DIEDRICH D-50		STATION / OFFSET: 2+49.4, 51.4 RT		EXPLORATION ID														
TYPE: BRIDGE REPLACEMENT		SAMPLING FIRM / LOGGER: HCN / DRK/DWW		HAMMER: CME AUTOMATIC		ALIGNMENT: PROPOSED BSB		L-6														
PID: 75119 BR ID:		DRILLING METHOD: 3.25" HSA / NQ		CALIBRATION DATE: 9/9/10		ELEVATION: 485.7 (MSL) EOB: 148.5 ft.		PAGE														
START: 6/28/10 END: 6/30/10		SAMPLING METHOD: SPT / ST / NQ		ENERGY RATIO (%): 83.7		COORD: 39.087930220, -84.523068980		1 OF 3														
MATERIAL DESCRIPTION AND NOTES			ELEV.	DEPTH	SPT/ RQD	N <sub>60</sub>	REC (%)	SAMPLE ID	HP (tsf)	GRADATION (%)					ATTERBERG				DOT CLASS (GI)	HOLE SEALED		
										GR	CS	FS	SI	CL	LL	PL	FI	WC				
CONCRETE PRE-DRILLED (VACUUM EXCAVATED)			485.7	1																		
				2																		
				3																		
				4																		
				5																		
				6																		
			478.2	7																		
STIFF, BROWN, SILT AND CLAY, TRACE SAND, MOIST				8	2	3	10	67	SS-1	2.00	-	-	-	-	-	-	-	-	21	A-6a (V)		
				9		4																
				10	2	3	11	83	SS-2	2.00	0	0	10	53	37	33	19	14	22	A-6a (10)		
				11		5																
				12																		
				13			83	ST-3	1.50	-	-	-	-	-	-	-	-	-	26	A-6a (V)		
				14																		
				15	3	3	8	67	SS-4	2.00	0	0	9	54	37	33	19	14	24	A-6a (10)		
				16																		
				17																		
				18																		
				19																		
				20	2	3	11	100	SS-5	2.00	-	-	-	-	-	-	-	-	25	A-6a (V)		
				21		5																
				22																		
				23																		
				24																		
			460.7	25	2	2	8	100	SS-6	1.50	0	0	5	62	33	32	20	12	27	A-6a (9)		
STIFF, GRAY, SILT AND CLAY, TRACE SILT SEAMS, TRACE SAND, MOIST				26		4																
				27																		
				28																		
				29																		
				30																		
				31			100	ST-7	1.25	0	0	10	56	34	30	19	11	28	A-6a (8)			
				32	1	2	8	100	SS-8	1.50	-	-	-	-	-	-	-	-	-	A-6a (V)		
				33		4																
				34																		
				35	1	2	7	100	SS-9	2.00	-	-	-	-	-	-	-	-	27	A-6a (V)		
				36		3																
				37																		
				38																		
				39																		
				40	1	2	7	100	SS-10	1.75	-	-	-	-	-	-	-	-	27	A-6a (V)		
				41		3																
				42																		
				43																		
				44																		
			440.7	45	3	4	13	78	SS-11	-	-	-	-	-	-	-	-	-	21	A-4b (V)		
MEDIUM DENSE TO DENSE, BROWN, SILT, LITTLE SAND, TRACE CLAY, LITTLE GRAVEL, VERY DENSE AT 70', WET				46		5																
				47																		
				48																		
				49																		
				50	9	10	27	67	SS-12	-	14	6	9	57	14	NP	NP	NP	23	A-4b (7)		
				51		9																
				52																		
				53																		
				54																		
				55	5	17	49	67	SS-13	-	-	-	-	-	-	-	-	-	21	A-4b (V)		
				56		18																
				57																		
				58																		
				59																		

MATERIAL DESCRIPTION AND NOTES	ELEV.	DEPTHS	SPT/RQD	N <sub>60</sub>	REC (%)	SAMPLE ID	HP (tsf)	GRADATION (%)					ATTERBERG			WC	ODOT CLASS (G)	HOLE SEALED
								GR	CS	FS	SI	CL	LL	PL	PI			
MEDIUM DENSE TO DENSE, BROWN, SILT, LITTLE SAND, TRACE CLAY, LITTLE GRAVEL, VERY DENSE AT 70', WET (continued)	425.7	61	15 18 17	49	33	SS-14	-	-	-	-	-	-	-	-	-	8	A-4b (V)	
		62																
		63																
		64																
		65																
		66		11 13 18	43	67	SS-15	-	-	-	-	-	-	-	-	16	A-4b (V)	
		67																
		68																
		69																
		70		19 37 34	99	78	SS-16	-	-	-	-	-	-	-	-	9	A-4b (V)	
	71																	
	72																	
	73																	
	74																	
	75		10 21 23	61	67	SS-17	-	-	-	-	-	-	-	-	11	A-4b (V)		
	76																	
	77																	
	78																	
	79																	
	80																	
DENSE TO VERY DENSE, BROWN, GRAVEL AND STONE FRAGMENTS WITH SAND, TRACE SILT, TRACE CLAY, WET	405.7	80	19 19 13	45	78	SS-18	-	-	-	-	-	-	-	-	9	A-1-b (V)		
		81																
		82																
		83																
		84																
	85		17 17 21	53	67	SS-19	-	-	-	-	-	-	-	-	12	A-1-b (V)		
	86																	
	87																	
	88																	
	89																	
VERY DENSE, GRAY, GRAVEL AND STONE FRAGMENTS WITH SAND, TRACE SILT, TRACE CLAY, WET	395.7	90	26 40 36	106	67	SS-20	-	31	28	27	10	4	NP	NP	NP	9	A-1-b (0)	
		91																
		92																
		93																
		94																
		95		50/5"	-	80	SS-21	-	-	-	-	-	-	-	-	8	A-1-b (V)	
		96																
		97																
		98																
		99																
	100		100/4"	-	75	SS-22	-	-	-	-	-	-	-	-	7	A-1-b (V)		
	101																	
	102																	
	103																	
	104																	
	105		44 39 50/5"	-	47	SS-23	-	-	-	-	-	-	-	-	10	A-1-b (V)		
	106																	
	107																	
	108																	
<b>INTERBEDDED LIMESTONE (75%) AND SHALE (25%);</b> LIMESTONE, GRAY, UNWEATHERED TO SLIGHTLY WEATHERED, MODERATELY STRONG TO STRONG, THIN BEDDED, FOSSILIFEROUS, LOSS 1%, RQD 42%; SHALE, GRAY, SLIGHTLY WEATHERED, VERY WEAK TO WEAK, LAMINATED, FISSILE, SH @ 110' SDI = 56.9  LS/SH @ 112'-112.4' QU=4889 PSI LS @ 114' POINT LOAD = 11720 PSI SH @ 117.7' SDI = 55.1 LS @ 120.5'-121' QU=14568 PSI LS @ 126.3' POINT LOAD = 12087 PSI.	377.2	109	100/1"	-	0	SS-24	-	-	-	-	-	-	-	-	-	-		
		110																
		111		11		100	NQ-1										CORE	
		112																
		113																
		114																
	115																	
	116		64		100	NQ-2											CORE	
	117																	
	118																	
	119																	
	120																	
	121		50		100	NQ-3											CORE	



MATERIAL DESCRIPTION AND NOTES	ELEV. 363.8	DEPTHS	SPT/ RQD	N <sub>60</sub>	REC (%)	SAMPLE ID	HP (tsf)	GRADATION (%)					ATTERBERG				ODOT CLASS (G)	HOLE SEALED	
								GR	CS	FS	SI	CL	LL	PL	PI	WC			
<b>LIMESTONE</b> , GRAY, UNWEATHERED, MODERATELY STRONG TO STRONG, THIN BEDDED, ARGILLACEOUS, ARGILLACEOUS SEAMS, FOSSILIFEROUS SEAMS, TRACE SHALE PARTINGS; LOSS 1%, RQD=68%  LS @130.5'-130.9' QU=9864 PSI LS @138'-138.3' QU=25530 PSI LS @147.5'-148' QU=10726 PSI.	362.2	123																	
		124																	
		125																	
		126	60		100	NQ-4												CORE	
		127																	
		128																	
		129																	
		130																	
		131	76		98	NQ-5													CORE
		132																	
	133																		
	134																		
	135																		
	136	56		100	NQ-6													CORE	
	137																		
	138																		
	139																		
	140																		
	141	76		100	NQ-8													CORE	
	142																		
	143																		
	144																		
	145																		
	146	82		100	NQ-7													CORE	
	147																		
	148																		
	337.2	EOB																	


STANDARD ODOT SOIL BORING LOG (11 X 17) - OH DOT.GDT - 3/9/11 10:07 - N:\PROJECTS\2010\N1105070\GINT\ODOT LOGS.GPJ

NOTES: WATER USED BELOW 45 FT. FOR DRILLING/ROCK CORING PURPOSES.

ABANDONMENT METHODS, MATERIALS, QUANTITIES: BACKFILLED WITH BENTONITE GROUT (12 BAGS CEMENT/1.5 BAGS BENTONITE)




BORING NO.: L- 6  
 CORE BOX NO.: 1 OF 3  
 DEPTH (ft.): 108.5-123.5  
 ELEVATION (ft.): 377.19  
 1/NQ: 108.5'-113.5'; REC. 98%, RQD 11%  
 2/NQ: 113.5'-118.5'; REC. 100%, RQD 64%  
 3/NQ: 118.5'-123.5'; REC. 100%, RQD 50%



BORING NO.: L- 6  
 CORE BOX NO.: 2 OF 3  
 DEPTH (ft.): 123.5-138.5  
 ELEVATION (ft.): 362.19  
 4/NQ: 123.5'-128.5'; REC. 100%, RQD 60%  
 5/NQ: 128.5'-133.5'; REC. 98%, RQD 76%  
 6/NQ: 133.5'-138.5'; REC. 100%, RQD 56%



BORING NO.: L- 6  
 CORE BOX NO.: 3 OF 3  
 DEPTH (ft.): 138.5-143.5  
 ELEVATION (ft.): 347.19  
 7/NQ: 138.5'-143.5'; REC. 100%, RQD 76%  
 8/NQ: 143.5'-148.5'; REC. 100%, RQD 82%

Project Mngr.: AJM	PN: N1105070	 611 LUNKEN PARK DRIVE CINCINNATI, OHIO 45226	<b>ROCK CORE PHOTOGRAPHS</b>	BORING
Drawn By: TCF	Scale: As Shown		BRENT SPENCE BRIDGE REPLACEMENT PARSONS BRINCKERHOFF CINCINNATI, OHIO	L-6
Chkd By: DWW	File No. Core B			
Approved By: AJM	Date: 9-8-10			

MATERIAL DESCRIPTION AND NOTES	ELEV.	DEPTHS	SPT/RQD	N <sub>60</sub>	REC (%)	SAMPLE ID	HP (tsf)	GRADATION (%)					ATTERBERG				HOLE SEALED		
								GR	CS	FS	SI	CL	LL	PL	PI	WC		ODOT CLASS (GI)	
ASPHALT PAVEMENT PRE-DRILLED (VACUUM EXCAVATED)	484.4	1-4																	
VERY LOOSE, GRAY AND BLACK, <b>SANDY SILT</b> , LITTLE GRAVEL, LITTLE CLAY, TRACE CONCRETE (FILL), MOIST	479.4	5	WOH																
		6	WOH 1	1	61	SS-1	-	-	-	-	-	-	-	-	26	A-4a (V)			
MEDIUM STIFF, GRAY, <b>SILT AND CLAY</b> , SOME GRAVEL, TRACE ORGANICS, TRACE SAND (FILL), MOIST	474.4	8	1	1	2	100	SS-2	-	23	17	22	20	18	NP	NP	NP	19	A-4a (1)	
		10	WOH																
STIFF TO VERY STIFF, BROWN AND GRAY, <b>SILT AND CLAY</b> , LITTLE SAND, TRACE GRAVEL, MOIST	469.4	11	WOH																
		12	WOH 1	1	100	SS-3	1.00	-	-	-	-	-	-	-	23	A-6a (V)			
MEDIUM DENSE, BROWN, <b>GRAVEL AND STONE FRAGMENTS</b> , AND SAND, TRACE SILT, TRACE CLAY, VERY LOOSE AT 45', WET	449.4	14			63	ST-4	-	31	2	8	30	29	29	17	12	21	A-6a (6)		
		15	2	3	4	8	100	SS-5	1.00	-	-	-	-	-	-	27	A-6a (V)		
		18	2	2	4	7	100	SS-6	-	-	-	-	-	-	-	23	A-6a (V)		
		21				100	ST-7	1.50	0	0	18	44	38	31	17	14	25	A-6a (10)	
		22	2	3	4	8	33	SS-8	2.50	0	0	17	48	35	32	18	14	23	A-6a (10)
		25	3	4	6	11	100	SS-9	1.00	-	-	-	-	-	-	-	30	A-6a (V)	
		30	1	1	2	3	100	SS-10	-	-	-	-	-	-	-	-	24	A-6a (V)	
		34				75	ST-11	-	33	4	14	25	24	31	17	14	25	A-6a (4)	
		35	3	3	4	8	100	SS-12	-	-	-	-	-	-	-	-	22	A-1-a (V)	
		40	3	4	5	10	44	SS-13	-	-	-	-	-	-	-	-	27	A-1-a (V)	
45	2	2	2	4	100	SS-14	-	-	-	-	-	-	-	-	33	A-1-a (V)			
50	53	9	7	18	67	SS-15	-	-	-	-	-	-	-	-	16	A-1-a (V)			
55	9	11	17	31	100	SS-16	-	-	-	-	-	-	-	-	10	A-1-a (V)			

MATERIAL DESCRIPTION AND NOTES	ELEV. 424.4	DEPTH	SPT/ RQD	N <sub>60</sub>	REC (%)	SAMPLE ID	HP (tsf)	GRADATION (%)					ATTERBERG			WC	DOT CLASS (G)	HOLE SEALED	
								GR	CS	FS	SI	CL	LL	PL	PI				
MEDIUM DENSE, BROWN, GRAVEL AND STONE FRAGMENTS, AND SAND, TRACE SILT, TRACE CLAY, VERY LOOSE AT 45', WET (continued)	424.4	61	13 14 14	31	67	SS-17	-	55	28	10	5	2	NP	NP	NP	10	A-1-a (0)		
		62																	
		63																	
		64																	
		65																	
		66																	
		67																	
		68																	
		69																	
		70																	
DENSE, BROWN, GRAVEL AND STONE FRAGMENTS, SOME SAND, TRACE COBBLES, TRACE SILT, TRACE CLAY, WET	409.4	75	14 13 15	31	83	SS-20	-	61	18	13	5	3	NP	NP	NP	9	A-1-a (0)		
		76																	
		77																	
		78																	
		79																	
		80																	
		81																	
		82																	
		83																	
		84																	
VERY DENSE, GRAY, GRAVEL AND STONE FRAGMENTS, SOME SAND, TRACE COBBLES, LITTLE SILT, TRACE CLAY, WET	399.4	85	100 50/0"	-	100	SS-22	-	-	-	-	-	-	-	-	-	10	A-1-b (V)		
		86																	
		87																	
		88																	
		89																	
		90																	
		91																	
		92																	
		93																	
		94																	
INTERBEDDED LIMESTONE (75%) AND SHALE (25%); LIMESTONE, GRAY, UNWEATHERED TO SLIGHTLY WEATHERED, MODERATELY STRONG, THIN BEDDED, FOSSILIFEROUS, LOSS 0%, RQD 66%; SHALE, GRAY, SLIGHTLY WEATHERED, VERY WEAK TO WEAK, LAMINATED, FISSILE, LS @ 101'-101.5' QU=8217 PSI SH @ 105.5' SDI = 65.9 SH @ 107.5' SDI = 93.3 LS @ 113.7'-114.2' QU=5847 PSI LS @ 116' POINT LOAD = 10879 PSI LS @ 125.7'-126.2' QU=23281 PSI SH @ 118.6' SDI = 77.0.	384.4	95	37 53 60	126	67	SS-24	-	-	-	-	-	-	-	-	-	10	A-1-b (V)		
		96																	
		97																	
		98																	
		99																	
		100																	
		101																	
		102																	
		103																	
		104																	
TR	384.4	100	100/4"	-	100	SS-25	-	-	-	-	-	-	-	-	-	-	Rock (V)		
		101																	
		102																	
		103																	
		104																	
		105																	
		106																	
		107																	
	384.4	108	70	100	100	NQ-3											CORE		
		109																	
		110																	
		111																	
		112																	
	384.4	113	82	100	100	NQ-4											CORE		
		114																	
		115																	
		116																	
		117																	
	384.4	118	84	100	100	NQ-5											CORE		
		119																	
		120																	
		121																	
		122																	

STANDARD ODOT SOIL BORING LOG (11 X 17) - OH.DOT.GDT - 3/9/11 10:07 - N:\PROJECTS\2010\1105070\GINT\ODOT LOGS.GPJ

MATERIAL DESCRIPTION AND NOTES	ELEV. 362.5	DEPTHS	SPT/ RQD	N <sub>60</sub>	REC (%)	SAMPLE ID	HP (tsf)	GRADATION (%)					ATTERBERG				ODOT CLASS (G)	HOLE SEALED	
								GR	CS	FS	SI	CL	LL	PL	PI	WC			
LIMESTONE, GRAY, UNWEATHERED, MODERATELY STRONG, ARGILLACEOUS, FOSSILIFEROUS SEAMS, TRACE SHALE PARTINGS; LOSS 0%, RQD=86%  LS/SH @132.5'-133.2' QU=4790 PSI  LS @ 139.7' POINT LOAD = 11517 PSI.	356.4	123	56		100	NQ-6												CORE	
		124																	
		125																	
		126																	
		127	76		100	NQ-7												CORE	
		128																	
		129																	
		130																	
		131	92		100	NQ-8												CORE	
		132																	
		133																	
		134																	
		135	90		100	NQ-9												CORE	
		136																	
		137																	
		138																	
	342.7	139																	
		140																	
		141																	
		EOB																	

STANDARD ODOT SOIL BORING LOG (11 X 17) - OH.DOT.GDT - 3/9/11 10:07 - N:\PROJECTS\2010\N1105070\GINT\ODOT LOGS.GPJ

NOTES: WATER USED BELOW 35 FT. FOR DRILLING/ROCK CORING PURPOSES.  
 ABANDONMENT METHODS, MATERIALS, QUANTITIES: BACKFILLED WITH BENTONITE GROUT (12 BAGS CEMENT/1 BAGS BENTONITE)




BORING NO.: L-7  
 CORE BOX NO.: 1 OF 3  
 DEPTH (ft.): 100.5-116.7  
 ELEVATION (ft.): 383.91  
 1/NQ: 100.5'-101.7'; REC. 100%, RQD 33%  
 2/NQ: 101.7'-106.7'; REC. 100%, RQD 48%  
 3/NQ: 106.7'-111.7'; REC. 100%, RQD 70%  
 4/NQ: 111.7'-116.7'; REC. 100%, RQD 82%



BORING NO.: L-7  
 CORE BOX NO.: 2 OF 3  
 DEPTH (ft.): 116.7-131.7  
 ELEVATION (ft.): 367.71  
 5/NQ: 116.7'-121.7'; REC. 100%, RQD 84%  
 6/NQ: 121.7'-126.7'; REC. 100%, RQD 56%  
 7/NQ: 126.7'-131.7'; REC. 100%, RQD 76%



BORING NO.: L-7  
 CORE BOX NO.: 3 OF 3  
 DEPTH (ft.): 131.7-141.7  
 ELEVATION (ft.): 352.71  
 8/NQ: 131.7'-136.7'; REC. 100%, RQD 92%  
 9/NQ: 136.7'-141.7'; REC. 100%, RQD 90%

Project Mngr.: AJM	PN: N1105070	 611 LUNKEN PARK DRIVE CINCINNATI, OHIO 45226	<b>ROCK CORE PHOTOGRAPHS</b>	BORING
Drawn By: TCF	Scale: As Shown		BRENT SPENCE BRIDGE REPLACEMENT PARSONS BRINCKERHOFF CINCINNATI, OHIO	L-7
Chkd By: DWW	File No. Core B			
Approved By: AJM	Date: 9-8-10			

PROJECT: BRENT SPENCE BRIDGE	DRILLING FIRM / OPERATOR: HCN / HH	DRILL RIG: CME 550X ATV-7253	STATION / OFFSET: 17+75.2, 41.52 RT	EXPLORATION ID: R-1
TYPE: BRIDGE REPLACEMENT	SAMPLING FIRM / LOGGER: HCN / DWW	HAMMER: CME AUTOMATIC	ALIGNMENT: PROPOSED BSB	
PID: 75119 BR ID:	DRILLING METHOD: 3.25" HSA / NQ	CALIBRATION DATE: 2/4/10	ELEVATION: 458.0 (MSL) EOB: 170.0 ft.	PAGE 1 OF 3
START: 7/9/10 END: 7/11/10	SAMPLING METHOD: SPT / NQ	ENERGY RATIO (%): 76.3	COORD: 39.092117290, -84.522898570	

MATERIAL DESCRIPTION AND NOTES	ELEV.	DEPTHS	SPT/RQD	N <sub>60</sub>	REC (%)	SAMPLE ID	HP (tsf)	GRADATION (%)					ATTERBERG				WC	ODOT CLASS (GI)	HOLE SEALED
								GR	CS	FS	SI	CL	LL	PL	FI	WC			
WATER (OHIO RIVER)	458.0	1-31																	
LOOSE, BROWN, GRAVEL AND STONE FRAGMENTS, LITTLE SAND, TRACE SILT, TRACE CLAY, VERY DENSE AT 33.5', WET	426.0	32-33	5	4	10	22	SS-1	-	87	11	2	0	0	NP	NP	NP	12	A-1-a (0)	
		34-35	9	24	23	60	SS-2	-	70	21	7	1	1	NP	NP	NP	13	A-1-a (0)	
	421.5	36-37	13	2	3	6	SS-3	-	-	-	-	-	-	-	-	-	-	A-1-a (V)	
MEDIUM DENSE, BROWN, GRAVEL AND STONE FRAGMENTS WITH SAND, TRACE SILT, TRACE CLAY, VERY LOOSE AT 36.5', WET		38-39	3	1	2	4	SS-4	-	2	64	29	2	3	NP	NP	NP	23	A-1-b (0)	
	418.5	40-41	5	6	6	15	SS-5	-	-	-	-	-	-	-	-	-	-	A-1-b (V)	
LOOSE TO MEDIUM DENSE, BROWN, FINE SAND, TRACE GRAVEL, TRACE SILT, TRACE CLAY, SAMPLE NOT OBTAINED AT 50' DUE TO SAND IN CASING, WET		42-43	3	2	2	5	SS-6	-	2	24	69	2	3	NP	NP	NP	23	A-3 (0)	
		44-45	2	4	10	18	SS-7	-	-	-	-	-	-	-	-	-	-	A-3 (V)	
		46-47	6	7	8	19	SS-8	-	-	-	-	-	-	-	-	-	-	A-3 (V)	
		48-49																	
		50-51				0	SS-10	-	-	-	-	-	-	-	-	-	-	A-3 (V)	
		52-53																	
		54-55																	
		56-57	6	7	7	18	SS-11	-	2	32	61	3	2	NP	NP	NP	21	A-3 (0)	
		58-59																	

STANDARD ODOT SOIL BORING LOG (11 X 17) - OH DOT.GDT - 3/9/11 10:07 - N:\PROJECTS\2010\N1105070\GINT\ODOT LOGS.GPJ

MATERIAL DESCRIPTION AND NOTES	ELEV.	DEPTHS	SPT/ RQD	N <sub>60</sub>	REC (%)	SAMPLE ID	HP (tsf)	GRADATION (%)					ATTERBERG			WC	ODOT CLASS (G)	HOLE SEALED	
								GR	CS	FS	SI	CL	LL	PL	PI				
LOOSE TO MEDIUM DENSE, BROWN, FINE SAND, TRACE GRAVEL, TRACE SILT, TRACE CLAY, SAMPLE NOT OBTAINED AT 50' DUE TO SAND IN CASING, WET (continued)	398.0	61	5 7 7	18	67	SS-12	-	-	-	-	-	-	-	-	-	-	26	A-3 (V)	
MEDIUM DENSE TO DENSE, BROWN, GRAVEL AND STONE FRAGMENTS WITH SAND, TRACE SILT, TRACE CLAY, WET	393.0	65	15 8 8	20	67	SS-13	-	-	-	-	-	-	-	-	-	-	14	A-1-b (V)	
		70	22 17 12	37	22	SS-14	-	-	-	-	-	-	-	-	-	-	14	A-1-b (V)	
		75	5 7 15	28	100	SS-15	-	-	-	-	-	-	-	-	-	-	19	A-1-b (V)	
ROCK (AUGERED TO 87')	377.0	80	50/0"	-	-	SS-16	-	-	-	-	-	-	-	-	-	-	-	A-1-b (V)	
LIMESTONE, GRAY, UNWEATHERED, MODERATELY STRONG TO STRONG, THIN BEDDED, ARGILLACEOUS, FOSSILIFEROUS SEAMS, MODERATELY FRACTURED, LOSS 2%, RQD 68%	371.0	87																	
LS @91.5'-92.1' QU=12758 PSI		88	50		93	NQ-1													CORE
LS @94.3'-95' QU=4903 PSI		90																	
LS @ 101' POINT LOAD = 10455 PSI		91																	
LS @104.5'-105' QU=3951 PSI		92	52		96	NQ-2													CORE
LS @ 110.2' POINT LOAD = 1282 PSI		93																	
LS @115'-115.9' 12584 PSI		94																	
LS @123'-123.5' QU=10024 PSI		95																	
LS @ 129.4' POINT LOAD = 11103 PSI		96																	
LS @136'-136.5' QU=14820 PSI		97	66		100	NQ-3													CORE
LS @137.7'-138.2' QU=15380 PSI		98																	
LS @145.3'-145.7' QU=7449 PSI		99																	
LS @ 145.7' POINT LOAD = 13095 PSI		100																	
LS @146.5'-147' QU=20779 PSI		101																	
LS @153'-153.6' QU=12853 PSI		102	52		100	NQ-4													CORE
LS @159.1'-159.9' QU=11057 PSI		103																	
LS @ 161.8' POINT LOAD = 14614 PSI		104																	
LS @163.5'-164.2' QU=14214 PSI		105																	
LS @168.2'-168.9' QU=13890 PSI.		106	66		100	NQ-5													CORE
		107																	
		108																	
		109																	
		110																	
		111																	
		112	70		96	NQ-6													CORE
		113																	
		114																	
		115																	
		116																	
		117	80		100	NQ-7													CORE
		118																	
		119																	
		120																	
		121																	


STANDARD ODOT SOIL BORING LOG (11 X 17) - OH.DOT.GDT - 3/9/11 10:07 - N:\PROJECTS\2010\1105070\GINT\ODOT LOGS.GPJ



MATERIAL DESCRIPTION AND NOTES	ELEV. 336.2	DEPTHS	SPT/ RQD	N <sub>60</sub>	REC (%)	SAMPLE ID	HP (tsf)	GRADATION (%)					ATTERBERG				ODOT CLASS (G)	HOLE SEALED		
								GR	CS	FS	SI	CL	LL	PL	PI	WC				
<b>LIMESTONE, GRAY, UNWEATHERED, MODERATELY STRONG TO STRONG, THIN BEDDED, ARGILLACEOUS, FOSSILIFEROUS SEAMS, MODERATELY FRACTURED, LOSS 2%, RQD 68%</b> LS @91.5'-92.1' QU=12758 PSI LS @94.3'-95' QU=4903 PSI LS @ 101' POINT LOAD = 10455 PSI LS @104.5'-105' QU=3951 PSI LS @ 110.2' POINT LOAD = 1282 PSI LS @115'-115.9' 12584 PSI LS @123'-123.5' QU=10024 PSI LS @ 129.4' POINT LOAD = 11103 PSI LS @136'-136.5' QU=14820 PSI LS @137.7'-138.2' QU=15380 PSI LS @145.3'-145.7' QU=7449 PSI LS @ 145.7' POINT LOAD = 13095 PSI LS @146.5'-147' QU=20779 PSI LS @153'-153.6' QU=12853 PSI LS @159.1'-159.9' QU=11057 PSI LS @ 161.8' POINT LOAD = 14614 PSI LS @163.5'-164.2' QU=14214 PSI LS @168.2'-168.9' QU=13890 PSI. (continued)		123	88		100	NQ-8											CORE			
			124																	
			125																	
			126																	
			127	84		100	NQ-9												CORE	
			128																	
			129																	
			130																	
			131																	
			132	46		100	NQ-10												CORE	
			133																	
			134																	
			135																	
			136																	
			137	72		98	NQ-11												CORE	
			138																	
			139																	
		140																		
		141																		
		142	76		100	NQ-12												CORE		
		143																		
		144																		
		145																		
		146																		
		147	78		100	NQ-13												CORE		
		148																		
		149																		
		150																		
		151																		
		152	80		100	NQ-14												CORE		
		153																		
		154																		
		155																		
		156																		
		157	82		98	NQ-15												CORE		
		158																		
		159																		
		160																		
		161																		
		162	74		100	NQ-16												CORE		
		163																		
		164																		
		165																		
		166																		
		167	38		86	NQ-17												CORE		
		168																		
		169																		
	288.0	170																		

STANDARD ODOT SOIL BORING LOG (11 X 17) - OH DOT.GDT - 3/9/11 10:07 - N:\PROJECTS\2010\1105070\GINT\ODOT LOGS.GPJ


NOTES: WATER USED BELOW 87 FT. FOR ROCK CORING PURPOSES.  
 ABANDONMENT METHODS, MATERIALS, QUANTITIES: BACKFILLED WITH BENTONITE GROUT (9 BAGS CEMENT/1 BAG BENTONITE)




BORING NO.: R-1  
 CORE BOX NO.: 1 OF 6  
 DEPTH (ft.): 87.0-105.0  
 ELEVATION (ft.): 371.04  
 1/NQ: 87.0'-90.0'; REC. 93%, RQD 50%  
 2/NQ: 90.0'-95.0'; REC. 96%, RQD 52%  
 3/NQ: 95.0'-100.0'; REC. 100%, RQD 66%  
 4/NQ: 100.0'-105.0'; REC. 100%, RQD 52%



BORING NO.: R-1  
 CORE BOX NO.: 2 OF 6  
 DEPTH (ft.): 105.0-120.0  
 ELEVATION (ft.): 353.04  
 5/NQ: 105.0'-110.0'; REC. 100%, RQD 66%  
 6/NQ: 110.0' - 115.0'; REC. 96%, RQD 70%  
 7/NQ: 115.0' - 120.0'; REC. 100%, RQD 80%




BORING NO.: R-1  
 CORE BOX NO.: 3 OF 6  
 DEPTH (ft.): 120.0-135.0  
 ELEVATION (ft.): 338.04  
 8/NQ: 120.0'-125.0'; REC. 100%, RQD 88%  
 9/NQ: 125.0'-130.0'; REC. 100%, RQD 84%  
 10/NQ: 130.0'-135.0'; REC. 100%, RQD 46%

Project Mngr.: AJM	PN: N1105070	 611 LUNKEN PARK DRIVE CINCINNATI, OHIO 45226	<b>ROCK CORE PHOTOGRAPHS</b>	BORING
Drawn By: TCF	Scale: As Shown		BRENT SPENCE BRIDGE REPLACEMENT PARSONS BRINCKERHOFF CINCINNATI, OHIO	R-1
Chkd By: DWW	File No. Core C			
Approved By: AJM	Date: 9-8-10			




BORING NO.: R-1  
 CORE BOX NO.: 4 OF 6  
 DEPTH (ft.): 135.0-150.0  
 ELEVATION (ft.): 323.04  
 11/NQ: 135.0'-140.0'; REC. 98%, RQD 72%  
 12/NQ: 140.0'-145.0'; REC. 100%, RQD 76%  
 13/NQ: 145.0'-150.0'; REC. 100%, RQD 78%



BORING NO.: R-1  
 CORE BOX NO.: 5 OF 6  
 DEPTH (ft.): 150.0-160.0  
 ELEVATION (ft.): 308.04  
 14/NQ: 150.0'-155.0'; REC. 100%, RQD 80%  
 15/NQ: 155.0'-160.0'; REC. 98%, RQD 82%



BORING NO.: R-1  
 CORE BOX NO.: 6 OF 6  
 DEPTH (ft.): 160.0-170.0  
 ELEVATION (ft.): 298.04  
 16/NQ: 160.0'-165.0'; REC. 100%, RQD 74%  
 17/NQ: 165.0'-170.0'; REC. 86%, RQD 38%

Project Mngr.: AJM	PN: N1105070	 611 LUNKEN PARK DRIVE CINCINNATI, OHIO 45226	<b>ROCK CORE PHOTOGRAPHS</b>	BORING
Drawn By: TCF	Scale: As Shown		BRENT SPENCE BRIDGE REPLACEMENT PARSONS BRINCKERHOFF CINCINNATI, OHIO	R-1
Chkd By: DWW	File No. Core C			
Approved By: AJM	Date: 9-8-10			

MATERIAL DESCRIPTION AND NOTES	ELEV.	DEPTH	SPT/RQD	N <sub>60</sub>	REC (%)	SAMPLE ID	HP (tsf)	GRADATION (%)					ATTERBERG				WC	DOT CLASS (GI)	HOLE SEALED
								GR	CS	FS	SI	CL	LL	PL	PI	WC			
WATER (OHIO RIVER)	458.1	1-28																	
VERY LOOSE, BROWN, GRAVEL AND STONE FRAGMENTS, LITTLE SAND, WET	429.1	29-32																	
	424.6	33	1	4	33	SS-1	-	87	11	2	0	0	NP	NP	NP	13	A-1-a (0)		
MEDIUM DENSE, BROWN, GRAVEL AND STONE FRAGMENTS WITH SAND, TRACE SILT, TRACE CLAY, WET	423.1	34	3	23	67	SS-2	-	22	58	16	2	2	NP	NP	NP	17	A-1-b (0)		
	421.6	35	6	12															
MEDIUM DENSE, BROWN, GRAVEL AND STONE FRAGMENTS, LITTLE SAND, TRACE SILT, TRACE CLAY, WET	421.6	36	17	6	13	33	SS-3	-	62	20	14	2	2	NP	NP	NP	15	A-1-a (0)	
LOOSE, BROWN, FINE SAND, LITTLE GRAVEL, TRACE SILT, TRACE CLAY, WET	420.1	37	4	4	10	100	SS-4	-	23	21	51	2	3	NP	NP	NP	18	A-3 (0)	
LOOSE TO MEDIUM DENSE, BROWN, GRAVEL AND STONE FRAGMENTS WITH SAND, TRACE SILT, TRACE CLAY, WET	413.1	38	11	9	20	0	SS-5	-	-	-	-	-	-	-	-	-	-	A-1-b (V)	
		39	4	5	13	100	SS-6	-	55	13	26	4	2	NP	NP	NP	15	A-1-b (0)	
		40	3	3	10	0	SS-7	-	-	-	-	-	-	-	-	-	-	A-1-b (V)	
		41																	
		42																	
		43																	
		44																	
LOOSE TO MEDIUM DENSE, BROWN, FINE SAND, TRACE SILT, TRACE GRAVEL, TRACE CLAY, WET	413.1	45	2	3	10	56	SS-8	-	9	18	69	1	3	NP	NP	NP	22	A-3 (0)	
		46																	
		47																	
		48	11	6	15	33	SS-9	-	-	-	-	-	-	-	-	-	-	28	A-3 (V)
		49																	
		50	6	6	15	44	SS-10	-	0	6	87	4	3	NP	NP	NP	25	A-3 (0)	
		51																	
		52																	
		53																	
		54																	
		55	15	10	27	44	SS-11	-	-	-	-	-	-	-	-	-	-	27	A-3 (V)
		56																	
		57																	
		58																	
		59																	

MATERIAL DESCRIPTION AND NOTES	ELEV. 398.1	DEPTHS	SPT/ RQD	N <sub>60</sub>	REC (%)	SAMPLE ID	HP (tsf)	GRADATION (%)					ATTERBERG			W <sub>C</sub>	ODOT CLASS (G)	HOLE SEALED			
								GR	CS	FS	SI	CL	LL	PL	PI						
LOOSE TO MEDIUM DENSE, BROWN, FINE SAND, TRACE SILT, TRACE GRAVEL, TRACE CLAY, WET (continued)	398.1	61	6	10	25	33	SS-12	-	1	12	80	3	4	NP	NP	NP	20	A-3 (0)			
		62																			
		63																			
		64																			
		65	11	11	28	33	SS-13	-	-	-	-	-	-	-	-	-	-	24		A-3 (V)	
		66																			
MEDIUM DENSE, BROWN, GRAVEL AND/OR STONE FRAGMENTS WITH SAND, TRACE SILT, TRACE CLAY, WET	388.1	70	6	9	32	67	SS-14	-	25	46	23	3	3	NP	NP	NP	15	A-1-b (0)			
		71																			
		72																			
		73																			
		74																			
		75	12	12	31	67	SS-15	-	17	40	37	3	3	NP	NP	NP	17	A-1-b (0)			
VERY DENSE, GRAY, STONE FRAGMENTS WITH SAND, LIMESTONE FLOATERS/COBBLES, WET	378.1	76																			
		77																			
		78																			
		79																			
		80	65	-	0	SS-16	-	-	-	-	-	-	-	-	-	-	-	-		A-1-b (V)	
		81																			
INTERBEDDED LIMESTONE (75%) AND SHALE (25%); LIMESTONE, LIGHT GRAY, UNWEATHERED TO SLIGHTLY WEATHERED, STRONG, THIN BEDDED, FOSSILIFEROUS; SHALE, GRAY, SLIGHTLY WEATHERED, VERY WEAK, VERY THIN TO THIN BEDDED, LOSS 5%, RQD 78%  LS @87.5'-88' QU=13147 PSI SH @ 88.2' SDI = 67.9 SH @ 89' SDI = 82.5 LS @89.3'-89.7' QU=9634 PSI LS @90.7'-91.6' QU=12836 PSI SH @ 93.7' SDI = 93.6 SH @93.7'-94' QU= 429 PSI LS @99.8'-100.1' QU=8025 PSI SH @ 100.4' SDI = 94.1 LS @ 107.7' POINT LOAD = 5783 PSI LS @112.9'-113.9' QU=14131 PSI.	371.1	85	50/0"	-	-	-	SS-17	-	-	-	-	-	-	-	-	-	-	A-1-b (V)	TR		
		86																			
		87																			
		88	45		100	NQ-1														CORE	
		89																			
		90																			
		91	74		100	NQ-2														CORE	
		92																			
		93																			
		94																			
		95																			
		96	80		86	NQ-3															CORE
		97																			
		98																			
99																					
100																					
101	82		94	NQ-4														CORE			
102																					
103																					
104																					
105																					
106	92		96	NQ-5														CORE			
107																					
108																					
109																					
110																					
111	74		98	NQ-6														CORE			
112																					
113																					
114																					
115																					
116	88		100	NQ-7														CORE			
117																					
118																					
119																					
120																					
121	76		94	NQ-8														CORE			

MATERIAL DESCRIPTION AND NOTES	ELEV. 336.2	DEPTHS	SPT/ RQD	N <sub>60</sub>	REC (%)	SAMPLE ID	HP (tsf)	GRADATION (%)					ATTERBERG				DOT CLASS (G)	HOLE SEALED	
								GR	CS	FS	SI	CL	LL	PL	PI	WC			
<b>LIMESTONE, GRAY, UNWEATHERED, STRONG, THIN BEDDED, FOSSILIFEROUS, ARGILLACEOUS, INTERMEDIATE SHALE SEAMS TO PARTINGS, LOSS 1%, RQD 84%</b>  LS @119.8'-120.6' QU=13926 PSI LS @ 130.7' POINT LOAD = 10575 PSI SH @ 134' SDI = 91.7 LS @139'-139.5' QU=7906 PSI LS @143.5'-144' QU=13836 PSI LS @ 148.5' POINT LOAD = 12884 PSI. (continued)	336.2	123																	
		124																	
		125																	
		126	88	100	NQ-9													CORE	
		127																	
		128																	
		129																	
		130																	
		131	76	100	NQ-10														CORE
		132																	
<b>LIMESTONE, GRAY, UNWEATHERED, VERY STRONG, THIN BEDDED, ARGILLACEOUS, LOSS 4%, RQD 83%</b>  LS @155.3'-155.6' QU=26538 PSI LS @ 159.5' POINT LOAD = 12962 PSI.	309.1	133																	
		134																	
		135																	
		136	86	100	NQ-11														CORE
		137																	
		138																	
		139																	
		140																	
		141	72	100	NQ-12														CORE
		142																	
	289.1	143																	
		144																	
		145																	
		146	100	100	NQ-13														CORE
		147																	
		148																	
		149																	
		150																	
		151	82	100	NQ-14														CORE
		152																	
	289.1	153																	
		154																	
		155																	
		156	100	100	NQ-15														CORE
		157																	
		158																	
		159																	
		160																	
		161	86	100	NQ-16														CORE
		162																	
	289.1	163																	
		164																	
		165																	
		166	64	82	NQ-17														CORE
		167																	
		168																	
		169																	

STANDARD ODOT SOIL BORING LOG (11 X 17) - OH.DOT.GDT - 3/9/11 10:07 - N:\PROJECTS\2010\1105070\GINT\ODOT LOGS.GPJ

NOTES: WATER USED BELOW 87 FT. FOR ROCK CORING PURPOSES.  
 ABANDONMENT METHODS, MATERIALS, QUANTITIES: BACKFILLED WITH BENTONITE GROUT (10 BAGS CEMENT/1 BAG BENTONITE)




BORING NO.: R-2  
 CORE BOX NO.: 1 OF 6  
 DEPTH (ft.): 87.0-104.0  
 ELEVATION (ft.): 371.1  
 1/NQ: 87.0'-89.0'; REC. 100%, RQD 45%  
 2/NQ: 89.0'-94.0'; REC. 100%, RQD 74%  
 3/NQ: 94.0'-99.0'; REC. 86%, RQD 80%  
 4/NQ: 99.0'-104.0'; REC. 94%, RQD 82%



BORING NO.: R-2  
 CORE BOX NO.: 2 OF 6  
 DEPTH (ft.): 104.0-114.0  
 ELEVATION (ft.): 354.1  
 5/NQ: 104.0'-109.0'; REC. 96%, RQD 92%  
 6/NQ: 109.0'-114.0'; REC. 98%, RQD 74%



BORING NO.: R-2  
 CORE BOX NO.: 3 OF 6  
 DEPTH (ft.): 114.0-134.0  
 ELEVATION (ft.): 344.1  
 7/NQ: 114.0'-119.0'; REC. 100%, RQD 88%  
 8/NQ: 119.0'-124.0'; REC. 94%, RQD 76%  
 9/NQ: 124.0'-129.0'; REC. 94%, RQD 76%  
 10/NQ: 129.0'-134.0'; REC. 100%, RQD 76%


Project Mngr.: AJM	PN: N1105070	 611 LUNKEN PARK DRIVE CINCINNATI, OHIO 45226	<b>ROCK CORE PHOTOGRAPHS</b>  BRENT SPENCE BRIDGE REPLACEMENT PARSONS BRINCKERHOFF CINCINNATI, OHIO	BORING
Drawn By: TCF	Scale: As Shown			R-2
Chkd By: DWW	File No. Core C			
Approved By: AJM	Date: 9-8-10			




BORING NO.: R-2  
 CORE BOX NO.: 4 OF 6  
 DEPTH (ft.): 134.0-144.0  
 ELEVATION (ft.): 324.1  
 11/NQ: 134.0'-139.0'; REC. 100%, RQD 86%  
 12/NQ: 139.0'-144.0'; REC. 100%, RQD 72%



BORING NO.: R-2  
 CORE BOX NO.: 5 OF 6  
 DEPTH (ft.): 144.0-154.0  
 ELEVATION (ft.): 314.1  
 13/NQ: 144.0'-149.0'; REC. 100%, RQD 100%  
 14/NQ: 149.0'-154.0'; REC. 100%, RQD 82%



BORING NO.: R-2  
 CORE BOX NO.: 6 OF 6  
 DEPTH (ft.): 154.0-169.0  
 ELEVATION (ft.): 304.1  
 15/NQ: 154.0'-159.0'; REC. 100%, RQD 100%  
 16/NQ: 159.0'-164.0'; REC. 100%, RQD 86%  
 17/NQ: 164.0'-169.0'; REC. 100%, RQD 64%

Project Mngr.: AJM	PN: N1105070	 611 LUNKEN PARK DRIVE CINCINNATI, OHIO 45226	<b>ROCK CORE PHOTOGRAPHS</b>	BORING
Drawn By: TCF	Scale: As Shown		BRENT SPENCE BRIDGE REPLACEMENT PARSONS BRINCKERHOFF CINCINNATI, OHIO	R-2
Chkd By: DWW	File No. Core C			
Approved By: AJM	Date: 9-8-10			



PROJECT: BRENT SPENCE BRIDGE		DRILLING FIRM / OPERATOR: HCN / HH		DRILL RIG: CME 550X ATV-7253		STATION / OFFSET: 17+10.4, 41.8 RT		EXPLORATION ID: R-2A											
TYPE: BRIDGE REPLACEMENT		SAMPLING FIRM / LOGGER: HCN / DWW		HAMMER: CME AUTOMATIC		ALIGNMENT: PROPOSED BSB													
PID: 75119 BR ID:		DRILLING METHOD: 3.25" HSA / HQ		CALIBRATION DATE: 2/4/10		ELEVATION: 457.6 (MSL) EOB: 190.5 ft.		PAGE 1 OF 4											
START: 8/27/10 END: 9/2/10		SAMPLING METHOD: SPT / HQ		ENERGY RATIO (%): 76.3		COORD: 39.091939445, -84.522976190													
MATERIAL DESCRIPTION AND NOTES		ELEV.	DEPTH	SPT/RQD	N <sub>60</sub>	REC (%)	SAMPLE ID	HP (tsf)	GRADATION (%)					ATTERBERG			WC	ODOT CLASS (GI)	HOLE SEALED
									GR	CS	FS	SI	CL	LL	PL	FI			
WATER (OHIO RIVER)		457.6	1																
			2																
			3																
			4																
			5																
			6																
			7																
			8																
			9																
			10																
			11																
			12																
			13																
			14																
			15																
			16																
			17																
			18																
			19																
			20																
			21																
			22																
			23																
			24																
			25																
			26																
			27																
			28																
		428.6	29	3															
MEDIUM DENSE TO DENSE, BROWN, GRAVEL AND STONE FRAGMENTS WITH SAND, LITTLE SILT, TRACE CLAY, WET			30	4 3	9	0	SS-1	-	-	-	-	-	-	-	-	-	-	21	A-1-b (V)
			31	4 5 9	18	33	SS-2	-	46	37	6	10	1	NP	NP	NP	18	A-1-b (0)	
			32	5															
			33	5 28 8	46	44	SS-3	-	-	-	-	-	-	-	-	-	-	-	A-1-b (V)
			34	8 6 7	17	0	SS-4	-	-	-	-	-	-	-	-	-	-	-	A-1-b (V)
			35	5															
			36	5 7 8	19	22	SS-5	-	-	-	-	-	-	-	-	-	-	16	A-1-b (V)
			37	12 6 4	13	33	SS-6	-	-	-	-	-	-	-	-	-	-	28	A-1-b (V)
			38	5															
			39	5 6 6	15	22	SS-7	-	-	-	-	-	-	-	-	-	-	27	A-1-b (V)
			40																
			41																
			42																
			43	13 10 7	22	22	SS-8	-	-	-	-	-	-	-	-	-	-	18	A-1-b (V)
			44																
			45	5															
			46	5 6 6	15	56	SS-9	-	32	36	27	3	2	NP	NP	NP	17	A-1-b (0)	
			47																
			48	15 6 9	19	0	SS-10	-	-	-	-	-	-	-	-	-	-	-	A-1-b (V)
			49																
			50	15 9 9	23	33	SS-11	-	-	-	-	-	-	-	-	-	-	29	A-1-b (V)
			51																
			52																
			53																
			54																
		402.6	55	4															
MEDIUM DENSE, BROWN, FINE SAND, TRACE GRAVEL, TRACE SILT, TRACE CLAY, WET			56	4 5 7	15	67	SS-12	-	3	30	62	3	2	NP	NP	NP	21	A-3 (0)	
			57																
			58																
			59																

MATERIAL DESCRIPTION AND NOTES	ELEV.	DEPTHS	SPT/RQD	N <sub>60</sub>	REC (%)	SAMPLE ID	HP (tsf)	GRADATION (%)					ATTERBERG			WC	ODOT CLASS (G)	HOLE SEALED	
								GR	CS	FS	SI	CL	LL	PL	PI				
MEDIUM DENSE, BROWN, FINE SAND, TRACE GRAVEL, TRACE SILT, TRACE CLAY, WET (continued)	397.6	61	3 6 7	17	100	SS-13	-	-	-	-	-	-	-	-	-	-	24	A-3 (V)	
DENSE, BROWN, GRAVEL AND STONE FRAGMENTS, SOME SAND, TRACE SILT, TRACE CLAY, WET	392.6	65	17 18 15	42	100	SS-14	-	60	15	17	6	2	NP	NP	NP	13	A-1-a (0)		
		70	14 15 13	36	67	SS-15	-	-	-	-	-	-	-	-	-	-	14	A-1-a (V)	
		75	12 18 15	42	33	SS-16	-	-	-	-	-	-	-	-	-	-	13	A-1-a (V)	
VERY DENSE, BROWN AND GRAY, GRAVEL AND STONE FRAGMENTS, SOME COBBLES, LITTLE SAND, WET	377.6	80	50/0"	-	-	SS-17	-	-	-	-	-	-	-	-	-	-	-	A-1-a (V)	
		85	50/0"	-	-	SS-18	-	-	-	-	-	-	-	-	-	-	-	A-1-a (V)	
INTERBEDDED LIMESTONE (50%) AND SHALE (50%); LIMESTONE, GRAY, UNWEATHERED TO SLIGHTLY WEATHERED, MODERATELY STRONG, THIN BEDDED, ARGILLACEOUS, FOSSILIFEROUS SEAMS; SHALE, GRAY, SLIGHTLY TO MODERATELY WEATHERED, VERY WEAK TO WEAK, LAMINATED TO THIN BEDDED, LOSS 2%, RQD 40%.	369.6	88																	TR
		92	40		100	HQ-1													CORE
		98	40		96	HQ-2													CORE
LIMESTONE, GRAY, UNWEATHERED, STRONG, THIN BEDDED, ARGILLACEOUS, SHALE PARTINGS, FOSSILIFEROUS SEAMS, LOSS 2%, RQD 75%	358.1	103	66		96	HQ-3													CORE
LS @99.5'-100.1' QU=14410 PSI		104																	
LS @ 105.1' POINT LOAD = 9027 PSI		105																	
LS @111.8'-112.2' QU=12314 PSI		106																	
LS @117.8'-118.2' QU=6058 PSI		107																	
LS/SH @120.5'-121' QU= 4222 PSI		108																	
LS @ 131.5' POINT LOAD = 8142 PSI		109																	
LS @134.4'-134.9' QU=7566 PSI		110																	
LS @140'-140.5' QU=7757 PSI		111																	
LS @ 141.2' POINT LOAD = 11014 PSI		112																	
LS @148'-148.5' QU=15226 PSI.		113	70		92	HQ-5													CORE
		118	80		100	HQ-6													CORE


STANDARD ODOT SOIL BORING LOG (11 X 17) - OH.DOT.GDT - 3/9/11 10:08 - N:\PROJECTS\2010\1105070\GINT\ODOT LOGS.GPJ

MATERIAL DESCRIPTION AND NOTES	ELEV.	DEPTH	SPT/RQD	N <sub>60</sub>	REC (%)	SAMPLE ID	HP (tsf)	GRADATION (%)					ATTERBERG				ODOT CLASS (G)	HOLE SEALED		
								GR	CS	FS	SI	CL	LL	PL	PI	WC				
<b>LIMESTONE</b> , GRAY, UNWEATHERED, STRONG, THIN BEDDED, ARGILLACEOUS, SHALE PARTINGS, FOSSILIFEROUS SEAMS, LOSS 2%, RQD 75%  LS @99.5'-100.1' QU=14410 PSI LS @ 105.1' POINT LOAD = 9027 PSI LS @111.8'-112.2' QU=12314 PSI LS @117.8'-118.2' QU=6058 PSI LS/SH @120.5'-121' QU= 4222 PSI LS @ 131.5' POINT LOAD = 8142 PSI LS @134.4'-134.9' QU=7566 PSI LS @140'-140.5' QU=7757 PSI LS @ 141.2' POINT LOAD = 11014 PSI LS @148'-148.5' QU=15226 PSI. <i>(continued)</i>	335.8	123	88		100	HQ-7											CORE			
	124																			
	125																			
	126																			
	127																			
	128			74		94	HQ-8												CORE	
	129																			
	130																			
	131																			
	132																			
	133																			
	134																			
	135																			
136			66		99	HQ-9													CORE	
137																				
138																				
139																				
140																				
141																				
142																				
143																				
144																				
145																				
146			89		100	HQ-10													CORE	
147																				
148																				
149																				
150																				
151	306.6																			
152																				
153																				
154																				
155																				
156																				
157																				
158																				
159																				
160																				
161																				
162																				
163																				
164																				
165																				
166																				
167																				
168																				
169																				
170																				
171																				
172																				
173																				
174																				
175																				
176																				
177																				
178																				
179																				
180																				
181																				
182																				
183																				


MATERIAL DESCRIPTION AND NOTES	ELEV. 273.9	DEPTHS	SPT/ RQD	N <sub>60</sub>	REC (%)	SAMPLE ID	HP (tsf)	GRADATION (%)					ATTERBERG				ODOT CLASS (G)	HOLE SEALED	
								GR	CS	FS	SI	CL	LL	PL	PI	WC			
<b>LIMESTONE</b> , GRAY, UNWEATHERED, STRONG, THIN TO MEDIUM BEDDED, CRYSTALLINE, LOSS 6%, RQD 80% LS @160'-160.5' QU=10770 PSI LS @ 166.9' POINT LOAD = 9985 PSI LS @175.9'-176.3' QU=10382 PSI LS @179.8'-180.3' QU=13212 PSI LS @183.5'-184' QU=9726 PSI. (continued)		184																	
		185	84		94	HQ-14													CORE
		186																	
		187																	
		188																	
		189																	
		190																	
	267.1	EOB																	

STANDARD ODOT SOIL BORING LOG (11 X 17) - OH DOT.GDT - 3/9/11 10:08 - N:\PROJECTS\2010\N1105070\GINT\ODOT LOGS.GPJ


NOTES: WATER USED BELOW 88 FT. FOR ROCK CORING PURPOSES. 3 INCH PVC CASING INSTALLED FROM SURFACE TO 139 FEET. UNABLE TO INSTALL CASING TO FULL DEPTH DUE TO OBSTRUCTION. ABANDONMENT METHODS, MATERIALS, QUANTITIES: BACKFILLED WITH BENTONITE GROUT (15 BAGS CEMENT/2.5 BAGS BENTONITE)




BORING NO.: R-2A  
 CORE BOX NO.: 1 OF 9  
 DEPTH (ft.): 88.0-100.1  
 ELEVATION (ft.): 369.64  
 1/NQ: 88.0'-95.5'; REC. 100%, RQD 40%  
 2/NQ: 95.5'-100.5'; REC. 96%, RQD 40%  
 3/NQ: 100.5'-105.5'; REC. 96%, RQD 66%




BORING NO.: R-2A  
 CORE BOX NO.: 2 OF 9  
 DEPTH (ft.): 100.1-112.2  
 ELEVATION (ft.): 357.54  
 4/NQ: 105.5'-110.5'; REC. 100%, RQD 64%  
 5/NQ: 110.5'-115.5'; REC. 92%, RQD 70%




BORING NO.: R-2A  
 CORE BOX NO.: 3 OF 9  
 DEPTH (ft.): 112.2-123.5  
 ELEVATION (ft.): 345.44  
 6/NQ: 115.5'-120.5'; REC. 100%, RQD 80%  
 7/NQ: 120.5'-125.5'; REC. 100%, RQD 88%

Project Mngr.: AJM	PN: N1105070	 611 LUNKEN PARK DRIVE CINCINNATI, OHIO 45226	<b>ROCK CORE PHOTOGRAPHS</b>	BORING  R-2A
Drawn By: TCF	Scale: As Shown		BRENT SPENCE BRIDGE REPLACEMENT PARSONS BRINCKERHOFF CINCINNATI, OHIO	
Chkd By: DWW	File No. Core C			
Approved By: AJM	Date: 9-8-10			




BORING NO.: R-2A  
 CORE BOX NO.: 4 OF 9  
 DEPTH (ft.): 123.5-135.4  
 ELEVATION (ft.): 334.14  
 8/NQ: 125.5'-130.5'; REC. 94%, RQD 74%  
 9/NQ: 130.5'-140.5'; REC. 99%, RQD 66%




BORING NO.: R-2A  
 CORE BOX NO.: 5 OF 9  
 DEPTH (ft.): 135.4-148.0  
 ELEVATION (ft.): 321.24  
 10/NQ: 140.5'-150.5'; REC. 100%, RQD 89%




BORING NO.: R-2A  
 CORE BOX NO.: 6 OF 9  
 DEPTH (ft.): 148.0-160.5  
 ELEVATION (ft.): 308.64  
 11/NQ: 10.5'-160.5'; REC. 95%, RQD 90%

Project Mngr.: AJM	PN: N1105070	 611 LUNKEN PARK DRIVE CINCINNATI, OHIO 45226	<b>ROCK CORE PHOTOGRAPHS</b>	BORING
Drawn By: TCF	Scale: As Shown		BRENT SPENCE BRIDGE REPLACEMENT PARSONS BRINCKERHOFF CINCINNATI, OHIO	R-2A
Chkd By: DWW	File No. Core C			
Approved By: AJM	Date: 9-8-10			




BORING NO.: R-2A  
 CORE BOX NO.: 7 OF 9  
 DEPTH (ft.): 160.5-176.3  
 ELEVATION (ft.): 296.14  
 12/NQ: 160.5'-170.5'; REC. 90%, RQD 67%



BORING NO.: R-2A  
 CORE BOX NO.: 8 OF 9  
 DEPTH (ft.): 176.3-180.5  
 ELEVATION (ft.): 280.34  
 13/NQ: 170.5'-180.5'; REC. 98%, RQD 80%



BORING NO.: R-2A  
 CORE BOX NO.: 9 OF 9  
 DEPTH (ft.): 180.5-190.5  
 ELEVATION (ft.): 276.14  
 14/NQ: 180.5'-190.5'; REC. 94%, RQD 84%

Project Mngr.: AJM	PN. N1105070	 611 LUNKEN PARK DRIVE CINCINNATI, OHIO 45226	<b>ROCK CORE PHOTOGRAPHS</b>	BORING
Drawn By: TCF	Scale: As Shown		BRENT SPENCE BRIDGE REPLACEMENT PARSONS BRINCKERHOFF CINCINNATI, OHIO	R-2A
Chkd By: DWW	File No. Core C			
Approved By: AJM	Date: 9-8-10			

PROJECT: BRENT SPENCE BRIDGE	DRILLING FIRM / OPERATOR: HCN / HH	DRILL RIG: CME 550X ATV-7253	STATION / OFFSET: 17+79.1, 35.6 LT	EXPLORATION ID: R-3
TYPE: BRIDGE REPLACEMENT	SAMPLING FIRM / LOGGER: HCN / DWW	HAMMER: CME AUTOMATIC	ALIGNMENT: PROPOSED BSB	
PID: 75119 BR ID:	DRILLING METHOD: 3.25" HSA / NQ	CALIBRATION DATE: 2/4/10	ELEVATION: 458.0 (MSL) EOB: 165.5 ft.	PAGE 1 OF 3
START: 7/12/10 END: 7/13/10	SAMPLING METHOD: SPT / NQ	ENERGY RATIO (%): 76.3	COORD: 39.092137310, -84.523169520	

MATERIAL DESCRIPTION AND NOTES	ELEV.	DEPTHS	SPT/RQD	N <sub>60</sub>	REC (%)	SAMPLE ID	HP (tsf)	GRADATION (%)					ATTERBERG				HOLE SEALED	
								GR	CS	FS	SI	CL	LL	PL	PI	WC		ODOT CLASS (GI)
WATER (OHIO RIVER)	458.0	1-27																
LOOSE TO MEDIUM DENSE, BROWN, GRAVEL AND STONE FRAGMENTS WITH SAND, TRACE SILT, TRACE CLAY, WET	430.0	28-31																
		31	1	2	5	0	SS-1	-	-	-	-	-	-	-	-	-	-	A-1-b (V)
		32	2	2														
		33	6	5	14	0	SS-2	-	-	-	-	-	-	-	-	-	-	A-1-b (V)
		34	3	6														
		35	6	9	19	67	SS-3	-	39	37	20	3	1	NP	NP	NP	15	A-1-b (0)
	422.5	36	5	3	6	22	SS-4	-	57	34	6	1	2	NP	NP	NP	17	A-1-a (0)
LOOSE, BROWN, GRAVEL AND STONE FRAGMENTS, TRACE SILT, TRACE CLAY, WET	421.0	37	2	2	5	67	SS-5	-	7	69	17	3	4	NP	NP	NP	18	A-1-b (0)
LOOSE, BROWN, GRAVEL AND STONE FRAGMENTS WITH SAND, TRACE SILT, TRACE CLAY, WET	418.0	38	2	2	5	67	SS-5	-	7	69	17	3	4	NP	NP	NP	18	A-1-b (0)
		39	7	4	10	0	SS-6	-	-	-	-	-	-	-	-	-	-	A-1-b (V)
		40	4	4														
MEDIUM DENSE, BROWN, FINE SAND, TRACE GRAVEL, TRACE SILT, TRACE CLAY, WET	413.0	41	3	5	13	33	SS-7	-	1	39	55	2	3	NP	NP	NP	19	A-3 (0)
		42																
		43	5	7	19	33	SS-8	-	-	-	-	-	-	-	-	-	25	A-3 (V)
		44	7	8														
		45	4	4	10	78	SS-9	-	9	48	39	2	2	NP	NP	NP	20	A-1-b (0)
LOOSE TO MEDIUM DENSE, BROWN, GRAVEL AND STONE FRAGMENTS WITH SAND, TRACE SILT, TRACE CLAY, WET	413.0	46	4	4	10	78	SS-9	-	9	48	39	2	2	NP	NP	NP	20	A-1-b (0)
		47																
		48	4	5	11	67	SS-10	-	25	36	34	2	3	NP	NP	NP	19	A-1-b (0)
		49	4	4														
		50	10	6	17	0	SS-11	-	-	-	-	-	-	-	-	-	-	A-1-b (V)
		51	6	7														
		52																
		53																
		54																
		55	6	7	19	67	SS-12	-	-	-	-	-	-	-	-	-	22	A-1-b (V)
		56	7	8														
		57																
		58																
		59																

STANDARD ODOT SOIL BORING LOG (11 X 17) - OH DOT.GDT - 3/9/11 10:08 - N:\PROJECTS\2010\1105070\GINT\ODOT LOGS.GPJ



MATERIAL DESCRIPTION AND NOTES	ELEV.	DEPTHS	SPT/RQD	N <sub>60</sub>	REC (%)	SAMPLE ID	HP (tsf)	GRADATION (%)					ATTERBERG			WC	ODOT CLASS (G)	HOLE SEALED
								GR	CS	FS	SI	CL	LL	PL	PI			
LOOSE TO MEDIUM DENSE, BROWN, <b>GRAVEL AND STONE FRAGMENTS WITH SAND</b> , TRACE SILT, TRACE CLAY, WET (continued)	398.0	61	8 9 10	24	89	SS-13	-	31	35	29	2	3	NP	NP	NP	19	A-1-b (0)	
		62																
		63																
		64																
		65																
MEDIUM DENSE TO DENSE, BROWN, <b>GRAVEL AND STONE FRAGMENTS</b> , SOME SAND, TRACE SILT, TRACE CLAY, WET	393.0	65	20 12 12	31	100	SS-14	-	70	13	13	3	1	NP	NP	NP	10	A-1-a (0)	
		66																
		67																
		68																
		69																
		70																
		71		15 9 6	19	67	SS-15	-	57	29	9	3	2	NP	NP	NP	16	A-1-a (0)
		72																
		73																
		74																
		75																
		76		22 14 12	33	56	SS-16	-	53	29	12	3	3	NP	NP	NP	13	A-1-a (0)
	77																	
	78																	
	79																	
	80		50/0"	-	-	SS-17	-	-	-	-	-	-	-	-	-	-	A-1-a (V)	
	81																	
	82																	
	83																	
	84																	
	85																	
	86																	
<b>LIMESTONE</b> , GRAY, UNWEATHERED TO SLIGHTLY WEATHERED, STRONG, THIN BEDDED, ARGILLACEOUS, MODERATELY FRACTURED, THIN SHALE SEAMS, LOSS 4%, RQD 75%  LS @92.3'-92.7' QU=9244 PSI LS @93.8'-94.5' QU=10241 PSI LS @ 98' POINT LOAD = 13271 PSI SH @102.7'-103.1' QU=7236 PSI LS @106.5'-107.1' QU=9187 PSI LS @ 113.3' POINT LOAD = 13042 PSI LS @ 117.2' POINT LOAD = 10568 PSI LS @123.8'-124.7' QU=6833 PSI.	371.5	87																
		88	50		80	NQ-1												CORE
		89																
		90																
		91																
		92																
		93	42		92	NQ-2												CORE
		94																
		95																
		96																
		97																
		98	62		100	NQ-3												CORE
		99																
		100																
		101																
		102																
	103	80		100	NQ-4												CORE	
	104																	
	105																	
	106																	
	107																	
	108	90		96	NQ-5												CORE	
	109																	
	110																	
	111																	
	112																	
	113	78		100	NQ-6												CORE	
	114																	
	115																	
	116																	
	117																	
	118	96		100	NQ-7												CORE	
	119																	
	120																	
	121																	


MATERIAL DESCRIPTION AND NOTES	ELEV. 336.1	DEPTHS	SPT/ RQD	N <sub>60</sub>	REC (%)	SAMPLE ID	HP (tsf)	GRADATION (%)					ATTERBERG				ODOT CLASS (G)	HOLE SEALED		
								GR	CS	FS	SI	CL	LL	PL	PI	WC				
<p><b>LIMESTONE</b>, GRAY, UNWEATHERED, STRONG, THIN BEDDED, ARGILLACEOUS, FOSSILIFEROUS SEAMS, VERY THIN SHALE PARTINGS, LOSS 2%, RQD 83%</p> <p>LS @106'-106.5' QU=14729 PSI                      LS @136.5'-137' QU=24544 PSI                      LS @140'-140.5' QU=9100 PSI                      LS @145.5'-146' QU=11767 PSI                      LS @157.3'-158' QU=14226 PSI.</p>	332.5	123	100		100	NQ-8											CORE			
		124																		
		125																		
		126																		
		127																		
		128			92		100	NQ-9												CORE
		129																		
		130																		
		131																		
		132																		
		133			84		80	NQ-10												CORE
		134																		
		135																		
		136																		
		137																		
		138			90		90	NQ-11												CORE
139																				
140																				
141																				
142																				
143			86		90	NQ-12												CORE		
144																				
145																				
146																				
147																				
148			80		100	NQ-13												CORE		
149																				
150																				
151																				
152																				
153			68		100	NQ-14												CORE		
154																				
155																				
156																				
157																				
158			84		100	NQ-15												CORE		
159																				
160																				
161																				
162																				
163			92		100	NQ-16												CORE		
164																				
165																				
	292.5	EOB																		

STANDARD ODOT SOIL BORING LOG (11 X 17) - OH.DOT.GDT - 3/9/11 10:08 - N:\PROJECTS\2010\1105070\GINT\ODOT LOGS.GPJ

NOTES: WATER USED BELOW 86.5 FT. FOR ROCK CORING PURPOSES.  
 ABANDONMENT METHODS, MATERIALS, QUANTITIES: BACKFILLED WITH BENTONITE GROUT (10 BAGS CEMENT/1 BAG BENTONITE)




BORING NO.: R-3  
 CORE BOX NO.: 1 OF 6  
 DEPTH (ft.): 86.5-100.5  
 ELEVATION (ft.): 371.51  
 1/NQ: 86.5'-90.5'; REC. 80%, RQD 50%  
 2/NQ: 90.5'-95.5'; REC. 92%, RQD 42%  
 3/NQ: 95.5'-100.5'; REC. 100%, RQD 62%



BORING NO.: R-3  
 CORE BOX NO.: 2 OF 6  
 DEPTH (ft.): 100.5-115.5  
 ELEVATION (ft.): 357.51  
 4/NQ: 100.5'-105.5'; REC. 100%, RQD 80%  
 5/NQ: 105.5'-110.5'; REC. 96%, RQD 90%  
 6/NQ: 110.5'-115.5'; REC. 100%, RQD 78%




BORING NO.: R-3  
 CORE BOX NO.: 3 OF 6  
 DEPTH (ft.): 115.5-130.5  
 ELEVATION (ft.): 342.51  
 7/NQ: 115.5'-120.5'; REC. 100%, RQD 96%  
 8/NQ: 120.5'-125.5'; REC. 100%, RQD 100%  
 9/NQ: 125.5'-130.5'; REC. 100%, RQD 92%


Project Mngr.: AJM	PN: N1105070	 611 LUNKEN PARK DRIVE CINCINNATI, OHIO 45226	<b>ROCK CORE PHOTOGRAPHS</b>	BORING
Drawn By: TCF	Scale: As Shown		BRENT SPENCE BRIDGE REPLACEMENT PARSONS BRINCKERHOFF CINCINNATI, OHIO	R-3
Chkd By: DWW	File No. Core D			
Approved By: AJM	Date: 9-23-10			




BORING NO.: R-3  
 CORE BOX NO.: 4 OF 6  
 DEPTH (ft.): 130.5-140.5  
 ELEVATION (ft.): 327.51  
 10/NQ: 130.5'-135.5'; REC. 80%, RQD 84%  
 11/NQ: 135.5'-140.5'; REC. 90%, RQD 90%



BORING NO.: R-3  
 CORE BOX NO.: 5 OF 6  
 DEPTH (ft.): 140.5-154.8  
 ELEVATION (ft.): 317.51  
 12/NQ: 140.5'-145.5'; REC. 90%, RQD 86%  
 13/NQ: 145.5'-150.5'; REC. 100%, RQD 80%  
 14/NQ: 150.5'-155.5'; REC. 100%, RQD 68%




BORING NO.: R-3  
 CORE BOX NO.: 6 OF 6  
 DEPTH (ft.): 154.8-166.5  
 ELEVATION (ft.): 302.51  
 15/NQ: 155.5'-160.5'; REC. 100%, RQD 84%  
 16/NQ: 160.5'-165.5'; REC. 100%, RQD 92%  
 17/NQ: 165.5'-166.5'; REC. 90%, RQD 90%

Project Mngr.: AJM	PN: N1105070	 611 LUNKEN PARK DRIVE CINCINNATI, OHIO 45226	<b>ROCK CORE PHOTOGRAPHS</b>	BORING
Drawn By: TCF	Scale: As Shown		BRENT SPENCE BRIDGE REPLACEMENT PARSONS BRINCKERHOFF CINCINNATI, OHIO	
Chkd By: DWW	File No. Core D			R-3
Approved By: AJM	Date: 9-23-10			




BORING NO.: R-3  
 CORE BOX NO.: 1 OF 6  
 DEPTH (ft.): 86.5-100.5  
 ELEVATION (ft.): 371.51  
 1/NQ: 86.5'-90.5'; REC. 80%, RQD 50%  
 2/NQ: 90.5-95.5'; REC. 92%, RQD 42%  
 3/NQ: 95.5-100.5'; REC. 100%, RQD 62%



BORING NO.: R-3  
 CORE BOX NO.: 2 OF 6  
 DEPTH (ft.): 100.5-115.5  
 ELEVATION (ft.): 357.51  
 4/NQ: 100.5'-105.5'; REC. 100%, RQD 80%  
 5/NQ: 105.5'-110.5'; REC. 96%, RQD 90%  
 6/NQ: 110.5'-115.5'; REC. 100%, RQD 78%




BORING NO.: R-3  
 CORE BOX NO.: 3 OF 6  
 DEPTH (ft.): 115.5-130.5  
 ELEVATION (ft.): 342.51  
 7/NQ: 115.5'-120.5'; REC. 100%, RQD 96%  
 8/NQ: 120.5'-125.5'; REC. 100%, RQD 100%  
 9/NQ: 125.5'-130.5'; REC. 100%, RQD 92%


Project Mngr.: AJM	PN: N1105070	 611 LUNKEN PARK DRIVE CINCINNATI, OHIO 45226	<b>ROCK CORE PHOTOGRAPHS</b>	BORING
Drawn By: TCF	Scale: As Shown		BRENT SPENCE BRIDGE REPLACEMENT PARSONS BRINCKERHOFF CINCINNATI, OHIO	R-3
Chkd By: DWW	File No. Core D			
Approved By: AJM	Date: 9-23-10			




BORING NO.: R-3  
 CORE BOX NO.: 4 OF 6  
 DEPTH (ft.): 130.5-140.5  
 ELEVATION (ft.): 327.51  
 10/NQ: 130.5'-135.5'; REC. 80%, RQD 84%  
 11/NQ: 135.5'-140.5'; REC. 90%, RQD 90%



BORING NO.: R-3  
 CORE BOX NO.: 5 OF 6  
 DEPTH (ft.): 140.5-154.8  
 ELEVATION (ft.): 317.51  
 12/NQ: 140.5'-145.5'; REC. 90%, RQD 86%  
 13/NQ: 145.5'-150.5'; REC. 100%, RQD 80%  
 14/NQ: 150.5'-155.5'; REC. 100%, RQD 68%



BORING NO.: R-3  
 CORE BOX NO.: 6 OF 6  
 DEPTH (ft.): 154.8-166.5  
 ELEVATION (ft.): 302.51  
 15/NQ: 155.5'-160.5'; REC. 100%, RQD 84%  
 16/NQ: 160.5'-165.5'; REC. 100%, RQD 92%  
 17/NQ: 165.5'-166.5'; REC. 90%, RQD 90%

Project Mngr.: AJM	PN: N1105070	 611 LUNKEN PARK DRIVE CINCINNATI, OHIO 45226	<b>ROCK CORE PHOTOGRAPHS</b>	BORING
Drawn By: TCF	Scale: As Shown		BRENT SPENCE BRIDGE REPLACEMENT PARSONS BRINCKERHOFF CINCINNATI, OHIO	
Chkd By: DWW	File No. Core D			R-3
Approved By: AJM	Date: 9-23-10			

MATERIAL DESCRIPTION AND NOTES	ELEV.	DEPTH	SPT/RQD	N <sub>60</sub>	REC (%)	SAMPLE ID	HP (tsf)	GRADATION (%)					ATTERBERG				WC	DOT CLASS (G)	HOLE SEALED
								GR	CS	FS	SI	CL	LL	FL	PI				
WATER (OHIO RIVER)	458.0	1-30																	
	427.5	31																	
LOOSE TO MEDIUM DENSE, BROWN, <b>GRAVEL AND STONE FRAGMENTS WITH SAND</b> , TRACE SILT, TRACE CLAY, WET		34	1	5	44	SS-1	-	17	68	10	3	2	NP	NP	NP	17	A-1-b (0)		
		35	1	9	56	SS-2	-	37	52	10	0	1	NP	NP	NP	19	A-1-b (0)		
		36	2	5															
		37	7	8	19	100	SS-3	-	28	60	9	2	1	NP	NP	NP	14	A-1-b (0)	
		38	4	5	13	33	SS-4	-	2	85	11	0	2	NP	NP	NP	21	A-1-b (0)	
		39	5	5															
		40	6	3	6	67	SS-5	-	39	42	14	3	2	NP	NP	NP	17	A-1-b (0)	
		41	2	3															
		42	3	5	10	33	SS-6	-	10	55	28	4	3	NP	NP	NP	25	A-1-b (0)	
		43	3	3	6	100	SS-7	-	-	-	-	-	-	-	-	-	25	A-1-b (V)	
		44																	
LOOSE TO MEDIUM DENSE, BROWN, <b>FINE SAND</b> , TRACE GRAVEL, TRACE SILT, TRACE CLAY, WET	413.0	45	1	6	33	SS-8	-	5	18	74	1	2	NP	NP	NP	22	A-3 (0)		
		46	2	3															
		47																	
		48	2	3	6	0	SS-9	-	-	-	-	-	-	-	-	-	-	A-3 (V)	
		49																	
		50	4	4	13	67	SS-10	-	2	22	72	1	3	NP	NP	NP	26	A-3 (0)	
		51	6																
		52																	
		53																	
		54																	
	55	8	9	24	67	SS-11	-	3	7	82	4	4	NP	NP	NP	22	A-3 (0)		
	56	10																	
	57																		
	58																		
	59																		

STANDARD ODOT SOIL BORING LOG (11 X 17) - OH DOT.GDT - 3/9/11 10:08 - N:\PROJECTS\2010\1105070\GINT\ODOT LOGS.GPJ

MATERIAL DESCRIPTION AND NOTES	ELEV.	DEPTH	SPT/RQD	N <sub>60</sub>	REC (%)	SAMPLE ID	HP (tsf)	GRADATION (%)					ATTERBERG			WC	ODOT CLASS (G)	HOLE SEALED		
								GR	CS	FS	SI	CL	LL	PL	PI					
LOOSE TO MEDIUM DENSE, BROWN, FINE SAND, TRACE GRAVEL, TRACE SILT, TRACE CLAY, WET (continued)	398.0	61	5 7 8	19	67	SS-12	-	-	-	-	-	-	-	-	-	24	A-3 (V)			
		62																		
		63																		
		64																		
		65																		
MEDIUM DENSE TO DENSE, BROWN, GRAVEL AND STONE FRAGMENTS, SOME SAND, TRACE SILT, TRACE CLAY, WET	393.0	66	8 12 12	31	56	SS-13	-	-	-	-	-	-	-	-	-	13	A-1-a (V)			
		67																		
		68																		
		69																		
		70																		
		71	14 21 13	43	22	SS-14	-	78	13	6	1	2	NP	NP	NP	16	A-1-a (0)			
		72																		
		73																		
		74																		
		75	14 6 6	15	33	SS-15	-	52	36	7	3	2	NP	NP	NP	16	A-1-a (0)			
		76																		
77																				
78																				
79																				
80		50/3"	-	0	SS-16	-	-	-	-	-	-	-	-	-	-	A-1-a (V)				
LIMESTONE, GRAY, UNWEATHERED TO SLIGHTLY WEATHERED, MODERATELY STRONG TO STRONG, THIN BEDDED, ARGILLACEOUS, SHALE SEAMS AND PARTINGS, CRYSTALLINE, FRACTURED, LOSS 8%, RQD 40%  LS @ 90.5'-91' QU=8320 PSI LS @ 95' POINT LOAD = 11920 PSI LS @ 95.5'-96' QU=5778 PSI.	371.5	81																		
		82																		
		83																		
		84																		
		85																		
		86																		
		87																		
		88																		
		89																		
		90																		
		91																		
		92																		
		93		56		100	NQ-2													
		94																		
		95																		
96																				
97																				
98		54		100	NQ-3															
99																				
100																				
LIMESTONE, GRAY, UNWEATHERED, STRONG, THIN BEDDED, ARGILLACEOUS, FOSSILIFEROUS SEAMS, MODERATELY FRACTURED, LOSS 0%, RQD 88%  LS @ 101' POINT LOAD = 13271 PSI LS @ 102.8'-103.3' QU=2644 PSI LS @ 111.3'-111.9' QU=5958 PSI LS @ 120.6'-121.3' QU=19133 PSI LS @ 121.9'-122.3' QU=15389 PSI LS @ 129.6'-130' QU=5754 PSI LS @ 139.6'-140.5' QU=16884 PSI LS @ 140.6'-141.1' QU=13586 PSI LS @ 147' POINT LOAD = 12473 PSI LS @ 152.8'-153.6' QU=10653 PSI LS @ 155.5' POINT LOAD = 13035 PSI LS @ 159.6'-160.5' QU=15762 PSI.	357.5	101																		
		102																		
		103																		
		104																		
		105																		
		106																		
		107																		
		108																		
		109																		
		110																		
		111																		
		112																		
		113																		
		114		82		100	NQ-6													
		115																		
116																				
117																				
118																				
119																				
120																				
121																				



MATERIAL DESCRIPTION AND NOTES	ELEV. 336.1	DEPTHS	SPT/ RQD	N <sub>60</sub>	REC (%)	SAMPLE ID	HP (tsf)	GRADATION (%)					ATTERBERG				ODOT CLASS (G)	HOLE SEALED	
								GR	CS	FS	SI	CL	LL	PL	PI	WC			
<b>LIMESTONE</b> , GRAY, UNWEATHERED, STRONG, THIN BEDDED, ARGILLACEOUS, FOSSILIFEROUS SEAMS, MODERATELY FRACTURED, LOSS 0%, RQD 88%  LS @ 101' POINT LOAD = 13271 PSI LS @ 102.8'-103.3' QU=2644 PSI LS @ 111.3'-111.9' QU=5958 PSI LS @ 120.6'-121.3' QU=19133 PSI LS @ 121.9'-122.3' QU=15389 PSI LS @ 129.6'-130' QU=5754 PSI LS @ 139.6'-140.5' QU=16884 PSI LS @ 140.6'-141.1' QU=13586 PSI LS @ 147' POINT LOAD = 12473 PSI LS @ 152.8'-153.6' QU=10653 PSI LS @ 155.5' POINT LOAD = 13035 PSI LS @ 159.6'-160.5' QU=15762 PSI. <i>(continued)</i>		123	96		100	NQ-8											CORE		
		124																	
		125																	
		126																	
		127																	
		128		82		100	NQ-9												CORE
		129																	
		130																	
		131																	
		132																	
		133		72		100	NQ-10												CORE
		134																	
		135																	
		136																	
		137																	
		138		94		100	NQ-11												CORE
	139																		
	140																		
	141																		
	142																		
	143		90		100	NQ-12												CORE	
	144																		
	145																		
	146																		
	147																		
	148		86		100	NQ-13												CORE	
	149																		
	150																		
	151																		
	152																		
	153		84		100	NQ-14												CORE	
	154																		
	155																		
	156																		
	157																		
	158		96		100	NQ-15												CORE	
	159																		
	160																		
	161																		
	162																		
	163		94		98	NQ-16												CORE	
	164																		
	165																		


292.5 EOB

STANDARD ODOT SOIL BORING LOG (11 X 17) - OH DOT.GDT - 3/9/11 10:08 - N:\PROJECTS\2010\1105070\GINT\ODOT LOGS.GPJ


NOTES: WATER USED BELOW 86.5 FT. FOR ROCK CORING PURPOSES. GAS POCKET AT 147.0'  
 ABANDONMENT METHODS, MATERIALS, QUANTITIES: BACKFILLED WITH BENTONITE GROUT (9 BAGS CEMENT/1 BAG BENTONITE)




BORING NO.: R-4  
 CORE BOX NO.: 1 OF 6  
 DEPTH (ft.): 86.5-100.5  
 ELEVATION (ft.): 371.48  
 1/NQ: 86.5'-90.5'; REC. 73%, RQD 0%  
 2/NQ: 90.5'-95.5'; REC. 100%, RQD 56%  
 3/NQ: 95.5'-100.5'; REC. 100%, RQD 54%



BORING NO.: R-4  
 CORE BOX NO.: 2 OF 6  
 DEPTH (ft.): 100.5-115.5  
 ELEVATION (ft.): 357.48  
 4/NQ: 100.5'-105.5'; REC. 100%, RQD 84%  
 5/NQ: 105.5'-110.5'; REC. 100%, RQD 92%  
 6/NQ: 110.5'-115.5'; REC. 100%, RQD 82%




BORING NO.: R-4  
 CORE BOX NO.: 3 OF 6  
 DEPTH (ft.): 115.5-130.5  
 ELEVATION (ft.): 342.48  
 7/NQ: 115.5'-120.5'; REC. 100%, RQD 94%  
 8/NQ: 120.5'-125.5'; REC. 100%, RQD 96%  
 9/NQ: 125.5'-130.5'; REC. 100%, RQD 82%


Project Mngr.: AJM	PN: N1105070	 611 LUNKEN PARK DRIVE CINCINNATI, OHIO 45226	<b>ROCK CORE PHOTOGRAPHS</b>	BORING
Drawn By: TCF	Scale: As Shown		BRENT SPENCE BRIDGE REPLACEMENT PARSONS BRINCKERHOFF CINCINNATI, OHIO	
Chkd By: DWW	File No. Core D			
Approved By: AJM	Date: 9-23-10			R-4




BORING NO.: R-4  
 CORE BOX NO.: 4 OF 6  
 DEPTH (ft.): 130.5-140.5  
 ELEVATION (ft.): 327.48  
 10/NQ: 130.5'-135.5'; REC. 100%, RQD 72%  
 11/NQ: 135.5'-140.5'; REC. 100%, RQD 94%



BORING NO.: R-4  
 CORE BOX NO.: 5 OF 6  
 DEPTH (ft.): 140.5-155.5  
 ELEVATION (ft.): 317.48  
 12/NQ: 140.5'-145.5'; REC. 100%, RQD 90%  
 13/NQ: 145.5'-150.5'; REC. 100%, RQD 86%  
 14/NQ: 150.5'-155.5'; REC. 100%, RQD 84%



BORING NO.: R-4  
 CORE BOX NO.: 6 OF 6  
 DEPTH (ft.): 155.5-165.5  
 ELEVATION (ft.): 302.48  
 15/NQ: 155.5'-160.5'; REC. 100%, RQD 96%  
 16/NQ: 160.5'-165.5'; REC. 98%, RQD 94%

Project Mngr.: AJM	PN. N1105070	 611 LUNKEN PARK DRIVE CINCINNATI, OHIO 45226	<b>ROCK CORE PHOTOGRAPHS</b>	BORING
Drawn By: TCF	Scale: As Shown		BRENT SPENCE BRIDGE REPLACEMENT PARSONS BRINCKERHOFF CINCINNATI, OHIO	R-4
Chkd By: DWW	File No. Core D			
Approved By: AJM	Date: 9-23-10			

PROJECT: BRENT SPENCE BRIDGE	DRILLING FIRM / OPERATOR: HCN / HH	DRILL RIG: CME 550X ATV-7253	STATION / OFFSET: 7+85.4, 58.4 RT
TYPE: BRIDGE REPLACEMENT	SAMPLING FIRM / LOGGER: HCN / DRK/DWW	HAMMER: CME AUTOMATIC	ALIGNMENT: PROPOSED BSB
PID: 75119 BR ID:	DRILLING METHOD: 3.25" HSA / NQ	CALIBRATION DATE: 2/4/10	ELEVATION: 458.6 (MSL) EOB: 165.4 ft.
START: 6/29/10 END: 7/1/10	SAMPLING METHOD: SPT / NQ	ENERGY RATIO (%): 76.3	COORD: 39.089400310, -84.522990520

EXPLORATION ID R-5  
PAGE 1 OF 3

MATERIAL DESCRIPTION AND NOTES	ELEV.	DEPTH	SPT/RQD	N <sub>60</sub>	REC (%)	SAMPLE ID	HP (tsf)	GRADATION (%)					ATTERBERG				WC	DOT CLASS (GI)	HOLE SEALED
								GR	CS	FS	SI	CL	LL	PL	FI	WC			
WATER (OHIO RIVER)	458.6	1-15																	
LOOSE TO MEDIUM DENSE, DARK GRAY, <b>COARSE AND FINE SAND</b> , LITTLE TO SOME GRAVEL, TRACE SILT, TRACE CLAY, WET	442.6	16	1	3	6	22	SS-1	-	19	16	49	10	6	NP	NP	NP	28	A-3a (0)	
	439.6	17	2	4	8	15	SS-2	-	30	18	41	7	4	NP	NP	NP	39	A-3a (0)	
MEDIUM DENSE, GRAY, <b>GRAVEL AND STONE FRAGMENTS WITH SAND</b> , TRACE SILT, TRACE CLAY, WET	438.1	18	3	4	5	11	SS-3	-	35	19	36	6	4	NP	NP	NP	40	A-1-b (0)	
SOFT TO MEDIUM STIFF, GRAY, <b>SILT AND CLAY</b> , TRACE TO SOME SAND, MOIST	431.1	19	2	2	2	5	SS-4	1.00	0	1	24	52	23	31	20	11	30	A-6a (8)	
		20	4	1	1	3	SS-5	0.75	-	-	-	-	-	-	-	-	-	A-6a (V)	
		21	3	2	2	5	SS-6	1.00	0	0	9	54	37	36	21	15	44	A-6a (10)	
		22	2	4	3	9	SS-7	1.00	-	-	-	-	-	-	-	-	49	A-6a (V)	
		23	12	13	15	36	SS-8	-	-	-	-	-	-	-	-	-	10	A-1-b (V)	
		24	6	11	11	28	SS-9	-	45	38	10	4	3	NP	NP	NP	10	A-1-b (0)	
		25	10	14	14	36	SS-10	-	-	-	-	-	-	-	-	-	7	A-1-b (V)	
		26	5	9	9	23	SS-11	-	-	-	-	-	-	-	-	-	21	A-1-b (V)	
		27	21	14	7	27	SS-12	-	47	30	13	7	3	NP	NP	NP	14	A-1-b (0)	
		28	13	14	14	36	SS-13	-	-	-	-	-	-	-	-	-	23	A-1-b (V)	
		29	13	8	8	20	SS-14	-	44	39	10	5	2	NP	NP	NP	16	A-1-b (0)	
		30	20	16	12	36	SS-15	-	-	-	-	-	-	NP	NP	NP	18	A-1-b (V)	

STANDARD ODOT SOIL BORING LOG (11 X 17) - OH DOT.GDT - 3/9/11 10:08 - N:\PROJECTS\2010\1105070\GINT\ODOT LOGS.GPJ

MATERIAL DESCRIPTION AND NOTES	ELEV.	DEPTHS	SPT/RQD	N <sub>60</sub>	REC (%)	SAMPLE ID	HP (tsf)	GRADATION (%)					ATTERBERG			WC	ODOT CLASS (G)	HOLE SEALED		
								GR	CS	FS	SI	CL	LL	PL	PI					
MEDIUM DENSE TO DENSE, GRAY, GRAVEL AND STONE FRAGMENTS WITH SAND, TRACE SILT, TRACE CLAY, WET (continued)	398.6	61-64	11 6	15	67	SS-16	-	-	-	-	-	-	-	-	-	-	13	A-1-b (V)		
VERY DENSE, GRAY, FINE SAND, LITTLE GRAVEL, TRACE SILT, TRACE CLAY, MEDIUM DENSE AT 65', WET	393.6	65-70	10 11 11	28	56	SS-17	-	12	21	59	3	5	NP	NP	NP		19	A-3 (0)		
VERY DENSE, GRAY, STONE FRAGMENTS WITH SAND, LITTLE SILT, TRACE CLAY, LIMESTONE FLOATERS, WET	383.6	71-74	20 40 51	116	67	SS-18	-	-	-	-	-	-	-	-	-	-	7	A-3 (V)		
VERY DENSE, GRAY, STONE FRAGMENTS WITH SAND, LITTLE SILT, TRACE CLAY, LIMESTONE FLOATERS, WET	373.6	75-84	65	-	100	SS-19	-	49	20	11	13	7	NP	NP	NP		16	A-1-b (0)		
<b>INTERBEDDED LIMESTONE (70%) AND SHALE (30%);</b> <b>LIMESTONE.</b> LIGHT GRAY, UNWEATHERED TO SLIGHTLY WEATHERED, STRONG, THIN BEDDED, FOSSILIFEROUS; <b>SHALE.</b> GRAY, SLIGHTLY TO MODERATELY WEATHERED, MODERATELY STRONG, VERY THIN TO THIN BEDDED, LOSS 3%, RQD 67%  LS @85.2'-85.7' QU=7099 PSI LS @86.4'-86.8' QU=10809 PSI LS @90.1'-90.8' QU=7024 PSI LS @92.2'-92.8' QU=118 PSI SH @ 92.2' SDI = 57.9 LS @93'-93.8' QU=14324 PSI LS @95'-95.3' QU=8193 PSI SH @ 95.7' SDI = 52.5 LS @ 100.8' POINT LOAD = 11011 PSI LS @103'-103.5' QU=4812 PSI LS @103.5'-104' QU=14991 PSI LS @ 108' POINT LOAD = 16192 PSI LS @ 118.2' POINT LOAD = 11057 PSI LS @128.1'-128.8' QU=19640 PSI.	373.6	85-121																		
		TR																		
			25		88	NQ-1														CORE
			66		100	NQ-2														CORE
			20		100	NQ-3														CORE
			58		100	NQ-4														CORE
			84		96	NQ-5														CORE
			98		100	NQ-6														CORE
			76		94	NQ-7														CORE

MATERIAL DESCRIPTION AND NOTES	ELEV. 336.7	DEPTHS	SPT/ RQD	N <sub>60</sub>	REC (%)	SAMPLE ID	HP (tsf)	GRADATION (%)					ATTERBERG				CORE CLASS (G)	HOLE SEALED	
								GR	CS	FS	SI	CL	LL	PL	PI	WC			
<b>INTERBEDDED LIMESTONE (70%) AND SHALE (30%);</b> <b>LIMESTONE</b> , LIGHT GRAY, UNWEATHERED TO SLIGHTLY WEATHERED, STRONG, THIN BEDDED, FOSSILIFEROUS; <b>SHALE</b> , GRAY, SLIGHTLY TO MODERATELY WEATHERED, MODERATELY STRONG, VERY THIN TO THIN BEDDED, LOSS 3%, RQD 67%  LS @85.2'-85.7' QU=7099 PSI LS @86.4'-86.8' QU=10809 PSI LS @90.1'-90.8' QU=7024 PSI LS @92.2'-92.8' QU=118 PSI SH @ 92.2' SDI = 57.9 LS @93'-93.8' QU=14324 PSI LS @95'-95.3' QU=8193 PSI SH @ 95.7' SDI = 52.5 LS @ 100.8' POINT LOAD = 11011 PSI LS @103'-103.5' QU=4812 PSI LS @103.5'-104' QU=14991 PSI LS @ 108' POINT LOAD = 16192 PSI LS @ 118.2' POINT LOAD = 11057 PSI LS @128.1'-128.8' QU=19640 PSI. (continued)	336.7	123	80	100	NQ-8											CORE			
		124																	
		125																	
		126																	
		127	94	100	NQ-9													CORE	
		128																	
		129																	
		130																	
		131																	
		132	36	88	NQ-10													CORE	
		133																	
		134																	
		135																	
		136																	
137	96	100	NQ-11													CORE			
138																			
139																			
140	318.6																		
<b>LIMESTONE</b> , GRAY, UNWEATHERED, STRONG, THIN BEDDED, LOSS 1%, RQD 99%  LS @146.2'-147' QU=12179 PSI SH @ 153' SDI = 98.8 LS @ 156.4' POINT LOAD = 14406 PSI.	318.6	141																	
		142	98	100	NQ-12												CORE		
		143																	
		144																	
		145																	
		146																	
		147	100	100	NQ-13												CORE		
		148																	
		149																	
		150																	
		151																	
		152	92	92	NQ-14												CORE		
		153																	
		154																	
		155																	
		156																	
157	96	96	NQ-15												CORE				
158																			
159																			
160																			
161																			
162																			
163	100	100	NQ-16												CORE				
164																			
165	293.2																		

EOB

STANDARD ODOT SOIL BORING LOG (11 X 17) - OH.DOT.GDT - 3/9/11 10:08 - N:\PROJECTS\2010\1105070\GINT\ODOT LOGS.GPJ

NOTES: WATER USED BELOW 85 FT. FOR ROCK CORING PURPOSES.

ABANDONMENT METHODS, MATERIALS, QUANTITIES: BACKFILLED WITH BENTONITE GROUT (11 BAGS CEMENT/1.5 BAGS BENTONITE)




BORING NO.: R-5  
 CORE BOX NO.: 1 OF 6  
 DEPTH (ft.): 75.5-95.0  
 ELEVATION (ft.): 373.59  
 1/NQ: 85.0'-90.0'; REC. 88%, RQD 25%  
 2/NQ: 90.0'-95.0'; REC. 100%, RQD 66%  
 3/NQ: 95.0'-100.0'; REC. 100%, RQD 20%



BORING NO.: R-5  
 CORE BOX NO.: 2 OF 6  
 DEPTH (ft.): 95.0-110.0  
 ELEVATION (ft.): 363.59  
 4/NQ: 100.0'-105.0'; REC. 100%, RQD 58%  
 5/NQ: 105.0'-110.0'; REC. 96%, RQD 84%



BORING NO.: R-5  
 CORE BOX NO.: 3 OF 6  
 DEPTH (ft.): 110.0-125.0  
 ELEVATION (ft.): 348.59  
 6/NQ: 110.0'-115.0'; REC. 100%, RQD 98%  
 7/NQ: 115.0'-120.0'; REC. 94%, RQD 76%  
 8/NQ: 120.0'-125.0'; REC. 100%, RQD 80%

Project Mngr.: AJM	PN: N1105070	 611 LUNKEN PARK DRIVE CINCINNATI, OHIO 45226	<b>ROCK CORE PHOTOGRAPHS</b>	BORING
Drawn By: TCF	Scale: As Shown		BRENT SPENCE BRIDGE REPLACEMENT PARSONS BRINCKERHOFF CINCINNATI, OHIO	R-5
Chkd By: DWW	File No. Core D			
Approved By: AJM	Date: 9-23-10			




BORING NO.: R-5  
 CORE BOX NO.: 4 OF 6  
 DEPTH (ft.): 125.0-140.0  
 ELEVATION (ft.): 333.59  
 9/NQ: 125.0'-130.0'; REC. 100%, RQD 94%  
 10/NQ: 130.0'-135.0'; REC. 88%, RQD 36%  
 11/NQ: 135.0'-140.0'; REC. 100%, RQD 96%



BORING NO.: R-5  
 CORE BOX NO.: 5 OF 6  
 DEPTH (ft.): 140.0-150.0  
 ELEVATION (ft.): 318.59  
 12/NQ: 140.0'-145.0'; REC. 100%, RQD 98%  
 13/NQ: 145.0'-150.0'; REC. 100%, RQD 100%



BORING NO.: R-5  
 CORE BOX NO.: 6 OF 6  
 DEPTH (ft.): 150.0-165.0  
 ELEVATION (ft.): 308.59  
 14/NQ: 150.0'-155.0'; REC. 92%, RQD 92%  
 15/NQ: 155.0'-160.0'; REC. 96%, RQD 96%  
 16/NQ: 160.0'-165.0'; REC. 100%, RQD 100%

Project Mngr.: AJM	PN: N1105070	 611 LUNKEN PARK DRIVE CINCINNATI, OHIO 45226	<b>ROCK CORE PHOTOGRAPHS</b>	BORING
Drawn By: TCF	Scale: As Shown		BRENT SPENCE BRIDGE REPLACEMENT PARSONS BRINCKERHOFF CINCINNATI, OHIO	R-5
Chkd By: DWW	File No. Core D			
Approved By: AJM	Date: 9-23-10			



MATERIAL DESCRIPTION AND NOTES	ELEV.	DEPTHS	SPT/ RQD	N <sub>60</sub>	REC (%)	SAMPLE ID	HP (tsf)	GRADATION (%)					ATTERBERG				DOT CLASS (GI)	HOLE SEALED	
								GR	CS	FS	SI	CL	LL	PL	FI	WC			
MEDIUM STIFF, BROWN AND GRAY, <b>SANDY SILT</b> , SOME CLAY, TRACE GRAVEL, MOIST	457.0	1	WOH	0	100	SS-1	0.50	1	1	25	49	24	28	19	9	29	A-4a (8)		
MEDIUM STIFF, BROWN, <b>SILT AND CLAY</b> , TRACE SAND, MOIST	454.5	2																	
MEDIUM STIFF, BROWN, <b>SILT AND CLAY</b> , TRACE SAND, MOIST	452.0	3	1	2	4	100	SS-2	1.00	0	0	2	67	31	35	22	13	32	A-6a (9)	
MEDIUM STIFF, BROWN, <b>SILTY CLAY</b> , TRACE GRAVEL, TRACE SAND, MOIST	450.0	4																	
MEDIUM STIFF, BROWN, <b>SILTY CLAY</b> , TRACE GRAVEL, TRACE SAND, MOIST	450.0	5																	
LOOSE, BROWN, <b>SILT</b> , SOME SAND, SOME CLAY, WET	447.0	6			100	ST-3	0.50	1	0	6	60	33	38	22	16	35	A-6b (10)		
LOOSE, BROWN, <b>SILT</b> , SOME SAND, SOME CLAY, WET	447.0	7	WOH	0	100	SS-4	-	0	0	22	52	26	30	20	10	33	A-4b (8)		
MEDIUM STIFF, BROWN, <b>SILT AND CLAY</b> , SOME SAND, WET	444.5	8	WOH	0	100	SS-4	-	0	0	22	52	26	30	20	10	33	A-4b (8)		
MEDIUM STIFF, BROWN AND GRAY, <b>SANDY SILT</b> , SOME CLAY, WET	442.0	9																	
MEDIUM STIFF, BROWN AND GRAY, <b>SILT AND CLAY</b> , LITTLE SAND, WET	440.0	10	1	1	3	100	SS-5	0.75	0	0	31	42	27	30	17	13	26	A-6a (8)	
MEDIUM STIFF, BROWN AND GRAY, <b>SILT AND CLAY</b> , LITTLE SAND, WET	440.0	11																	
MEDIUM STIFF, BROWN AND GRAY, <b>SILT AND CLAY</b> , LITTLE SAND, WET	440.0	12																	
MEDIUM STIFF, GRAY, <b>SANDY SILT</b> , LITTLE CLAY, TRACE GRAVEL, WET	432.0	13	1	1	3	100	SS-6	0.50	0	0	39	39	22	26	17	9	24	A-4a (5)	
MEDIUM STIFF, GRAY, <b>SANDY SILT</b> , LITTLE CLAY, TRACE GRAVEL, WET	432.0	14																	
MEDIUM STIFF, GRAY, <b>SANDY SILT</b> , LITTLE CLAY, TRACE GRAVEL, WET	432.0	15																	
MEDIUM STIFF, GRAY, <b>SANDY SILT</b> , LITTLE CLAY, TRACE GRAVEL, WET	432.0	16			92	ST-7	-	0	0	18	55	27	34	23	11	-	A-6a (8)		
MEDIUM STIFF, GRAY, <b>SANDY SILT</b> , LITTLE CLAY, TRACE GRAVEL, WET	432.0	17	2	2	6	100	SS-8	1.00	6	1	43	31	19	26	17	9	26	A-4a (3)	
MEDIUM STIFF, GRAY, <b>SANDY SILT</b> , LITTLE CLAY, TRACE GRAVEL, WET	432.0	18																	
MEDIUM STIFF, GRAY, <b>SANDY SILT</b> , LITTLE CLAY, TRACE GRAVEL, WET	432.0	19																	
MEDIUM STIFF, GRAY, <b>SANDY SILT</b> , LITTLE CLAY, TRACE GRAVEL, WET	432.0	20																	
MEDIUM STIFF, GRAY, <b>SANDY SILT</b> , LITTLE CLAY, TRACE GRAVEL, WET	432.0	21	2	1	3	100	SS-9	1.00	0	1	32	40	27	33	23	10	48	A-4a (6)	
MEDIUM STIFF, GRAY, <b>SANDY SILT</b> , LITTLE CLAY, TRACE GRAVEL, WET	432.0	22																	
MEDIUM STIFF, GRAY, <b>SANDY SILT</b> , LITTLE CLAY, TRACE GRAVEL, WET	432.0	23																	
MEDIUM STIFF, GRAY, <b>SANDY SILT</b> , LITTLE CLAY, TRACE GRAVEL, WET	432.0	24																	
MEDIUM DENSE TO DENSE, BROWN, <b>GRAVEL AND STONE FRAGMENTS</b> , TRACE TO SOME SAND, TRACE SILT, TRACE CLAY, WET	412.0	25	4	5	12	56	SS-10	-	85	4	2	6	3	NP	NP	NP	10	A-1-a (0)	
MEDIUM DENSE TO DENSE, BROWN, <b>GRAVEL AND STONE FRAGMENTS</b> , TRACE TO SOME SAND, TRACE SILT, TRACE CLAY, WET	412.0	26																	
MEDIUM DENSE TO DENSE, BROWN, <b>GRAVEL AND STONE FRAGMENTS</b> , TRACE TO SOME SAND, TRACE SILT, TRACE CLAY, WET	412.0	27																	
MEDIUM DENSE TO DENSE, BROWN, <b>GRAVEL AND STONE FRAGMENTS</b> , TRACE TO SOME SAND, TRACE SILT, TRACE CLAY, WET	412.0	28																	
MEDIUM DENSE TO DENSE, BROWN, <b>GRAVEL AND STONE FRAGMENTS</b> , TRACE TO SOME SAND, TRACE SILT, TRACE CLAY, WET	412.0	29																	
MEDIUM DENSE TO DENSE, BROWN, <b>GRAVEL AND STONE FRAGMENTS</b> , TRACE TO SOME SAND, TRACE SILT, TRACE CLAY, WET	412.0	30	8	11	30	67	SS-11	-	-	-	-	-	-	-	-	-	8	A-1-a (V)	
MEDIUM DENSE TO DENSE, BROWN, <b>GRAVEL AND STONE FRAGMENTS</b> , TRACE TO SOME SAND, TRACE SILT, TRACE CLAY, WET	412.0	31																	
MEDIUM DENSE TO DENSE, BROWN, <b>GRAVEL AND STONE FRAGMENTS</b> , TRACE TO SOME SAND, TRACE SILT, TRACE CLAY, WET	412.0	32																	
MEDIUM DENSE TO DENSE, BROWN, <b>GRAVEL AND STONE FRAGMENTS</b> , TRACE TO SOME SAND, TRACE SILT, TRACE CLAY, WET	412.0	33																	
MEDIUM DENSE TO DENSE, BROWN, <b>GRAVEL AND STONE FRAGMENTS</b> , TRACE TO SOME SAND, TRACE SILT, TRACE CLAY, WET	412.0	34																	
MEDIUM DENSE TO DENSE, BROWN, <b>GRAVEL AND STONE FRAGMENTS</b> , TRACE TO SOME SAND, TRACE SILT, TRACE CLAY, WET	412.0	35	16	13	44	100	SS-12	-	58	20	12	6	4	NP	NP	NP	9	A-1-a (0)	
MEDIUM DENSE TO DENSE, BROWN, <b>GRAVEL AND STONE FRAGMENTS</b> , TRACE TO SOME SAND, TRACE SILT, TRACE CLAY, WET	412.0	36																	
MEDIUM DENSE TO DENSE, BROWN, <b>GRAVEL AND STONE FRAGMENTS</b> , TRACE TO SOME SAND, TRACE SILT, TRACE CLAY, WET	412.0	37																	
MEDIUM DENSE TO DENSE, BROWN, <b>GRAVEL AND STONE FRAGMENTS</b> , TRACE TO SOME SAND, TRACE SILT, TRACE CLAY, WET	412.0	38																	
MEDIUM DENSE TO DENSE, BROWN, <b>GRAVEL AND STONE FRAGMENTS</b> , TRACE TO SOME SAND, TRACE SILT, TRACE CLAY, WET	412.0	39																	
MEDIUM DENSE TO DENSE, BROWN, <b>GRAVEL AND STONE FRAGMENTS</b> , TRACE TO SOME SAND, TRACE SILT, TRACE CLAY, WET	412.0	40	4	7	25	67	SS-13	-	-	-	-	-	-	-	-	-	9	A-1-a (V)	
MEDIUM DENSE TO DENSE, BROWN, <b>GRAVEL AND STONE FRAGMENTS</b> , TRACE TO SOME SAND, TRACE SILT, TRACE CLAY, WET	412.0	41																	
MEDIUM DENSE TO DENSE, BROWN, <b>GRAVEL AND STONE FRAGMENTS</b> , TRACE TO SOME SAND, TRACE SILT, TRACE CLAY, WET	412.0	42																	
MEDIUM DENSE TO DENSE, BROWN, <b>GRAVEL AND STONE FRAGMENTS</b> , TRACE TO SOME SAND, TRACE SILT, TRACE CLAY, WET	412.0	43																	
MEDIUM DENSE TO DENSE, BROWN, <b>GRAVEL AND STONE FRAGMENTS</b> , TRACE TO SOME SAND, TRACE SILT, TRACE CLAY, WET	412.0	44																	
MEDIUM DENSE TO DENSE, BROWN, <b>GRAVEL AND STONE FRAGMENTS</b> , TRACE TO SOME SAND, TRACE SILT, TRACE CLAY, WET	412.0	45	13	9	28	100	SS-14	-	33	39	20	5	3	NP	NP	NP	13	A-1-b (0)	
MEDIUM DENSE TO DENSE, BROWN, <b>GRAVEL AND STONE FRAGMENTS</b> , TRACE TO SOME SAND, TRACE SILT, TRACE CLAY, WET	412.0	46																	
MEDIUM DENSE TO DENSE, BROWN, <b>GRAVEL AND STONE FRAGMENTS</b> , TRACE TO SOME SAND, TRACE SILT, TRACE CLAY, WET	412.0	47																	
MEDIUM DENSE TO DENSE, BROWN, <b>GRAVEL AND STONE FRAGMENTS</b> , TRACE TO SOME SAND, TRACE SILT, TRACE CLAY, WET	412.0	48																	
MEDIUM DENSE TO DENSE, BROWN, <b>GRAVEL AND STONE FRAGMENTS</b> , TRACE TO SOME SAND, TRACE SILT, TRACE CLAY, WET	412.0	49																	
MEDIUM DENSE TO DENSE, BROWN, <b>GRAVEL AND STONE FRAGMENTS</b> , TRACE TO SOME SAND, TRACE SILT, TRACE CLAY, WET	407.0	50	9	10	28	72	SS-15	-	56	21	18	3	2	NP	NP	NP	17	A-1-a (0)	
MEDIUM DENSE TO DENSE, BROWN, <b>GRAVEL AND STONE FRAGMENTS</b> , TRACE TO SOME SAND, TRACE SILT, TRACE CLAY, WET	407.0	51																	
MEDIUM DENSE TO DENSE, BROWN, <b>GRAVEL AND STONE FRAGMENTS</b> , TRACE TO SOME SAND, TRACE SILT, TRACE CLAY, WET	407.0	52																	
MEDIUM DENSE TO DENSE, BROWN, <b>GRAVEL AND STONE FRAGMENTS</b> , TRACE TO SOME SAND, TRACE SILT, TRACE CLAY, WET	407.0	53																	
MEDIUM DENSE TO DENSE, BROWN, <b>GRAVEL AND STONE FRAGMENTS</b> , TRACE TO SOME SAND, TRACE SILT, TRACE CLAY, WET	407.0	54																	
MEDIUM DENSE TO DENSE, BROWN, <b>GRAVEL AND STONE FRAGMENTS</b> , TRACE TO SOME SAND, TRACE SILT, TRACE CLAY, WET	407.0	55	9	8	21	100	SS-16	-	-	-	-	-	-	-	-	-	14	A-1-a (V)	
MEDIUM DENSE TO DENSE, BROWN, <b>GRAVEL AND STONE FRAGMENTS</b> , TRACE TO SOME SAND, TRACE SILT, TRACE CLAY, WET	407.0	56																	
MEDIUM DENSE TO DENSE, BROWN, <b>GRAVEL AND STONE FRAGMENTS</b> , TRACE TO SOME SAND, TRACE SILT, TRACE CLAY, WET	407.0	57																	
MEDIUM DENSE TO DENSE, BROWN, <b>GRAVEL AND STONE FRAGMENTS</b> , TRACE TO SOME SAND, TRACE SILT, TRACE CLAY, WET	407.0	58																	
MEDIUM DENSE TO DENSE, BROWN, <b>GRAVEL AND STONE FRAGMENTS</b> , TRACE TO SOME SAND, TRACE SILT, TRACE CLAY, WET	407.0	59																	

MATERIAL DESCRIPTION AND NOTES	ELEV. 397.0	DEPTHS	SPT/ RQD	N <sub>60</sub>	REC (%)	SAMPLE ID	HP (tsf)	GRADATION (%)					ATTERBERG			WC	ODOT CLASS (G)	HOLE SEALED
								GR	CS	FS	SI	CL	LL	PL	PI			
DENSE TO VERY DENSE, BROWN, GRAVEL AND/OR STONE FRAGMENTS, SOME SAND, TRACE COBBLES, TRACE SILT, TRACE CLAY, WET		61	12 9 16	28	100	SS-17	-	-	-	-	-	-	-	-	-	22	A-1-a (V)	
		62																
		63																
		64																
		65																
		66	25 25 27	58	100	SS-18	-	54	18	20	6	2	NP	NP	NP	15	A-1-a (0)	
		67																
		68																
		69																
		70																
	71	55 23 26	55	100	SS-19	-	-	-	-	-	-	-	-	-	6	A-1-a (V)		
	72																	
	73																	
	74																	
	75	100 60/3"	-	100	SS-20	-	58	13	17	8	4	NP	NP	NP	9	A-1-a (0)		
	76																	
	77																	
	78																	
	79																	
	80	100/4"	-	100	SS-21	-	-	-	-	-	-	-	-	-	6	A-1-a (V)		
	81																	
	82																	
	83																	
	373.0																	
INTERBEDDED LIMESTONE (60%) AND SHALE (40%); LIMESTONE, LIGHT GRAY, UNWEATHERED TO SLIGHTLY WEATHERED, STRONG, THIN BEDDED; SHALE, GRAY, MODERATELY WEATHERED, VERY WEAK TO WEAK, LOSS 1%, RQD 53%		84																
		85	48		92	NQ-1											CORE	
		86																
		87																
		88																
		89	48		100	NQ-2												CORE
		90																
		91																
		92																
		93																
	94	44		100	NQ-3												CORE	
	95																	
	96																	
	97																	
	98																	
	99	68		100	NQ-4												CORE	
	100																	
	101																	
	355.5																	
LIMESTONE, LIGHT GRAY, UNWEATHERED, STRONG, THIN BEDDED, FOSSILIFEROUS, INTERMEDIATE SHALE SEAMS TO PARTINGS, LOSS 0%, RQD 81%		102																
		103																
		104	82		100	NQ-5												CORE
		105																
		106																
		107																
		108																
		109	78		100	NQ-6												CORE
		110																
		111																
	112																	
	113																	
	114	86		100	NQ-7												CORE	
	115																	
	116																	
	117																	
	118																	
	119	82		100	NQ-8												CORE	
	120																	
	121																	

STANDARD ODOT SOIL BORING LOG (11 X 17) - OH.DOT.GDT - 3/9/11 10:08 - N:\PROJECTS\2010\1105070\GINT\ODOT LOGS.GPJ

MATERIAL DESCRIPTION AND NOTES	ELEV. 335.2	DEPTHS	SPT/ RQD	N <sub>60</sub>	REC (%)	SAMPLE ID	HP (tsf)	GRADATION (%)					ATTERBERG				HOLE SEALED	
								GR	CS	FS	SI	CL	LL	PL	PI	WC		ODOT CLASS (G)
<b>LIMESTONE</b> , LIGHT GRAY, UNWEATHERED, STRONG, THIN BEDDED, FOSSILIFEROUS, INTERMEDIATE SHALE SEAMS TO PARTINGS, LOSS 0%, RQD 81%  LS @100.1'-100.5' QU=12695 PSI LS @ 105' POINT LOAD = 12607 PSI LS @107.1'-107.5' QU=8745 PSI LS @114.5'-115' QU=10184 PSI LS @ 124.7' POINT LOAD = 11607 PSI. (continued)	335.2	123	84		100	NQ-9												CORE
		124																
		125																
		126																
		127																
		128																
		129																
		130																
		131																
		132																
<b>LIMESTONE</b> , GRAY, UNWEATHERED, STRONG, THIN BEDDED, ARGILLACEOUS, LOSS 2%, RQD 93%  LS @136.5'-137.3' QU=11456 PSI LS @ 153.1' POINT LOAD = 13102 PSI LS @158.4'-158.9' QU=22557 PSI LS @159.8'-160.2' QU=8843 PSI.	325.5	133	76		90	NQ-11												CORE
		134																
		135																
		136																
		137																
		138																
		139																
		140																
		141																
		142																
143																		
144																		
145																		
146																		
147																		
148																		
149																		
150																		
151																		
152																		
153																		
154																		
155																		
156																		
157																		
158																		
159																		
160																		
161																		
162																		
163																		
164																		
	293.0	EOB																

STANDARD ODOT SOIL BORING LOG (11 X 17) - OH DOT.GDT - 3/9/11 10:08 - N:\PROJECTS\2010\1105070\GINT\ODOT LOGS.GPJ

NOTES: DRILL FLUID USED BELOW 10 FT. WATER USED BELOW 84 FT. FOR ROCK CORING PURPOSES.

ABANDONMENT METHODS, MATERIALS, QUANTITIES: BACKFILLED WITH BENTONITE GROUT (12 BAGS CEMENT/1.5 BAGS BENTONITE)




BORING NO.: R-6  
 CORE BOX NO.: 1 OF 6  
 DEPTH (ft.): 84.0-96.2  
 ELEVATION (ft.): 373  
 1/NQ: 84.0'-86.5'; REC. 92%, RQD 48%  
 2/NQ: 86.5'-91.5'; REC. 100%, RQD 48%  
 3/NQ: 91.5'-96.1'; REC. 50%, RQD 48%



BORING NO.: R-6  
 CORE BOX NO.: 2 OF 6  
 DEPTH (ft.): 96.2-111.5  
 ELEVATION (ft.): 360.8  
 4/NQ: 96.1'-101.5'; REC. 93%, RQD 63%  
 5/NQ: 101.5'-106.5'; REC. 100%, RQD 82%  
 6/NQ: 106.5'-111.5'; REC. 100%, RQD 78%



BORING NO.: R-6  
 CORE BOX NO.: 3 OF 6  
 DEPTH (ft.): 111.5-125.7  
 ELEVATION (ft.): 345.5  
 7/NQ: 111.5'-116.5'; REC. 100%, RQD 86%  
 8/NQ: 116.5'-121.5'; REC. 100%, RQD 82%  
 9/NQ: 121.5'-126.5'; REC. 100%, RQD 84%

Project Mngr.: AJM	PN: N1105070	 611 LUNKEN PARK DRIVE CINCINNATI, OHIO 45226	<b>ROCK CORE PHOTOGRAPHS</b>	BORING
Drawn By: TCF	Scale: As Shown		BRENT SPENCE BRIDGE REPLACEMENT PARSONS BRINCKERHOFF CINCINNATI, OHIO	R-6
Chkd By: DWW	File No. Core D			
Approved By: AJM	Date: 9-23-10			




BORING NO.: R-6  
 CORE BOX NO.: 4 OF 6  
 DEPTH (ft.): 125.7-140.7  
 ELEVATION (ft.): 331.3  
 10/NQ: 126.5'-131.5'; REC. 100%, RQD 72%  
 11/NQ: 131.5'-136.5'; REC. 90%, RQD 76%  
 12/NQ: 136.5'-141.5'; REC. 100%, RQD 84%



BORING NO.: R-6  
 CORE BOX NO.: 5 OF 6  
 DEPTH (ft.): 140.7-153.9  
 ELEVATION (ft.): 316.3  
 13/NQ: 141.5'-146.5'; REC. 100%, RQD 100%  
 14/NQ: 146.5'-151.6'; REC. 100%, RQD 100%  
 15/NQ: 151.5'-156.5'; REC. 100%, RQD 100%



BORING NO.: R-6  
 CORE BOX NO.: 6 OF 6  
 DEPTH (ft.): 153.9-164.0  
 ELEVATION (ft.): 303.1  
 16/NQ: 156.5'-161.5'; REC. 83%, RQD 83%  
 17/NQ: 161.5'-164.0'; REC. 92%, RQD 92%

Project Mngr.: AJM	PN: N1105070	 611 LUNKEN PARK DRIVE CINCINNATI, OHIO 45226	<b>ROCK CORE PHOTOGRAPHS</b>	BORING
Drawn By: TCF	Scale: As Shown		BRENT SPENCE BRIDGE REPLACEMENT PARSONS BRINCKERHOFF CINCINNATI, OHIO	R-6
Chkd By: DWW	File No. Core D			
Approved By: AJM	Date: 9-23-10			

PROJECT: BRENT SPENCE BRIDGE	DRILLING FIRM / OPERATOR: HCN / HH	DRILL RIG: CME 550X ATV-7253	STATION / OFFSET: 7+85.2, 32.7 LT	EXPLORATION ID: R-7
TYPE: BRIDGE REPLACEMENT	SAMPLING FIRM / LOGGER: HCN / DRK/DWW	HAMMER: CME AUTOMATIC	ALIGNMENT: PROPOSED BSB	
PID: 75119 BR ID:	DRILLING METHOD: 3.25" HSA / NQ	CALIBRATION DATE: 2/4/10	ELEVATION: 458.5 (MSL) EOB: 164.5 ft.	PAGE 1 OF 3
START: 7/2/10 END: 7/4/10	SAMPLING METHOD: SPT / NQ	ENERGY RATIO (%): 76.3	COORD: 39.089410800, -84.523311230	

MATERIAL DESCRIPTION AND NOTES	ELEV.	DEPTHS	SPT/RQD	N <sub>60</sub>	REC (%)	SAMPLE ID	HP (tsf)	GRADATION (%)					ATTERBERG				HOLE SEALED
								GR	CS	FS	SI	CL	LL	PL	PI	WC	
WATER (OHIO RIVER)	458.5	1-20															
MEDIUM STIFF, GRAY, CLAY, AND SILT, TRACE ORGANICS, TRACE GRAVEL, TRACE SAND, WET	437.5	21-22	1	4	0	SS-1	1.00	-	-	-	-	-	-	-	-	-	A-7-6 (V)
	434.5	23-24	2	5	100	SS-2	0.75	5	2	10	45	38	42	22	20	46	A-7-6 (12)
MEDIUM STIFF, GRAY, SILT AND CLAY, SOME GRAVEL, SOME SAND, WET		25-26	1	5	33	SS-3	1.00	33	3	21	25	18	32	18	14	24	A-6a (3)
		27-28	4	3	2	SS-4	1.00	34	4	24	22	16	-	-	-	31	A-6a (V)
		29-30	2	3	9	SS-5	1.00	35	4	21	25	15	-	-	-	33	A-6a (V)
		31-32	50/0"	-	-	SS-6	1.25	-	-	-	-	-	-	-	-	-	A-6a (V)
	426.0	33-34	9	6	4	SS-7	-	-	-	-	-	-	-	-	-	-	A-6a (V)
MEDIUM DENSE TO DENSE, BROWN, GRAVEL AND STONE FRAGMENTS, SOME SAND, TRACE SILT, TRACE CLAY, VERY DENSE AT 60', WET		35-36	9	5	8	SS-8	-	68	19	5	5	3	-	-	-	12	A-1-a (V)
		37-38	16	18	50/0"	SS-9	-	-	-	-	-	-	-	-	-	-	A-1-a (V)
		39-40	7	14	11	SS-10	-	-	-	-	-	-	-	-	-	10	A-1-a (V)
		41-42	9	9	12	SS-11	-	62	16	11	7	4	NP	NP	NP	10	A-1-a (0)
		43-44															
		45-46	14	15	16	SS-12	-	-	-	-	-	-	-	-	-	7	A-1-a (V)
		47-48															
		49-50	16	9	8	SS-13	-	57	27	8	5	3	NP	NP	NP	13	A-1-a (0)
		51-52															
		53-54															
		55-56	18	12	10	SS-14	-	-	-	-	-	-	-	-	-	13	A-1-a (V)
		57-58															
		59															

STANDARD ODOT SOIL BORING LOG (11 X 17) - OH DOT.GDT - 3/9/11 10:08 - N:\PROJECTS\2010\N1105070\GINT\ODOT LOGS.GPJ

MATERIAL DESCRIPTION AND NOTES	ELEV.	DEPTHS	SPT/ RQD	N <sub>60</sub>	REC (%)	SAMPLE ID	HP (tsf)	GRADATION (%)					ATTERBERG				WC	ODOT CLASS (G)	HOLE SEALED	
								GR	CS	FS	SI	CL	LL	PL	PI					
MEDIUM DENSE TO DENSE, BROWN, GRAVEL AND STONE FRAGMENTS, SOME SAND, TRACE SILT, TRACE CLAY, VERY DENSE AT 60', WET (continued)	398.5	61	24 25 26	65	67	SS-15	-	60	16	14	5	5	NP	NP	NP	10	A-1-a (0)			
		62																		
		63																		
		64																		
		65																		
		66		45 20 18	48	67	SS-16	-	-	-	-	-	-	-	-	-	-	A-1-a (V)		
		67																		
		68																		
		69																		
		70	388.5		50/4"	-	100	SS-17	-	71	12	8	5	4	NP	NP	NP	13	A-1-a (0)	
71																				
72																				
73																				
74																				
75			50/0"	-	-	SS-18	-	-	-	-	-	-	-	-	-	-	A-1-a (V)			
76																				
77																				
78																				
79																				
80																				
81																				
82	376.0	TR																		
INTERBEDDED LIMESTONE (65%) AND SHALE (35%); LIMESTONE, LIGHT GRAY, SLIGHTLY TO MODERATELY WEATHERED, STRONG, THIN BEDDED, FOSSILIFEROUS; SHALE, GRAY, MODERATELY WEATHERED, VERY WEAK, LOSS 5%, RQD 26%  LS @83.5'-83.9' QU=8872 PSI SH @ 93.4' SDI = 79.5 SH @ 95.7' SDI = 72.8 LS @98'-98.5' QU=6802 PSI LS @ 89.7' POINT LOAD = 12982 PSI.	376.0	83	25		85	NQ-1												CORE		
		84																		
		85																		
		86																		
		87		20		94	NQ-2												CORE	
		88																		
		89																		
		90																		
		91																		
		92		20		94	NQ-3												CORE	
93																				
94																				
95																				
96																				
97		40		100	NQ-4												CORE			
98																				
99																				
100	359.0																			
INTERBEDDED LIMESTONE (75%) AND SHALE (25%); LIMESTONE, LIGHT GRAY, UNWEATHERED TO SLIGHTLY WEATHERED, STRONG, THIN BEDDED, FOSSILIFEROUS; SHALE, GRAY, SLIGHTLY WEATHERED, MODERATELY STRONG, LOSS 2%, RQD 80%  LS @ 100.8' POINT LOAD = 11981 PSI SH @ 102' SDI = 92.6 LS @106.2'-106.7' QU=16419 PSI SH @ 121.1' SDI = 80.4 SH @121.1'-121.4' QU=1833 PSI LS @ 125.9' POINT LOAD = 14914 PSI LS @128.7'-129.5' QU=8525 PSI.	359.0	101																		
		102		72		100	NQ-5											CORE		
		103																		
		104																		
		105																		
		106																		
		107		92		100	NQ-6											CORE		
		108																		
		109																		
		110																		
111																				
112		92		100	NQ-7												CORE			
113																				
114																				
115																				
116																				
117		70		92	NQ-8												CORE			
118																				
119																				
120																				
121																				

STANDARD ODOT SOIL BORING LOG (11 X 17) - OH DOT.GDT - 3/9/11 10:08 - N:\PROJECTS\2010\101105070\GINT\DOT LOGS.GPJ

MATERIAL DESCRIPTION AND NOTES	ELEV.	DEPTHS	SPT/RQD	N <sub>60</sub>	REC (%)	SAMPLE ID	HP (tsf)	GRADATION (%)					ATTERBERG				ODOT CLASS (G)	HOLE SEALED
								GR	CS	FS	SI	CL	LL	PL	PI	WC		
<b>INTERBEDDED LIMESTONE (75%) AND SHALE (25%);</b> <b>LIMESTONE</b> , LIGHT GRAY, UNWEATHERED TO SLIGHTLY WEATHERED, STRONG, THIN BEDDED, FOSSILIFEROUS; <b>SHALE</b> , GRAY, SLIGHTLY WEATHERED, MODERATELY STRONG, LOSS 2%, RQD 80%  LS @ 100.8' POINT LOAD = 11981 PSI SH @ 102' SDI = 92.6 LS @106.2'-106.7' QU=16419 PSI SH @ 121.1' SDI = 80.4 SH @121.1'-121.4' QU=1833 PSI LS @ 125.9' POINT LOAD = 14914 PSI LS @128.7'-129.5' QU=8525 PSI. (continued)	336.6		66		100	NQ-9											CORE	
			123															
			124															
			125															
			126															
			127	74		100	NQ-10											CORE
			128															
			129															
			130															
			131															
		132	96		96	NQ-11											CORE	
		133																
		134																
	324.0	135																
<b>LIMESTONE</b> , LIGHT GRAY, UNWEATHERED, STRONG, THIN BEDDED, ARGILLACEOUS, LOSS 2%, RQD 94%  LS @136.6'-137.6' QU=11974 PSI LS @ 145.5' POINT LOAD = 13149 PSI LS @154.5'-155.1' QU=12586 PSI LS @163.7'-164.5' QU=8772 PSI.		136																
		137	92		100	NQ-12											CORE	
		138																
		139																
		140																
		141																
		142	90		96	NQ-13											CORE	
		143																
		144																
		145																
	146																	
	147	100		100	NQ-14											CORE		
	148																	
	149																	
	150																	
	151																	
	152	90		94	NQ-15											CORE		
	153																	
	154																	
	155																	
	156																	
	157	100		100	NQ-16											CORE		
	158																	
	159																	
	160																	
	161																	
	162	94		100	NQ-17											CORE		
	163																	
	164																	
	294.0																	

EOB

STANDARD ODOT SOIL BORING LOG (11 X 17) - OH.DOT.GDT - 3/9/11 10:08 - N:\PROJECTS\2010\1105070\GINT\ODOT LOGS.GPJ


NOTES: WATER USED BELOW 82.5 FT. FOR ROCK CORING PURPOSES.

ABANDONMENT METHODS, MATERIALS, QUANTITIES: BACKFILLED WITH BENTONITE GROUT (10 BAGS CEMENT/1 BAG BENTONITE)






BORING NO.: R-7  
 CORE BOX NO.: 1 OF 6  
 DEPTH (ft.): 78.0-96.7  
 ELEVATION (ft.): 376.0  
 1/NQ: 82.5'-84.5'; REC. 85%, RQD 25%  
 2/NQ: 84.5'-89.5'; REC. 94%, RQD 20%  
 3/NQ: 89.5'-94.5'; REC. 94%, RQD 20%  
 4/NQ: 94.5'-99.5'; REC. 100%, RQD 40%




BORING NO.: R-7  
 CORE BOX NO.: 2 OF 6  
 DEPTH (ft.): 96.7-111.0  
 ELEVATION (ft.): 357.3  
 5/NQ: 99.5'-104.5'; REC. 100%, RQD 72%  
 6/NQ: 104.5'-109.5'; REC. 100%, RQD 92%  
 7/NQ: 109.5'-114.5'; REC. 100%, RQD 92%



BORING NO.: R-7  
 CORE BOX NO.: 3 OF 6  
 DEPTH (ft.): 111.0-124.5  
 ELEVATION (ft.): 343  
 8/NQ: 114.5'-119.5'; REC. 92%, RQD 70%  
 9/NQ: 119.5'-124.5'; REC. 100%, RQD 66%

Project Mngr.: AJM	PN: N1105070	 611 LUNKEN PARK DRIVE CINCINNATI, OHIO 45226	<b>ROCK CORE PHOTOGRAPHS</b>	BORING
Drawn By: TCF	Scale: As Shown		BRENT SPENCE BRIDGE REPLACEMENT PARSONS BRINCKERHOFF CINCINNATI, OHIO	
Chkd By: DWW	File No. Core D			R-7
Approved By: AJM	Date: 9-23-10			




BORING NO.: R-7  
 CORE BOX NO.: 4 OF 6  
 DEPTH (ft.): 124.5-136.8  
 ELEVATION (ft.): 329.5  
 10/NQ: 124.5'-129.5'; REC. 100%, RQD 74%  
 11/NQ: 129.5'-134.5'; REC. 96%, RQD 96%  
 12/NQ: 134.5'-139.5'; REC. 100%, RQD 92%



BORING NO.: R-7  
 CORE BOX NO.: 5 OF 6  
 DEPTH (ft.): 136.8-149.5  
 ELEVATION (ft.): 317.2  
 13/NQ: 139.5'-144.5'; REC. 96%, RQD 90%  
 14/NQ: 144.5'-149.5'; REC. 100%, RQD 100%



BORING NO.: R-7  
 CORE BOX NO.: 6 OF 6  
 DEPTH (ft.): 149.5-164.5  
 ELEVATION (ft.): 304.5  
 15/NQ: 149.5'-154.5'; REC. 94%, RQD 90%  
 16/NQ: 154.5'-159.5'; REC. 100%, RQD 100%  
 17/NQ: 159.5'-164.5'; REC. 100%, RQD 94%

Project Mngr: AJM	PN: N1105070	 611 LUNKEN PARK DRIVE CINCINNATI, OHIO 45226	<b>ROCK CORE PHOTOGRAPHS</b>	BORING
Drawn By: TCF	Scale: As Shown		BRENT SPENCE BRIDGE REPLACEMENT PARSONS BRINCKERHOFF CINCINNATI, OHIO	
Chkd By: DWW	File No. Core D			R-7
Approved By: AJM	Date: 9-23-10			

MATERIAL DESCRIPTION AND NOTES	ELEV.	DEPTH	SPT/RQD	N <sub>60</sub>	REC (%)	SAMPLE ID	HP (tsf)	GRADATION (%)					ATTERBERG				WC	ODOT CLASS (G)	HOLE SEALED	
								GR	CS	FS	SI	CL	LL	PL	PI	FL				FI
VERY SOFT TO SOFT, BROWN, SILT AND CLAY, TRACE SAND, MOIST TO WET	455.7	1	1	0	1	44	SS-1	0.25	-	-	-	-	-	-	-	-	-	36	A-6a (V)	
		2	1	0	0	33	SS-2	0.25	0	0	6	63	31	36	21	15	33	A-6a (10)		
		3	2	2	5	100	SS-3	0.25	-	-	-	-	-	-	-	-	-	29	A-6a (V)	
		4	2	2	4	100	SS-4	0.50	-	-	-	-	-	-	-	-	-	28	A-6a (V)	
		5	2	2	5	67	SS-5	0.25	-	-	-	-	-	-	-	-	-	28	A-6a (V)	
		6	1	3	6	100	SS-6	0.25	-	-	-	-	-	-	-	-	-	30	A-6a (V)	
		7	1	2	5	100	SS-7	0.25	-	-	-	-	-	-	-	-	-	28	A-6a (V)	
		8	1	1	3	100	SS-8	0.25	-	-	-	-	-	-	-	-	-	31	A-6a (V)	
		9	1	2	4	100	SS-9	0.50	0	0	24	52	24	30	21	9	40	A-4b (8)		
		10	1	2	4	100	SS-10	0.25	-	-	-	-	-	-	-	-	-	36	A-4b (V)	
		11	1	1	4	100	SS-11	0.25	-	-	-	-	-	-	-	-	-	33	A-4b (V)	
		12	1	2	3	6	100	SS-12	0.25	-	-	-	-	-	-	-	-	34	A-4b (V)	
	SOFT TO MEDIUM STIFF, BROWN, SILT, SOME SAND, SOME CLAY, WET	440.7	13	8	14	43	100	SS-13	-	-	-	-	-	-	-	-	-	9	A-1-b (V)	
		14	7	14	41	100	SS-14	-	-	-	-	-	-	-	-	-	10	A-1-b (V)		
		15	3	6	22	100	SS-15	-	39	35	20	4	2	NP	NP	NP	17	A-1-b (0)		
		16	10	15	39	100	SS-16	-	-	-	-	-	-	-	-	-	-	10	A-1-b (V)	
		17	10	10	27	100	SS-17	-	-	-	-	-	-	-	-	-	-	14	A-1-b (V)	
		18	13	20	52	100	SS-18	-	27	49	15	6	3	NP	NP	NP	12	A-1-b (0)		
		19																		
		20																		
		21																		
		22																		
		23																		
		24																		
MEDIUM DENSE TO DENSE, BROWN, GRAVEL AND STONE FRAGMENTS WITH SAND, TRACE SILT, TRACE CLAY, VERY DENSE AT 55', WET		425.7	25																	
		26																		
		27																		
		28																		
		29																		
		30																		
		31																		
		32																		
		33																		
		34																		
		35																		
		36																		
		37																		

MATERIAL DESCRIPTION AND NOTES	ELEV.	DEPTHS	SPT/RQD	N <sub>60</sub>	REC (%)	SAMPLE ID	HP (tsf)	GRADATION (%)					ATTERBERG				WC	DOT CLASS (G)	HOLE SEALED	
								GR	CS	FS	SI	CL	LL	PL	PI					
MEDIUM DENSE TO DENSE, BROWN, GRAVEL AND STONE FRAGMENTS WITH SAND, TRACE SILT, TRACE CLAY, VERY DENSE AT 55', WET (continued)	395.7	61	7 22 22	56	100	SS-19	-	-	-	-	-	-	-	-	-	-	17	A-1-b (V)		
		62																		
		63																		
		64																		
		65																		
		66		12 10 20	38	100	SS-20	-	-	-	-	-	-	-	-	-	-	14	A-1-b (V)	
		67																		
VERY DENSE, BROWN AND GRAY, GRAVEL AND STONE FRAGMENTS, SOME COBBLES, LITTLE SAND, WET	388.7	68																		
		69																		
		70		12 50/2"	-	0	SS-21	-	-	-	-	-	-	-	-	-	-	-	A-1-a (V)	
		71																		
		72																		
		73																		
		74																		
INTERBEDDED LIMESTONE (50%) AND SHALE (50%); LIMESTONE, GRAY, UNWEATHERED TO SLIGHTLY WEATHERED, STRONG, THIN BEDDED, TRACE FOSSILIFEROUS SEAMS; SHALE, GRAY, SLIGHTLY WEATHERED, VERY WEAK, LAMINATED, LOSS 2%, RQD 41% LS @87.8'-88.2' QU=9645 PSI LS @ 96' POINT LOAD = 10656 PSI.	375.7	75	50/0"	-	-	SS-22	-	-	-	-	-	-	-	-	-	-	-	A-1-a (V)		
		76																		
		77																		
		78																		
		79																		
		80																		
		81		42		100	NQ-1													CORE
LIMESTONE, GRAY, UNWEATHERED, STRONG, THIN TO MEDIUM BEDDED, ARGILLACEOUS, FOSSILIFEROUS SEAMS, LOSS 1%, RQD 92% SH @ 88.4' SDI = 66.8 LS @100.5'-101' QU=11240 PSI LS @101.8'-102.3' QU=4944 PSI LS @ 118.6' POINT LOAD = 10656 PSI LS @126.3'-126.7' QU=11631 PSI LS @127.8'-128.3' QU=10674 PSI LS @135.5'-136' QU=10495 PSI LS @141'-141.5' QU=12721 PSI LS @149'-149.5 QU=12619 PSI LS @151.8'-152.1' QU=10244 PSI LS @158.7'-159.2' QU=12011 PSI.	357.7	82																		
		83																		
		84		43		100	NQ-2													CORE
		85																		
		86																		
		87																		
		88		20		94	NQ-3													CORE
		89																		
		90																		
		91																		
		92																		
		93		60		100	NQ-4													CORE
		94																		
		95																		
		96																		
		97																		
		98		68		94	NQ-5													CORE
		99																		
		100																		
		101																		
		102																		
		103																		
		104		90		100	NQ-6													CORE
		105																		
		106																		
		107																		
		108																		
		109		80		100	NQ-7													CORE
		110																		
		111																		
		112																		
		113																		
		114		92		100	NQ-8													CORE
		115																		
		116																		
		117																		
		118																		
		119		90		96	NQ-9													CORE
		120																		
		121																		

STANDARD ODOT SOIL BORING LOG (11 X 17) - OH DOT.GDT - 3/9/11 10:09 - N:\PROJECTS\2010\1105070\GINT\ODOT LOGS.GPJ

PID: 75119		BR ID:		PROJECT: BRENT SPENCE BRIDGE		STATION / OFFSET: 6+97.7, 41.1 LT		START: 9/3/10		END: 9/4/10		PG 3 OF 3		R-8					
MATERIAL DESCRIPTION AND NOTES			ELEV. 333.8	DEPTHS	SPT/ RQD	N <sub>60</sub>	REC (%)	SAMPLE ID	HP (tsf)	GRADATION (%)					ATTERBERG				HOLE SEALED
										GR	CS	FS	SI	CL	LL	PL	PI	WC	
<b>LIMESTONE</b> , GRAY, UNWEATHERED, STRONG, THIN TO MEDIUM BEDDED, ARGILLACEOUS, FOSSILIFEROUS SEAMS, LOSS 1%, RQD 92%  SH @ 88.4' SDI = 66.8 LS @100.5'-101' QU=11240 PSI LS @101.8'-102.3' QU=4944 PSI LS @ 118.6' POINT LOAD = 10656 PSI LS @126.3'-126.7' QU=11631 PSI LS @127.8'-128.3' QU=10674 PSI LS @135.5'-136' QU=10495 PSI LS @141'-141.5' QU=12721 PSI LS @149'-149.5' QU=12619 PSI LS @151.8'-152.1' QU=10244 PSI LS @158.7'-159.2' QU=12011 PSI. (continued)			123	82	100	NQ-10											CORE		
			124																
			125																
			126																
			127																
			128	96	100	NQ-11													CORE
			129																
			130																
			131																
			132																
			133																
			134	100	100	NQ-12													CORE
			135																
			136																
			137																
			138																
			139	100	100	NQ-13													CORE
140																			
141																			
142																			
143																			
144	98	98	NQ-14													CORE			
145																			
146																			
147																			
148																			
149	98	100	NQ-15													CORE			
150																			
151																			
152																			
153																			
154	100	100	NQ-16													CORE			
155																			
156																			
157																			
158																			
159	98	96	NQ-17													CORE			
160																			
161																			
			294.7	EOB															

STANDARD ODOT SOIL BORING LOG (11 X 17) - OH.DOT.GDT - 3/9/11 10:09 - N:\PROJECTS\2010\1105070\GINT\ODOT LOGS.GPJ

NOTES: WATER USED BELOW 80 FT. FOR ROCK CORING PURPOSES.


ABANDONMENT METHODS, MATERIALS, QUANTITIES: BACKFILLED WITH BENTONITE GROUT (11 BAGS CEMENT/1 BAGS BENTONITE)




BORING NO.: R-8  
 CORE BOX NO.: 1 OF 6  
 DEPTH (ft.): 80.0-94.0  
 ELEVATION (ft.): 375.70  
 1/NQ: 80.0'-81.0'; REC. 100%, RQD 40%  
 2/NQ: 81.0'-86.0'; REC. 100%, RQD 44%  
 3/NQ: 86.0'-91.0'; REC. 94%, RQD 20%  
 4/NQ: 91.0'-96.0'; REC. 100%, RQD 60%



BORING NO.: R-8  
 CORE BOX NO.: 2 OF 6  
 DEPTH (ft.): 94.0-108.2  
 ELEVATION (ft.): 361.7  
 5/NQ: 96.0'-101.0'; REC. 94%, RQD 68%  
 6/NQ: 101.0'-106.0'; REC. 100%, RQD 90%  
 7/NQ: 106.0'-111.0'; REC. 100%, RQD 80%




BORING NO.: R-8  
 CORE BOX NO.: 3 OF 6  
 DEPTH (ft.): 108.2-121.0  
 ELEVATION (ft.): 347.5  
 8/NQ: 111.0'-116.0'; REC. 100%, RQD 92%  
 9/NQ: 116.0'-121.0'; REC. 96%, RQD 90%


Project Mngr.: AJM	PN. N1105070	 611 LUNKEN PARK DRIVE CINCINNATI, OHIO 45226	<b>ROCK CORE PHOTOGRAPHS</b>	BORING
Drawn By: TCF	Scale: As Shown		BRENT SPENCE BRIDGE REPLACEMENT PARSONS BRINCKERHOFF CINCINNATI, OHIO	R-8
Chkd By: DWW	File No. Core D			
Approved By: AJM	Date: 9-23-10			




BORING NO.: R-8  
 CORE BOX NO.: 4 OF 6  
 DEPTH (ft.): 121.0-134.5  
 ELEVATION (ft.): 334.7  
 10/NQ: 121.0'-126.0'; REC. 100%, RQD 82%  
 11/NQ: 126.0'-131.0'; REC. 100%, RQD 96%  
 12/NQ: 131.0'-136.0'; REC. 100%, RQD 100%



BORING NO.: R-8  
 CORE BOX NO.: 5 OF 6  
 DEPTH (ft.): 134.5-149.0  
 ELEVATION (ft.): 321.2  
 13/NQ: 136.0'-141.0'; REC. 100%, RQD 100%  
 14/NQ: 141.0'-146.0'; REC. 98%, RQD 98%  
 15/NQ: 146.0'-151.0'; REC. 100%, RQD 98%



BORING NO.: R-8  
 CORE BOX NO.: 6 OF 6  
 DEPTH (ft.): 149.0-161.0  
 ELEVATION (ft.): 306.7  
 16/NQ: 151.0'-156.0'; REC. 100%, RQD 100%  
 17/NQ: 156.0'-161.0'; REC. 98%, RQD 98%

Project Mngr.: AJM	PN: N1105070	 611 LUNKEN PARK DRIVE CINCINNATI, OHIO 45226	<b>ROCK CORE PHOTOGRAPHS</b>	BORING
Drawn By: TCF	Scale: As Shown		BRENT SPENCE BRIDGE REPLACEMENT PARSONS BRINCKERHOFF CINCINNATI, OHIO	
Chkd By: DWW	File No. Core D			R-8
Approved By: AJM	Date: 9-23-10			

**Geotechnical Engineering Report**

Brent Spence Bridge Replacement ■ Cincinnati, Ohio-Covington, Kentucky

March 11, 2011 ■ HCN/Terracon Project No. N1105070



**EXHIBIT A-8**  
**EXISTING BRENT SPENCE BRIDGE**  
**TEST BORING LOGS (1958)**



**BORING-1**  
Sta. 602+05, 17' R/L

Classification	Stratigraphic Elev.	Sample Elev.	Sample No.	Hammer Blows on Sampler Per Ft. on Casing	Hammer Blows Per Ft. on Casing
Br. l. gray silty clay, fine to coarse gravel & cinders fill, moist-loose to dense.	495.5	494.5	1	12	14
Dark br. fine to coarse silty cinders and brick fill, moist-loose	487.5	486.5	3	12	14
Cinders with gr. silty clay layers, fill, moist-loose, to medium dense.	475.5	474.5	6	12	14
Br. l. of silty clay, brick, cinders & organic matter fill, moist-medium stiff.	455.5	454.5	10	12	14
Gray silty clay with fine sand seams, moist-medium stiff.	442.5	441.5	13	12	14
Gray sandy clay with fine to coarse gravel, moist-medium stiff.	433.5	432.5	14	12	14
Br. fine sand, moist-dense to very dense.	422.5	421.5	16	12	14
Br. fine to coarse sd. & gravel, moist-very dense.	418.5	417.5	17	12	14
Br. fine to coarse sd. moist-medium dense.	411.5	410.5	18	12	14
Br. fine to coarse sd. & fine gravel, moist-medium dense.	406.5	405.5	20	12	14
Brown fine to coarse sd. and gravel, moist-very dense.	393.5	392.5	21	12	14
	388.5	387.5	22	12	14
	383.5	382.5	23	12	14
	373.0	372.0	24	12	14

35' I.D. Casing driven to 59'. 25' I.D. Casing inserted at 59'. Sampling unsuccessful at EL. 392.5 due to B sand upheaval. Casing was driven to refusal of EL. 579. This was assumed to be top of rock. Groundwater elev. = 441.5

**BORING-2**  
Sta. 602+05, 63' L/L

Classification	Stratigraphic Elev.	Sample Elev.	Sample No.	Hammer Blows on Sampler Per Ft. on Casing	Hammer Blows Per Ft. on Casing
Br. fine to coarse sd. & gravel, cinders, brick, fill, moist-medium dense.	492.6	491.6	1	12	14
Br. sandy clay with cinders fill, moist-very soft.	488.6	487.6	3	12	14
Dark br. sandy clay, fine to coarse gravel, cinders & brick & organic matter, fill, moist-loose to medium dense.	476.6	475.6	6	12	14
Mottled br. & gray silty clay & brick fill, moist-medium stiff.	466.6	465.6	9	12	14
Dark br. fine to medium sand, cinders & organic matter, fill, moist-dense.	456.6	455.6	10	12	14
Gray silty clay with silt lenses & organic matter, moist-medium stiff.	441.6	440.6	13	12	14
Br. fine to coarse sand with fine gravel, moist-dense.	426.6	425.6	16	12	14
Br. fine to medium sand with fine gravel & organic matter, moist-dense to very dense.	416.6	415.6	18	12	14
Br. silty fine to coarse sd. with fine gravel, moist-very dense to dense.	397.6	396.6	22	12	14
Br. silty fine sand with fine gravel, moist-very dense.	387.6	386.6	24	12	14
Br. fine to coarse sd. & fine gravel, moist-very dense.	381.6	380.6	25	12	14

No recovery on sample #25  
Groundwater elev. = 441.6

**BORING-3**  
Sta. 597+70.7, 218' R/L

Classification	Stratigraphic Elev.	Sample Elev.	Sample No.	Hammer Blows on Sampler Per Ft. on Casing	Hammer Blows Per Ft. on Casing
Barge Well.	445.2				
Water.					
Br. fine to coarse sand, fine gravel & organic matter, wet-loose.	422.2	421.2	1	12	14
Br. fine to coarse sand & gravel, wet-loose.	414.2	413.2	3	12	14
Br. fine to medium sand with fine gravel, moist-dense.	402.2	401.2	4	12	14
Br. fine to medium sand wet-medium dense.	404.2	403.2	5	12	14
Br. fine to coarse sand & fine gravel, wet-loose to very dense.	394.2	393.2	6	12	14
Br. fine to coarse sd. and gravel with clay traces, wet-very dense.	374.2	373.2	11	12	14
Layered weathered gray shale and limestone. Approx. 50% limestone in 1' to 5' layers.	361.6	360.6	14	NX	83%

No recovery on sample #2

**BORING-4**  
Sta. 597+80.6, 68.5' L/L

Classification	Stratigraphic Elev.	Sample Elev.	Sample No.	Hammer Blows on Sampler Per Ft. on Casing	Hammer Blows Per Ft. on Casing
Barge Well.	445.0				
Water.					
Br. fine to coarse sd. & gravel, wet-medium dense to dense.	418.0	417.0	2	12	14
Br. fine sand and gravel, wet-dense.	414.0	413.0	3	12	14
Br. fine to coarse sd. & gravel, wet-medium dense.	404.0	403.0	5	12	14
Br. fine to medium sd. with fine gravel, wet-medium dense.	394.0	393.0	7	12	14
Br. fine to coarse sd. and fine gravel, wet-very dense to dense.	389.0	388.0	8	12	14
Br. fine to coarse sd. wet-very dense.	380.0	379.0	10	12	14
Br. fine to coarse sd. & gravel with clay traces, wet-very dense.	374.0	373.0	11	12	14
Layered gray weathered shale, gray shale and limestone. Approx. 55 to 50% limestone in 1 to 5' layers.	361.7	360.7	13	NX	80%

No recovery on sample #5

**SOIL TEST DATA**  
BORING-1

Sample No.	Elevation	% Sand, Silt & Clay	% Moisture	Natural Com. (Wet)	Moist. Per. Co. (%)	Unconf. Comp. (psi)	Strength (psi)	Failure Strain	Atterberg Limits	Classification U.S.C.S.	Classification AASHTO
S2	494.5	48% CL	31.3	115.8	2130	25%	22.8	11%	27.8	CL	A-4


**NOTES**

Borings were made in October and November 1958 by H.C. Nutting Company of Cincinnati, Ohio. Jar samples, rock core samples, and sealed tube laboratory samples have been delivered to the Kentucky Department of Highways, District Highway Building, Covington, Kentucky. NX - Denotes core sample. S - Denotes undisturbed sealed tube sample.

Drwg. No 14355

COMMONWEALTH OF KENTUCKY  
DEPARTMENT OF HIGHWAYS  
FRANKFORT  
COUNTY OF KENTON  
BORINGS 1, 2, 3 & 4  
COVINGTON-CINCINNATI OHIO RIVER BRIDGE  
ROAD: COVINGTON-LEXINGTON  
STATION: 504+74.0 TO 632+0.5 PROJECT NO. 175-B  
MODJESKI & MASTERS, ENGINEERS  
HARRISBURG, PENNSYLVANIA

TEST BORINGS  
DRILLED IN 1958  
BY H.C. NUTTING CO.



**H.C. NUTTING COMPANY**  
CORPORATE OFFICE - 611 LUNKEN PARK DRIVE  
CINCINNATI, OHIO 45226  
(513) 321-5816  
EMPLOYER OWNED

GEOTECHNICAL, ENVIRONMENTAL AND TESTING ENGINEERS

EXISTING BRIDGE DATA ( B-1 To B-4 )

CLIENT: PARSONS BRINCKERHOFF  
PROPOSED QUEENSGATE ALIGNMENT  
BRENT SPENCE BRIDGE REPLACEMENT

W.O. 10974.054  
JUNE 2007  
FIGURE 4A

**BORING-5**  
Sta. 597+41.6-19.1' R.I.

Casing - 3.5" I.D. Hammer - 300" Drop 24"	Stratum Elev.	Sample Elev.	Sample No.	Hammer Blows per 6" on Sampler	Hammer Blows per 12" on Casing
Split Spoon - 2" O.D. Hammer - 140" Drop - 30"					
Classification					
Barge Well	445.1				
Water					
Drum fine to coarse sd. & organic matter, wet - loose	423.1	422.1	1	11	10
Drum fine to coarse sd. & gravel, wet - medium dense	416.0	414.1	2	11	10
Drum fine sd., wet - dense	411.0	409.1	3	11	10
Drum fine to coarse sd. w/ fine gravel, wet - loose	405.0	403.1	4	11	10
Drum fine to medium sd., wet - medium dense	400.0	399.1	5	11	10
Drum fine to medium sd. w/ fine gravel, wet - very dense	395.0	394.1	6	11	10
Drum fine to coarse sd. & fine gravel, wet - dense	392.0	389.1	7	11	10
Drum fine to coarse sd., wet - dense to very dense	384.1	384.1	8	11	10
Coarse gravel & cobbles, wet - dense	379.0	379.0	9	11	10
Drum fine to coarse sd. & gravel, wet - very dense	374.8	374.1	10	11	10
Layered gray medium shale & limestone	368.5	368.5	11	11	10
gray shale & limestone	363.5	363.5	12	11	10

**BORING-6**  
Sta. 597+392-673' L.I.

Casing - 3.5" I.D. Hammer - 300" Drop 24"	Stratum Elev.	Sample Elev.	Sample No.	Hammer Blows per 6" on Sampler	Hammer Blows per 12" on Casing
Split Spoon - 2" O.D. Hammer - 140" Drop - 30"					
Classification					
Barge Well	444.7				
Water					
Brown fine to coarse sd. & gravel, cinders & organic matter, wet - loose	420.7	419.7	1	14	10
Brown fine to coarse sd., wet - medium dense	415.7	413.7	2	14	10
Brown fine to coarse sd. w/ some coarse gravel, wet - very dense	408.8	408.7	3	14	10
Brown fine to medium sd., wet - medium dense	398.7	398.7	4	14	10
Brown fine to coarse sd., wet - dense	393.7	393.7	5	14	10
Brown fine to coarse sd. & gravel, wet - very dense	388.7	388.7	6	14	10
Brown fine to coarse sd. & gravel, wet - very dense	383.7	383.7	7	14	10
Brown fine to coarse sd. & gravel, wet - very dense	378.7	378.7	8	14	10
Layered gray medium shale & limestone	374.2	374.2	9	14	10
gray shale & limestone	368.0	368.0	10	14	10
gray shale & limestone	361.0	361.0	11	14	10
gray shale & limestone	356.0	356.0	12	14	10
gray shale & limestone	351.0	351.0	13	14	10
gray shale & limestone	346.0	346.0	14	14	10

**BORING-7**  
Sta. 589+462-237' R.I.

Casing - 3.5" I.D. Hammer - 300" Drop 24"	Stratum Elev.	Sample Elev.	Sample No.	Hammer Blows per 6" on Sampler	Hammer Blows per 12" on Casing
Split Spoon - 2" O.D. Hammer - 140" Drop - 30"					
Classification					
Barge Well	444.0				
Water					
Gray clayey silt w/ fine to coarse sand & gravel, wet - dense	431.8	428.8	1	17	10
Gray fine to coarse sand & gravel, wet - very dense	427.7	423.8	2	17	10
Gray fine to coarse sand, wet - medium dense	418.8	413.8	3	17	10
Gray fine to coarse sand & gravel, wet - medium dense	409.1	408.8	4	17	10
Gray fine sand, wet - med. dense	404.7	403.8	5	17	10
Brown fine to medium sand & fine gravel, wet - medium dense	398.0	393.0	6	17	10
Brown fine sand, wet - dense	389.0	388.0	7	17	10
Brown fine to coarse sand & fine gravel, wet - very dense	384.3	381.4	8	17	10
Gray fine to coarse sand & fine gravel & limestone fragments, wet - very dense	378.8	377.9	9	17	10
Coarse gravel & cobbles, wet - dense	373.9	372.2	10	17	10
Layered gray medium shale & limestone	367.4	367.4	11	17	10
gray shale & limestone	362.8	362.8	12	17	10
Layered gray medium shale & limestone	357.9	357.9	13	17	10
gray shale & limestone	353.0	353.0	14	17	10
gray shale & limestone	348.0	348.0	15	17	10

**BORING-8**  
Sta. 589+47-68' L.I.


Casing - 3.5" I.D. Hammer - 300" Drop 24"	Stratum Elev.	Sample Elev.	Sample No.	Hammer Blows per 6" on Sampler	Hammer Blows per 12" on Casing
Split Spoon - 2" O.D. Hammer - 140" Drop - 30"					
Classification					
Barge Well	445.4				
Water					
Gray silty clay w/ fine to coarse gravel, wet - soft	431.9	430.9	1	11	20
Brown fine to coarse sand & gravel, wet - medium dense	424.4	419.4	2	11	20
Drum fine to coarse sand, wet - medium dense	418.4	414.4	3	11	20
Brown fine to coarse sand & fine gravel, wet - medium dense to dense	404.0	399.4	4	11	20
Brown silty fine to coarse sand & fine gravel, wet - very dense	389.9	384.4	5	11	20
Layered gray medium shale & limestone	379.4	372.7	6	11	20
gray shale & limestone	367.7	367.7	7	11	20

For Notes, see Sheet No. 7

Drwg. No. 14355

COMMONWEALTH OF KENTUCKY  
DEPARTMENT OF HIGHWAYS  
FRANKFORT  
COUNTY OF KENTON  
**BORINGS 5, 6, 7 & 8**  
COVINGTON - CINCINNATI OHIO RIVER BRIDGE  
ROAD - COVINGTON - LEXINGTON  
STATION 589+740 TO 602+10.5 PROJECT NO. 175-B  
MODJESKI & MASTERS, ENGINEERS  
HARRISBURG, PENNSYLVANIA

TEST BORINGS  
DRILLED IN 1958  
BY H.C. NUTTING CO.



**H.C. NUTTING COMPANY**  
CORPORATE OFFICE - 611 LUNKEN PARK DRIVE  
CINCINNATI, OHIO 45226  
(613) 321-5816  
EMPLOYEE OWNED  
GEOTECHNICAL, ENVIRONMENTAL AND TESTING ENGINEERS  
**EXISTING BRIDGE DATA ( B-5 To B-8 )**  
CLIENT: PARSONS BRINCKERHOFF  
PROPOSED QUEENSGATE ALIGNMENT  
BRENT SPENCE BRIDGE REPLACEMENT  
W.O. 10974.054  
JUNE 2007

**BORING-9**  
Sta 539+07.2, 22.4 RL.

Casing 35" I.D. Hammer 300" Drop 24"	Shelby Elev.	Sample Elev.	Sample No.	Hammer Blows per Ft. on Casing	Hammer Blows per Ft. on Shelby
Split Spoon 2" O.D. Hammer 140" Drop 30"					
Classification					
Barge well	4448				
Water	4420				
Br silty clay with organic matter, wet-very soft	4327	4327	1		
Br silty clay with organic matter, wet-soft	4328	4328	2		
Br fine to coarse sand & fine gravel, wet-medium dense	4280	4280	3		
Br fine to coarse sand & fine gravel, wet-medium dense	4286	4286	4		
Br fine to coarse sand & fine gravel, wet-medium dense	4130	4130	5		
Br fine to medium sand & fine gravel, wet-med dense	4136	4136	6		
Br fine sand, wet-medium dense	4098	4098	7		
Br fine to medium sand & fine gravel, wet-med dense to very dense	4010	4010	8		
Br fine sand with coarse gravel, moist-very dense	3990	3990	9		
Br fine sand with coarse gravel, moist-very dense	3870	3870	10		
Br fine to coarse sand & gravel, moist-very dense	3886	3886	11		
Gray fine to coarse sand & gravel, wet-very dense	3838	3838	12		
Laminated gray limestone (gray shale approx 45-50% limestone in 1 1/2' layers)	3749		13	NX	78%
Laminated gray limestone (gray shale approx 25-30% limestone in 1 1/2' layers)	3698				
Laminated gray limestone (gray shale approx 40-45% limestone in 1 1/2' layers)	3632				

**BORING-10**  
Sta 529+07.5, 68.5' L.I.

Casing 35" I.D. Hammer 300" Drop 24"	Shelby Elev.	Sample Elev.	Sample No.	Hammer Blows per Ft. on Casing	Hammer Blows per Ft. on Shelby
Split Spoon 2" O.D. Hammer 140" Drop 30"					
Classification					
Barge well	4445				
Water	4418				
Gray silty clay with organic matter, wet-very soft	4335	4335	1		
Gray silty clay with organic matter, wet-soft	4325	4325	2		
Gray silty clay w/ fine sand lenses & gravel, wet-soft	4285	4285	3		
Gray fine to coarse sand & gravel, wet-dense	4235	4235	4		
Br fine to coarse sand & fine gravel, wet-med dense	4185	4185	5		
Br fine to coarse sand & fine gravel, wet-med dense	4135	4135	6		
Br fine sand, wet-medium dense	4085	4085	7		
Br fine to medium sand, wet-dense	4025	4025	8		
Br fine sand with fine to coarse gravel, moist-very dense	3985	3985	9		
Br fine sand with fine to coarse gravel, moist-very dense	3905	3905	10		
Br fine to coarse sand & gravel, limestone fragments, wet-very dense	3890	3890	11		
Br fine to coarse sand & gravel, limestone fragments, wet-very dense	3835	3835	12		
Br fine to coarse sand & gravel, limestone fragments, wet-very dense	3795	3795	13		
Laminated gray weathered shale & limestone approx 30-35% limestone in 1 1/2' layers	3752		K	NX	80%
Laminated gray weathered shale & limestone approx 40-45% limestone in 1 1/2' layers	3652		L	NX	87%

**BORING-11**  
Sta 584+74.0, 17' L.I.

Casing 35" I.D. Hammer 300" Drop 24"	Shelby Elev.	Sample Elev.	Sample No.	Hammer Blows per Ft. on Casing	Hammer Blows per Ft. on Shelby
Split Spoon 2" O.D. Hammer 140" Drop 30"					
3" Shelby Tube					
Classification					
Brown silty clay and cinders, fill, moist-medium dense	486.5	485.6	1		
Brown silty clay and cinders, fill, moist-medium dense	481.5	480.6	2		
Cinders, fill, moist-loose	473.6	472.6	3		
Cinders, fill, moist-loose	470.6	469.6	4		
Cinders, fill, wet-loose	466.6	465.6	5		
Cinders, fill, wet-loose	461.6	460.6	6		
Gray silty clay with organic matter, wet-soft	455.5	453.6	7		
Gray silty clay with organic matter, wet-soft	450.6	448.6	8		
Gray silty clay with organic matter, still lenses, wet-soft	446.6	444.6	9		
Gray fine sandy silt, wet-medium dense	441.6	440.6	10		
Gray sandy clay with layers of fine sand and fine gravel, wet-soft	439.6	438.6	11		
Gray sandy clay with layers of fine sand and fine gravel, wet-soft	431.6	430.6	12		
Brown fine to coarse sand and fine gravel, wet-med dense to very dense	425.6	424.6	13		
Brown fine to coarse sand and fine gravel, wet-med dense to very dense	420.6	419.6	14		
Brown fine to coarse sand and fine gravel, wet-med dense to very dense	415.6	414.6	15		
Brown fine to coarse sand and fine gravel, wet-med dense to very dense	410.6	409.6	16		
Brown fine to medium sand & fine gravel, wet-med dense to very dense	405.6	404.6	17		
Brown fine to medium sand & fine gravel, wet-med dense to very dense	400.6	399.6	18		
Brown fine to medium sand & fine gravel, wet-med dense to very dense	395.6	394.6	19		
Brown fine to coarse sand & gravel, wet-very dense	391.6	390.6	20		
Brown fine to coarse sand & gravel, wet-very dense	387.6	386.6	21		
Brown fine to coarse sand & gravel, wet-very dense	382.6	381.6	22		
Ground-water elev. = 466.6					

Undisturbed Shelby Tube Samples

Sample No.	Elev.	Dead Weight (Tools etc.)	Hydraulic Pressure	Total Pressure	Time (Sec)
S1	456.6-493.5	338*	0*	398*	8
	455-484.5	338*	440*	830*	
S2	441.6-448.6	450*	0*	450*	
	440.6-438.6	450*	3420*	3870*	12

**BORING-12**  
Sta 584+74.0-63' L.I.

Casing 35" I.D. Hammer 300" Drop 24"	Shelby Elev.	Sample Elev.	Sample No.	Hammer Blows per Ft. on Casing	Hammer Blows per Ft. on Shelby
Split Spoon 2" O.D. Hammer 140" Drop 30"					
3" Shelby Tube					
Classification					
Gray silty clay cinders & fine gravel, fill, wet-soft	483.3	482.3	1		
Brown silty clay cinders, fill, moist-stiff	478.3	477.3	2		
Brown silty clay cinders, fine gravel & shale frag. ments, fill, moist-stiff	473.3	472.3	3		
Cinders & brown silty clay, fill, wet-very loose	469.3	468.3	4		
Cinders, fill, wet-loose	464.3	463.3	5		
Gray silty clay with organic matter, wet-soft	458.3	457.3	6		
Gray silty clay with organic matter, wet-soft	453.3	452.3	7		
Gray silty clay to brown & gray silty clay with fine gravel, moist-med-stiff	448.3	447.3	8		
Brown & gray sandy clay with fine gravel, wet-soft	443.3	442.3	9		
Gray clayey fine to coarse sand & fine gravel, wet-medium dense	438.3	437.3	10		
Brown silty fine to coarse sand & gravel, wet-dense	433.3	432.3	11		
Brown silty fine to coarse sand & gravel, wet-dense	428.3	427.3	12		
Brown silty fine to coarse sand & gravel, wet-dense	423.3	422.3	13		
Brown silty fine to coarse sand & gravel, wet-dense	418.3	417.3	14		
Brown silty fine to coarse sand & gravel, wet-dense	413.3	412.3	15		
Brown silty fine to coarse sand & gravel, wet-dense	408.3	407.3	16		
Brown silty fine to coarse sand & gravel, wet-dense	403.3	402.3	17		
Brown silty fine to coarse sand & gravel, wet-dense	398.3	397.3	18		
Brown silty fine to coarse sand & gravel, wet-dense	393.3	392.3	19		
Brown silty fine to coarse sand & gravel, wet-dense	388.3	387.3	20		
Brown silty fine to coarse sand & gravel, wet-dense	383.3	382.3	21		
Brown silty fine to coarse sand & gravel, wet-dense	378.3	377.3	22		
*For 0.25" penetration					
Ground-water elev. = 464.3					

Undisturbed Shelby Tube Samples

Sample No.	Elev.	Dead Weight (Tools etc.)	Hydraulic Pressure	Total Pressure	Time (Sec)
S1	459.3-489.3	346*	320*	926*	10
	458.3-457.3	346*	1220*	1566*	
S2	449.3-448.3	398*	1730*	2177*	
	448.3-447.3	398*	2720*	3118*	14

**SOIL TEST DATA**


Sample No.	Elevation	% Sand, s-1 & Clay	% Moisture	Natural (or Wet) Weight for Cu 11 lbs., Cu 11	Unconfined Compressive Strength	Failure Strain	Atterberg Limits	Consolidation U.S.C.S.	Classification AASHTO
<b>BORING-11</b>									
S1	485.6	32.9	113.5	2130	11.8	44.7%	23.9%	CL	A7-6
<b>BORING-12</b>									
S2	480.3	24.7	12.3	5130	9.8	38.6%	22.8%	CL	A6

For Notes, see Sheet No. 7.

Drwg. No. 14355

COMMONWEALTH OF KENTUCKY  
DEPARTMENT OF HIGHWAYS  
FRANKFORT COUNTY OF KENTON  
**BORINGS 9, 10, 11, & 12**  
COVINGTON-CINCINNATI OHIO RIVER BRIDGE  
ROAD COVINGTON-LEXINGTON  
STATION 584+74.0 TO 62+10.5 PROJECT NO. 175-B  
MOJESKI & MASTERS ENGINEERS  
HARRISBURG, PENNSYLVANIA  
NO. 8

TEST BORINGS  
DRILLED IN 1958  
BY H.C. NUTTING CO.



**H.C. NUTTING COMPANY**  
CORPORATE OFFICE - 611 LUNKEN PARK DRIVE  
CINCINNATI, OHIO 45226  
(513) 321-5816  
EMPLOYEE OWNED  
GEOTECHNICAL, ENVIRONMENTAL AND TESTING ENGINEERS  
**EXISTING BRIDGE DATA (B-9 TO B-12)**  
CLIENT: PARSONS BRINCKERHOFF  
PROPOSED QUEENSGATE ALIGNMENT  
BRENT SPENCE BRIDGE REPLACEMENT  
W.O. 10974.054  
JUNE 2007 **FIGURE 4C**

**Geotechnical Engineering Report**

Brent Spence Bridge Replacement ■ Cincinnati, Ohio-Covington, Kentucky

March 11, 2011 ■ HCN/Terracon Project No. N1105070



**EXHIBIT A-9**  
**QUEENSGATE ALIGNMENT**  
**TEST BORING LOGS (2007)**



W.D. 10974.054

State of Ohio  
Department of Transportation  
Division of Highways  
Testing Laboratory



Date Started 9/28/06  
Date Completed 10/3/06  
Sampler: Type 3  
Core Barrels Type N 3905 20.0"  
SS 5 HSA 1.375" I.D.  
NO/ANX Size 2" O.D.  
LOG OF BORING  
Project Identification: HAM-71/75-0.00/0.22  
Brent Spence Queensgate Alignment  
Preliminary Geotechnical Study  
Cincinnati/Covington, OH/KY  
Surface Elev. 487.5 ft

Elev. (ft)	Depth (ft)	Sd. ROD	Pm./ ROD	Latitude/Longitude	Rec. (ft)	Loss (ft)	FID (cm v/v)	Description	Sample No.	Physical Characteristics							ODOT Class	
										X Agg	X C.S.	X F.S.	X Silt	X Clay	L.L.	P.L.		W.C.
487.5	0							0 - 2.5 [2.5] Dark brown sandy silt and brick fragments, some sand, little clinters (FILL), moist-silty/loose	1	-	-	-	-	-	-	-	-	VISUAL
485.0	2							2.5 - 3 [0.5] Dark brown sandy silt, trace clinters and brick fragments (FILL), moist-very stiff	2	-	-	-	-	-	-	-	-	VISUAL
483.5	4							3 - 7.5 [4.5] Brown clay, trace sand and root matter (ALUMINUM), slightly moist-very stiff to stiff	3	0	0	10	34	56	44	19	19	A-7-9(12)
480.0	8							7.5 - 17.5 [10] Brown SILTY CLAY, trace to little sand (ALUMINUM), moist-medium stiff to stiff	4	-	-	-	-	-	-	-	-	VISUAL
	10								5	0	0	9	44	47	36	16	18	A-6A(10)
	12								6	-	-	-	-	-	-	-	-	VISUAL
	14								7	-	-	-	-	-	-	-	-	VISUAL
	16									-	-	-	-	-	-	-	-	VISUAL
470.0	18							17.5 - 30 [12.5] Brown SILT AND CLAY, some sand (ALUMINUM), very moist-medium stiff to very soft ---Occasional wet sand/silt seams	8	-	-	-	-	-	-	-	-	VISUAL
	20								9	-	-	-	-	-	-	-	-	VISUAL
	22								10	-	-	-	-	-	-	-	-	VISUAL
	24									-	-	-	-	-	-	-	-	VISUAL
	26								11	0	1	20	39	40	31	12	29	A-6(9)
	28									-	-	-	-	-	-	-	-	VISUAL
457.5	30							30 - 42 [12] Grey SANDY SILT (ALUMINUM), very moist-very soft to medium stiff ---Occasional wet sand/silt seams	12	-	-	-	-	-	-	-	-	VISUAL
	32									-	-	-	-	-	-	-	-	VISUAL
	34									-	-	-	-	-	-	-	-	VISUAL
445.5	36								13	0	0	30	36	34	30	10	32	A-4(7)
	38									-	-	-	-	-	-	-	-	VISUAL
	40								14	-	-	-	-	-	-	-	-	VISUAL
445.5	42							42 - 45 [3] Brown GRAVEL WITH SAND AND SILT, little rock fragments (OUTWASH), wet-medium dense	15	-	-	-	-	-	-	-	-	VISUAL
	44									-	-	-	-	-	-	-	-	VISUAL
442.5	46							45 - 50 [5] Brown COARSE AND FINE SAND, little gravel (OUTWASH), wet-very loose	16	-	-	-	-	-	-	-	-	VISUAL
	48									-	-	-	-	-	-	-	-	VISUAL
437.5	50							50 - 55 [5] Brown GRAVEL WITH SAND AND SILT, little rock fragments (OUTWASH), wet-medium dense	17	51	12	8	-29-	0	0	-	-	A-2-4(0)
	52									-	-	-	-	-	-	-	-	VISUAL
	54									-	-	-	-	-	-	-	-	VISUAL
432.5	56							55 - 60 [5] Brown GRAVEL WITH SAND (OUTWASH), wet-dense	18	-	-	-	-	-	-	-	-	VISUAL
	58									-	-	-	-	-	-	-	-	VISUAL
427.5	60							60 - 60.5 [0.5] Brown GRAVEL WITH SAND AND SILT (OUTWASH), wet-medium dense	19	25	17	27	-3-	0	0	-	-	A-2-4(0)
422.0	62							60.5 - 65 [4.5] Grey SHALE, moist-soft	19A	-	-	-	-	-	-	-	-	VISUAL
	64									-	-	-	-	-	-	-	-	VISUAL
422.5	66							65 - 81.5 [16.3] Interbedded SHALE AND LIMESTONE Shale is grey, medium tough to tough, calcareous, occupies 71% of matrix, Limestone is light grey, hard, fossiliferous and argillaceous, evenly distributed in 1/2" to 9" layers, occupies 29% of matrix.	20	-	-	-	-	-	-	-	-	VISUAL
	68								21	-	-	-	-	-	-	-	-	VISUAL
	70									-	-	-	-	-	-	-	-	VISUAL
	72								22	-	-	-	-	-	-	-	-	VISUAL
	74									-	-	-	-	-	-	-	-	VISUAL
	76								23	-	-	-	-	-	-	-	-	VISUAL
	78									-	-	-	-	-	-	-	-	VISUAL
	80									-	-	-	-	-	-	-	-	VISUAL
406.2	82							81.5 - 85.6 [2.3] Grey SHALE, tough, calcareous, occasional limestone seams (less than 1/4"), soft zone from 83.5" to 83.6"	24	-	-	-	-	-	-	-	-	VISUAL
403.9	84							83.6 - 93.1 [9.5] Interbedded SHALE AND LIMESTONE Shale is grey, tough, calcareous, occupies 52% of matrix, Limestone is light grey, hard, occasionally argillaceous and shaly, evenly distributed in 1/4" to 9" layers, occupies 48% of matrix.	25	-	-	-	-	-	-	-	-	VISUAL
	86									-	-	-	-	-	-	-	-	VISUAL
	88									-	-	-	-	-	-	-	-	VISUAL
	90									-	-	-	-	-	-	-	-	VISUAL
	92								26	-	-	-	-	-	-	-	-	VISUAL
394.4	94							93.1 - 94.9 [1.8] Light grey LIMESTONE, hard, argillaceous, occasionally fossiliferous, occasional shale seams (less than 1/4")	27	-	-	-	-	-	-	-	-	VISUAL
392.6	96							94.9 - 110.1 [15.2] Interbedded SHALE AND LIMESTONE Shale is grey, tough, calcareous, occupies 51% of matrix, Limestone is light grey, hard, occasionally argillaceous, shaly, and fossiliferous, evenly distributed in 1/4" to 10" layers, occupies 49% of matrix.	28	-	-	-	-	-	-	-	-	VISUAL
	98									-	-	-	-	-	-	-	-	VISUAL
	100									-	-	-	-	-	-	-	-	VISUAL
	102								29	-	-	-	-	-	-	-	-	VISUAL
	104									-	-	-	-	-	-	-	-	VISUAL
	106									-	-	-	-	-	-	-	-	VISUAL
	108									-	-	-	-	-	-	-	-	VISUAL
377.4	110									-	-	-	-	-	-	-	-	VISUAL

W.O. 10974.054

State of Ohio  
Department of Transportation  
Division of Highways  
Testing Laboratory

LOG OF BORING

Date Started 11/30/06 Date Completed 11/30/06 Sampler: Type \_\_\_\_\_ Core Barret: Type \_\_\_\_\_  
 SS 5' HSA Dia. 1.375" Water Elev. 453.0 Ft. Project Identification: HAM-71/75-0.00/0.22  
 NG/NX Size 2" O.D. Core Barret: Length \_\_\_\_\_ Preliminary Geotechnical Study  
 Boring No. B-3 Latitude/Longitude N 39°05'24.3" / W 84°31'32.9" Surface Elev. 458.0 ft. Cincinnati/Covington, OH/KY

Elev. (ft)	Depth (ft)	Std. Pen./RQP	Rec. (ft)	Loss (ft)	FID (ppm v/v)	Description	Sample No.	Physical Characteristics					ODOT Class						
								% Agg	% C.S.	% F.S.	% Silt	% clay		P.I.	W.C.				
458.0	0					0 - 5 [5] Barge Platform													
453.0	2																		
	4																		
	6																		
	8																		
	10																		
	12																		
	14																		
	16																		
	18																		
	20																		
	22																		
	24																		
	26																		
	28																		
429.0	30	70 / 50/0.3'	0.8		7/3	29 - 30.5 [1.5] Gray SHALE, some limestone fragments/layers, wet-medium tough	1											Visual	
427.5	32	RQD = 0	1.2	3.3		30.5 - 35.2 [4.7] Dark gray SHALE, soft to medium tough, calcareous, highly fractured	2											Visual	
	34																		
422.8	36	RQD = 64	9.6	0.4		35.2 - 75 [39.8] Interbedded SHALE AND LIMESTONE: Shale is gray, medium to very tough, calcareous, occasional soft/fractured zones up to 2" thick, occupies 65% of matrix. Limestone is light gray and gray, hard, occasionally fossiliferous and shaly, vertical fracture @ 47.6, very steep fracture @ 57.3, 1/16" to 1/8" cavities @ 72.2, evenly distributed in 1/2" to 6 1/2" layers, occupies 31% of matrix.	3											Visual	
	38																		
	40																		
	42																		
	44																		
	46	RQD = 70	10.0	0.0			4												Visual
	48																		
	50																		
	52																		
	54																		
	56	RQD = 86	9.8	0.2			5												Visual
	58																		
	60																		
	62																		
	64																		
	66	RQD = 91	10.0	0.0			6												Visual
	68																		
	70																		
	72																		
383.0	74																		

Boring completed at 75.0 feet

Particle Sizes: Agg => 2.00mm, Coarse Sand = 2.00-0.42mm, Fine Sand = 0.42-0.074mm, Silt = 0.074-0.005mm, Clay =< 0.005mm.

State of Ohio  
Department of Transportation  
Division of Highways  
Testing Laboratory

W.O. 10974.054

Date Started 11/29/06 Sampler: Type \_\_\_\_\_  
 Date Completed 11/30/06 Casing: Length \_\_\_\_\_  
 Core Barrel: Type \_\_\_\_\_  
 Project Identification: HAM-71/75-0.00/0.22  
 Brent Spence Queensgate Alignment  
 Preliminary Geotechnical Study  
 Cincinnati/Covington, OH/KY  
 SS \_\_\_\_\_ Dia. 1.375" Water Elev. 453.0 Ft.  
 5' HSA Dia. 3.375" I.D.  
 NQ/NX Size 2" O.D.  
 Boring No. B-4 Latitude/Longitude N 39°05'37.4" / W 84°31'35.9" Surface Elev. 458.0 ft

Elev. (ft)	Depth (ft)	Std. Pen./ROD	Rec. (ft)	Loss (ft)	FID (ppm v/v)	Description	Sample No.	Physical Characteristics					ODOT Class								
								% Agg	% C.S.	% F.S.	% Silt	% Clay		L.L.	P.I.	W.C.					
459.0	0					0 - 5 [5] Barge platform															
453.0	6					5 - 32.5 [27.5] Water (Ohio River)															
425.5	32	41	0.5			32.5 - 33 [0.5] Brown GRAVEL WITH SAND, some silt (OUTWASH), saturated-very dense	1A													Visual	
425.0	34	36 / 101	1.0		80/3	33 - 35.3 [2.3] Gray SHALE (thin limestone fragments, wet, medium tough)	1B													Visual	
422.7	36	50/0.3	1.2	0.9		Interbedded SHALE AND LIMESTONE; Shale is dark gray to gray, medium to very tough, calcareous, occasional soft fractured zones up to 2" thick, occupies 25% of matrix. Limestone is light gray, hard, occasionally to frequently shaley, fossiliferous from 80' to 82.3', evenly distributed in 1/4" to 10" layers, occupies 25% of matrix.	2													Visual	
	38	ROD = 72	5.0	0.0			3														Visual
	40						4														Visual
	42	ROD = 75	10.0	0.0			5														Visual
	44																				
	46																				
	48																				
	50																				
	52																				
	54	ROD = 61	9.8	0.2			6														Visual
	56																				
	58																				
	60																				
	62	ROD = 82	4.9	0.1			7														Visual
	64																				
	66																				
	68	ROD = 84	4.4	0.5			8														Visual
	70																				
	72	ROD = 87	10.0	0.0			9														Visual
	74																				
	76																				
	78																				
	80																				
375.7	82																				

Boring completed at 82.3 feet

Particle Sizes: Agg => 2.00mm, Coarse Sand = 2.00-0.42mm, Fine Sand = 0.42-0.074mm, Silt = 0.074-0.005mm, Clay =< 0.005mm.



Date Started 10/4/06  
Date Completed 10/6/06  
Boring No. B-5  
SS Dia. 1.375" I.D.  
5" HSA Dia. 3.375" I.D.  
SS Dia. 1.375" I.D.  
5" HSA Dia. 3.375" I.D.  
LOG OF BORING  
Water Elev. Immediate 461.5 Ft.  
Surface Elev. 491.5 ft

Project Identification HAM-71/75-0.00/0.22  
Brent Spence Quarzite Alignment  
Preliminary Geotechnical Study  
Chadron/Cedarhurst, OH/KY

Elev. (ft)	Depth (ft)	Silt, %	Pct. Finer, %	Liquidity/Plasticity	Cone Resist. (tsf)	Pen. (in)	Roc. (ft)	Sample No.	Description	Physical Characteristics										Visual Class			
										% Ag.	% C.S.	% F.S.	% Clay	L.L.	P.L.	W.C.							
491.5	0							1	Black soil (FILL), moist-very dense													VSUAL	
486.5	2							2														VSUAL	
481.5	4							3	Grey gravel and red brick fragments, some sand (FILL), moist-very dense to medium dense													VSUAL	
471.5	6							4														VSUAL	
466.5	8							5	10 - 20 [10] Black coal and grey gravel, trace brick fragments (FILL), moist-medium dense to very loose													VSUAL	
461.5	10							6	20 - 25 [5] Dark brown sandy silt, trace gravel, chiders, and brick fragments (FILL), moist-medium stiff —Petroleum odor from 20' to 21.5'													VSUAL	
456.5	12							7	25 - 30 [5] Black soil, trace gravel (FILL), moist-very loose													VSUAL	
451.5	14							8	30 - 35 [5] Dark brown sandy silt, trace organics and chiders (FILL), very moist-stiff —Organic odor													A-4d(3)	
446.5	16							9	35 - 40 [5] Dark brown and grey SILT AND CLAY, some sand, trace gravel and organics (ALUMINUM), very moist-medium stiff													VSUAL	
441.5	18							10	40 - 45 [5] Dark grey SILT AND CLAY, some organics and wood fragments (ALUMINUM), moist-medium stiff —Loss-on-ignition=21%													VSUAL	
436.5	20							11	45 - 55 [10] Dark brown and grey SANDY SILT, trace organics (ALUMINUM), very moist-stiff to medium stiff													VSUAL	
431.5	22							12	50 - 60 [5] Dark brown SANDY SILT, little gravel, trace wood fragments (ALUMINUM), very moist-stiff —Loss-on-ignition=8%													VSUAL	
426.5	24							13	55 - 65 [5] Brown GRAVEL and sand (OUTWASH), wet-very dense to medium dense													VSUAL	
421.5	26							14	60 - 65 [5] Interbedded SHALE AND LIMESTONE. Shale is grey, medium tough to tough, calcareous, completely softened from 79.5' to 74.5', occupies 55% of matrix. Limestone is light grey, hard, frequently fossiliferous and argillaceous, evenly distributed in 1/4" to 7/8" layers, occupies 45% of matrix.														VSUAL
416.5	28							15	65 - 75 [10] Brown to grey GRAVEL, some sand (OUTWASH), wet-very dense to medium dense													VSUAL	
392.5	30							16	80 - 85 [2.2] Grey SHALE, tough, calcareous													VSUAL	
390.3	32							17	101.2 - 120.7 [19.5] Interbedded SHALE AND LIMESTONE. Shale is grey, tough, calcareous, softened from 109.5' to 104.5', occupies 57% of matrix. Limestone is light grey, hard, occasionally fossiliferous and argillaceous, evenly distributed in 1/2" to 12 1/2" layers, occupies 43% of matrix.														VSUAL

Boring completed at 120.7 feet

Particle Sizes Agg >= 2.00mm, Coarse Sand = 2.00-0.42mm, Fine Sand = 0.42-0.075mm, SW = 0.074-0.005mm, Clay <= 0.005mm.

W.O. 10974.054

State of Ohio  
Department of Transportation  
Division of Highways  
Testing Laboratory

1/8

Project Identification: HAM-71/75-0.00/0.22  
Brent Spence Queensgate Alignment  
Preliminary Geotechnical Study  
Cincinnati/Covington, OH/KY

LOG OF BORING  
SS Dia. 1.375" I.D. Water Elev. Immediate 462.1 Ft.  
5" HSA Dia. 3.375" I.D.  
NO/NK Size 2" O.D.

Date Started 10/2/06 Sampler Type  
Date Completed 10/3/06 Coating Length  
Core Barrel Type  
Boring No. B-6 Latitude/Longitude N 39°05'45.3" / W 84°31'37.9" Surface Elev. 487.1 ft

Elev. (ft)	Depth (ft)	Sid. Pen. ROD	Rec. (ft)	Loss (ft)	FID (ppm v/v)	Description	Sample No.	Physical Characteristics										OOOT Class
								K Agg	X C.S.	X F.S.	X Sil	X clay	LL	P.I.	W.C.			
487.1	0	7 / 24 / 8	1.5		22/12	0 - 5 [5] Dark brown silt and clay with brick fragments, little sand and cinders, trace organics (FILL), moist-hard	1	-	-	-	-	-	-	-	-	-	18	VISUAL
487.1	2	17 / 21 / 21	1.5		13		2	-	-	-	-	-	-	-	-	-	-	VISUAL
482.1	4	3 / 2 / 3	1.5		6	5 - 12.5 [7.5] Dark brown sandy silt, trace gravel, cinders, and brick fragments (FILL), moist-medium stiff	3	3	1	24	40	32	24	7	18	A-4c(7)	VISUAL	
474.6	6	SHELBY TUBE	2.0		<1		4	-	-	-	-	-	-	-	-	27	VISUAL	
	8	2 / 2 / 5	1.5		<1		5	-	-	-	-	-	-	-	-	27	VISUAL	
474.6	10	2 / 4 / 5	0.3		6	12.5 - 18 [6.5] Brown and trace grey SILT AND CLAY, trace sand and gravel (ALLUVIUM), moist-stiff to medium stiff	6	1	4	42	52	57	15	25	A-6a(10)	25	VISUAL	
	12	2 / 3 / 5	1.5		<1		7	-	-	-	-	-	-	-	-	24	VISUAL	
487.1	14	SHELBY TUBE	2.0		<1		8	0	28	39	33	27	9	24	A-4c(7)	24	VISUAL	
	16	2 / 2 / 3	1.5		<1		9	-	-	-	-	-	-	-	-	26	VISUAL	
482.1	18	WOH / WOH /	1.5		4	18 - 25 [7] Brown SANDY SILT (ALLUVIUM), moist-medium stiff	8	0	1	43	-56-	0	0	-	-	A-4c(4)	-	VISUAL
	20						10	0	1	17	46	36	29	9	28	A-4c(8)	-	VISUAL
487.1	22	2 / 1 / 1	1.5		<1	30 - 35 [5] Brown SANDY SILT (ALLUVIUM), wet-very loose	11	0	1	46	36	29	9	28	A-4c(8)	-	VISUAL	
	24						12	-	-	-	-	-	-	-	-	28	VISUAL	
452.1	26	2 / 1 / 2	1.5		<1	35 - 40 [5] Grey SANDY SILT (ALLUVIUM), very moist-soft	12	-	-	-	-	-	-	-	-	28	VISUAL	
	28						13	-	-	-	-	-	-	-	-	-	VISUAL	
447.1	30	3 / 3 / 4	0.8		<1	40 - 50 [10] Brown GRAVEL WITH SAND, little clay (OUTWASH), wet-loose to medium dense	13	-	-	-	-	-	-	-	-	-	VISUAL	
	32						14	50	29	10	-11-	0	0	-	-	A-1-b(0)	-	VISUAL
	34	8 / 6 / 7	1.5		<1		14	50	29	10	-11-	0	0	-	-	A-1-b(0)	-	VISUAL
	36						15	17	25	41	-17-	0	0	-	-	A-3c(0)	-	VISUAL
487.1	38	11 / 11 / 18	1.5		<1	50 - 60 [10] Brown COARSE AND FINE SAND, little silt and clay, trace gravel (OUTWASH), wet-medium dense	15	17	25	41	-17-	0	0	-	-	A-3c(0)	-	VISUAL
	40						16	-	-	-	-	-	-	-	-	-	VISUAL	
426.6	42	15 / 14 / 11	1.2		3	60 - 60.5 [0.5] Grey SHALE, moist-soft	16	-	-	-	-	-	-	-	-	-	VISUAL	
	44						17	-	-	-	-	-	-	-	-	-	VISUAL	
427.1	46	ROD = 0	0.5	0.8	65/5	60.5 - 82.8 [22.3] Interbedded SHALE AND LIMESTONE: Shale is grey, medium tough to tough, calcareous, occupies 75% of matrix, Limestone is light grey, occasionally fossiliferous and argillaceous, evenly distributed in 1/2" to 8" layers, occupies 25% of matrix.	17	-	-	-	-	-	-	-	-	-	VISUAL	
	48	ROD = 53	9.3	0.7			18	-	-	-	-	-	-	-	-	-	VISUAL	
	50						19	-	-	-	-	-	-	-	-	-	VISUAL	
	52						20	-	-	-	-	-	-	-	-	-	VISUAL	
	54	ROD = 90	9.2	0.8			20	-	-	-	-	-	-	-	-	-	VISUAL	
	56						21	-	-	-	-	-	-	-	-	-	VISUAL	
404.3	58	ROD = 100	10.0	0.0		82.8 - 85.6 [2.8] Grey SHALE, tough, calcareous	21	-	-	-	-	-	-	-	-	-	VISUAL	
	60						22	-	-	-	-	-	-	-	-	-	VISUAL	
401.5	62	ROD = 75	9.7	0.3		85.6 - 106.3 [20.7] Interbedded SHALE AND LIMESTONE: Shale is grey, tough, calcareous, softened from 93.5' to 93.9', occupies 40% of matrix, Limestone is light grey, hard, frequently fossiliferous, shaly, and argillaceous, evenly distributed in 1/2" to 10" layers, occupies 60% of matrix.	22	-	-	-	-	-	-	-	-	-	VISUAL	
	64						23	-	-	-	-	-	-	-	-	-	VISUAL	
	66						23	-	-	-	-	-	-	-	-	-	VISUAL	
	68						23	-	-	-	-	-	-	-	-	-	VISUAL	
	70						23	-	-	-	-	-	-	-	-	-	VISUAL	
	72						23	-	-	-	-	-	-	-	-	-	VISUAL	
	74						23	-	-	-	-	-	-	-	-	-	VISUAL	
	76						23	-	-	-	-	-	-	-	-	-	VISUAL	
	78						23	-	-	-	-	-	-	-	-	-	VISUAL	
	80						23	-	-	-	-	-	-	-	-	-	VISUAL	
	82						23	-	-	-	-	-	-	-	-	-	VISUAL	
	84						23	-	-	-	-	-	-	-	-	-	VISUAL	
	86						23	-	-	-	-	-	-	-	-	-	VISUAL	
	88						23	-	-	-	-	-	-	-	-	-	VISUAL	
	90						23	-	-	-	-	-	-	-	-	-	VISUAL	
	92						23	-	-	-	-	-	-	-	-	-	VISUAL	
	94						23	-	-	-	-	-	-	-	-	-	VISUAL	
	96						23	-	-	-	-	-	-	-	-	-	VISUAL	
	98						23	-	-	-	-	-	-	-	-	-	VISUAL	
	100						23	-	-	-	-	-	-	-	-	-	VISUAL	
	102						23	-	-	-	-	-	-	-	-	-	VISUAL	
	104						23	-	-	-	-	-	-	-	-	-	VISUAL	
380.8	106						23	-	-	-	-	-	-	-	-	-	VISUAL	

Boring completed at 106.3 feet

**Geotechnical Engineering Report**

Brent Spence Bridge Replacement ■ Cincinnati, Ohio-Covington, Kentucky

March 11, 2011 ■ HCN/Terracon Project No. N1105070



**EXHIBIT A-10**  
**ENVIRONMENTAL SCREENING RESULTS**

**PID Readings**

Parsons Brinckerhoff ■ Brent Spence Bridge Replacement ■ Cincinnati, Ohio  
 March 11, 2011 ■ HCN/Terracon Project No. N1105070

**ENVIRONMENTAL SCREENING RESULTS**

Boring	Sample Number	Reading (ppm-V/V)
L-1	1	2
L-1	2	<1
L-1	3	<1
L-1	4	-
L-1	5	<1
L-1	6	57/53
L-1	6A	53/13
L-1	7	<1
L-1	7A	<1
L-1	8	1
L-1	9	10/6
L-1	10	8
L-1	11	5
L-1	12	56/21
L-1	13	67/20
L-1	14	19/15
L-1	15	1
L-1	16	45/17
L-1	17	3
L-1	18	5
L-1	19	45/18
L-1	20	1
L-1	21	<1
L-1	22	25/14
L-1	23	77/27
L-1	24	14/12
L-1	25	9
L-1	26	69/16
L-1	27	15/5
L-1	28	8
L-1A	1	<1
L-1A	2	2
L-1A	3	23/22
L-1A	4	-
L-1A	5	45/23
L-1A	6	5

Boring	Sample Number	Reading (ppm-V/V)
L-1A	7	10/13
L-1A	8	-
L-1A	9	9
L-1A	9A	<1
L-1A	10	5
L-1A	11	<1
L-1A	12	82/1
L-1A	13	27/39
L-1A	14	<1
L-1A	15	<1
L-1A	16	<1
L-1A	17	<1
L-1A	18	24/22
L-1A	19	<1
L-1A	20	14/10
L-1A	21	16/1
L-1A	22	<1
L-1A	23	<1
L-1A	24	30/17
L-1A	25	<1
L-1A	26	20/13
L-1A	27	5
L-1A	28	55/17
L-1A	28A	37/40
L-2A	1	5
L-2A	2	3
L-2A	3	158/27
L-2A	4	16/<1
L-2A	5	3
L-2A	6	9
L-2A	7	-
L-2A	8	92/25
L-2A	9	30/20
L-2A	10	3900/3000
L-2A	11	430/514
L-2A	12	-

**PID Readings**

Parsons Brinckerhoff ■ Brent Spence Bridge Replacement ■ Cincinnati, Ohio  
 March 11, 2011 ■ HCN/Terracon Project No. N1105070



Boring	Sample Number	Reading (ppm-V/V)
L-2A	13	10/8
L-2A	14	20/9
L-2A	15	20/6
L-2A	16	<1
L-2A	17	8
L-2A	18	13/1
L-2A	19	<1
L-2A	20	77/35
L-2A	21	16/17
L-2A	22	33/5
L-2A	23	22/19
L-2A	24	36/22
L-2A	25	27/25
L-2A	26	32/16
L-2A	27	42/26
L-2A	28	39/17
L-2A	29	43/19
L-2A	30	6
L-3	1	-
L-3	2	2730/1100
L-3	3	2730/850
L-3	4	-
L-3	5	-
L-3	6	15/4
L-3	7	3
L-3	8	<1
L-3	9	<1
L-3	10	13/3
L-3	11	6
L-3	12	11/2
L-3	13	16/5
L-3	14	19/14
L-3	15	7
L-3	16	13/4
L-3	17	-
L-4	1	648/114
L-4	2	5
L-4	3	<1

Boring	Sample Number	Reading (ppm-V/V)
L-4	4	447/112
L-4	5	47/19
L-4	6	49/23
L-4	7	-
L-4	8	181/48
L-4	9	1914/165
L-4	10	3900/1500
L-4	11	-
L-4	12	1270/819
L-4	13	9
L-4	14	<1
L-4	15	125/69
L-4	16	161/65
L-4	17	2
L-4	18	25/17
L-4	19	82/31
L-4	20	<1
L-4	21	29/13
L-4	22	34/15
L-4	23	11/5
L-4	24	30/10
L-4	25	75/17
L-4	26	-
L-4	27	-
L-5	1	<1
L-5	2	<1
L-5	3	<1
L-5	4	<1
L-5	5	2
L-5	6	2
L-5	7	14/33
L-5	8	108/78
L-5	9	2
L-5	10	15/12
L-5	11	12/7
L-5	12	40/22
L-5	13	13/3
L-5	14	26/7

**PID Readings**

Parsons Brinckerhoff ■ Brent Spence Bridge Replacement ■ Cincinnati, Ohio  
 March 11, 2011 ■ HCN/Terracon Project No. N1105070



Boring	Sample Number	Reading (ppm-V/V)
L-5	15	43/20
L-5	16	68/23
L-5	17	5
L-5	18	23/21
L-5	19	31/14
L-5	20	40/29
L-5	21	58/38
L-5	22	-
L-6	1	<1
L-6	2	-
L-6	3	<1
L-6	4	<1
L-6	5	<1
L-6	6	-
L-6	7	2
L-6	8	7
L-6	9	<1
L-6	10	-
L-6	11	<1
L-6	12	<1
L-6	13	<1
L-6	14	<1
L-6	15	<1
L-6	16	<1
L-6	17	<1
L-6	18	-
L-6	19	<1
L-6	20	-
L-6	21	14/5
L-6	22	-
L-7	1	340/190
L-7	2	400/364
L-7	3	54/31
L-7	4	No sample
L-7	5	<1
L-7	6	2
L-7	7	No sample
L-7	8	7

Boring	Sample Number	Reading (ppm-V/V)
L-7	9	2750/2700
L-7	10	2800/2600
L-7	11	No Sample
L-7	12	74/74
L-7	13	2
L-7	14	<1
L-7	15	62/40
L-7	16	50/20
L-7	17	103/66
L-7	18	3
L-7	19	73/42
L-7	20	<1
R-1	1	1
R-1	2	8
R-1	3	-
R-1	4	2
R-1	5	-
R-1	6	1
R-1	7	2
R-1	8	5
R-1	9	6
R-1	10	-
R-1	11	<1
R-1	12	2
R-1	13	8
R-1	14	8
R-1	15	7
R-1	16	
R-2	1	<1
R-2	2	10/6
R-2	3	7
R-2	4	11/5
R-2	5	-
R-2	6	18/11
R-2	7	-
R-2	8	8
R-2	9	9
R-2	10	4

**PID Readings**

Parsons Brinckerhoff ■ Brent Spence Bridge Replacement ■ Cincinnati, Ohio  
 March 11, 2011 ■ HCN/Terracon Project No. N1105070



Boring	Sample Number	Reading (ppm-V/V)
R-2	11	24/3
R-2	12	13/11
R-2	13	13/10
R-2	14	3
R-2	15	40/13
R-2	16	64/39
R-3	1	-
R-3	2	-
R-3	3	3
R-3	4	2
R-3	5	-
R-3	6	2
R-3	7	8
R-3	8	1
R-3	9	<1
R-3	10	3
R-3	11	-
R-3	12	3
R-3	13	1
R-3	14	2
R-3	15	5
R-3	16	14/4
R-3	17	-
R-4	1	<1
R-4	2	11/7
R-4	3	4700/3900
R-4	4	42/63
R-4	5	3
R-4	6	3
R-4	7	6
R-4	8	<1
R-4	9	-
R-4	10	<1
R-4	11	12/14
R-4	12	9
R-4	13	16/11
R-4	14	19/10
R-4	15	16/12

Boring	Sample Number	Reading (ppm-V/V)
R-4	16	1
R-5	1	5
R-5	2	2/4800
R-5	3	2/6000
R-5	4	5844/-
R-5	5	-
R-5	6	3620/5800
R-5	7	5700/5900
R-5	8	154/196
R-5	9	2
R-5	10	52/34
R-5	11	12/13
R-5	12	104/62
R-5	13	62/32
R-5	14	67/33
R-5	15	95/51
R-5	16	2
R-5	17	20.7
R-5	18	28/23
R-5	19	27/19
R-6	1	1
R-6	2	5
R-6	3	-
R-6	4	13/10
R-6	5	6
R-6	6	<1
R-6	7	-
R-6	8	1
R-6	9	70/76
R-6	10	2
R-6	11	25/17
R-6	12	58/26
R-6	13	9
R-6	14	59/28
R-6	15	19/7
R-6	16	40/8
R-6	17	38/10
R-6	18	37/14

**PID Readings**

Parsons Brinckerhoff ■ Brent Spence Bridge Replacement ■ Cincinnati, Ohio  
March 11, 2011 ■ HCN/Terracon Project No. N1105070



<b>Boring</b>	<b>Sample Number</b>	<b>Reading (ppm-V/V)</b>
R-6	19	39/21
R-6	20	43/18
R-6	21	93/43
R-7	2	3500/3000
R-7	3	8300/8300
R-7	4	2500/3576
R-7	5	2100/2200
R-7	6	-
R-7	7	-
R-7	8	21/30
R-7	9	-
R-7	10	28/61
R-7	11	37/101
R-7	12	29/51
R-7	13	64/84
R-7	14	79/142
R-7	15	35/39
R-7	16	50/48
R-7	17	40/27



**Geotechnical Engineering Report**

Brent Spence Bridge Replacement ■ Cincinnati, Ohio-Covington, Kentucky

March 11, 2011 ■ HCN/Terracon Project No. N1105070



**EXHIBIT A-11**  
**GEOVISION SUSPENSION LOGGING REPORT**



**SUSPENSION PS VELOCITIES  
BORINGS L-1, L-4 AND R-2A**

**BRENT SPENCE BRIDGE REPLACEMENT  
CINCINNATI, OHIO**

**Report 10261-01 rev a  
September 22, 2010**

**SUSPENSION PS VELOCITIES  
BORINGS L-1, L-4 AND R-2A**

**BRENT SPENCE BRIDGE REPLACEMENT  
CINCINNATI, OHIO**

**Report 10261-01 rev a**

**September 22, 2010**

**Prepared for:**

**H.C. Nutting, a Terracon Company**

**611 Lunken Park Drive**

**Cincinnati, Ohio 45226**

**(513) 321 5816 ext. 372**

**Prepared by**

**GEOVision Geophysical Services**

**1124 Olympic Drive**

**Corona, California 92881**

**(951) 549-1234**

# TABLE OF CONTENTS

<b>TABLE OF CONTENTS</b> .....	<b>3</b>
<b>TABLE OF FIGURES</b> .....	<b>4</b>
<b>TABLE OF TABLES</b> .....	<b>4</b>
<b>INTRODUCTION</b> .....	<b>5</b>
<b>SCOPE OF WORK</b> .....	<b>5</b>
<b>INSTRUMENTATION</b> .....	<b>7</b>
SUSPENSION INSTRUMENTATION .....	7
<b>MEASUREMENT PROCEDURES</b> .....	<b>10</b>
SUSPENSION MEASUREMENT PROCEDURES .....	10
<b>DATA ANALYSIS</b> .....	<b>11</b>
SUSPENSION ANALYSIS .....	11
<b>RESULTS</b> .....	<b>13</b>
SUSPENSION RESULTS .....	13
<b>SUMMARY</b> .....	<b>14</b>
DISCUSSION OF SUSPENSION RESULTS .....	14
QUALITY ASSURANCE .....	15
SUSPENSION DATA RELIABILITY .....	15

## Table of Figures

Figure 1: Concept illustration of P-S logging system .....	16
Figure 2: Example of filtered (1400 Hz lowpass) record .....	17
Figure 3: Example of unfiltered record .....	18
Figure 4: Boring L-1, Suspension R1-R2 P- and S <sub>H</sub> -wave velocities.....	19
Figure 5: Boring L-4, Suspension R1-R2 P- and S <sub>H</sub> -wave velocities.....	21
Figure 6: Boring R-2A, Suspension R1-R2 S <sub>H</sub> -wave velocities .....	23

## Table of Tables

Table 1 Boring locations and logging dates.....	5
Table 2. Logging dates and depth ranges .....	10
Table 3. Boring L-1, Suspension R1-R2 depths and P- and S <sub>H</sub> -wave velocities .....	20
Table 4. Boring L-4, Suspension R1-R2 depths and P- and S <sub>H</sub> -wave velocities .....	22
Table 5. Boring R-2A, Suspension R1-R2 depths and S <sub>H</sub> -wave velocities.....	24

## APPENDICES

**APPENDIX A            SUSPENSION VELOCITY MEASUREMENT QUALITY  
ASSURANCE SUSPENSION SOURCE TO RECEIVER  
ANALYSIS RESULTS**

**APPENDIX B            GEOPHYSICAL LOGGING SYSTEMS - NIST TRACEABLE  
CALIBRATION PROCEDURES AND CALIBRATION RECORDS**

## INTRODUCTION

Boring geophysical measurements were collected in three cased borings for the Brent Spence Bridge Replacement project in Cincinnati, Ohio. Geophysical data acquisition was performed in two on-land borings on August 3, 2010 by Victor Gonzalez and one boring in the Ohio River on September 2, 2010 by Chuck Carter of **GEOVision**. Data analysis was performed by Victor Gonzalez and Chuck Carter and reviewed by Robert Steller of **GEOVision**. Report preparation was performed by Victor Gonzalez and reviewed by Robert Steller of **GEOVision**. The work was performed under subcontract with H.C. Nutting (HCN) with Bill Meadows serving as the point of contact for HCN.

This report describes the field measurements, data analysis, and results of this work.

## SCOPE OF WORK

This report presents the results of boring geophysical measurements collected on August 3, 2010 on land and on September 2, 2010 in the Ohio River in three 3-inch PVC cased borings, as detailed in Table 1. The purpose of the study was to acquire shear wave velocities and compressional wave velocities as a function of depth.

BORING DESIGNATION	DATES LOGGED	ELEVATION - FEET MSL <sup>(1)</sup>	COORDINATES – FEET <sup>(1)</sup>	
			NORTHING	EASTING
L-1	08/03/2010	494.59	39.093833610	84.522929480
L-4	08/03/2010	479.97	39.088805640	84.523275430
R-2A	09/02/2010	457.64 (DECK LEVEL)	NA	NA

<sup>(1)</sup> Coordinates and elevations provided by HCN

Table 1 Boring locations and logging dates

The OYO Suspension Logging System was used to obtain in-situ horizontal shear and compressional wave velocity measurements at 1.6-foot intervals. The acquired data were analyzed and a profile of velocity versus depth was produced for both compressional and horizontally polarized shear waves.

A detailed reference for the velocity measurement techniques used in this study is:

Guidelines for Determining Design Basis Ground Motions, Report TR-102293,  
Electric Power Research Institute, Palo Alto, California, November 1993,  
Sections 7 and 8.

# INSTRUMENTATION

## Suspension Instrumentation

Suspension soil velocity measurements were performed in all borings using the PS suspension logging system, manufactured by OYO Corporation. This system directly determines the average velocity of a 3.3-foot high segment of the soil column surrounding the boring of interest by measuring the elapsed time between arrivals of a wave propagating upward through the soil column. The receivers that detect the wave, and the source that generates the wave, are moved as a unit in the boring producing relatively constant amplitude signals at all depths.

The suspension system probe consists of a combined reversible polarity solenoid horizontal shear-wave source ( $S_H$ ) and compressional-wave source (P), joined to two biaxial receivers by a flexible isolation cylinder, as shown in Figure 1. The separation of the two receivers is 3.3 feet, allowing average wave velocity in the region between the receivers to be determined by inversion of the wave travel time between the two receivers. The total length of the probe as used in these surveys is 19 feet, with the center point of the receiver pair 12.1 feet above the bottom end of the probe.

The probe receives control signals from, and sends the receiver signals to, instrumentation on the surface via an armored 4 or 7 conductor cable. The cable is wound onto the drum of a winch and is used to support the probe. Cable travel is measured to provide probe depth data, using a 3.28-foot circumference sheave fitted with a digital rotary encoder.

The entire probe is suspended in the boring by the cable, therefore, source motion is not coupled directly to the boring walls; rather, the source motion creates a horizontally propagating impulsive pressure wave in the fluid filling the boring and surrounding the source. This pressure wave is converted to P and  $S_H$ -waves in the surrounding soil and rock as it impinges upon the wall of the boring. These waves propagate through the soil and rock surrounding the boring, in turn causing a pressure wave to be generated in the fluid surrounding the receivers as the soil



waves pass their location. Separation of the P and  $S_H$ -waves at the receivers is performed using the following steps:

1. Orientation of the horizontal receivers is maintained parallel to the axis of the source, maximizing the amplitude of the recorded  $S_H$  -wave signals.
2. At each depth,  $S_H$ -wave signals are recorded with the source actuated in opposite directions, producing  $S_H$ -wave signals of opposite polarity, providing a characteristic  $S_H$ -wave signature distinct from the P-wave signal.
3. The 6.3-foot separation of source and receiver 1 permits the P-wave signal to pass and damp significantly before the slower  $S_H$ -wave signal arrives at the receiver. In saturated soils, the received P-wave signal is typically of much higher frequency than the received  $S_H$  -wave signal, permitting additional separation of the two signals by low pass filtering.
4. Direct arrival of the original pressure pulse in the fluid is not detected at the receivers because the wavelength of the pressure pulse in fluid is significantly greater than the dimension of the fluid annulus surrounding the probe, preventing significant energy transmission through the fluid medium.

In operation, a distinct, repeatable pattern of impulses is generated at each depth as follows:

1. The source is fired in one direction producing dominantly horizontal shear with some vertical compression, and the signals from the horizontal receivers situated parallel to the axis of motion of the source are recorded.
2. The source is fired again in the opposite direction and the horizontal receiver signals are recorded.
3. The source is fired again and the vertical receiver signals are recorded. The repeated source pattern facilitates the picking of the P and  $S_H$ -wave arrivals; reversal of the source changes the polarity of the  $S_H$ -wave pattern but not the P-wave pattern.

The data from each receiver during each source activation is recorded as a different channel on the recording system. The Suspension PS system has six channels (two simultaneous recording channels), each with a 1024 sample record. The recorded data are displayed as six channels with a common time scale. Data are stored on disk for further processing. Up to 8 sampling sequences can be summed to improve the signal to noise ratio of the signals.

Review of the displayed data on the recorder or computer screen allows the operator to set the gains, filters, delay time, pulse length (energy), sample rate, and summing number to optimize the quality of the data before recording. Verification of the calibration of the Suspension PS digital recorder is performed every twelve months using a NIST traceable frequency source and counter, as outlined in Appendix B.

## MEASUREMENT PROCEDURES

### Suspension Measurement Procedures

Three 4 7/8-inch borings containing 3-inch schedule 40 PVC casing filled with fresh water were logged. Measurements followed the **GEOVision** Procedure for P-S Suspension Seismic Velocity Logging, revision 1.4. Prior to each logging run, the probe was positioned with the top of the probe at the top of the barge deck, ground surface, or other stationary reference point. Subsequently, the electronic depth counter was set to 6.56 feet, the distance between the mid-point of the receiver and the top of the probe, minus the height of the stationary reference point, as verified with a tape measure, and recorded on the field logs. The probe was lowered to the bottom of the boring or until the probe descent was inhibited, stopping at 1.6-foot intervals to collect data, as summarized in Table 2.

At each measurement depth the measurement sequence of two opposite horizontal records and one vertical record was performed, and the gains were adjusted as required. The data from each depth were viewed on the computer display, checked, and recorded on disk before moving to the next depth.

Upon completion of the measurements, the probe zero depth indication at the stationary reference point was verified and recorded on the field logs prior to removal from the boring. Field data were backed up to USB flash drive each day upon completion of data acquisition.

BORING NUMBER	TOOL AND RUN NUMBER	DEPTH RANGE (FEET)	DEPTH TO BOTTOM OF BORING (FEET)	SAMPLE INTERVAL (FEET)	DATE LOGGED
L-1	SUSPENSION PS 1	6.56 – 167.32	182	1.6	08/03/2010
L-4	SUSPENSION PS 1	6.56 – 139.44	154	1.6	08/03/2010
R-2A	SUSPENSION PS 1	3.28 – 123.03	139	1.6	09/02/2010

Table 2. Logging dates and depth ranges

## DATA ANALYSIS

### Suspension Analysis

Using the proprietary OYO program PSLOG.EXE version 1.0, the recorded digital waveforms were analyzed to locate the most prominent first minima, first maxima, or first break on the vertical axis records, indicating the arrival of P-wave energy. The difference in travel time between receiver 1 and receiver 2 (R1-R2) arrivals was used to calculate the P-wave velocity for that 3.3-foot segment of the soil column. When observable, P-wave arrivals on the horizontal axis records were used to verify the velocities determined from the vertical axis data. The time picks were then transferred into an EXCEL template to complete the velocity calculations based on the arrival time picks made in PSLOG.

The P-wave velocity over the 6.33-foot interval from source to receiver 1 (S-R1) was also picked using PSLOG, and calculated and plotted in EXCEL, for quality assurance of the velocity derived from the travel time between receivers. In this analysis, the depth values as recorded were increased by 4.53 feet to correspond to the mid-point of the 6.33-foot S-R1 interval. Travel times were obtained by picking the first break of the P-wave signal at receiver 1 and subtracting 4.0 milliseconds, the calculated and experimentally verified delay from source trigger pulse (beginning of record) to source impact. This delay corresponds to the duration of acceleration of the solenoid before impact.

As with the P-wave records, using PSLOG, the recorded digital waveforms were analyzed to locate the presence of clear  $S_H$ -wave pulses, as indicated by opposite polarity pulses on each pair of horizontal records. Ideally, the  $S_H$ -wave signals from the 'normal' and 'reverse' source pulses are very nearly inverted images of each other. Digital FFT - IFFT lowpass filtering can be used to remove the higher frequency P-wave signal from the  $S_H$ -wave signal, if present.

Generally, the first maxima were picked for the 'normal' signals and the first minima for the 'reverse' signals, although other points on the waveform were used if the first pulse was distorted.

The absolute arrival time of the 'normal' and 'reverse' signals may vary by +/- 0.2 milliseconds, due to differences in the actuation time of the solenoid source caused by constant mechanical bias in the source or by boring inclination. This variation does not affect the R1-R2 velocity determinations, as the differential time is measured between arrivals of waves created by the same source actuation. The final velocity value is the average of the values obtained from the 'normal' and 'reverse' source actuations.

As with the P-wave data,  $S_H$ -wave velocity calculated from the travel time over the 6.33-foot interval from source to receiver 1 was calculated and plotted for verification of the velocity derived from the travel time between receivers. In this analysis, the depth values were increased by 4.53 feet to correspond to the mid-point of the 6.33-foot S-R1 interval. Travel times were obtained by picking the first break of the  $S_H$ -wave signal at the near receiver and subtracting 4.0 milliseconds, the calculated and experimentally verified delay from the beginning of the record at the source trigger pulse to source impact.

These data and analysis were reviewed by Robert Steller as a component of **GEOVision's** in-house QA-QC program.

Figure 2 shows an example of R1 - R2 measurements on a sample filtered suspension record. In Figure 2, the time difference over the 3.3-foot interval of 1.88 milliseconds for the horizontal signals is equivalent to an  $S_H$ -wave velocity of 1745 feet/second. Whenever possible, time differences were determined from several phase points on the  $S_H$ -waveform records to verify the data obtained from the first arrival of the  $S_H$ -wave pulse. Figure 3 displays the same record before filtering of the  $S_H$ -waveform record with a 1400 Hz FFT - IFFT digital lowpass filter, illustrating the presence of higher frequency P-wave energy at the beginning of the record, and distortion of the lower frequency  $S_H$ -wave by residual P-wave signal.

# RESULTS

## Suspension Results

Suspension R1-R2 P-wave and  $S_H$ -wave velocities are plotted in Figures 4, 5 and 6. The suspension velocity data presented in these figures are presented in Tables 3, 4 and 5, respectively. These plots and data are included in the EXCEL analysis files in the boring specific directories on the data disk (CD-R) that accompanies this report.

P- and  $S_H$ -wave velocity data from R1-R2 analysis and quality assurance analysis of S-R1 data are plotted together in Figures A-1 through A-3 to aid in visual comparison. It should be noted that R1-R2 data are an average velocity over a 3.3-foot segment of the soil column; S-R1 data are an average over 6.33 feet, creating a significant smoothing relative to the R1-R2 plots. S-R1 data are presented in Tables A-1 through A-3, and included in the EXCEL analysis files.

Calibration procedures and records for the suspension PS measurement system are presented in Appendix B.

# SUMMARY

## Discussion of Suspension Results

Suspension PS velocity data are ideally collected in an uncased fluid filled boring, drilled with rotary mud (rotary wash) methods. The data collected in these uncased borings were of fair overall quality.

Suspension PS velocity data quality is judged based upon 5 criteria:

	Criteria	Results for L-1, L-4, and R-2A
1	Consistent data between receiver to receiver (R1 – R2) and source to receiver (S – R1) data.	Data tracks fairly well between R1-R2 and S-R1 data. This correlation is generally degraded slightly in cased borings such as these.
2	Consistency between data from adjacent depth intervals.	All three borings show moderate scatter between adjacent depth intervals. This is expected in thinly interbedded sediments and fractured rock. This may be the case at this site, but the soil logs do not present sufficient detail to ascertain if this is indeed the case.
3	Consistent relationship between P-wave and S <sub>H</sub> -wave (excluding transition to saturated soils)	Relationship between P-wave and S <sub>H</sub> -wave is consistent, except above 50 feet in L-1. This drop of P-wave velocity below 5000 feet/sec is indicative of gases trapped in organic materials. Poisson's Ratio is within expected ranges for these materials.
4	Clarity of P-wave and S <sub>H</sub> -wave onset, as well as damping of later oscillations.	Clarity of P-wave and S <sub>H</sub> -wave onsets are poor in some sections of the softer sediments, which may indicate an enlarged boring filled with grout. Particularly in L-4 above 45 feet, the arrivals are very consistent, which may indicate signal arriving through the grout column. There are no low frequency un-damped signals that would indicate un-coupled casing.
5	Consistency of profile between adjacent borings, if available.	Similar S <sub>H</sub> -wave velocity profiles are seen in similar units in all three borings. One exception is the section of bedrock between 104 and 119 feet in L-4. This presents a very low velocity for bedrock, particularly since it is overlaid by a much faster layer of stone fragments with sand. This may be due to weathering of the rock, or the presence of weaker shale. This velocity inversion is present in both P-wave and S <sub>H</sub> -wave, and in both R1-R2 and S-R1 data, substantiating its presence.

## Quality Assurance

These boring geophysical measurements were performed using industry-standard or better methods for measurements and analyses. All work was performed under **GEOVision** quality assurance procedures, which include:

- Use of NIST-traceable calibrations, where applicable, for field and laboratory instrumentation
- Use of standard field data logs
- Use of independent verification of velocity data by comparison of receiver-to-receiver and source-to-receiver velocities
- Independent review of calculations and results by a registered professional engineer, geologist, or geophysicist.

## Suspension Data Reliability

P- and  $S_H$ -wave velocity measurement using the Suspension Method gives average velocities over a 3.3-foot interval of depth. This high resolution results in the scatter of values shown in the graphs. In uncased borings, individual measurements are very reliable, with estimated precision of +/- 5%. In cased borings, with uncertain grout bond, estimated precision is +/- 15%. Standardized field procedures and quality assurance checks contribute to the reliability of the data.






Figure 1: Concept illustration of P-S logging system




Figure 2: Example of filtered (1400 Hz lowpass) record




Figure 3. Example of unfiltered record

## BRENT SPENCE BRIDGE REPLACEMENT BORING L-1




Figure 4: Boring L-1, Suspension R1-R2 P- and S<sub>H</sub>-wave velocities

Depth (feet)	Elevation (feet)	V <sub>s</sub> (feet/sec)	V <sub>p</sub> (feet/sec)	Poisson's Ratio	Depth (feet)	Elevation (feet)	V <sub>s</sub> (feet/sec)	V <sub>p</sub> (feet/sec)	Poisson's Ratio
6.6	488.0	556	2563	0.48	88.6	406.0	777	6309	0.49
8.2	486.4	800	2217	0.43	90.2	404.4	754	5561	0.49
9.8	484.7	676	2310	0.45	91.9	402.7	881	5126	0.48
11.5	483.1	650	1745	0.42	93.5	401.1	831	5468	0.49
13.1	481.5	725	2013	0.43	95.1	399.4	1384	6190	0.47
14.8	479.8	795	2090	0.42	96.8	397.8	1122	5965	0.48
16.4	478.2	905	2076	0.38	98.4	396.2	746	5657	0.49
18.0	476.5	725	2144	0.44	100.1	394.5	1600	5468	0.45
19.7	474.9	684	1485	0.37	101.7	392.9	1299	5468	0.47
21.3	473.3	721	1624	0.38	103.3	391.2	899	5468	0.49
23.0	471.6	721	1736	0.40	105.0	389.6	905	5208	0.48
24.6	470.0	625	1727	0.42	106.6	388.0	951	5561	0.48
26.2	468.3	613	1988	0.45	108.3	386.3	899	5561	0.49
27.9	466.7	608	1367	0.38	109.9	384.7	1182	5756	0.48
29.5	465.1	741	1445	0.32	111.5	383.0	1151	6835	0.49
31.2	463.4	781	2343	0.44	113.2	381.4	1161	6309	0.48
32.8	461.8	698	2076	0.44	114.8	379.8	1131	6190	0.48
34.4	460.1	746	1577	0.36	116.5	378.1	1172	6981	0.49
36.1	458.5	702	2232	0.45	118.1	376.5	1262	6076	0.48
37.7	456.9	666	2202	0.45	119.8	374.8	1161	6835	0.49
39.4	455.2	815	1608	0.33	121.4	373.2	841	7132	0.49
41.0	453.6	911	2294	0.41	123.0	371.6	1959	7456	0.46
42.7	451.9	643	1886	0.43	124.7	369.9	1562	7456	0.48
44.3	450.3	875	1953	0.37	126.3	368.3	2573	7456	0.43
45.9	448.7	709	1373	0.32	128.0	366.6	3281	8867	0.42
47.6	447.0	616	2734	0.47	129.6	365.0	3860	9374	0.40
49.2	445.4	781	2929	0.46	131.2	363.4	4525	10936	0.40
50.9	443.7	958	4687	0.48	132.9	361.7	3365	9374	0.43
52.5	442.1	566	6190	0.50	134.5	360.1	3547	8412	0.39
54.1	440.5	616	4261	0.49	136.2	358.4	3977	9374	0.39
55.8	438.8	540	3906	0.49	137.8	356.8	3038	8867	0.43
57.4	437.2	631	4001	0.49	139.4	355.2	3977	9942	0.40
59.1	435.5	576	5657	0.49	141.1	353.5	3052	11313	0.46
60.7	433.9	599	5561	0.49	142.7	351.9	4687	10253	0.37
62.3	432.3	729	5292	0.49	144.4	350.2	3586	11717	0.45
64.0	430.6	628	5468	0.49	146.0	348.6	3750	11717	0.44
65.6	429.0	958	6309	0.49	147.6	347.0	4374	10936	0.40
67.3	427.3	583	5965	0.50	149.3	345.3	3365	9113	0.42
68.9	425.7	852	5756	0.49	150.9	343.7	3125	10583	0.45
70.5	424.1	1017	5965	0.49	152.6	342.0	4687	11717	0.40
72.2	422.4	1274	5965	0.48	154.2	340.4	4654	12151	0.41
73.8	420.8	979	6190	0.49	155.8	338.8	6562	13670	0.35
75.5	419.1	1204	6190	0.48	157.5	337.1	5249	11717	0.37
77.1	417.5	893	6309	0.49	159.1	335.5	5249	10583	0.34
78.7	415.8	1299	6433	0.48	160.8	333.8	6562	15623	0.39
80.1	414.5	1025	4971	0.48	162.4	332.2	6907	16404	0.39
82.0	412.6	1017	5965	0.49	164.0	330.5	7291	15623	0.36
83.7	410.9	1141	5561	0.48	165.7	328.9	7291	14913	0.34
85.3	409.3	1050	5468	0.48	167.3	327.3	7291	15623	0.36
86.9	407.6	663	5561	0.49					

Table 3. Boring L-1, Suspension R1-R2 depths and P- and S<sub>H</sub>-wave velocities

## BRENT SPENCE BRIDGE REPLACEMENT BORING L-4




Figure 5: Boring L-4, Suspension R1-R2 P- and S<sub>H</sub>-wave velocities

Depth (feet)	Elevation (feet)	V <sub>s</sub> (feet/sec)	V <sub>p</sub> (feet/sec)	Poisson's Ratio
7.2	472.8			
8.2	471.8			
9.8	470.1			
11.5	468.5	754	5378	0.49
13.1	466.8	777	5561	0.49
14.8	465.2	821	5859	0.49
16.4	463.6	786	5965	0.49
18.0	461.9	805	5965	0.49
19.7	460.3	805	5756	0.49
21.3	458.6	805	5292	0.49
23.0	457.0	805	5756	0.49
24.6	455.4	810	5965	0.49
26.2	453.7	800	5756	0.49
27.9	452.1	795	6190	0.49
29.5	450.4	781	5965	0.49
31.2	448.8	781	5859	0.49
32.8	447.2	759	5561	0.49
34.8	445.2	800	5859	0.49
36.1	443.9	875	6076	0.49
37.7	442.2	911	5561	0.49
39.4	440.6	772	5292	0.49
41.0	439.0	777	5126	0.49
42.7	437.3	805	5468	0.49
44.3	435.7	810	6076	0.49
45.9	434.0	759	5657	0.49
47.6	432.4	1058	6433	0.49
49.2	430.8	1151	6309	0.48
50.9	429.1	1122	5378	0.48
52.5	427.5	1172	5965	0.48
54.1	425.8	1215	6562	0.48
55.4	424.5	1161	5859	0.48
57.4	422.6	905	6309	0.49
59.1	420.9	836	6309	0.49
60.7	419.3	937	5756	0.49
62.3	417.6	1215	6433	0.48
64.3	415.7	852	7456	0.49
65.6	414.4	869	6835	0.49
67.6	412.4	1339	5657	0.47
68.9	411.1	951	5859	0.49
70.5	409.4	501	5657	0.50
71.9	408.1	1381	6433	0.48
73.8	406.2	1161	7812	0.49
75.5	404.5	594	6696	0.50
77.1	402.9	825	6433	0.49
78.7	401.2	1620	5756	0.46
80.4	399.6	1151	5047	0.47
82.0	397.9	979	6076	0.49
83.7	396.3	646	4971	0.49
85.3	394.7	676	5657	0.49
86.9	393.0	1131	6835	0.49

Depth (feet)	Elevation (feet)	V <sub>s</sub> (feet/sec)	V <sub>p</sub> (feet/sec)	Poisson's Ratio
88.6	391.4	2224	7291	0.45
90.2	389.7	2117	7291	0.45
91.9	388.1	2853	8412	0.44
93.5	386.5	2625	8002	0.44
95.1	384.8	2386	8634	0.46
96.8	383.2	3365	8867	0.42
98.4	381.5	4101	8412	0.34
100.1	379.9	3860	8202	0.36
101.7	378.3	3125	7812	0.40
103.3	376.6	3454	8002	0.39
105.0	375.0	2678	7291	0.42
106.6	373.3	670	6190	0.49
108.6	371.4	1141	5965	0.48
109.9	370.1	1426	5859	0.47
111.5	368.4	1215	6696	0.48
113.2	366.8	750	6433	0.49
114.8	365.1	777	6190	0.49
116.5	363.5	1442	6076	0.47
118.1	361.9	2983	8867	0.44
119.8	360.2	4687	9113	0.32
121.4	358.6	6249	10583	0.23
123.0	356.9	7720	14913	0.32
124.7	355.3	7291	14913	0.34
126.3	353.7	7291	15623	0.36
128.0	352.0	6562	15623	0.39
129.6	350.4	6249	14913	0.39
131.6	348.4	6249	14265	0.38
133.2	346.8	5965	13670	0.38
134.5	345.5	5706	13123	0.38
136.2	343.8	5047	12151	0.40
137.8	342.2	5047	13123	0.41
139.4	340.5	4861	14265	0.43

Table 4. Boring L-4, Suspension R1-R2 depths and P- and S<sub>H</sub>-wave velocities

## BRENT SPENCE BRIDGE REPLACEMENT BORING R-2A




Figure 6: Boring R-2A, Suspension R1-R2 S<sub>H</sub>-wave velocities



Depth (feet)	Elevation (feet)	V <sub>s</sub> (feet/sec)	V <sub>p</sub> (feet/sec)	Poisson's Ratio
33.9	423.7	628	5292	0.49
35.6	422.1	443	5047	0.50
37.2	420.4	741	5126	0.49
38.8	418.8	341	5249	0.50
40.5	417.2	610	4897	0.49
42.1	415.5	352	5292	0.50
43.8	413.9	392	5468	0.50
45.4	412.2	451	5047	0.50
47.0	410.6	443	5423	0.50
48.7	409.0	409	5423	0.50
50.3	407.3	637	5468	0.49
52.0	405.7	462	5468	0.50
53.6	404.0	432	5167	0.50
55.2	402.4	449	5126	0.50
56.9	400.8	581	5047	0.49
58.5	399.1	509	5126	0.50
60.2	397.5	437	5335	0.50
61.8	395.8	554	5335	0.49
63.4	394.2	331	5208	0.50
65.1	392.6	440	5514	0.50
66.7	390.9	937	5965	0.49
68.4	389.3	958	5657	0.49
70.0	387.6	1307	5468	0.47
71.7	386.0	1161	5514	0.48
73.3	384.3	781	5965	0.49
74.9	382.7	680	5378	0.49
76.6	381.1	734	6309	0.49
78.2	379.4	1159	6907	0.49
79.9	377.8	1042	6562	0.49
81.5	376.1	2853	7456	0.41
83.1	374.5	3837	8634	0.38
84.8	372.9	3331	7456	0.38
86.4	371.2	2916	7291	0.40
88.1	369.6	2804	8634	0.44
89.7	367.9	4464	9113	0.34
91.3	366.3	3038	9650	0.44
93.0	364.7	3232	10253	0.44
94.6	363.0	3248	9374	0.43
96.3	361.4	4434	8989	0.34
97.9	359.7	4317	10936	0.41
99.5	358.1	4687	10253	0.37
101.2	356.5	4261	10253	0.40
102.8	354.8	4790	11313	0.39
104.5	353.2	4621	11313	0.40
106.1	351.5	6628	14265	0.36
107.7	349.9	7132	15260	0.36
109.4	348.3	5657	14265	0.41
111.0	346.6	4654	10757	0.38
112.7	345.0	5208	10936	0.35
114.3	343.3	5167	11313	0.37

Depth (feet)	Elevation (feet)	V <sub>s</sub> (feet/sec)	V <sub>p</sub> (feet/sec)	Poisson's Ratio
115.9	341.7	5514	13670	0.40
117.6	340.1	5009	12619	0.41
119.2	338.4	5423	12151	0.38
120.9	336.8	4971	12151	0.40
122.5	335.1	5561	10583	0.31
124.1	333.5	6309	11717	0.30
127.4	330.2	4790	10583	0.37
129.1	328.6	6190	14265	0.38
130.7	326.9	6433	13961	0.37
132.3	325.3	5561	10936	0.33
134.0	323.7	5087	11717	0.38
135.6	322.0	4755	10583	0.37
137.3	320.4	4971	11717	0.39
138.9	318.7	5657	12151	0.36
140.5	317.1	5911	11717	0.33
142.2	315.5	6981	14265	0.34
143.8	313.8	6076	12619	0.35
145.5	312.2	5561	10583	0.31
147.1	310.5	5965	11930	0.33
148.8	308.9	6562	14581	0.37
150.4	307.2	7211	14913	0.35
152.0	305.6	7291	14913	0.34

Table 5. Boring R-2A, Suspension R1-R2 depths and S<sub>H</sub>-wave velocities

**APPENDIX A**

**SUSPENSION VELOCITY MEASUREMENT  
QUALITY ASSURANCE SUSPENSION SOURCE  
TO RECEIVER ANALYSIS RESULTS**

# BRENT SPENCE BRIDGE REPLACEMENT BORING L-1




Figure A-1. Boring L-1, R1 - R2 high resolution analysis and S - R1 quality assurance analysis P- and S<sub>H</sub>-wave data

Depth (feet)	Elevation (feet)	V <sub>s</sub> (feet/sec)	V <sub>p</sub> (feet/sec)	Poisson's Ratio	Depth (feet)	Elevation (feet)	V <sub>s</sub> (feet/sec)	V <sub>p</sub> (feet/sec)	Poisson's Ratio
11.7	482.9	751	2236	0.44	93.7	400.9	650	5443	0.49
13.4	481.2	735	2134	0.43	95.4	399.2	798	5802	0.49
15.0	479.6	793	1950	0.40	97.0	397.6	731	5662	0.49
16.6	478.0	780	2429	0.44	98.7	395.9	669	5443	0.49
18.3	476.3	735	1696	0.38	100.3	394.3	656	5279	0.49
19.9	474.7	685	1978	0.43	101.9	392.7	633	5051	0.49
21.6	473.0	695	1393	0.33	103.6	391.0	598	5279	0.49
23.2	471.4	713	1396	0.32	105.2	389.4	565	5401	0.49
24.8	469.8	688	2372	0.45	106.9	387.7	590	5443	0.49
26.5	468.1	706	1769	0.41	108.5	386.1	619	5662	0.49
28.1	466.5	447	2499	0.48	110.1	384.5	669	5802	0.49
29.8	464.8	725	1618	0.37	111.8	382.8	1160	5708	0.48
31.4	463.2	600	1448	0.40	113.4	381.2	1151	6441	0.48
33.0	461.6	580	1546	0.42	115.1	379.5	1170	5708	0.48
34.7	459.9	598	1688	0.43	116.7	377.9	1190	6562	0.48
36.3	458.3	603	1956	0.45	118.3	376.3	1211	6501	0.48
38.0	456.6	616	1773	0.43	120.0	374.6	1200	6441	0.48
39.6	455.0	665	1614	0.40	121.6	373.0	1170	6687	0.48
41.2	453.3	675	1614	0.39	123.3	371.3	1132	6383	0.48
42.9	451.7	751	1696	0.38	124.9	369.7	1132	7715	0.49
44.5	450.1	802	1978	0.40	126.5	368.0	1325	8164	0.49
46.2	448.4	872	2258	0.41	128.2	366.4	1978	9118	0.48
47.8	446.8	812	2421	0.44	129.8	364.8	3601	8776	0.40
49.4	445.1	619	2753	0.47	131.5	363.1	3266	8358	0.41
51.1	443.5	633	3066	0.48	133.1	361.5	2925	9001	0.44
52.7	441.9	633	3235	0.48	134.7	359.8	2866	9001	0.44
54.4	440.2	662	3676	0.48	136.4	358.2	3191	8776	0.42
56.0	438.6	688	3564	0.48	138.0	356.6	3343	9889	0.44
57.6	436.9	709	3922	0.48	139.7	354.9	3795	10030	0.42
59.3	435.3	735	4058	0.48	141.3	353.3	4681	10479	0.38
60.9	433.7	685	4530	0.49	142.9	351.6	5240	11702	0.37
62.6	432.0	717	4842	0.49	144.6	350.0	3510	10802	0.44
64.2	430.4	763	5015	0.49	146.2	348.4	4255	10970	0.41
65.8	428.7	780	5617	0.49	147.9	346.7	4388	10325	0.39
67.5	427.1	836	5851	0.49	149.5	345.1	4472	10802	0.40
69.1	425.5	872	6105	0.49	151.1	343.4	4130	10970	0.42
70.8	423.8	906	6105	0.49	152.8	341.8	4530	11510	0.41
72.4	422.2	955	6383	0.49	154.4	340.2	4842	12765	0.42
74.0	420.5	878	6383	0.49	156.1	338.5	5201	12105	0.39
75.7	418.9	872	7021	0.49	157.7	336.9	5851	13502	0.38
77.3	417.3	851	6383	0.49	159.4	335.2	5900	13002	0.37
79.0	415.6	872	6105	0.49	161.0	333.6	6105	14042	0.38
80.6	414.0	851	5851	0.49	162.6	332.0	7391	15263	0.35
82.3	412.3	767	5708	0.49	164.3	330.3	7391	17124	0.39
83.9	410.7	735	5528	0.49	165.9	328.7	7391	15602	0.36
85.2	409.4	731	5401	0.49	167.6	327.0	7801	15602	0.33
87.2	407.4	731	5088	0.49	169.2	325.4	7801	15602	0.33
88.8	405.8	728	5360	0.49	170.8	323.8	7021	15957	0.38
90.5	404.1	699	5319	0.49	172.5	322.1	7021	15602	0.37
92.1	402.5	611	5617	0.49					

Table A-1. Boring L-1, S - R1 quality assurance analysis P- and S<sub>H</sub>-wave data

## BRENT SPENCE BRIDGE REPLACEMENT BORING L-4




Figure A-2. Boring L-4, R1 - R2 high resolution analysis and S - R1 quality assurance analysis P- and S<sub>H</sub>-wave data

Depth (feet)	Elevation (feet)	V <sub>s</sub> (feet/sec)	V <sub>p</sub> (feet/sec)	Poisson's Ratio
12.4	467.6	630	5201	0.49
13.4	466.6	638	5201	0.49
15.0	465.0	674	5572	0.49
16.6	463.3	674	5617	0.49
18.3	461.7	675	5528	0.49
19.9	460.1	690	5617	0.49
21.6	458.4	706	5572	0.49
23.2	456.8	709	5572	0.49
24.8	455.1	706	5528	0.49
26.5	453.5	709	5617	0.49
28.1	451.9	713	5755	0.49
29.8	450.2	724	5662	0.49
31.4	448.6	728	5851	0.49
33.0	446.9	678	5900	0.49
34.7	445.3	709	6383	0.49
36.3	443.7	728	5279	0.49
38.0	442.0	709	5360	0.49
39.9	440.0	826	5755	0.49
41.2	438.7	826	5279	0.49
42.9	437.1	826	5401	0.49
44.5	435.4	826	5572	0.49
46.2	433.8	924	5279	0.48
47.8	432.2	1018	5662	0.48
49.4	430.5	996	6105	0.49
51.1	428.9	989	6159	0.49
52.7	427.2	1010	6213	0.49
54.4	425.6	1032	6105	0.49
56.0	424.0	1064	6053	0.48
57.6	422.3	1072	6269	0.48
59.3	420.7	1056	6213	0.49
60.6	419.4	1025	6325	0.49
62.6	417.4	1010	6269	0.49
64.2	415.8	996	6269	0.49
65.8	414.1	989	6269	0.49
67.5	412.5	942	6053	0.49
69.5	410.5	682	5900	0.49
70.8	409.2	669	5755	0.49
72.7	407.2	522	5485	0.50
74.0	405.9	532	5617	0.50
75.7	404.3	534	5617	0.50
77.0	403.0	585	5617	0.49
79.0	401.0	624	5617	0.49
80.6	399.4	650	5401	0.49
82.3	397.7	650	5401	0.49
83.9	396.1	699	5401	0.49
85.5	394.4	716	5617	0.49
87.2	392.8	841	6383	0.49
88.8	391.2	1040	6751	0.49
90.5	389.5	1448	7092	0.48
92.1	387.9	1596	7469	0.48

Depth (feet)	Elevation (feet)	V <sub>s</sub> (feet/sec)	V <sub>p</sub> (feet/sec)	Poisson's Ratio
93.7	386.2	3177	7715	0.40
95.4	384.6	3026	7801	0.41
97.0	383.0	3191	7801	0.40
98.7	381.3	3425	7715	0.38
100.3	379.7	3177	7715	0.40
101.9	378.0	3177	7391	0.39
103.6	376.4	2507	7801	0.44
105.2	374.8	1734	7801	0.47
106.9	373.1	1300	7391	0.48
108.5	371.5	1265	7391	0.48
110.1	369.8	1138	7021	0.49
111.8	368.2	1048	6687	0.49
113.7	366.2	918	6687	0.49
115.1	364.9	859	7391	0.49
116.7	363.3	962	8260	0.49
118.3	361.6	1288	9361	0.49
120.0	360.0	2006	10802	0.48
121.6	358.3	4012	11510	0.43
123.3	356.7	7021	13247	0.30
124.9	355.1	7021	14042	0.33
126.5	353.4	7021	14042	0.33
128.2	351.8	7021	14627	0.35
129.8	350.1	6687	14627	0.37
131.5	348.5	6687	14627	0.37
133.1	346.9	4530	13247	0.43
134.7	345.2	4255	12765	0.44
136.7	343.3	4388	13767	0.44
138.4	341.6	4388	13002	0.44
139.7	340.3	4388	14042	0.45
141.3	338.7	4681	14042	0.44
142.9	337.0	4681	14042	0.44
144.6	335.4	4842	12765	0.42

Table A-2. Boring L-4, S - R1 quality assurance analysis P- and S<sub>H</sub>-wave data

## BRENT SPENCE BRIDGE REPLACEMENT BORING R-2A




Figure A-3. Boring R-2A, R1 - R2 high resolution analysis and S - R1 quality assurance analysis  $S_H$ -wave data

Depth (feet)	Elevation (feet)	V <sub>s</sub> (feet/sec)	V <sub>p</sub> (feet/sec)	Poisson's Ratio
39.1	418.6	235	5125	0.50
40.7	416.9	250	5220	0.50
42.4	415.3	264	5201	0.50
44.0	413.6	271	5201	0.50
45.6	412.0	277	5401	0.50
47.3	410.4	284	5401	0.50
48.9	408.7	298	5617	0.50
50.6	407.1	315	5617	0.50
52.2	405.4	323	5464	0.50
53.8	403.8	326	5401	0.50
55.5	402.2	319	5401	0.50
57.1	400.5	317	5401	0.50
58.8	398.9	309	4927	0.50
60.4	397.2	309	5182	0.50
62.0	395.6	327	6105	0.50
63.7	394.0	376	5900	0.50
65.3	392.3	399	5685	0.50
67.0	390.7	429	6687	0.50
68.6	389.0	442	6105	0.50
70.2	387.4	417	6105	0.50
71.9	385.8	397	5851	0.50
73.5	384.1	442	5851	0.50
75.2	382.5	539	6562	0.50
76.8	380.8	592	7021	0.50
78.4	379.2	613	7391	0.50
80.1	377.6	1195	8260	0.49
81.7	375.9	1536	7590	0.48
83.4	374.3	2071	7201	0.45
85.0	372.6	2808	8070	0.43
86.6	371.0	3837	7715	0.34
88.3	369.4	4281	8070	0.30
89.9	367.7	4130	10030	0.40
91.6	366.1	4058	9618	0.39
93.2	364.4	3922	8459	0.36
94.8	362.8	4058	10030	0.40
96.5	361.2	3989	9118	0.38
98.1	359.5	4154	9488	0.38
99.8	357.9	4307	10479	0.40
101.4	356.2	4472	10802	0.40
103.0	354.6	4712	10802	0.38
104.7	353.0	5051	11510	0.38
106.3	351.3	5240	12002	0.38
108.0	349.7	5162	12650	0.40
109.6	348.0	5051	12318	0.40
111.3	346.4	4589	12002	0.41
112.9	344.7	4650	10479	0.38
114.5	343.1	4712	11144	0.39
116.2	341.5	4944	11510	0.39
117.8	339.8	5125	11900	0.39
119.5	338.2	5319	11416	0.36

Depth (feet)	Elevation (feet)	V <sub>s</sub> (feet/sec)	V <sub>p</sub> (feet/sec)	Poisson's Ratio
121.1	336.5	6053	11800	0.32
122.7	334.9	6624	11234	0.23
124.4	333.3	6562	12105	0.29
126.0	331.6	6325	12765	0.34
127.7	330.0	5900	12318	0.35
129.3	328.3	5485	11605	0.36
132.6	325.1	4910	9751	0.33
134.2	323.4	4416	10802	0.40
135.9	321.8	4559	10802	0.39
137.5	320.1	5125	11510	0.38
139.1	318.5	5755	10802	0.30
140.8	316.9	6269	12105	0.32
142.4	315.2	6325	13247	0.35
144.1	313.6	6213	11900	0.31
145.7	311.9	6269	10802	0.25
147.3	310.3	6325	11900	0.30
149.0	308.7	6441	12318	0.31
150.6	307.0	7021	12883	0.29
152.3	305.4	7238	13502	0.30
153.9	303.7	7238	14329	0.33
155.5	302.1	7238	14476	0.33
157.2	300.5	7391	14476	0.32

Table A-3. Boring R-2A, S - R1 quality assurance analysis S<sub>H</sub>-wave data



**APPENDIX B**

**GEOPHYSICAL LOGGING SYSTEMS –  
NIST TRACEABLE CALIBRATION  
PROCEDURES AND CALIBRATION RECORDS**

# GEOVision SUSPENSION PS SEISMIC LOGGER/RECORDER CALIBRATION PROCEDURE

Reviewed 7/21/08

## Objective

The timing/sampling accuracy of seismic recorders or data loggers is required for several GEOVision field procedures including Seismic Refraction, Downhole P-S Seismic Velocity Logging, and Suspension P-S Seismic Velocity Logging. This procedure describes the method for measuring the timing accuracy of a seismic data logger, such as the OYO Model 170 or OYO/Robertson Model 3403. The objective of this procedure is to verify that the timing accuracy of the recorder is accurate to within 1%.

## Frequency of Calibration

The calibration of each GEOVision seismic data logger is twelve (12) months. In the case of rented seismic logger/recorders, calibration must be performed prior to use.

## Test Equipment Required

The following equipment is required. Item #2 must have current NIST traceable calibration.

1. Function generator, Krohn Hite 5400B or equivalent
2. Frequency counter, HP 5315A or equivalent
3. Test cables, from item 1 to item 2, and from item 1 to subject data logger.

## Procedure

This procedure is designed to be performed using the accompanying Suspension P-S Seismic Logger/Recorder Calibration Data Form with the same revision number. All data must be entered and the procedure signed by the technician performing the test.

1. Record all identification data on the form provided.
2. Connect function generator to data logger (such as OYO Model 170) using test cable
3. Connect the function generator to the frequency counter using test cable.
4. Set signal generator to target frequency specified on data form, 0.25 volt (amplitude is approximate, modify as necessary to yield less than full scale waveforms on



Suspension PS Seismic Logger/Recorder Calibration Procedure  
Revision 2.0 Page 1

logger display) peak sine wave. Verify frequency using the counter and note actual frequency on the data form.

5. Set data logger to file length specified on data form and record a data file to disk. Note file name on data form.
6. Measure the duration of 9 complete sine wave cycles on the data file. This measurement must be made using the analysis program PSLOG.EXE version 1.00, and saved as a .sps pick file. Note the duration in milliseconds in the spaces provided on the data form. Calculate average recorded sine wave frequency for each channel pair (Hn, Hr, V) by dividing the duration by 9. Note the average frequency of each channel pair on the data form.
7. Repeat steps 4 through 6 until all target frequencies have been recorded, producing 6 separate data and pick files.

**Criteria**

The average frequency for the nine cycles (obtained by dividing 9 cycles by the duration in seconds) must be within plus or minus 1% of the actual frequency for each of the 6 records.

If the results are outside this range, the data logger must be marked with a GEOVision REJECT tag until it can be repaired and retested.

If results are acceptable affix label indicating the initials of the person performing the calibration, the date of calibration, and the due date for the next calibration (12 months).

**Procedure Approval**

Approved by:

\_\_\_\_\_ John G. Diehl \_\_\_\_\_

Name

\_\_\_\_\_  
Signature

\_\_\_\_\_ President \_\_\_\_\_

Title

\_\_\_\_\_ July 21, 2008 \_\_\_\_\_

Date


Calibration Laboratory Approval (if required):

\_\_\_\_\_  
Name

\_\_\_\_\_  
Title

\_\_\_\_\_  
Signature

\_\_\_\_\_  
Date

	Suspension PS Seismic Logger/Recorder Calibration Procedure Revision 2.0 Page 2
---	--



MICRO PRECISION CALIBRATION, INC.  
 12686 HOOVER STREET  
 GARDEN GROVE CA. 92841-1823  
 714.901.5659

## Certificate of Calibration

Date: 10/16/2009

Lab # AC-1274

Certificate #: 749437

**Customer:**

GEOVISION  
 1124 OLYMPIC DRIVE  
 CORONA, CA, 92881

Purchase Order: 9333-100601-001  
 Work Order: 61143

MPC Control #: AM6767  
 Asset ID: 160023  
 Gage Type: LOGGER  
 Manufacturer: OYO  
 Model Number: 3403  
 Size: N/A  
 Temp./RH: 73 °F / 45 %

Serial Number: 160023  
 Department: N/A  
 Performed By: KYU HAN  
 Received Condition: IN TOLERANCE  
 Returned Condition: IN TOLERANCE  
 Cal Date: October 12, 2009  
 Cal. Interval: 12 MONTHS  
 Cal. Due Date: October 12, 2010

**Found conditions meet or exceed manufacturer specifications.**

**\*Calibration Notes:**

The UUT (unit under test) was calibrated using the customers procedures in our Garden Grove lab. The UUT was operated by the customers personnel and data collection was observed by MPC personnel. The UUT was found to be in tolerance to customer supplied specifications. The reference standards used are in compliance with ISO/IEC 17025:2005, ISO9001:2000, ANSI/NCSL Z540-1-1994 and laboratory accreditation for lab code 935.11. Frequency is accredited. Measurement uncertainty is 0.2 x E12 Hz. Please see attached data sheet.

**Standards Used To Calibrate Equipment**

I.D.	Description	Model	Serial	Manufacturer	Cal. Due Date	Traceability #
AM4000	WAVEFORM GENERATOR	33250A	MY40000703	AGILENT	7/15/2010	662404
T1100	COUNTER	53131A	3546A09912	HEWLETT PACKARD	1/12/2010	646688

Calibrating Technician:

KYU HAN

QC Approval:

Tammy Webster

Unless Otherwise Noted, Uncertainty Estimated at  $\geq 4$  to 1. Uncertainties have been estimated at a 95 percent confidence level (k=2). Services rendered comply with ISO 17025:2005, ISO 9001:2000, ANSI/NCSL Z540-1, MPC Quality Manual, MPC CSD and with customer purchase order instructions.

Calibration cycles and resulting due dates were submitted/approved by the customer. Any number of factors may cause an instrument to drift out of tolerance before the next scheduled calibration. Recalibration cycles should be based on frequency of use, environmental conditions and customer's established systematic accuracy. The information on this report, pertains only to the instrument identified.

All standards are traceable to the National Institute of Standards and Technology (NIST). Services rendered include proper manufacture's service instructions and are warranted for no less than (30) days. This report may not be reproduced in part or in whole without the prior written approval of the issuing MPC lab.

AM 6767



**SUSPENSION PS SEISMIC LOGGER/RECORDER CALIBRATION DATA FORM**

**INSTRUMENT DATA**

System mfg.:	Oyo	Model no.:	3403
Serial no.:	160023	Calibration date:	10/12/2009
By:	Charles Carter	Due date:	10/12/2010
Counter mfg.:	Hewlett-Packard	Model no.:	53131A
Serial no.:	3546a09912	Calibration date:	1/12/2009
By:	Microprecision	Due date:	1/12/2010
Signal generator mfg.:	Agilent	Model no.:	33250A
Serial no.:	MY40000703	Calibration date:	7/15/2009
By:	Microprecision	Due date:	7/15/2010

**SYSTEM SETTINGS:**

Gain:	2
Filter:	10KHz
Range:	See sample period in table below
Delay:	0
Stack (1 std):	1
System date = correct date and time	10/12/2009

**PROCEDURE:**

Set sine wave frequency to target frequency with amplitude of approximately 0.25 volt peak  
 Note actual frequency on data form.  
 Set sample period and record data file to disk. Note file name on data form.  
 Pick duration of 9 cycles using PSLOG.EXE program, note duration on data form, and save as .sps file. Calculate average frequency for each channel pair and note on data form.  
 Average frequency must be within +/- 1% of actual frequency at all data points.

Maximum error ((AVG-ACT)/ACT\*100)%      As found      + 0.20%      As left      + 0.20%

Target Frequency (Hz)	Actual Frequency (Hz)	Sample Period (microS)	File Name	Time for 9 cycles Hr (msec)	Average Frequency Hr (Hz)	Time for 9 cycles Hr (msec)	Average Frequency Hr (Hz)	Time for 9 cycles V (msec)	Average Frequency V (Hz)
50.00	50.00	200	2	180.2	49.94	179.8	50.06	180.2	49.94
100.0	100.0	100	3	90.00	100.0	90.10	99.9	90.00	100.0
200.0	200.0	50	4	44.95	200.2	44.95	200.2	44.95	200.2
500.0	500.0	20	5	18.00	500.0	18.00	500.0	18.00	500.0
1000	1000	10	6	9.000	1000	8.990	1001.1	9.000	1000.0
2000	2000	5	7	4.495	2002	4.505	1998	4.500	2000

Calibrated by: Charles Carter      10/12/2009      *Charles Carter*  
 Name      Date      Signature

Witnessed by: Kyu Han      10/12/2009      *[Signature]*  
 Name      Date      Signature

Suspension PS Seismic Recorder/Logger Calibration Data Form Rev 2.0 July 21, 2008

**Geotechnical Engineering Report**

Brent Spence Bridge Replacement ■ Cincinnati, Ohio-Covington, Kentucky

March 11, 2011 ■ HCN/Terracon Project No. N1105070



**EXHIBIT A-12**  
**PHOTO SCIENCE GEOSPATIAL SOLUTIONS REPORT**

September 14, 2010

**REVISED**

Survey Report of  
BSB River Boring Locations

For

Parson Brinckerhoff Americas, Inc.  
312 Elm Street Suite 2500  
Cincinnati, OH 45202

PSI NO. 7069-005

presented by



2670 Wilhite Drive  
Lexington, KY 40503  
859-277-8700



2670 WILHITE DRIVE  
LEXINGTON, KENTUCKY 40503  
PHONE 859-277-8700 + FAX 859-277-8901  
WWW.PHOTOSCIENCE.COM

September 14, 2010

**Revision**

## **Report of Field Survey**

### **BSB River Boring Locations**

### **PSI Project Number 7069-005**

Purpose of this revision is to include three additional Borings that were conducted by H.C. Nutting after the original survey report was submitted.

One River Boring (R2-A) and two Land Borings (L1-2 and L1A-2) were surveyed on August 27, 2010.

#### **NAD83 KY Single Zone USFeet NAVD88**




	<b>Northing</b>	<b>Easting</b>	<b>Elevation</b>	
L1A-2	4288504.15	5269616.44	489.72	Ground
L1-2	4288344.49	5269644.75	494.59	Ground
R2-A	4287656.44	5269581.56	457.64	Top of Deck

#### **NAD83 Ohio South Zone USFeet NAVD88**

	<b>Northing</b>	<b>Easting</b>	<b>Elevation</b>	
L1A-2	404978.23	1394463.06	489.72	Ground
L1-2	404817.69	1394485.67	494.59	Ground
R2-A	404132.45	1394398.08	457.64	Top of Deck

\*\* It should be noted that no Borings were conducted at original sites L1 and L1A. These locations were within Duke Energy's property and not accessible for H.C. Nutting Drilling Rigs.





L1A-2

L1A

L1

L1-2

L2A

L2

L3A

L3B

R3

R2

R1

R4

R2-A

use St

75

Brent Spence Br

Image U.S. Geological Survey

© 2010 Google

© 2010 Europa Technologies

Imagery Date: May 7, 2007

39°05'35.10" N 84°31'20.19" W elev 476 ft

Eye alt 1488 ft

© 2009 Google







July 16, 2010

## Survey Report of BSB River Boring Locations

For

Parson Brinckerhoff Americas, Inc.  
312 Elm Street Suite 2500  
Cincinnati, OH 45202

PSI NO. 7069-005

presented by



2670 Wilhite Drive  
Lexington, KY 40503  
859-277-8700



2670 WILHITE DRIVE  
LEXINGTON, KENTUCKY 40503  
PHONE 859-277-8700 + FAX 859-277-8901  
WWW.PHOTOSCIENCE.COM

July 16, 2010

## **Report of Field Survey**

### **BSB River Boring Locations**

### **PSI Project Number 7069-005**

Photo Science, Inc. was given permission to proceed on June 29, 2010 by Duane Phelps of Parsons Brinckerhoff Americas, Inc for field surveying services at the Brent Spence Bridge Boring Site under Task Order 7.1.10.5. The field survey for this project was to locate approximately eighteen boring locations within the project area and a large culvert on the Kentucky side of the Ohio River.

A two-person RTK (real time kinematics) GPS crew was mobilized to the site on July 1, 2010. The crew was equipped with dual-frequency Trimble 5700 Base, Trimble R8 Rover GPS units, and Trimble TRIMMARK 3 Radio, to establish horizontal and vertical control values for the Boring Locations. The crew used BSB/PSI's control monuments 11 and 12 as base known positions.

Both RTK and Traditional surveying techniques were used in locating the Boring's. All River Borings were located with a TOPCON GTS223 Total Station by making use of two control points set by RTK near the River's Edge. When allowable, boring locations on land were located by direct RTK occupation. If the boring location wasn't suitable for direct occupation, a pair of control points were established nearby and then located with the total station.

At this time the culvert on the Kentucky side has not been surveyed. Photo Science is waiting on additional information from Mr. Phelps as to the location of the culvert. The Surveying Crew made a thorough search of the river bank for evidence of said culvert without uncovering any indication of its location. It's possible the culvert is below the waterline or is covered with debris.





Final position summary sheet is provided for both, Kentucky State Plane Single and Ohio South Zones. Also included is a photo of each "survey setup" on the boring locations.

The horizontal datum is based on NAD 83 (2007) while the vertical datum is NAVD 88.

PHOTO SCIENCE, INC.  
 BSB BORE HOLES  
 KENTUCKY-OHIO  
 PSI #7069-005

PT#	Northing(Y) (SPC KY SINGLE) US FEET	Easting(X) (SPC KY SINGLE) US FEET	Elev(Z) NAVD 88 US FEET	Description
L2	4288131.73	5269499.24	496.26	L2 GROUND
L2A	4288244.14	5269607.61	494.50	L2A GROUND
L3A	4288035.34	5269496.11	496.05	L3A GROUND
L3B	4287897.88	5269553.98	458.66	L3B TOP OF DECK
L4	4286513.60	5269492.16	479.97	L4 GROUND
L5	4286320.80	5269488.42	486.33	L5 GROUND
L6	4286195.50	5269554.96	485.69	L6 GROUND
L7	4286100.55	5269491.85	484.41	L7 GROUND
R1	4287721.26	5269583.28	458.04	R1 TOP OF DECK
R2	4287702.96	5269562.17	458.10	R2 TOP OF DECK
R3	4287727.53	5269506.27	458.01	R3 TOP OF DECK
R4	4287670.82	5269503.75	457.98	R4 TOP OF DECK
R5	4286731.27	5269570.19	458.59	R5 TOP OF DECK
R6	4286646.07	5269550.32	457.04	R6 GROUND
R7	4286733.89	5269479.10	458.46	R7 TOP OF DECK
R8	4286646.68	5269468.06	455.70	R8 GROUND

PT#	Northing(Y) (SPC OH S) US FEET	Easting(X) (SPC OH S) US FEET	Elev(Z) NAVD 88 US FEET	Description
L2	404610.28	1394332.72	496.26	L2 GROUND
L2A	404718.74	1394445.00	494.50	L2A GROUND
L3A	404514.08	1394326.17	496.05	L3A GROUND
L3B	404374.67	1394379.10	458.66	L3B TOP OF DECK
L4	402993.71	1394268.14	479.97	L4 GROUND
L5	402801.20	1394257.55	486.33	L5 GROUND
L6	402673.64	1394319.58	485.69	L6 GROUND
L7	402581.01	1394253.15	484.41	L7 GROUND
R1	404197.15	1394402.10	458.04	R1 TOP OF DECK
R2	404179.62	1394380.36	458.10	R2 TOP OF DECK
R3	404206.16	1394325.38	458.01	R3 TOP OF DECK
R4	404149.58	1394320.85	457.98	R4 TOP OF DECK
R5	403208.43	1394353.84	458.59	R5 TOP OF DECK
R6	403124.01	1394330.96	457.04	R6 GROUND
R7	403214.29	1394262.92	458.46	R7 TOP OF DECK
R8	403127.54	1394248.79	455.70	R8 GROUND



L1A-2

L1A

L1

L1-2

L2A

L2

L3A

L3B

R3

R2

R1

R4

R2-A

use St

75

Brent Spence Br

Image U.S. Geological Survey

© 2010 Google

© 2010 Europa Technologies


Imagery Date: May 7, 2007

39°05'35.10" N 84°31'20.19" W elev 476 ft

Eye alt 1488 ft

© 2009 Google





71

R7

R5

R8

R6

L4

L5

L6

L7

8

W 3rd St

Brent Spence Brg

Image U.S. Geological Survey  
© 2010 Google

Google

2009

Eye alt 1540 ft

Imagery Date: May 7, 2007

39°05'17.86" N 84°31'24.76" W elev 486 ft





















Brent Spence Bridge  
7/1/10  
CORE HOLE  
L5











BSB  
R-2



BSB  
CORE HOLE  
R-5











BSB  
CORE HOLE  
R-7







BSB  
Cott. Hole  
R-8









BSB

R-1











BSB

R-4



# Kentucky Transportation Cabinet Ohio Department of Highways I-75 I-71 Control



## Control Monument Information Sheet


Site/Quad  Covington	Station Description (Description is to be complete) (type, size, depth set, etc.) Concrete Monument 5/8" Rebar 2 1/2" Aluminum Cap 24" Concrete			Station Designation  MON 11	
Locality/County  Kenton				Stamping on Mark  I75-I71 CONTROL	
Date Set or Found (Date, with S or F)  2/22/2010 S	Latitude 39°05'11.19732"N	Longitude 84°31'17.39378"W	Horiz. Datum NAD83	Zone KY Single	Vert. Datum 1988
	Northing (KY SP1Z) (US Survey Feet) 4,285,659.91	Easting (KY SP1Z) (US Survey Feet) 5,270,007.96	Elevation 496.51	Derived From Level	Order Accuracy 3rd
Person filling out form  AFS	Northing (OH SPSZ) (US Survey Feet) 402122.39	Easting (OH SPSZ) (US Survey Feet) 1394753.18	Geoid Model Geoid 09	Ellipsoid Ht. 384.64	Other Info.
Established by Agency  Photo Science, Inc.	Project Factor	Back Station I.D.	Datum Azimuth - Distance to back station  ° ' " (ft)		
Scale Factor 1.00012828	Elev. Factor 0.99998164	Ahead Station I.D.	Datum Azimuth - Distance to ahead station  ° ' " (ft)		

Kentucky Registered Land Surveyor in charge of monumentation

Anthony F. Stith

Ky. Registration No.  
1877

Give a complete sketch and location description so that monument may be recovered by others





GPS CONTROL SURVEY  
FIELD DATA SHEET

PAGE:

2

JOB REFERENCE  
I-75 & I-71 Control

POINT ID:  
Proj. No.:

Mon 11  
7069-004

2670 Wilhite Drive  
Lexington, KY 40503  
859-277-8700 voice 859-277-8901 fax

PHOTO:



PHOTO:




PHOTO:




PHOTO:







**Kentucky Transportation Cabinet  
Ohio Department of Highways  
I-75 I-71 Control**



**Control Monument  
Information Sheet**

Site/Quad <b>Covington</b>	Station Description (Description is to be complete) (type, size, depth set, etc.) <b>Concrete Monument 5/8" Rebar 2 1/2" Aluminum Cap 24" Concrete</b>			Station Designation <b>MON 12</b>	
Locality/County <b>Hamilton</b>				Stamping on Mark <b>I75-I71 CONTROL</b>	
Date Set or Found (Date, with S or F)  <b>2/22/2010 S</b>	Latitude <b>39°05'39.45612"N</b>	Longitude <b>84°31'08.62875"W</b>	Horiz. Datum <b>NAD83</b>	Zone <b>KY Single</b>	Vert. Datum <b>1929</b>
	Northing (KY SP1Z) (US Survey Feet) <b>4,288,528.22</b>	Easting (KY SP1Z) (US Survey Feet) <b>5,270,661.40</b>	Elevation <b>486.48</b>	Derived From Level	Order Accuracy <b>3rd</b>
Person filling out form  <b>AFS</b>	Northing (OH SPSZ) (US Survey Feet) <b>404965.15</b>	Easting (OH SPSZ) (US Survey Feet) <b>1395508.02</b>	Geoid Model <b>Geoid 09</b>	Ellipsoid Ht. <b>374.55</b>	Other Info.
Established by Agency  <b>Photo Science, Inc.</b>	Project Factor	Back Station I.D.	Datum Azimuth - Distance to back station  ° ' " (ft)		
Scale Factor <b>1.00013119</b>	Elev. Factor <b>0.99998212</b>	Ahead Station I.D.	Datum Azimuth - Distance to ahead station  ° ' " (ft)		


Kentucky Registered Land Surveyor in charge of monumentation

**Anthony F. Stith**

Ky. Registration No.  
**1877**

Give a complete sketch and location description so that monument may be recovered by others

- A) 25.0ft flag pole.
- B) 30.0ft NW corner of sign column.
- C) 3.0ft to edge of sidewalk.





GPS CONTROL SURVEY  
FIELD DATA SHEET

PAGE:

2

JOB REFERENCE  
I-75 & I-71 Control

POINT ID: Mon 12  
Proj. No.: 7069-004

2670 Wilhite Drive  
Lexington, KY 40503  
859-277-8700 voice 859-277-8901 fax

PHOTO:



PHOTO:



PHOTO:



PHOTO:



**Geotechnical Engineering Report**

Brent Spence Bridge Replacement ■ Cincinnati, Ohio-Covington, Kentucky  
March 11, 2011 ■ HCN/Terracon Project No. N1105070



**APPENDIX B**  
**LABORATORY TESTING**

**Geotechnical Engineering Report**

Brent Spence Bridge Replacement ■ Cincinnati, Ohio-Covington, Kentucky

March 11, 2011 ■ HCN/Terracon Project No. N1105070



**EXHIBIT B-1**  
**LABORATORY TEST RESULTS**  
**(Sieve, Hydrometer, Atterberg Limits, Moisture)**

**Laboratory Test Results**

Brent Spence Bridge Replacement ■ Cincinnati, Ohio  
 March 11, 2011 ■ HCN/Terracon Project No. N1105070



Classification Test Data														
Boring No.	Sample ID	Top Depth (feet)	Bottom Depth (feet)	Gradation (%)					Atterberg			Moisture Content (%)	ODOT Classification (GI)	LOI (%)
				Gravel	Coarse Sand	Fine Sand	Silt	Clay	Liquid Limit	Plastic Limit	Plasticity Index			
L-1	1	6	7.5									17.2		
	2	7.5	9	16.9	4.7	27.3	35.7	15.4	27	17	10	30.4	A-4a(3)	
	3	10	11.5	0.0	0.0	36.5	46.6	16.9	24	16	8	19.0	A-6a(6)	
	5	14	16.5	0.0	0.4	23.9	55.8	19.9	27	17	10	22.4	A-6b(8)	
	6	17.5	19									22.9		1.60
	7	20	21.5	0.0	0.0	43.5	40.3	16.2	20	18	2	20.6	A-6a(4)	
	8	25	26.5									18.9		
	9	30	31.5	0.0	1.4	35.9	44.3	18.4	23	17	6	18.7	A-4a(6)	
	10	35	36.5									27.9		
	11	40	41.5	37.3	19.1	17.3	19.5	6.8	24	16	8	14.5	A-2-4(0)	
	12	45	46.5	61.4	19.7	11.1	6.1	1.7	NP	NP	NP	10.3	A-1-a(0)	
	13	50	51.5									15.1		
	14	55	56.5	11.6	32.1	38.6	13.5	4.2	NP	NP	NP	16.2	A-3a(0)	
	15	60	61.5									18.5		
	16	65	66.5	6.1	27.1	53.9	8.8	4.1	NP	NP	NP	19.1	A-3a(0)	
	17	70	71.5									10.7		
	18	75	76.5	32.5	20.3	37.6	6.2	3.4	NP	NP	NP	15.4	A-1-b(0)	
	19	80	81.5									59.2		
	20	85	86.5	0.9	20.6	70.7	4.1	3.7	NP	NP	NP	21.7	A-3(0)	
	21	90	91.5									11.3		
	20	85	86.5	*										
	21	90	91.5	*										
	22	95	96.5	47.8	25.5	19.9	5.1	1.7	NP	NP	NP	11.4	A-1-b(0)	
	23	100	101.5									23.0		
	24	105	106.5									22.7		
	25	110	111.5	58.0	21.2	12.6	7.1	1.1	NP	NP	NP	12.1	A-1-a(0)	
	26	115	116.5									9.5		
	27	120	121.5	10.5	52.4	29.2	6.6	1.3	NP	NP	NP	15.4	A-1-b(0)	
	28	125	126.5									9.6		

**Laboratory Test Results**

Brent Spence Bridge Replacement ■ Cincinnati, Ohio  
 March 11, 2011 ■ HCN/Terracon Project No. N1105070



Classification Test Data															
Boring No.	Sample ID	Top Depth (feet)	Bottom Depth (feet)	Gradation (%)					Atterberg			Moisture Content (%)	ODOT Classification (GI)	LOI (%)	
				Gravel	Coarse Sand	Fine Sand	Silt	Clay	Liquid Limit	Plastic Limit	Plasticity Index				
L-1A	1	5	6.5										28.6		
	2	7.5	9	0.0	0.0	32.4	49.0	18.6	26	16	10	19.4	A-4a(7)		
	3	10	11.5	0.4	1.8	17.8	51.9	18.1	24	16	8	20.0	A-4a(7)		
	5	15	16.5	0.0	2.0	48.2	38.5	11.3	NP	NP	NP	22.0	A-4a(0)		
	6	17.5	19									21.4			
	7	20	21.5	0.0	0.0	29.9	51.1	19.0	25	16	9	21.9	A-4b(7)		
	9	25	26.5									24.9			
	10	30	31.5	0.0	0.0	15.4	62.6	22.0	28	18	10	29.0	A-4b(8)		
	11	35	36.5	0.0	0.0	30.1	54.2	15.7	27	20	7	26.1	A-4b(7)		
	12	40	41.5	52.3	25.1	93.0	9.6	3.7	NP	NP	NP	8.1	A-1-a(0)		
	13	45	46.5	18.6	27.3	36.9	12.8	4.4	NP	NP	NP	17.6	A-3a(0)		
	14	50	51.5	0.6	22.3	59.5	13.1	4.5	NP	NP	NP	22.2	A-3a(0)		
	15	55	56.5									18.3			
	16	60	61.5	21.8	13.3	33.9	20.9	10.1	NP	NP	NP	20.8	A-2-4(0)		
	17	65	66.5									17.4			
	18	70	71.5	2.6	32.2	57.2	3.8	4.2	NP	NP	NP	19.7	A-3(0)		
	19	75	76.5									14.0			
	20	80	81.5	7.3	28.2	55.5	4.9	4.1	NP	NP	NP	18.5	A-3(0)		
	21	85	86.5									20.9			
	22	90	91.5	39.1	20.5	33.8	4.0	2.6	NP	NP	NP	13.9	A-1-b(0)		
	23	95	96.5									20.1			
	24	100	101.5	32.2	30.9	27.9	6.0	3.0	NP	NP	NP	15.1	A-1-b(0)		
	25	105	106.5									15.8			
	26	110	111.5	43.0	34.8	15.9	3.9	2.4	NP	NP	NP	9.2	A-1-b(0)		
	27	115	116.5									8.1			
	28	120	121.5	74.2	7.0	11.6	5.1	2.1	Insufficient Sample			8.5	A-1-a(0)		

**Laboratory Test Results**

Brent Spence Bridge Replacement ■ Cincinnati, Ohio  
 March 11, 2011 ■ HCN/Terracon Project No. N1105070



Classification Test Data															
Boring No.	Sample ID	Top Depth (feet)	Bottom Depth (feet)	Gradation (%)					Atterberg			Moisture Content (%)	ODOT Classification (GI)	LOI (%)	
				Gravel	Coarse Sand	Fine Sand	Silt	Clay	Liquid Limit	Plastic Limit	Plasticity Index				
L-2	3	15	16.5										35.1		
	4	17.5	19										36.9		
	5	20	21.5										34.2		
	6	25	26.5										40.4		
	7	30	31.5	27.0	23.0	9.5	20.5	20.0	35	17	18	15.7	A-6b(3)		
	8	35	36.5									30.3			
	9	40	41.5	0.0	0.2	7.7	60.5	31.6	48	29	19	38.2	A-7-6(13)		
	11	46.5	48									31.6			
	12	50	51.5									23.7			
	14	60	61.5									21.5			
	15	65	66.5	7.8	45.4	37.6	6.1	3.1				24.8	A-1-b(0)		
	17	75	76.5									31.0			
	20	90	91.5									31.7			
	21	95	96.5	3.2	33.7	54.4	5.9	2.8				20.1	A-3(0)		
	22	100	101.5									14.7			
	23	105	106.5									8.3			
	24	110	111.5									19.0			

**Laboratory Test Results**

Brent Spence Bridge Replacement ■ Cincinnati, Ohio  
 March 11, 2011 ■ HCN/Terracon Project No. N1105070



Classification Test Data														
Boring No.	Sample ID	Top Depth (feet)	Bottom Depth (feet)	Gradation (%)					Atterberg			Moisture Content (%)	ODOT Classification (GI)	LOI (%)
				Gravel	Coarse Sand	Fine Sand	Silt	Clay	Liquid Limit	Plastic Limit	Plasticity Index			
L-2A	1	3	4.5									8.8		
	2	5	6.5									9.4		
	3	7.5	9									45.8		
	4	10	11.5									21.9		
	5	12.5	14									14.8		
	6	15	16.5									14.4		
	7	18	20	0.0	0.2	38.1	49.5	12.2	NP	NP	NP	32.4	A-4a(0)	4.90
	8	20	21.5									23.8		
	9	25	26.5									28.6		
	10	30	31.5									44.1		
	11	35	36.5	47.8	23.9	16.5	8.9	2.9	NP	NP	NP	12.6	A-1-b(0)	
	13	41.5	43									21.5		
	14	45	46									7.6		
	15	50	51.5	30.3	30.3	26.0	9.9	3.5	NP	NP	NP	15.0	A-1-b(0)	
	16	55	56.5									16.5		
	17	60	61.5									14.8		
	18	65	66.5									15.7		
	19	70	71.5	0.7	35.3	54.0	5.8	4.2	NP	NP	NP	18.8	A-3(0)	
	20	75	76.5	37.3	32.5	21.3	6.4	2.5				10.5	A-1-b(0)	
	21	80	81.5									9.5		
	22	85	86.5	49.6	34.0	9.8	4.1	2.5	NP	NP	NP	11.3	A-1-b(0)	
	23	90	91.5									22.0		
	24	95	96.5	21.2	39.9	29.2	7.4	2.3				15.4	A-1-b(00)	
	25	100	101.5									10.4		
	26	105	106.5	1.0	3.4	79.6	12.2	3.8	NP	NP	NP	23.7	A-3a(0)	
	27	110	111.5									22.7		
	28	115	116.5	53.9	22.1	13.6	7.3	3.1				8.2	A-1-a(0)	
	29	120	121.5									6.8		
	30	125	126.5									6.5		



**Laboratory Test Results**

Brent Spence Bridge Replacement ■ Cincinnati, Ohio  
 March 11, 2011 ■ HCN/Terracon Project No. N1105070



Classification Test Data															
Boring No.	Sample ID	Top Depth (feet)	Bottom Depth (feet)	Gradation (%)					Atterberg			Moisture Content (%)	ODOT Classification (GI)	LOI (%)	
				Gravel	Coarse Sand	Fine Sand	Silt	Clay	Liquid Limit	Plastic Limit	Plasticity Index				
L-3	2	21	22.5										29.3		
	3	22.5	24	29.1	36.0	24.3	6.1	4.5	NP	NP	NP	25.7	A-1-b(0)		
	6	30	31.5									7.5			
	7	32.5	34	6.1	25.9	63.0	2.6	2.4	NP	NP	NP	23.1	A-3(0)		
	8	35	36.5									52.0			
	9	40	41.5	1.1	38.6	56.3	2.0	2.0	NP	NP	NP	24.6	A-3(0)		
	10	45	46.5									4.6			
	11	50	51.5	61.7	13.8	15.9	6.2	2.4	NP	NP	NP	10.4	A-1-a(0)		
	12	55	56.5	4.1	31.9	54.1	6.0	3.9	NP	NP	NP	24.2	A-3(0)		
	13	60	61.5	11.7	27.9	54.8	3.4	2.2	NP	NP	NP	20.6	A-3(0)		
	14	65	66.5	27.2	36.1	28.9	5.2	2.6	NP	NP	NP	14.5	A-1-b(0)		
	15	70	71.5	21.7	58.0	14.6	3.0	2.7	NP	NP	NP	16.3	A-1-b(0)		
	16	75	76.5	9.3	52.2	32.8	3.5	2.2	NP	NP	NP	18.8	A-1-b(0)		

**Laboratory Test Results**

Brent Spence Bridge Replacement ■ Cincinnati, Ohio  
 March 11, 2011 ■ HCN/Terracon Project No. N1105070



Classification Test Data														
Boring No.	Sample ID	Top Depth (feet)	Bottom Depth (feet)	Gradation (%)					Atterberg			Moisture Content (%)	ODOT Classification (GI)	LOI (%)
				Gravel	Coarse Sand	Fine Sand	Silt	Clay	Liquid Limit	Plastic Limit	Plasticity Index			
L-3A	1	7.5	9									24.6		
	2	10.0	11.5									21.6		
	3	12.5	14.0									35.8		
	4	15.0	16.5									39.2		
	5	17.5	19.0	49.1	30.5	9.8	6.5	4.1	Insufficient Sample			64.5	A-1-b	
	6	20.0	21.5									39.9		
	7	25.0	26.5									43.3		
	8	30.0	31.5	25.2	32.4	24.6	9.0	8.8	Insufficient Sample			61.8	A-1-b	
	9	35.0	36.5									46.5		
	10	40.0	41.5									85.8		
	11	45.0	46.5									29.1		
	12	50.0	51.5	17.2	17.2	21.5	24.0	20.1	26	17	9	26.6	A-4a(2)	
	14	60.0	61.5									17.9		
	15	65.0	66.5									28.6		
	16	70.0	71.5									17.8		
	17	75.0	76.5	6.6	38.4	45.2	4.6	5.2	NP	NP	NP	20.3	A-3	
	18	80.0	81.5									18.7		
	19	85.0	86.5									14.0		
	20	90.0	91.5									23.6		
	21	95.0	96.5									18.2		
	23	105.0	106.5	38.7	33.1	23.4	1.4	3.4	NP	NP	NP	17.7	A-1-b	
	24	110.0	111.5									14.2		
	25	115.0	116.5									16.7		
	26	120.0	121.5	59.1	17.2	16.8	3.9	3.0	NP	NP	NP	12.2	A-1-a	
	27	122.5	124.0									19.6		

**Laboratory Test Results**

Brent Spence Bridge Replacement ■ Cincinnati, Ohio  
 March 11, 2011 ■ HCN/Terracon Project No. N1105070



Classification Test Data															
Boring No.	Sample ID	Top Depth (feet)	Bottom Depth (feet)	Gradation (%)					Atterberg			Moisture Content (%)	ODOT Classification (GI)	LOI (%)	
				Gravel	Coarse Sand	Fine Sand	Silt	Clay	Liquid Limit	Plastic Limit	Plasticity Index				
L-4	1	0.0	1.5										37.7		
	2	2.5	4.0										18.7		
	3	5.0	6.5										26.1		
	4	7.5	9.0	10.0	24.1	18.2	31.2	16.5	35	24	11	26.9	A-6a(3)		
	5	10.0	11.5										132.4		
	6	12.5	14.0										17.6		
	8	17.5	19.0										23.5		
	9	20.0	21.5										27.8		
	10	25.0	26.5	0.0	0.2	1.8	61.6	36.4	50	29	21	44.3	A-7-6(14)	5.40	
	ST/11	30.0	32.0	0.0	0.0	0.6	62.1	37.3	46	25	21		A-7-6(14)		
	12	32.0	33.5										43.6		
	13	35.0	36.5										31.9		
	14	40.0	41.5										24.4		
	15	45.0	46.5										7.0		
	16	50.0	51.5										10.0		
	17	55.0	56.5	53.4	9.2	27.2	7.2	3.0	NP	NP	NP	12.2	A-1-b(0)		
	18	60.0	61.5										13.5		
	19	65.0	66.5										7.4		
	20	70.0	71.5	56.0	24.5	13.3	3.7	2.5	NP	NP	NP	10.5	A-1-a(0)		
	21	75.0	76.5										9.6		
	22	80.0	81.5	19.1	63.1	11.5	3.4	2.9	NP	NP	NP	17.5	A-1-b(0)		
	23	85.0	86.5										15.2		
	24	90.0	91.5										5.6		
	25	95.0	96.5										11.4		

**Laboratory Test Results**

Brent Spence Bridge Replacement ■ Cincinnati, Ohio  
 March 11, 2011 ■ HCN/Terracon Project No. N1105070



Classification Test Data														
Boring No.	Sample ID	Top Depth (feet)	Bottom Depth (feet)	Gradation (%)					Atterberg			Moisture Content (%)	ODOT Classification (GI)	LOI (%)
				Gravel	Coarse Sand	Fine Sand	Silt	Clay	Liquid Limit	Plastic Limit	Plasticity Index			
L-5	1	5.0	6.5									37.8		
	2	7.5	9.0									19.6		
	3	10.0	11.5									20.5		
	4	12.5	14.0									16.5		
	5	15.0	16.5									25.8		
	7	20.0	21.5									22.8		
	8	23.0	25.0	0.0	0.2	15.6	45.1	38.1	29	17	12		A-6a(9)	
	9	25.0	26.5									22.1		
	10	30.0	31.5									26.8		
	11	35.0	36.5									27.4		
	12	38.0	40.0	0.0	0.2	20.9	47.7	31.2	29	19	10		A-4a(8)	
	13	40.0	41.5									28.0		
	14	45.0	46.5									13.4		
	15	50.0	51.5									17.7		
	16	55.0	56.5									7.8		
	17	60.0	61.5									13.9		
	18	65.0	66.5									10.8		
	19	70.0	71.5									10.8		
	20	75.0	76.5	55.4	17.5	17.2	6.8	3.1	NP	NP	NP	11.5	A-1-a(0)	
	21	80.0	81.5									10.1		
	22	85.0	86.5									8.6		
	23	90.0	91.5									9.8		
	24	95.0	96.5									7.3		

**Laboratory Test Results**

Brent Spence Bridge Replacement ■ Cincinnati, Ohio  
 March 11, 2011 ■ HCN/Terracon Project No. N1105070



Classification Test Data															
Boring No.	Sample ID	Top Depth (feet)	Bottom Depth (feet)	Gradation (%)					Atterberg			Moisture Content (%)	ODOT Classification (GI)	LOI (%)	
				Gravel	Coarse Sand	Fine Sand	Silt	Clay	Liquid Limit	Plastic Limit	Plasticity Index				
L-6	1	7.5	9.0										20.8		
	2	10.0	11.5	0.0	0.0	10.4	53.0	36.6	33	19	14		22.4	A-6a(10)	
	3	12.5	14.5										26.3		
	3/ST	14.5	16.0	0.0	0.0	8.8	54.2	37.0	33	19	14			A-6a(10)	
	4	14.5	16.0										24.2		
	5	20.0	21.5										24.7		
	6	25.0	26.5	0.0	0.0	5.3	61.3	33.4	32	10	12		26.5	A-6a(9)	
	6/ST	30.0	32.0	0.0	0.2	9.6	55.8	34.4	30	19	11			A-6a(8)	
	7	35.0	36.5										26.6		
	8	40.0	41.5										27.1		
	9	45.0	46.5										20.6		
	10	50.0	51.5	13.5	6.0	9.4	57.1	14.0	NP	NP	NP		22.8	A-4b(00)	
	11	55.0	56.5										20.5		
	12	60.0	61.5										7.7		
	13	65.0	66.5										15.6		
	14	70.0	71.5										9.3		
	15	75.0	76.5										10.6		
	16	80.0	81.5										8.8		
	17	85.0	86.5										12.3		
	18	90.0	91.5	31.7	28.1	26.5	10.0	3.7	NP	NP	NP		9.0	A-1-b(0)	
	19	95.0	96.5										8.2		
	20	100.0	101.5										7.3		
	21	105.0	106.5										10.2		
	22	108.5	110.0										NO. REC.		

**Laboratory Test Results**

Brent Spence Bridge Replacement ■ Cincinnati, Ohio  
 March 11, 2011 ■ HCN/Terracon Project No. N1105070



Classification Test Data															
Boring No.	Sample ID	Top Depth (feet)	Bottom Depth (feet)	Gradation (%)					Atterberg			Moisture Content (%)	ODOT Classification (GI)	LOI (%)	
				Gravel	Coarse Sand	Fine Sand	Silt	Clay	Liquid Limit	Plastic Limit	Plasticity Index				
L-7	1	5	6.5										25.8		
	2	7.5	9	23.3	17.1	21.6	20.1	17.9	NP	NP	NP		18.9	A-4a(0)	
	3	10	11.5										22.9		
	4	13	15	32.0	1.6	7.5	29.5	29.4	29	17	12			A-6a(6)	
	5	15	16.5										27.2		
	6	17.5	19										22.6		
	7	20	22	0.0	0.0	18.3	43.9	37.8	31	17	14			A-6a(10)	
	8	22	23.5	0.0	0.2	17.1	47.9	34.8	32	18	14		23.4	A-6a(10)	
	9	25	26.5										30.1		
	10	30	31.5										23.7		
	11	33	35	32.3	4.0	14.3	25.6	23.8	31	17	14			A-6a(4)	
	12	35	36.5										22.1		
	13	40	41.5										26.9		
	14	45	46.5										32.6		
	15	50	51.5										15.5		
	16	55	56.5										10.4		
	17	60	61.5	55.4	27.8	10.3	4.1	2.4	NP	NP	NP		10.3	A-1-a(0)	
	18	65	66.5										19.3		
	19	70	71.5										12.3		
	20	75	76.5	60.8	18.4	12.7	5.5	2.6	NP	NP	NP		8.9	A-1-a(0)	
	21	80	81.5										9.0		
	22	85	85.5										103.0		
	23	90	90.4	52.6	14.4	16.5	10.6	5.9	Insufficient Sample				8.2	A-1-b(00)	
	24	95	96.5										9.9		
R-1	1	32	33.5										12.0		
	2	32.5	35	69.5	20.8	7.3	1.2	1.2	NP	NP	NP		12.5	A-1-a(0)	
	4	36.5	38	3.1	63.5	28.6	1.9	2.9					23.0	A-1-b(0)	
	6	39.5	41	2.1	23.9	69.1	1.9	3.0	NP	NP	NP		23.0	A-3(0)	
	7	41	42.5										23.2		
	8	42.5	44										20.8		
	9	45	46.5										20.4		
	11	55	56.5	1.7	32.2	61.4	2.3	2.4					21.2	A-3(0)	
	12	60	61.5										25.8		
	13	65	66.5										13.8		
	14	70	71.5										14.0		
	15	75	76.5										18.9		

H.C. Nutting, a Terracon Company  
 611 Lunken Park Drive, Cincinnati, Ohio 45226  
 P [513] 321.5816 F [513] 321.4540

**Laboratory Test Results**

Brent Spence Bridge Replacement ■ Cincinnati, Ohio  
 March 11, 2011 ■ HCN/Terracon Project No. N1105070



Classification Test Data														
Boring No.	Sample ID	Top Depth (feet)	Bottom Depth (feet)	Gradation (%)					Atterberg			Moisture Content (%)	ODOT Classification (GI)	LOI (%)
				Gravel	Coarse Sand	Fine Sand	Silt	Clay	Liquid Limit	Plastic Limit	Plasticity Index			
R-2	1	32	33.5	87.5	10.8	1.5	0.0	0.2	Insufficient Sample			12.6	A-1-a(0)	
	2	33.5	35	21.6	57.9	16.3	2.4	1.8	NP	NP	NP	17.0	A-1-b(0)	
	3	35	36.5	61.8	19.5	14.3	2.0	2.4	Insufficient Sample			14.7	A-1-a(0)	
	4	36.5	38	23.3	20.9	51.0	1.5	3.3	NP	NP	NP	17.6	A-3(0)	
	6	39.5	41	55.1	13.0	26.4	4.0	1.5	NP	NP	NP	14.7	A-1-b(0)	
	8	45	46.5	9.4	17.5	68.8	1.6	2.7	NP	NP	NP	21.5	A-3(0)	
	9	47.5	49									27.6		
	10	50	51.5	0.0	6.6	86.8	3.6	3.0	NP	NP	NP	24.5	A-3(0)	
	11	55	56.5									26.5		
	12	60	61.5	1.0	12.3	80.1	3.1	3.5	NP	NP	NP	20.3	A-3(0)	
	13	65	66.5									24.4		
	14	70	71.5	25.0	46.0	23.3	3.0	2.7	NP	NP	NP	14.9	A-1-b(0)	
	15	75	76.5	17.4	39.6	37.1	2.9	3.0	NP	NP	NP	16.8	A-1-b(0)	

**Laboratory Test Results**

Brent Spence Bridge Replacement ■ Cincinnati, Ohio  
 March 11, 2011 ■ HCN/Terracon Project No. N1105070



Classification Test Data																
Boring No.	Sample ID	Top Depth (feet)	Bottom Depth (feet)	Gradation (%)					Atterberg			Moisture Content (%)	ODOT Classification (GI)	LOI (%)		
				Gravel	Coarse Sand	Fine Sand	Silt	Clay	Liquid Limit	Plastic Limit	Plasticity Index					
R-2A	2	29	30.5										21.2			
	3	30.5	32	45.4	37.2	6.1	10.0	1.3	NP	NP	NP		17.6	A-1-b(0)		
	5	35	36.5										16.4			
	6	36.5	38										27.5			
	7	38	39.5										27.3			
	8	42.5	44										18.1			
	9	45	46.5	32.3	35.6	27.2	3.0	1.9	NP	NP	NP		16.5	A-1-b(0)		
	11	50	51.5										29.3			
	12	55	56.5	3.9	29.6	61.9	2.9	1.7	NP	NP	NP		21.3	A-3(0)		
	13	60	61.5										24.4			
	14	65	66.5	60.6	14.5	16.8	6.3	1.8	NP	NP	NP		13.2	A-1-a(0)		
	15	70	71.5										13.5			
	16	75	76.5										13.2			
R-3	3	34	35.5	38.3	37.3	20.0	3.3	1.1	NP	NP	NP		14.9	A-1-b(0)		
	4	35.5	37	57.8	33.5	5.9	1.3	1.5	NP	NP	NP		16.7	A-1-a(0)		
	5	37	38.5	6.3	68.9	17.5	3.1	4.2	NP	NP	NP		18.1	A-1-b(00)		
	6	38.5	40	No Sample at this depth												
	7	40	41.5	1.1	39.2	54.6	2.6	2.5	NP	NP	NP		18.8	A-3(0)		
	8	42.5	44										24.5			
	9	45	46.5	8.4	48.0	39.4	2.5	1.7	NP	NP	NP		20.3	A-1-b(0)		
	10	47.5	49	25.4	36.0	34.1	1.4	3.1	NP	NP	NP		18.7	A-1-b(0)		
	12	55	56.5										22.4			
	13	60	61.5	32.1	34.5	28.6	2.3	2.5	NP	NP	NP		19.2	A-1-b(0)		
	14	65	66.5	70.3	12.6	13.4	2.3	1.4	NP	NP	NP		10.0	A-1-a(0)		
	15	70	71.5	56.7	29.4	9.1	2.6	2.2	NP	NP	NP		15.5	A-1-a(0)		
	16	75	76.5	52.1	29.4	12.1	3.8	2.6	NP	NP	NP		13.0	A-1-a(0)		
	17	80	81.5									No Samp.				



**Laboratory Test Results**

Brent Spence Bridge Replacement ■ Cincinnati, Ohio  
 March 11, 2011 ■ HCN/Terracon Project No. N1105070



Classification Test Data														
Boring No.	Sample ID	Top Depth (feet)	Bottom Depth (feet)	Gradation (%)					Atterberg			Moisture Content (%)	ODOT Classification (GI)	LOI (%)
				Gravel	Coarse Sand	Fine Sand	Silt	Clay	Liquid Limit	Plastic Limit	Plasticity Index			
R-4	1	33.5	35	18.0	67.9	9.5	2.9	1.7	NP	NP	NP	17.4	A-1-b(0)	
	2	35	36.5	37.3	51.7	9.7	0.1	1.2	NP	NP	NP	19.4	A-1-b(0)	
	3	36.5	38	28.6	59.6	9.1	1.3	1.4	NP	NP	NP	13.9	A-1-b(0)	
	4	38	39.5	2.1	84.8	11.4	0.2	1.5	NP	NP	NP	21.1	A-3a(0)	
	5	39.5	41	38.1	42.2	14.4	3.2	2.1	NP	NP	NP	16.6	A-1-b(0)	
	6	41	42.5	10.5	54.9	27.9	3.5	3.2	NP	NP	NP	25.3	A-1-b(0)	
	7	42.5	44									25.2		
	8	45	46.5	5.1	17.7	74.4	0.4	2.4	NP	NP	NP	21.8	A-3(0)	
	9	47.5	49									No Samp.		
	10	50	51.5	1.8	22.4	71.7	0.7	3.4	NP	NP	NP	26.0	A-3(0)	
	11	55	56.5	3.5	7.3	81.7	3.5	4.0	NP	NP	NP	21.8	A-3(0)	
	12	60	61.5									23.9		
	13	65	66.5									13.4		
	14	70	71.5	77.8	12.8	6.1	1.6	1.8	NP	NP	NP	16.2	A-1-a(0)	
	15	75	76.5	51.9	36.5	6.9	2.5	2.2	NP	NP	NP	15.8	A-1-a(0)	
	16	80	81.5									No Samp		
R-5	1	16	17.5	18.5	16.3	49.5	9.9	5.8	NP	NP	NP	27.5	A-3a(0)	
	2	17.5	19	30.4	17.6	40.9	6.9	4.2	NP	NP	NP	39.2	A-3a(0)	
	3	19	20.5	36.3	18.5	35.7	5.1	4.4	NP	NP	NP	39.5	A-1-b(0)	
	4	20.5	22	0.0	0.4	24.4	52.3	22.9	31	20	11	30.3	A-6a(8)	
	6	23.5	25	0.0	0.2	9.3	53.5	37.0	36	21	15	43.8	A-6a(10)	
	7	25	26.5									49.2		
	8	27.5	29									10.2		
	9	30	31.5	44.8	38.2	9.7	4.0	3.3	NP	NP	NP	10.2	A-1-b(0)	
	10	32.5	34									7.1		
	11	35	36.5									21.2		
	12	40	41.5	47.5	30.3	12.7	6.3	3.2	NP	NP	NP	13.6	A-1-b(0)	
	13	45	46.5									23.3		
	14	50	51.5	44.2	39.0	10.3	4.1	2.4	NP	NP	NP	16.3	A-1-b(0)	
	15	55	56.5	50.3	30.4	10.2	5.4	3.7	NP	NP	NP	18.1	A-1-a(0)	
	16	60	61.5									12.9		
	17	65	66.5	12.6	20.7	5.9	3.2	4.5	NP	NP	NP	19.4	A-3(0)	
	18	70	71.5									7.3		
	19	75	75.5	49.2	20.4	10.7	13.2	19.7	Insufficient Sample			16.4	A-1-b(0)	

**Laboratory Test Results**

Brent Spence Bridge Replacement ■ Cincinnati, Ohio  
 March 11, 2011 ■ HCN/Terracon Project No. N1105070



Classification Test Data															
Boring No.	Sample ID	Top Depth (feet)	Bottom Depth (feet)	Gradation (%)					Atterberg			Moisture Content (%)	ODOT Classification (GI)	LOI (%)	
				Gravel	Coarse Sand	Fine Sand	Silt	Clay	Liquid Limit	Plastic Limit	Plasticity Index				
R-6	1	0	1.5	0.5	1.3	24.9	49.8	23.5	28	19	9	28.7	A-4a(8)		
	2	2.5	4	0.0	0.2	2.2	67.1	30.5	35	22	13	32.2	A-6a(9)		
	ST/3	5	7	0.3	0.4	5.9	60.5	32.9	38	22	16		A-6b(10)		
	4	7	8.5	0.0	0.2	21.5	52.3	26.0	30	20	10	33.1	A-4b(8)		
	5	10	11.56	0.0	0.2	30.8	41.9	27.1	30	17	13	26.0	A-6a(8)		
	6	12.5	14	0.0	0.0	39.0	38.7	22.3	26	17	9	24.0	A-4a(5)		
	ST/7	15	17	0.0	0.4	18.1	54.9	26.6	34	23	11		A-6a(8)		
	8	17	18.5	5.9	0.8	43.7	42.9	18.8	26	17	9	26.3	A-4a(3)		
	9	20	21.5	0.4	0.6	31.7	40.6	26.7	33	23	10	48.2	A-4a(6)		
	10	25	26.5	84.3	4.4	2.2	6.5	2.6	Insufficient Sample			10.0	A-1-a(0)		
	11	30	31.5									8.4			
	12	35	36.5	58.0	20.2	11.9	6.0	3.9	NP	NP	NP	9.3	A-1-a(0)		
	13	40	41.5									8.5			
	14	45	46.5	33.5	38.8	20.2	4.9	2.6	NP	NP	NP	13.0	A-1-b(0)		
	15	50	51.5	55.9	21.2	18.2	3.1	1.6	NP	NP	NP	17.1	A-1-a(0)		
	16	55	56.5									14.1			
	17	60	61.5									21.7			
	18	65	66.5	54.3	18.4	19.7	5.2	2.4	NP	NP	NP	14.7	A-1-a(0)		
	19	70	71.5									6.4			
	20	75	75.9	57.6	12.6	17.4	8.8	3.6	NP	NP	NP	8.7	A-1-a(0)		
	21	80	80.4									5.8			
	22	84										No Samp.			
R-7	2	22.5	24	5.7	2.0	9.5	44.5	38.3	42	22	20	45.6	A-7-6(12)		
	3	24	25.5	32.9	3.3	20.6	25.3	17.9	32	18	14	24.4	A-6a(3)		
	4	22.5	27	34.5	3.5	23.8	22.0	16.2	Insufficient Sample			31.4	A-4a(0)		
	5	27	28.5	35.5	3.9	20.6	24.8	15.2	Insufficient Sample			33.2	A-4a(0)		
	8	32.5	34	67.8	19.3	5.0	5.3	2.6	Insufficient Sample			12.3	A-1-a(0)		
	9	35	36.2	No sample at this depth											
	10	37.5	39									10.0			
	11	40	41.5	61.4	16.4	11.0	7.4	3.8	NP	NP	NP	10.2	A-1-a(0)		
	12	45	46.5									7.0			
	13	50	51.5	57.2	26.9	84.0	4.6	2.9	NP	NP	NP	13.1	A-1-a(0)		
	14	55	56.5									13.2			
	15	60	61.5	59.6	15.6	14.5	5.3	5.0	NP	NP	NP	10.0	A-1-a(0)		
	16	65	66.5									83.8			
	17	70	70.4	71.1	12.1	8.2	4.5	4.1	Insufficient Sample			12.8	A-1-a(0)		

H.C. Nutting, a Terracon Company  
 611 Lunken Park Drive, Cincinnati, Ohio 45226  
 P [513] 321.5816 F [513] 321.4540

**Laboratory Test Results**

Brent Spence Bridge Replacement ■ Cincinnati, Ohio  
 March 11, 2011 ■ HCN/Terracon Project No. N1105070





Classification Test Data															
Boring No.	Sample ID	Top Depth (feet)	Bottom Depth (feet)	Gradation (%)					Atterberg			Moisture Content (%)	ODOT Classification (GI)	LOI (%)	
				Gravel	Coarse Sand	Fine Sand	Silt	Clay	Liquid Limit	Plastic Limit	Plasticity Index				
R-8	1	0	1.5										35.7		
	2	1.5	3	0.0	0.2	5.8	62.9	31.1	36	21	15	33.0	A-6a(10)		
	3	3	4.5									29.1			
	4	4.5	6									28.3			
	5	6	7.5									28.0			
	6	7.5	9									29.5			
	7	9	10.5									28.3			
	8	12.5	14									30.7			
	9	15	16.5	0.0	0.4	23.9	51.9	23.8	30	21	9	39.6	A-4a(8)		
	10	17.5	19									35.6			
	11	20	21.5									32.6			
	12	25	26.5									33.9			
	13	30	31.5									8.7			
	14	35	36.5									9.8			
	15	40	41.5	38.3	34.9	20.5	3.9	2.4	NP	NP	NP	17.0	A-1-b(0)		
	16	45	56.5									9.7			
	17	50	51.5									13.9			
	18	55	56.5	27.4	48.7	14.8	6.3	2.8	NP	NP	NP	12.2	A-1-b(0)		
	19	60	61.5									16.7			
	20	65	66.5									13.8			

**Geotechnical Engineering Report**

Brent Spence Bridge Replacement ■ Cincinnati, Ohio-Covington, Kentucky  
March 11, 2011 ■ HCN/Terracon Project No. N1105070



**EXHIBIT B-2**  
**TRIAxIAL TESTING RESULTS**



Sample No.	1	
Initial	Water Content, %	19.3
	Dry Density, pcf	105.4
	Saturation, %	86.9
	Void Ratio	0.5989
	Diameter, in.	2.800
At Test	Height, in.	5.590
	Water Content, %	19.3
	Dry Density, pcf	105.4
	Saturation, %	86.9
	Void Ratio	0.5989
Diameter, in.	2.800	
Height, in.	5.590	
Strain rate, in./min.	0.055	
Back Pressure, psi	0.00	
Cell Pressure, psi	10.00	
Fail. Stress, psi	22.22	
Ult. Stress, psi		
$\sigma_1$ Failure, psi	32.22	
$\sigma_3$ Failure, psi	10.00	

**Type of Test:**

Unconsolidated Undrained

**Sample Type:** UU

**Description:** BROWN SANDY LEAN CLAY  
NOTED GRAVEL, MOIST - STIFF

**Assumed Specific Gravity=** 2.70

**Remarks:** Lab No. 7251

**Client:** PARSONS BRINCKERHOFF

**Project:** BRENT SPENCE BRIDGE REPLACEMENT

**Source of Sample:** L-1

**Depth:** 12-14'

**Sample Number:** ST/4

**Proj. No.:** N1105070

**Date Sampled:** 8-23-10



TRIAxIAL SHEAR TEST REPORT

**H.C. Nutting**  
A Terracon Company

Figure \_\_\_\_\_

Tested By: SV

Checked By: GS



Sample No.		1
Initial	Water Content,	36.9
	Dry Density, pcf	82.1
	Saturation,	94.7
	Void Ratio	1.0519
	Diameter, in.	2.860
At Test	Height, in.	5.580
	Water Content,	36.9
	Dry Density, pcf	82.1
	Saturation,	94.7
	Void Ratio	1.0519
	Diameter, in.	2.860
	Height, in.	5.580
	Strain rate, in./min.	0.055
	Back Pressure, psf	0.0
	Cell Pressure, psf	17.0
	Fail. Stress, psf	2046.7
	Ult. Stress, psf	
	$\sigma_1$ Failure, psf	2063.7
	$\sigma_3$ Failure, psf	17.0

**Type of Test:**  
Unconsolidated Undrained

**Sample Type:** ST

**Description:** BROWN CLAY, MOIST - STIFF

LL= 46      PL= 25      PI= 21

**Assumed Specific Gravity=** 2.70

**Remarks:** Lab No. 6500

**Client:** PARSONS BRINCKERHOFF

**Project:** BRENT SPENCE BRIDGE REPLACEMENT

**Source of Sample:** L-4      **Depth:** 30-32'



**Sample Number:** ST/11

**Proj. No.:** N1105070      **Date:** 9-23-10

TRIAxIAL SHEAR TEST REPORT

## H. C. NUTTING COMPANY

Figure \_\_\_\_\_



Sample No.	1	2	3	
Initial	Water Content,	24.9	23.6	21.7
	Dry Density, pcf	99.8	102.7	106.0
	Saturation,	97.8	98.5	98.4
	Void Ratio	0.6885	0.6480	0.5962
	Diameter, in.	2.840	2.850	2.840
	Height, in.	5.580	5.570	5.590
At Test	Water Content,	24.9	23.6	21.7
	Dry Density, pcf	99.8	102.7	106.0
	Saturation,	97.8	98.5	98.4
	Void Ratio	0.6885	0.6480	0.5962
	Diameter, in.	2.840	2.850	2.840
	Height, in.	5.580	5.570	5.590
Strain rate, in./min.	0.055	0.055	0.055	
Back Pressure, psi	0.00	0.00	0.00	
Cell Pressure, psi	9.00	18.00	36.00	
Fail. Stress, psi	17.16	13.85	19.10	
Ult. Stress, psi				
$\sigma_1$ Failure, psi	26.16	31.85	55.10	
$\sigma_3$ Failure, psi	9.00	18.00	36.00	

**Type of Test:**

Unconsolidated Undrained

**Sample Type:** ST

**Description:** BROWN SILT AND CLAY, MOIST - MED STIFF

LL= 29      PL= 17      PI= 12

**Assumed Specific Gravity=** 2.70

**Remarks:** Lab No. 5689

**Client:** PARSONS BRINCKERHOFF

**Project:** BRENT SPENCE BRIDGE REPLACEMENT

**Source of Sample:** L-5

**Depth:** 23-25'

**Sample Number:** 8

**Proj. No.:** N1105070

**Date:** 9-21-10



TRIAxIAL SHEAR TEST REPORT

**H. C. NUTTING COMPANY**

Figure \_\_\_\_\_

Tested By: SV

Checked By: GS



Sample No.	1	2	3	
Initial	Water Content,	30.8	27.6	27.4
	Dry Density, pcf	90.3	95.6	96.0
	Saturation,	95.9	97.7	97.9
	Void Ratio	0.8670	0.7625	0.7562
	Diameter, in.	2.840	2.840	2.840
	Height, in.	5.580	5.600	5.600
At Test	Water Content,	30.8	27.5	27.4
	Dry Density, pcf	90.3	95.6	96.0
	Saturation,	95.9	97.5	97.9
	Void Ratio	0.8670	0.7625	0.7562
	Diameter, in.	2.840	2.840	2.840
	Height, in.	5.580	5.600	5.600
Strain rate, in./min.	0.055	0.056	0.056	
Back Pressure, psi	0.00	0.00	0.00	
Cell Pressure, psi	15.00	30.00	60.00	
Fail. Stress, psi	29.76	21.70	31.58	
Ult. Stress, psi				
$\sigma_1$ Failure, psi	44.76	51.70	91.58	
$\sigma_3$ Failure, psi	15.00	30.00	60.00	

**Type of Test:**

Unconsolidated Undrained

**Sample Type:** ST

**Description:** GRAY SANDY SILT, MOIST - STIFF

LL= 29      PL= 19      PI= 10

**Assumed Specific Gravity=** 2.70

**Remarks:** Lab No. 5693

**Client:** PARSONS BRINCKERHOFF

**Project:** BRENT SPENCE BRIDGE REPLACEMENT

**Source of Sample:** L-5

**Depth:** 38-40'

**Sample Number:** 12

**Proj. No.:** N1105070



**Date:** 9-21-10

TRIAXIAL SHEAR TEST REPORT

**H. C. NUTTING COMPANY**

Figure \_\_\_\_\_





Sample No.	1	2	3	
Initial	Water Content,	24.7	24.2	22.8
	Dry Density, pcf	100.9	101.1	103.4
	Saturation,	99.5	97.9	97.7
	Void Ratio	0.6699	0.6666	0.6307
	Diameter, in.	2.840	2.840	2.840
	Height, in.	5.570	5.580	5.590
At Test	Water Content,	24.7	24.2	22.8
	Dry Density, pcf	100.9	101.1	103.4
	Saturation,	99.5	97.9	97.7
	Void Ratio	0.6699	0.6666	0.6307
	Diameter, in.	2.840	2.840	2.840
	Height, in.	5.570	5.580	5.590
Strain rate, in./min.	0.055	0.055	0.055	
Back Pressure, psi	0.00	0.00	0.00	
Cell Pressure, psi	5.00	10.00	20.00	
Fail. Stress, psi	20.87	24.92	33.19	
Ult. Stress, psi				
$\sigma_1$ Failure, psi	25.87	34.92	53.19	
$\sigma_3$ Failure, psi	5.00	10.00	20.00	

**Type of Test:**

Unconsolidated Undrained

**Sample Type:** ST

**Description:** BROWN SILT AND CLAY, MOIST-STIFF

LL= 33      PL= 19      PI= 14

Assumed Specific Gravity= 2.70

Remarks: Lab No. 5728

**Client:** PARSONS BRINCKERHOFF

**Project:** BRENT SPENCE BRIDGE REPLACEMENT

**Source of Sample:** L-6

**Depth:** 14.5-16.0'

**Sample Number:** 3/ST

**Proj. No.:** N1105070

**Date:** 9-21-10



TRIAXIAL SHEAR TEST REPORT

**H. C. NUTTING COMPANY**

Figure \_\_\_\_\_

Tested By: SV

Checked By: GS



Sample No.		1	2	3
Initial	Water Content,	28.0	26.4	26.2
	Dry Density, pcf	95.9	98.0	98.4
	Saturation,	99.8	98.9	99.2
	Void Ratio	0.7568	0.7207	0.7126
	Diameter, in.	2.850	2.850	2.860
	Height, in.	5.580	5.590	5.590
At Test	Water Content,	28.0	26.4	26.2
	Dry Density, pcf	95.9	98.0	98.4
	Saturation,	99.8	98.9	99.2
	Void Ratio	0.7568	0.7207	0.7126
	Diameter, in.	2.850	2.850	2.860
	Height, in.	5.580	5.590	5.590
Strain rate, in./min.		0.055	0.055	0.055
Back Pressure, psi		0.00	0.00	0.00
Cell Pressure, psi		12.00	24.00	48.00
Fail. Stress, psi		21.18	25.84	24.82
Ult. Stress, psi				
$\sigma_1$ Failure, psi		33.18	49.84	72.82
$\sigma_3$ Failure, psi		12.00	24.00	48.00

**Type of Test:**

Unconsolidated Undrained

**Sample Type:** ST

**Description:** GRAY SILT AND CLAY, MOIST - STIFF

LL= 30      PL= 19      PI= 11

**Assumed Specific Gravity=** 2.70

**Remarks:** Lab No. 5729

Figure \_\_\_\_\_

**Client:** PARSONS BRINCKERHOFF

**Project:** BRENT SPENCE BRIDGE REPLACEMENT

**Source of Sample:** L-6      **Depth:** 30-32'

**Sample Number:** 6/ST



**Proj. No.:** N1105070      **Date:** 9-21-10

TRIAxIAL SHEAR TEST REPORT

**H. C. NUTTING COMPANY**

Tested By: SV

Checked By: GS



Sample No.		1	2
Initial	Water Content,	20.8	20.8
	Dry Density, pcf	104.3	107.7
	Saturation,	91.3	99.2
	Void Ratio	0.6157	0.5655
	Diameter, in.	2.840	2.820
	Height, in.	5.590	5.600
At Test	Water Content,	20.8	20.8
	Dry Density, pcf	104.3	107.7
	Saturation,	91.3	99.2
	Void Ratio	0.6157	0.5655
	Diameter, in.	2.840	2.820
	Height, in.	5.590	5.600
Strain rate, in./min.		0.055	0.056
Back Pressure, psf		0.0	0.0
Cell Pressure, psf		5.0	10.0
Fail. Stress, psf		1986.6	3784.3
Ult. Stress, psf			
$\sigma_1$ Failure, psf		1991.6	3794.3
$\sigma_3$ Failure, psf		5.0	10.0

**Type of Test:**

Unconsolidated Undrained

**Sample Type:** ST

**Description:** BROWN GRAY SILT, CLAY AND GRAVEL, MOIST - STIFF

LL= 29      PL= 17      PI= 12

**Assumed Specific Gravity=** 2.70

**Remarks:** Lab No. 5733

**Client:** PARSONS BRINCKERHOFF

**Project:** BRENT SPENCE BRIDGE REPLACEMENT

**Source of Sample:** L-7

**Depth:** 13-15'

**Sample Number:** 4

**Proj. No.:** N1105070

**Date:** 9-21-10



TRIAxIAL SHEAR TEST REPORT

**H. C. NUTTING COMPANY**

Figure \_\_\_\_\_

Tested By: SV

Checked By: GS



Sample No.	1	2	3	
Initial	Water Content,	22.7	23.0	23.2
	Dry Density, pcf	103.5	103.3	103.1
	Saturation,	97.4	98.2	98.8
	Void Ratio	0.6289	0.6322	0.6354
	Diameter, in.	2.840	2.840	2.850
At Test	Height, in.	5.580	5.580	5.580
	Water Content,	22.7	23.0	23.2
	Dry Density, pcf	103.5	103.3	103.1
	Saturation,	97.4	98.2	98.8
	Void Ratio	0.6289	0.6322	0.6354
Strain rate, in./min.	Diameter, in.	2.840	2.840	2.850
	Height, in.	5.580	5.580	5.580
Back Pressure, psf	0.0	0.0	0.0	
Cell Pressure, psf	8.0	16.0	32.0	
Fail. Stress, psf	2819.9	2959.8	2591.9	
Ult. Stress, psf				
$\sigma_1$ Failure, psf	2827.9	2975.8	2623.9	
$\sigma_3$ Failure, psf	8.0	16.0	32.0	

**Type of Test:**

Unconsolidated Undrained

**Sample Type:** ST

**Description:** BROWN SILT AND CLAY, MOIST-STIFF

LL= 31      PL= 17      PI= 14

Assumed Specific Gravity= 2.70

Remarks: Lab No. 5736

**Client:** PARSONS BRINCKERHOFF

**Project:** BRENT SPENCE BRIDGE REPLACEMENT

**Source of Sample:** L-7

**Depth:** 20-22'

**Sample Number:** 7

**Proj. No.:** N1105070

**Date:** 9-22-10



TRIAXIAL SHEAR TEST REPORT

**H. C. NUTTING COMPANY**

Figure \_\_\_\_\_

Tested By: SV

Checked By: GS



Sample No.	1	2
Initial		
Water Content,	25.3	24.9
Dry Density, pcf	99.1	100.8
Saturation,	97.5	100.0
Void Ratio	0.7009	0.6720
Diameter, in.	2.870	2.830
Height, in.	5.610	5.570
At Test		
Water Content,	25.3	24.9
Dry Density, pcf	99.1	100.8
Saturation,	97.5	100.0
Void Ratio	0.7009	0.6720
Diameter, in.	2.870	2.830
Height, in.	5.610	5.570
Strain rate, in./min.	0.056	0.055
Back Pressure, psf	0.0	0.0
Cell Pressure, psf	14.0	28.0
Fail. Stress, psf	2741.0	4434.4
Ult. Stress, psf		
$\sigma_1$ Failure, psf	2755.0	4462.4
$\sigma_3$ Failure, psf	14.0	28.0

**Type of Test:**

Unconsolidated Undrained

**Sample Type:** ST

**Description:** BROWN GRAY SILT AND CLAY AND GRAVEL, MOIST - MED STIFF

LL= 31      PL= 17      PI= 14

**Assumed Specific Gravity=** 2.70

**Remarks:** Lab No. 5740

Only 2pt test, Insufficient for 3rd pt

**Client:** PARSONS BRINCKERHOFF

**Project:** BRENT SPENCE BRIDGE REPLACEMENT

**Source of Sample:** L-7

**Depth:** 33-35'

**Sample Number:** 11

**Proj. No.:** N1105070

**Date:** 9-22-10



TRIAxIAL SHEAR TEST REPORT

**H. C. NUTTING COMPANY**

Figure \_\_\_\_\_

Tested By: SV

Checked By: GS



Sample No.		1
Initial	Water Content, %	35.2
	Dry Density, pcf	87.6
	Saturation, %	102.6
	Void Ratio	0.9247
	Diameter, in.	2.790
At Test	Height, in.	5.600
	Water Content, %	35.2
	Dry Density, pcf	87.6
	Saturation, %	102.6
	Void Ratio	0.9247
Diameter, in.		2.790
Height, in.		5.600
Strain rate, in./min.		0.056
Back Pressure, psi		0.00
Cell Pressure, psi		5.00
Fail. Stress, psi		32.39
Ult. Stress, psi		
$\sigma_1$ Failure, psi		37.39
$\sigma_3$ Failure, psi		5.00

**Type of Test:**  
Unconsolidated Undrained

**Sample Type:** ST

**Description:** GRAY BROWN LEAN CLAY W/  
SAND LENSES, MOIST - STIFF

**Assumed Specific Gravity:** 2.70

**Remarks:** Lab No. 6610

**Client:** PARSONS BRINCKERHOFF

**Project:** BRENT SPENCE BRIDGE REPLACEMENT

**Source of Sample:** R-6      **Depth:** 5-7'

**Sample Number:** 3/ST

**Proj. No.:** N1105070      **Date Sampled:** 9-17-10

TRIAXIAL SHEAR TEST REPORT

**H.C. Nutting**  
A Terracon Company

Figure \_\_\_\_\_

Tested By: SV

Checked By: GS

**Geotechnical Engineering Report**


Brent Spence Bridge Replacement ■ Cincinnati, Ohio-Covington, Kentucky

March 11, 2011 ■ HCN/Terracon Project No. N1105070



**EXHIBIT B-3**  
**CONSOLIDATION TESTING RESULTS**

# CONSOLIDATION TEST REPORT



Coefficients of Consolidation and Secondary Consolidation

No.	Load (tsf)	$C_v$ (ft.2/day)	$C_\alpha$	No.	Load (tsf)	$C_v$ (ft.2/day)	$C_\alpha$	No.	Load (tsf)	$C_v$ (ft.2/day)	$C_\alpha$
2	0.12	1.30									
3	0.25	0.42									
4	0.50	0.37									
5	1.00	0.66									
6	2.00	0.56									
7	4.00	0.52									
8	8.00	0.58									
9	16.00	1.01									

Natural		Dry Dens. (pcf)	LL	PI	Sp. Gr.	Overburden (tsf)	$P_c$ (tsf)	$C_c$	$C_r$	Swell Press. (tsf)	Swell %	$e_0$
Sat.	Moist.											
91.5 %	20.3 %	105.5			2.702		1.34	0.15	0.02			0.599

MATERIAL DESCRIPTION	USCS	AASHTO
BROWN SANDY LEAN CLAY NOTED GRAVEL, MOIST - STIFF		

<b>Project No.</b> N1105070 <b>Client:</b> PARSONS BRINCKERHOFF <b>Project:</b> BRENT SPENCE BRIDGE REPLACEMENT <b>Source:</b> L-1 <b>Sample No.:</b> ST/4 <b>Elev./Depth:</b> 12-14'	<b>Remarks:</b> Lab No. 7251
<b>H.C. Nutting</b> A Terracon Company Cincinnati, Ohio	

Figure



# Dial Reading vs. Time





Project No.: N1105070

Project: BRENT SPENCE BRIDGE REPLACEMENT

Source: L-1

Sample No.: ST/4

Elev./Depth: 12-14'



**H.C. Nutting**  
A Terracon Company  
Cincinnati, Ohio

Figure

# Dial Reading vs. Time





Project No.: N1105070

Project: BRENT SPENCE BRIDGE REPLACEMENT

Source: L-1

Sample No.: ST/4


Elev./Depth: 12-14'



**H.C. Nutting**  
A Terracon Company  
Cincinnati, Ohio

Figure

# CONSOLIDATION TEST REPORT



Coefficients of Consolidation and Secondary Consolidation

No.	Load (tsf)	$C_v$ (ft.2/day)	$C_\alpha$	No.	Load (tsf)	$C_v$ (ft.2/day)	$C_\alpha$	No.	Load (tsf)	$C_v$ (ft.2/day)	$C_\alpha$
2	0.25	0.42									
3	0.50	0.20									
4	1.00	0.38									
5	2.00	0.37									
6	4.00	0.76									
7	8.00	0.75									
8	16.00	0.32									

Natural		Dry Dens. (pcf)	LL	PI	Sp. Gr.	Overburden (tsf)	$P_c$ (tsf)	$C_c$	$C_r$	Swell Press. (tsf)	Swell %	$e_0$
Sat.	Moist.											
95.4 %	21.5 %	104.6			2.690		2.61	0.19	0.02			0.606

MATERIAL DESCRIPTION	USCS	AASHTO
BROWN LEAN CLAY, MOIST - STIFF		

<b>Project No.</b> N1105070 <b>Client:</b> PARSONS BRINCKERHOFF <b>Project:</b> BRENT SPENCE BRIDGE REPLACEMENT <b>Source:</b> L-1A <b>Sample No.:</b> ST/4 <b>Elev./Depth:</b> 13-15'	<b>Remarks:</b> Lab No. 7279
<b>H.C. Nutting</b> A Terracon Company Cincinnati, Ohio	

Figure

# Dial Reading vs. Time





Project No.: N1105070

Project: BRENT SPENCE BRIDGE REPLACEMENT

Source: L-1A

Sample No.: ST/4

Elev./Depth: 13-15'



**H.C. Nutting**  
A Terracon Company  
Cincinnati, Ohio

Figure

# Dial Reading vs. Time




Project No.: N1105070

Project: BRENT SPENCE BRIDGE REPLACEMENT

Source: L-1A

Sample No.: ST/4


Elev./Depth: 13-15'



**H.C. Nutting**  
A Terracon Company  
Cincinnati, Ohio

Figure

# CONSOLIDATION TEST REPORT



Coefficients of Consolidation and Secondary Consolidation

No.	Load (tsf)	$C_v$ (ft.2/day)	$C_\alpha$	No.	Load (tsf)	$C_v$ (ft.2/day)	$C_\alpha$	No.	Load (tsf)	$C_v$ (ft.2/day)	$C_\alpha$
2	0.25	0.95									
3	0.50	0.15									
4	1.00	0.14									
5	2.00	0.30									
6	4.00	0.16									
7	8.00	2.28									
8	16.00	0.49									

Natural		Dry Dens. (pcf)	LL	PI	Sp. Gr.	Overburden (tsf)	$P_c$ (tsf)	$C_c$	$C_r$	Swell Press. (tsf)	Swell %	$e_0$
Sat.	Moist.											
75.1 %	34.3 %	75.2	34	11	2.671		5.05	0.29	0.05			1.218

MATERIAL DESCRIPTION	USCS	AASHTO
BROWN SILT AND CLAY, MOIST - MED STIFF		ODOT=A-6a(8)

<b>Project No.</b> N1105070 <b>Client:</b> PARSONS BRINCKERHOFF <b>Project:</b> BRENT SPENCE BRIDGE REPLACEMENT <b>Source:</b> R-6 <b>Sample No.:</b> 7/ST <b>Elev./Depth:</b> 15-17'	<b>Remarks:</b> Lab No. 6614
<b>H.C. Nutting</b> A Terracon Company Cincinnati, Ohio	
<b>Figure</b>	

# Dial Reading vs. Time





Project No.: N1105070

Project: BRENT SPENCE BRIDGE REPLACEMENT

Source: R-6

Sample No.: 7/ST

Elev./Depth: 15-17'



**H.C. Nutting**  
A Terracon Company  
Cincinnati, Ohio

Figure

# Dial Reading vs. Time




Project No.: N1105070

Project: BRENT SPENCE BRIDGE REPLACEMENT

Source: R-6

Sample No.: 7/ST

Elev./Depth: 15-17'



**H.C. Nutting**  
A Terracon Company  
Cincinnati, Ohio

Figure



**Geotechnical Engineering Report**


Brent Spence Bridge Replacement ■ Cincinnati, Ohio-Covington, Kentucky

March 11, 2011 ■ HCN/Terracon Project No. N1105070




# **UNCONFINED COMPRESSIVE STRENGTH TESTING RESULTS AND FIGURES**

## Unconfined Compressive Strength Distribution





### ELEVATION VS. UNCONFINED COMPRESSIVE STRENGTH



**Unconfined Compression Test Results**

Parsons Brinckerhoff ■ Brent Spence Bridge Replacement ■ Cincinnati, Ohio

March 11, 2011 ■ HCN/Terracon Project No. N1105070

**UNCONFINED COMPRESSION TEST RESULTS**

Boring	Top Depth (ft.)	Top Elevation (ft.)	Bottom Depth (ft.)	Bottom Elevation (ft.)	Unconfined Strength (psf)	Unconfined Strength (psi)	Water Content (%)	Rock Type
L-1	129.9	363.56	130.3	363.16	1581417	10982	0.2	Limestone
L-1	142.7	350.76	143.2	350.26	1349949	9375	0.4	Limestone
L-1	153.5	339.96	154	339.46	1731345	12023	0.5	Limestone
L-1	156	337.46	157	336.46	1463837	10166	0.2	Limestone
L-1	162.5	330.96	163	330.46	1245899	8652	1.3	Limestone/Shale
L-1A	123.1	368.35	123.7	367.75	1467597	10192	0.1	Limestone
L-1A	132.3	359.15	132.8	358.65	1958018	13597	0.2	Limestone
L-1A	143	348.45	143.5	347.95	848262	5891	1.2	Limestone
L-1A	150.7	340.75	151.1	340.35	1928313	13391	0.2	Limestone
L-1A	160	331.45	160.5	330.95	634960	4409	1.9	Limestone
L-2	126.7	369.56	127	369.26	1844685	12810	2.4	Limestone
L-2	130	366.26	130.7	365.56	1591219	11050	0.8	Limestone
L-2	137	359.26	137.5	358.76	1746923	12131	1.1	Limestone
L-2	144	352.26	144.5	351.76	2229975	15486	1.1	Limestone
L-2	148.2	348.06	148.5	347.76	599284	4162	2.4	Shale
L-2	153	343.26	153.5	342.76	1398280	9710	3.6	Limestone
L-2	154.5	341.76	155	341.26	1564616	10865	1.1	Limestone
L-2	158.5	337.76	158.9	337.36	1280499	8892	1.2	Limestone
L-2	163.6	332.66	164	332.26	899381	6246	1.7	Limestone
L-2	165.1	331.16	165.4	330.86	1542930	10715	1.1	Limestone
L-2A	130.1	364.40	130.5	364.00	1164152	8084	0.1	Limestone
L-2A	131.5	363.00	132.2	362.30	1264643	8782	0.3	Limestone
L-2A	137	357.50	137.4	357.10	267975	1861	4.5	Shale
L-2A	157.8	336.70	158.3	336.20	1233462	8566	0.7	Limestone
L-3	97.6	361.06	98	360.66	471917	3277	1.9	Limestone/Shale
L-3	100.2	358.46	100.4	358.26	1863379	12940	0.7	Limestone
L-3	103.8	354.86	104.4	354.26	1917187	13314	1.4	Limestone
L-3	121.2	337.46	121.8	336.86	965311	6704	1.3	Limestone/Shale
L-3	124.6	334.06	125.2	333.46	569305	3954	1.2	Limestone/Shale
L-3	145.2	313.46	146.2	312.46	1661279	11537	0.7	Limestone
L-3	145.6	313.06	146.1	312.56	1358505	9434	1.5	Limestone/Shale
L-3	158.7	299.96	160.2	298.46	2475252	17189	0.4	Limestone
L-3	162.8	295.86	163.3	295.36	1744346	12114	0.2	Limestone
L-3	164.5	294.16	165.2	293.46	2176614	15115	0.8	Limestone

### Unconfined Compression Test Results

Parsons Brinckerhoff ■ Brent Spence Bridge Replacement ■ Cincinnati, Ohio

March 11, 2011 ■ HCN/Terracon Project No. N1105070



Boring	Top Depth (ft.)	Top Elevation (ft.)	Bottom Depth (ft.)	Bottom Elevation (ft.)	Unconfined Strength (psf)	Unconfined Strength (psi)	Water Content (%)	Rock Type
L-3A	126.5	369.55	126.75	369.30	82023	570	6.3	Shale
L-3A	142.3	353.80	142.5	353.55	615192	4272	2	Shale
L-3A	157.7	338.35	158	338.05	397254	2759	0.8	Limestone
L-4	116	363.97	116.5	363.47	1965081	13646	0.5	Limestone
L-4	120.4	359.57	120.9	359.07	1829521	12705	1.1	Limestone
L-4	140.5	339.47	141	338.97	1880122	13056	0.8	Limestone
L-4	143	336.97	143.5	336.47	1801226	12509	0.4	Limestone
L-5	113.5	372.83	114	372.33	972696	6755	2.4	Limestone/Shale
L-5	120.2	366.13	120.6	365.73	1567920	10888	0.2	Limestone
L-5	130.3	356.03	131	355.33	738738	5130	0.3	Limestone/Shale
L-5	133.3	353.03	133.8	352.53	1217480	8455	1.7	Limestone/Shale
L-6	112	373.69	112.4	373.29	703969	4889	0.3	Limestone/Shale
L-6	120.5	365.19	121	364.69	2097849	14568	0.2	Limestone
L-6	130.5	355.19	130.9	354.79	1420383	9864	0.2	Limestone
L-6	147.5	338.19	148	337.69	1544585	10726	0.2	Limestone
L-7	101	383.41	101.5	382.91	1183176	8217	0.3	Limestone
L-7	113.7	370.71	114.2	370.21	842027	5847	0.3	Limestone
L-7	132.5	351.91	133.2	351.21	689715	4790	0.6	Limestone/Shale
R-1	91.5	366.54	92.1	365.94	1837107	12758	0.4	Limestone
R-1	94.3	363.74	95	363.04	706054	4903	2.4	Limestone
R-1	104.5	353.54	105	353.04	568922	3951	2.4	Limestone
R-1	123	335.04	123.5	334.54	1443507	10024	0.8	Limestone
R-1	136	322.04	136.5	321.54	2134074	14820	0.6	Limestone
R-1	145.3	312.74	145.7	312.34	1072646	7449	1.3	Limestone
R-1	153	305.04	153.6	304.44	1850857	12853	0.6	Limestone
R-1	159.1	298.94	159.9	298.14	1592203	11057	0.7	Limestone
R-1	163.5	294.54	164.2	293.84	2046785	14214	1.2	Limestone
R-1	168.2	289.84	168.9	289.14	2000122	13890	1.2	Limestone
R-2	87.5	370.60	88	370.10	1893232	13147	0.2	Limestone
R-2	89.3	368.80	89.7	368.40	1387302	9634	0.6	Limestone
R-2	90.7	367.40	91.6	366.50	1848338	12836	0.4	Limestone
R-2	93.7	364.40	94	364.10	709761	4929	2.2	Shale
R-2	99.8	358.30	100.1	358.00	1155667	8025	0.8	Limestone
R-2	112.9	345.20	113.9	344.20	2034883	14131	0.2	Limestone
R-2	119.8	338.30	120.6	337.50	2005345	13926	0.4	Limestone
R-2	139	319.10	139.5	318.60	1138483	7906	1.2	Limestone
R-2A	99.5	358.14	100.1	357.54	2075031	14410	0.6	Limestone

### Unconfined Compression Test Results

Parsons Brinckerhoff ■ Brent Spence Bridge Replacement ■ Cincinnati, Ohio  
 March 11, 2011 ■ HCN/Terracon Project No. N1105070



Boring	Top Depth (ft.)	Top Elevation (ft.)	Bottom Depth (ft.)	Bottom Elevation (ft.)	Unconfined Strength (psf)	Unconfined Strength (psi)	Water Content (%)	Rock Type
R-2A	111.8	345.84	112.2	345.44	1773180	12314	1.1	Limestone
R-2A	117.8	339.84	118.2	339.44	872331	6058	1.9	Limestone
R-2A	120.5	337.13	121	336.64	607979	4222	1.7	Limestone/Shale
R-2A	134.4	323.24	134.9	322.74	1089495	7566	1.2	Limestone
R-2A	140	317.64	140.5	317.14	1117004	7757	0.7	Limestone
R-2A	148	309.64	148.5	309.14	2192551	15226	0.2	Limestone
R-2A	160	297.64	160.5	297.14	1550817	10770	0.6	Limestone
R-2A	175.8	281.84	176.3	281.34	1495031	10382	0.8	Limestone
R-2A	179.8	277.84	180.3	277.34	1902575	13212	0.1	Limestone
R-2A	183.5	274.14	184	273.64	1400566	9726	0.1	Limestone
R-3	92.3	365.71	92.7	365.31	1331115	9244	0.7	Limestone
R-3	93.8	364.21	94.5	363.51	1474639	10241	0.2	Limestone
R-3	102.7	355.31	103.1	354.91	1041933	7236	1.7	Limestone/Shale
R-3	106.5	351.51	107.1	350.91	1322957	9187	2.2	Limestone/Shale
R-3	123.8	334.21	124.7	333.31	983924	6833	0.9	Limestone/Shale
R-3	140	318.01	140.5	317.51	1310334	9100	0.5	Limestone
R-3	145.5	312.51	146	312.01	1694430	11767	1.1	Limestone
R-3	157.3	300.71	158	300.01	2048572	14226	0.5	Limestone
R-4	90.5	367.48	91	366.98	1198015	8320	4.2	Limestone
R-4	95.5	362.48	96	361.98	832099	5778	4.2	Limestone
R-4	102.8	355.18	103.3	354.68	380693	2644	1.9	Limestone/Shale
R-4	111.3	346.68	111.9	346.08	857943	5958	1.5	Limestone
R-4	121.9	336.08	122.3	335.68	2216031	15389	1.1	Limestone
R-4	129.6	328.38	130	327.98	828577	5754	1.5	Limestone
R-4	140.6	317.38	141.1	316.88	1956363	13586	0.4	Limestone
R-4	152.8	305.18	153.6	304.38	1534100	10653	1.1	Limestone
R-4	159.6	298.38	160.5	297.48	2269771	15762	0.5	Limestone
R-5	85.2	373.39	85.7	372.89	1022251	7099	2.9	Limestone
R-5	86.4	372.19	86.8	371.79	1556479	10809	0.3	Limestone
R-5	90.1	368.49	90.8	367.79	1011411	7024	0.5	Limestone
R-5	92.2	366.39	92.8	365.79	16945	118	8.6	Shale
R-5	93	365.59	93.8	364.79	2062678	14324	0.6	Limestone
R-5	95	363.59	95.3	363.29	1179728	8193	0.5	Limestone
R-5	103	355.59	103.5	355.09	692912	4812	1.5	Limestone/Shale
R-5	146.2	312.39	147	311.59	1753704	12179	0.5	Limestone
R-6	84.1	372.94	84.5	372.54	851152	5911	0.6	Limestone
R-6	88.5	368.54	89	368.04	1150291	7988	0.7	Limestone

### Unconfined Compression Test Results


Parsons Brinckerhoff ■ Brent Spence Bridge Replacement ■ Cincinnati, Ohio

March 11, 2011 ■ HCN/Terracon Project No. N1105070



Boring	Top Depth (ft.)	Top Elevation (ft.)	Bottom Depth (ft.)	Bottom Elevation (ft.)	Unconfined Strength (psf)	Unconfined Strength (psi)	Water Content (%)	Rock Type
R-6	94.5	362.54	94.9	362.14	1403296	9745	0.1	Limestone
R-6	100.1	356.94	100.5	356.54	1828127	12695	0.1	Limestone
R-6	107.1	349.94	107.5	349.54	1259226	8745	0.5	Limestone
R-6	114.5	342.54	115	342.04	1466508	10184	0.2	Limestone
R-6	136.5	320.54	137.3	319.74	1649615	11456	0.3	Limestone
R-6	159.8	297.24	160.2	296.84	1273413	8843	0.8	Limestone
R-7	83.5	374.96	83.9	374.56	1277541	8872	0.3	Limestone
R-7	88.4	370.06	89	369.46	1748783	12144	0.3	Limestone
R-7	98	360.46	98.5	359.96	979514	6802	1.0	Limestone
R-7	121.1	337.36	121.4	337.06	263952	1833	3.5	Shale
R-7	128.7	329.76	129.5	328.96	1227670	8525	0.5	Limestone
R-7	136.6	321.86	137.6	320.86	1724247	11974	0.4	Limestone
R-7	154.5	303.96	155.1	303.36	1812415	12586	0.5	Limestone
R-7	163.7	294.76	164.5	293.96	1263171	8772	0.4	Limestone
R-8	87.8	367.90	88.2	367.50	1388903	9645	0.1	Limestone
R-8	100.5	355.20	101	354.70	1618490	11240	0.6	Limestone
R-8	101.8	353.90	102.3	353.40	711870	4944	1	Limestone/Shale
R-8	126.3	329.40	126.7	329.00	1674834	11631	0.7	Limestone
R-8	127.8	327.90	128.3	327.40	1537026	10674	0.3	Limestone
R-8	135.5	320.20	136	319.70	1511267	10495	0.5	Limestone
R-8	141	314.70	141.5	314.20	1831836	12721	0.3	Limestone
R-8	149	306.70	149.5	306.20	1817085	12619	0.3	Limestone
R-8	151.8	303.90	152.1	303.60	1475126	10244	0.2	Limestone
R-8	158.7	297.00	159.2	296.50	1729572	12011	0.2	Limestone

# UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	1581417.8			
Undrained shear strength, psf	790708.9			
Failure strain, %	0.9			
Strain rate, in./min.	0.042			
Water content, %	0.2			
Wet density, pcf	166.4			
Dry density, pcf	166.0			
Saturation, %	N/A			
Void ratio	N/A			
Specimen diameter, in.	1.970			
Specimen height, in.	4.220			
Height/diameter ratio	2.14			

**Description:** LIMESTONE

LL =      PL =      PI =      Assumed GS=      Type: Limestone

**Project No.:** N1105070  
**Date Sampled:** 7-29-10  
**Remarks:**  
 Lab No. 6003

**Client:** PARSONS BRINCKERHOFF  
**Project:** BRENT SPENCE BRIDGE REPLACEMENT  
**Source of Sample:** L-1      **Depth:** 129.9-130.3'  
**Sample Number:** 1

UNCONFINED COMPRESSION TEST


**H.C. Nutting**  
 A Terracon Company

Figure \_\_\_\_\_

**Tested By:** SV \_\_\_\_\_ **Checked By:** GS \_\_\_\_\_



# UNCONFINED COMPRESSION TEST



Sample No.	1		
Unconfined strength, psf	1349949.2		
Undrained shear strength, psf	674974.6		
Failure strain, %	0.5		
Strain rate, in./min.	0.037		
Water content, %	0.4		
Wet density, pcf	167.3		
Dry density, pcf	166.6		
Saturation, %	N/A		
Void ratio	N/A		
Specimen diameter, in.	1.975		
Specimen height, in.	3.790		
Height/diameter ratio	1.92		

**Description:** LIMESTONE

LL =      PL =      PI =      Assumed GS=      Type: Limestone

**Project No.:** N1105070  
**Date Sampled:** 7-29-10  
**Remarks:**  
 Lab No. 6006

**Client:** PARSONS BRINCKERHOFF  
**Project:** BRENT SPENCE BRIDGE REPLACEMENT  
**Source of Sample:** L-1      **Depth:** 142.7-143.2'  
**Sample Number:** 4

UNCONFINED COMPRESSION TEST



**H.C. Nutting**  
 A Terracon Company

**Figure** \_\_\_\_\_

**Tested By:** SV \_\_\_\_\_

**Checked By:** GS \_\_\_\_\_

# UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	1731345.1			
Undrained shear strength, psf	865672.5			
Failure strain, %	0.7			
Strain rate, in./min.	0.041			
Water content, %	0.5			
Wet density, pcf	167.6			
Dry density, pcf	166.7			
Saturation, %	N/A			
Void ratio	N/A			
Specimen diameter, in.	1.970			
Specimen height, in.	4.140			
Height/diameter ratio	2.10			

**Description:** LIMESTONE

LL =	PL =	PI =	Assumed GS=	Type: Limestone
------	------	------	-------------	-----------------

**Project No.:** N1105070  
**Date Sampled:** 7-29-10  
**Remarks:**  
 Lab No. 6010


**Figure** \_\_\_\_\_

**Client:** PARSONS BRINCKERHOFF  
**Project:** BRENT SPENCE BRIDGE REPLACEMENT  
**Source of Sample:** L-1      **Depth:** 153.5-154'  
**Sample Number:** 8

UNCONFINED COMPRESSION TEST  
**H.C. Nutting**  
 A Terracon Company

**Tested By:** SV \_\_\_\_\_ **Checked By:** GS \_\_\_\_\_

# UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	1463837.5			
Undrained shear strength, psf	731918.8			
Failure strain, %	0.5			
Strain rate, in./min.	0.040			
Water content, %	0.2			
Wet density, pcf	168.0			
Dry density, pcf	167.6			
Saturation, %	N/A			
Void ratio	N/A			
Specimen diameter, in.	1.970			
Specimen height, in.	4.090			
Height/diameter ratio	2.08			

**Description:** LIMESTONE

LL =	PL =	PI =	Assumed GS=	Type: Limestone
------	------	------	-------------	-----------------

**Project No.:** N1105070  
**Date Sampled:** 7-29-10  
**Remarks:**  
 Lab No. 6011

**Client:** PARSONS BRINCKERHOFF  
**Project:** BRENT SPENCE BRIDGE REPLACEMENT  
**Source of Sample:** L-1      **Depth:** 156-157'  
**Sample Number:** 9


UNCONFINED COMPRESSION TEST

**H.C. Nutting**  
 A Terracon Company

Figure \_\_\_\_\_

**Tested By:** SV \_\_\_\_\_ **Checked By:** GS \_\_\_\_\_

# UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	1245899.8			
Undrained shear strength, psf	622949.9			
Failure strain, %	0.5			
Strain rate, in./min.	0.041			
Water content, %	1.3			
Wet density, pcf	167.0			
Dry density, pcf	164.9			
Saturation, %	N/A			
Void ratio	N/A			
Specimen diameter, in.	1.980			
Specimen height, in.	4.100			
Height/diameter ratio	2.07			

**Description:** LIMESTONE AND SHALE

LL =	PL =	PI =	Assumed GS=	Type: Limestone and Shale
------	------	------	-------------	---------------------------

<p><b>Project No.:</b> N1105070  <b>Date Sampled:</b> 7-29-10  <b>Remarks:</b>                  Lab No. 6013</p>	<p><b>Client:</b> PARSONS BRINCKERHOFF  <b>Project:</b> BRENT SPENCE BRIDGE REPLACEMENT  <b>Source of Sample:</b> L-1      <b>Depth:</b> 162.5-163'  <b>Sample Number:</b> 11</p>
--	---



UNCONFINED COMPRESSION TEST

**H.C. Nutting**  
A Terracon Company

Figure \_\_\_\_\_

**Tested By:** SV      **Checked By:** GS

# UNCONFINED COMPRESSION TEST



Sample No.	1		
Unconfined strength, psf	1467597.4		
Undrained shear strength, psf	733798.7		
Failure strain, %	0.6		
Strain rate, in./min.	0.039		
Water content, %	0.1		
Wet density, pcf	164.2		
Dry density, pcf	164.0		
Saturation, %	N/A		
Void ratio	N/A		
Specimen diameter, in.	1.990		
Specimen height, in.	3.980		
Height/diameter ratio	2.00		

**Description:** LIMESTONE

**LL =**      **PL =**      **PI =**      **Assumed GS=**      **Type:** Limestone

**Project No.:** N1105070  
**Date Sampled:** 8-27-10  
**Remarks:**  
 Lab No. 7314

**Client:** PARSONS BRINCKERHOFF  
**Project:** BRENT SPENCE BRIDGE REPLACEMENT  
**Source of Sample:** L-1A      **Depth:** 123.1-123.7'  
**Sample Number:** 1


UNCONFINED COMPRESSION TEST

**H.C. Nutting**  
 A Terracon Company

**Figure** \_\_\_\_\_

**Tested By:** SV      **Checked By:** GS

# UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	1958018.3			
Undrained shear strength, psf	979009.1			
Failure strain, %	0.4			
Strain rate, in./min.	0.039			
Water content, %	0.2			
Wet density, pcf	164.6			
Dry density, pcf	164.2			
Saturation, %	N/A			
Void ratio	N/A			
Specimen diameter, in.	2.000			
Specimen height, in.	3.930			
Height/diameter ratio	1.97			

**Description:** LIMESTONE

LL =	PL =	PI =	Assumed GS=	Type: Limestone
------	------	------	-------------	-----------------

**Project No.:** N1105070

**Date Sampled:** 8-27-10

**Remarks:**  
Lab No. 7315

**Client:** PARSONS BRINCKERHOFF

**Project:** BRENT SPENCE BRIDGE REPLACEMENT

**Source of Sample:** L-1A      **Depth:** 132.3-132.8'

**Sample Number:** 2


UNCONFINED COMPRESSION TEST

**H.C. Nutting**  
A Terracon Company

Figure \_\_\_\_\_

**Tested By:** SV      **Checked By:** GS

# UNCONFINED COMPRESSION TEST



Sample No.	1		
Unconfined strength, psf	848262.7		
Undrained shear strength, psf	424131.4		
Failure strain, %	0.4		
Strain rate, in./min.	0.039		
Water content, %	1.2		
Wet density, pcf	162.0		
Dry density, pcf	160.0		
Saturation, %	N/A		
Void ratio	N/A		
Specimen diameter, in.	1.990		
Specimen height, in.	3.920		
Height/diameter ratio	1.97		

**Description:** LIMESTONE

LL =	PL =	PI =	Assumed GS=	Type: Limestone
------	------	------	-------------	-----------------

**Project No.:** N1105070  
**Date Sampled:** 8-27-10  
**Remarks:**  
 Lab No. 7317

**Client:** PARSONS BRINCKERHOFF  
**Project:** BRENT SPENCE BRIDGE REPLACEMENT  
**Source of Sample:** L-1A      **Depth:** 143-143.5'  
**Sample Number:** 4


UNCONFINED COMPRESSION TEST

**H.C. Nutting**  
 A Terracon Company

**Figure** \_\_\_\_\_

**Tested By:** SV \_\_\_\_\_ **Checked By:** GS \_\_\_\_\_

# UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	1928313.7			
Undrained shear strength, psf	964156.9			
Failure strain, %	0.5			
Strain rate, in./min.	0.038			
Water content, %	0.2			
Wet density, pcf	167.5			
Dry density, pcf	167.2			
Saturation, %	N/A			
Void ratio	N/A			
Specimen diameter, in.	1.990			
Specimen height, in.	3.870			
Height/diameter ratio	1.94			

**Description:** LIMESTONE

LL =	PL =	PI =	Assumed GS=	Type: Limestone
------	------	------	-------------	-----------------

**Project No.:** N1105070  
**Date Sampled:** 8-27-10  
**Remarks:**  
 Lab No. 7319

**Client:** PARSONS BRINCKERHOFF  
**Project:** BRENT SPENCE BRIDGE REPLACEMENT  
**Source of Sample:** L-1A      **Depth:** 150.7-151.2'  
**Sample Number:** 6

UNCONFINED COMPRESSION TEST


**H.C. Nutting**  
 A Terracon Company

**Figure** \_\_\_\_\_

**Tested By:** SV \_\_\_\_\_ **Checked By:** GS \_\_\_\_\_



# UNCONFINED COMPRESSION TEST



Sample No.	1		
Unconfined strength, psf	634960.3		
Undrained shear strength, psf	317480.1		
Failure strain, %	0.4		
Strain rate, in./min.	0.039		
Water content, %	1.9		
Wet density, pcf	162.7		
Dry density, pcf	159.7		
Saturation, %	N/A		
Void ratio	N/A		
Specimen diameter, in.	1.990		
Specimen height, in.	3.900		
Height/diameter ratio	1.96		

**Description:** LIMESTONE

LL =	PL =	PI =	Assumed GS=	Type: Limestone
------	------	------	-------------	-----------------

**Project No.:** N1105070

**Date Sampled:** 8-27-10

**Remarks:**

Lab No. 7322

**Client:** PARSONS BRINCKERHOFF

**Project:** BRENT SPENCE BRIDGE REPLACEMENT

**Source of Sample:** L-1A      **Depth:** 160-160.5'

**Sample Number:** 9

UNCONFINED COMPRESSION TEST


**H.C. Nutting**  
A Terracon Company

**Figure** \_\_\_\_\_

**Tested By:** SV

**Checked By:** GS

# UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	1844685.1			
Undrained shear strength, psf	922342.5			
Failure strain,	1.1			
Strain rate, in./min.	0.034			
Water content, %	2.4			
Wet density, pcf	160.9			
Dry density, pcf	157.1			
Saturation, %	N/A			
Void ratio	N/A			
Specimen diameter, in.	2.010			
Specimen height, in.	3.480			
Height/diameter ratio	1.73			

**Description:** LIMESTONE

LL =	PL =	PI =	Assumed GS=	Type: Limestone
------	------	------	-------------	-----------------

**Project No.:** N1105070

**Date:** 6-15-10

**Remarks:**

Lab No. 4882

**Client:** PARSONS BRINCKERHOFF

**Project:** BRENT SPENCE BRIDGE REPLACEMENT

**Source of Sample:** L-2

**Depth:** 126.7-127'

**Sample Number:** 1/NQ

UNCONFINED COMPRESSION TEST


## H. C. NUTTING COMPANY

Figure \_\_\_\_\_

Tested By: SV

Checked By: GS

# UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	1591219.7			
Undrained shear strength, psf	795609.8			
Failure strain,	0.8			
Strain rate, in./min.	0.041			
Water content, %	0.8			
Wet density, pcf	163.4			
Dry density, pcf	162.1			
Saturation, %	N/A			
Void ratio	N/A			
Specimen diameter, in.	2.010			
Specimen height, in.	4.140			
Height/diameter ratio	2.06			

**Description:** LIMESTONE

**LL =**      **PL =**      **PI =**      **Assumed GS=**      **Type:** Limestone

**Project No.:** N1105070

**Date:** 6-15-10

**Remarks:**  
Lab No. 4884

**Client:** PARSONS BRINCKERHOFF

**Project:** BRENT SPENCE BRIDGE REPLACEMENT

**Source of Sample:** L-2      **Depth:** 130-130.7'

**Sample Number:** 4/NQ

UNCONFINED COMPRESSION TEST


## H. C. NUTTING COMPANY

**Figure** \_\_\_\_\_

**Tested By:** SV \_\_\_\_\_

**Checked By:** GS \_\_\_\_\_

# UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	1746923.7			
Undrained shear strength, psf	873461.9			
Failure strain,	0.8			
Strain rate, in./min.	0.041			
Water content, %	1.1			
Wet density, pcf	163.7			
Dry density, pcf	161.9			
Saturation, %	N/A			
Void ratio	N/A			
Specimen diameter, in.	2.010			
Specimen height, in.	4.180			
Height/diameter ratio	2.08			

**Description:** LIMESTONE

LL =	PL =	PI =	Assumed GS=	Type: Limestone
------	------	------	-------------	-----------------

**Project No.:** N1105070

**Date:** 6-15-10

**Remarks:**

Lab No. 4885

**Client:** PARSONS BRINCKERHOFF

**Project:** BRENT SPENCE BRIDGE REPLACEMENT

**Source of Sample:** L-2

**Depth:** 137-137.5'

**Sample Number:** 3/NQ

UNCONFINED COMPRESSION TEST


## H. C. NUTTING COMPANY

Figure \_\_\_\_\_

Tested By: SV

Checked By: GS

# UNCONFINED COMPRESSION TEST



Sample No.	1		
Unconfined strength, psf	2229975.2		
Undrained shear strength, psf	1114987.6		
Failure strain,	1.0		
Strain rate, in./min.	0.039		
Water content, %	1.1		
Wet density, pcf	164.8		
Dry density, pcf	163.1		
Saturation, %	N/A		
Void ratio	N/A		
Specimen diameter, in.	2.010		
Specimen height, in.	3.930		
Height/diameter ratio	1.96		

**Description:** LIMESTONE

LL =	PL =	PI =	Assumed GS=	Type: Limestone
------	------	------	-------------	-----------------

**Project No.:** N1105070  
**Date:** 6-15-10  
**Remarks:**  
 Lab No. 4887


**Client:** PARSONS BRINCKERHOFF  
**Project:** BRENT SPENCE BRIDGE REPLACEMENT  
**Source of Sample:** L-2      **Depth:** 144-144.5'  
**Sample Number:** 5/NQ

Figure \_\_\_\_\_

UNCONFINED COMPRESSION TEST  
**H. C. NUTTING COMPANY**

Tested By: SV      Checked By: GS

# UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	599284.8			
Undrained shear strength, psf	299642.4			
Failure strain,	1.7			
Strain rate, in./min.	0.024			
Water content, %	2.4			
Wet density, pcf	144.2			
Dry density, pcf	140.7			
Saturation, %	N/A			
Void ratio	N/A			
Specimen diameter, in.	2.010			
Specimen height, in.	2.490			
Height/diameter ratio	1.24			

**Description:** SHALE

LL =	PL =	PI =	Assumed GS=	Type: Shale
------	------	------	-------------	-------------

**Project No.:** NI105070  
**Date:** 6-15-10  
**Remarks:**  
 Lab No. 4888


**Client:** PARSONS BRINCKERHOFF  
**Project:** BRENT SPENCE BRIDGE REPLACEMENT  
**Source of Sample:** L-2      **Depth:** 148.2-148.5'  
**Sample Number:** 5/NQ

Figure \_\_\_\_\_

UNCONFINED COMPRESSION TEST  
**H. C. NUTTING COMPANY**

**Tested By:** SV      **Checked By:** GS

# UNCONFINED COMPRESSION TEST



Sample No.	1		
Unconfined strength, psf	1398280.1		
Undrained shear strength, psf	699140.0		
Failure strain,	1.1		
Strain rate, in./min.	0.038		
Water content, %	3.6		
Wet density, pcf	161.9		
Dry density, pcf	156.3		
Saturation, %	N/A		
Void ratio	N/A		
Specimen diameter, in.	2.010		
Specimen height, in.	3.810		
Height/diameter ratio	1.90		

**Description:** LIMESTONE

LL =	PL =	PI =	Assumed GS=	Type: Limestone
------	------	------	-------------	-----------------

**Project No.:** N1105070

**Date:** 6-15-10

**Remarks:**

Lab No. 4889

**Client:** PARSONS BRINCKERHOFF

**Project:** BRENT SPENCE BRIDGE REPLACEMENT

**Source of Sample:** L-2

**Depth:** 153-153.5'

**Sample Number:** 6/NQ

UNCONFINED COMPRESSION TEST

## H. C. NUTTING COMPANY

Figure \_\_\_\_\_


Tested By: SV

Checked By: GS





# UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	1280499.4			
Undrained shear strength, psf	640249.7			
Failure strain,	0.8			
Strain rate, in./min.	0.035			
Water content, %	1.2			
Wet density, pcf	159.3			
Dry density, pcf	157.5			
Saturation, %	N/A			
Void ratio	N/A			
Specimen diameter, in.	2.010			
Specimen height, in.	3.590			
Height/diameter ratio	1.79			

**Description:** LIMESTONE

LL =      PL =      PI =      Assumed GS=      Type: Limestone

**Project No.:** N1105070

**Date:** 6-15-10

**Remarks:**  
Lab No. 4891

**Client:** PARSONS BRINCKERHOFF

**Project:** BRENT SPENCE BRIDGE REPLACEMENT

**Source of Sample:** L-2      **Depth:** 158.5-158.9'

**Sample Number:** 8/NQ


UNCONFINED COMPRESSION TEST.

## H. C. NUTTING COMPANY

Figure \_\_\_\_\_

Tested By: SV      Checked By: GS

# UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	899381.1			
Undrained shear strength, psf	449690.5			
Failure strain,	0.9			
Strain rate, in./min.	0.029			
Water content, %	1.7			
Wet density, pcf	160.4			
Dry density, pcf	157.7			
Saturation, %	N/A			
Void ratio	N/A			
Specimen diameter, in.	2.010			
Specimen height, in.	2.990			
Height/diameter ratio	1.49			

**Description:** LIMESTONE

LL =	PL =	PI =	Assumed GS=	Type: Limestone
------	------	------	-------------	-----------------

**Project No.:** N1105070  
**Date:** 6-15-10  
**Remarks:**  
 Lab No. 4892


**Client:** PARSONS BRINCKERHOFF  
**Project:** BRENT SPENCE BRIDGE REPLACEMENT  
**Source of Sample:** L-2      **Depth:** 163.6-164'  
**Sample Number:** 9/NQ

Figure \_\_\_\_\_

UNCONFINED COMPRESSION TEST  
**H. C. NUTTING COMPANY**

Tested By: SV      Checked By: GS

# UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	1542930.8			
Undrained shear strength, psf	771465.4			
Failure strain,	1.1			
Strain rate, in./min.	0.030			
Water content, %	1.1			
Wet density, pcf	163.8			
Dry density, pcf	162.0			
Saturation, %	N/A			
Void ratio	N/A			
Specimen diameter, in.	2.010			
Specimen height, in.	3.090			
Height/diameter ratio	1.54			

**Description:** LIMESTONE

LL =	PL =	PI =	Assumed GS=	Type: Limestone
------	------	------	-------------	-----------------

**Project No.:** NI105070  
**Date:** 6-15-10  
**Remarks:**  
 Lab No. 4893


Figure \_\_\_\_\_

**Client:** PARSONS BRINCKERHOFF  
**Project:** BRENT SPENCE BRIDGE REPLACEMENT  
**Source of Sample:** L-2      **Depth:** 165.1-165.4'  
**Sample Number:** 9/NQ

UNCONFINED COMPRESSION TEST  
**H. C. NUTTING COMPANY**

Tested By: SV      Checked By: GS

# UNCONFINED COMPRESSION TEST



Sample No.	1		
Unconfined strength, psf	1164152.5		
Undrained shear strength, psf	582076.2		
Failure strain,	0.7		
Strain rate, in./min.	0.038		
Water content, %	0.1		
Wet density, pcf	165.7		
Dry density, pcf	165.4		
Saturation, %	N/A		
Void ratio	N/A		
Specimen diameter, in.	1.980		
Specimen height, in.	3.830		
Height/diameter ratio	1.93		

**Description:** LIMESTONE

LL =      PL =      PI =      Assumed GS=      Type: Limestone

**Project No.:** N1105070

**Date:** 7-28-10

**Remarks:**  
Lab No. 5914

**Client:** PARSONS BRINCKERHOFF

**Project:** BRENT SPENCE BRIDGE REPLACEMENT

**Source of Sample:** L-2A      **Depth:** 130.1-130.5'

**Sample Number:** 1/NQ

UNCONFINED COMPRESSION TEST


## H. C. NUTTING COMPANY

Figure \_\_\_\_\_

Tested By: SV

Checked By: GS

# UNCONFINED COMPRESSION TEST



Sample No.	1		
Unconfined strength, psf	1264643.3		
Undrained shear strength, psf	632321.6		
Failure strain, %	0.7		
Strain rate, in./min.	0.040		
Water content, %	0.3		
Wet density, pcf	167.7		
Dry density, pcf	167.2		
Saturation, %	N/A		
Void ratio	N/A		
Specimen diameter, in.	1.980		
Specimen height, in.	4.030		
Height/diameter ratio	2.04		

**Description:** LIMESTONE

LL =      PL =      PI =      Assumed GS=      Type: Limestone

**Project No.:** N1105070

**Date Sampled:** 7-28-10

**Remarks:**  
lab No. 5915

**Client:** PARSONS BRINCKERHOFF

**Project:** BRENT SPENCE BRIDGE REPLACEMENT

**Source of Sample:** L-2A      **Depth:** 131.5-132.2'

**Sample Number:** 2/NQ


UNCONFINED COMPRESSION TEST

**H.C. Nutting**  
A Terracon Company

Figure \_\_\_\_\_

Tested By: SV      Checked By: GS

# UNCONFINED COMPRESSION TEST



Sample No.	1		
Unconfined strength, psf	267975.4		
Undrained shear strength, psf	133987.7		
Failure strain, %	1.6		
Strain rate, in./min.	0.041		
Water content, %	4.5		
Wet density, pcf	158.4		
Dry density, pcf	151.7		
Saturation, %	N/A		
Void ratio	N/A		
Specimen diameter, in.	1.980		
Specimen height, in.	4.150		
Height/diameter ratio	2.10		

**Description:** SHALE

LL =      PL =      PI =      Assumed GS=      Type: Shale

**Project No.:** N1105070  
**Date Sampled:** 7-28-10  
**Remarks:**  
 Lab No. 5916

**Client:** PARSONS BRINCKERHOFF  
**Project:** BRENT SPENCE BRIDGE REPLACEMENT  
**Source of Sample:** L-2A      **Depth:** 137-137.4'  
**Sample Number:** 3/NQ


UNCONFINED COMPRESSION TEST

**H.C. Nutting**  
 A Terracon Company

Figure \_\_\_\_\_

Tested By: SV      Checked By: GS

# UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	1233462.3			
Undrained shear strength, psf	616731.2			
Failure strain, %	0.5			
Strain rate, in./min.	0.040			
Water content, %	0.7			
Wet density, pcf	167.6			
Dry density, pcf	166.4			
Saturation, %	N/A			
Void ratio	N/A			
Specimen diameter, in.	1.980			
Specimen height, in.	4.000			
Height/diameter ratio	2.02			

**Description:** LIMESTONE


LL =	PL =	PI =	Assumed GS=	Type: Limestone
------	------	------	-------------	-----------------

<p><b>Project No.:</b> N1105070</p> <p><b>Date Sampled:</b> 5921</p> <p><b>Remarks:</b> Lab No. 5921</p>	<p><b>Client:</b> PARSONS BRINCKERHOFF</p> <p><b>Project:</b> BRENT SPENCE BRIDGE REPLACEMENT</p> <p><b>Source of Sample:</b> L-2A      <b>Depth:</b> 157.8-158.3'</p> <p><b>Sample Number:</b> 7/NQ</p>
UNCONFINED COMPRESSION TEST <b>H.C. Nutting</b> A Terracon Company	
Figure _____	

Tested By: SV

Checked By: GS

# UNCONFINED COMPRESSION TEST



Sample No.	1		
Unconfined strength, psf	471917.2		
Undrained shear strength, psf	235958.6		
Failure strain, %	1.2		
Strain rate, in./min.	0.039		
Water content, %	1.9		
Wet density, pcf	164.0		
Dry density, pcf	161.0		
Saturation, %	N/A		
Void ratio	N/A		
Specimen diameter, in.	1.975		
Specimen height, in.	3.980		
Height/diameter ratio	2.02		

**Description:** SHALE & LIMESTONE

LL =                      PL =                      PI =                      Assumed GS=                      Type: Shale & Limestone

<p><b>Project No.:</b> N1105070</p> <p><b>Date Sampled:</b></p> <p><b>Remarks:</b></p>	<p><b>Client:</b> PARSONS BRINCKERHOFF</p> <p><b>Project:</b> BRENT SPENCE BRIDGE REPLACEMENT</p> <p><b>Source of Sample:</b> L-3                      <b>Depth:</b> 97.6-98'</p> <p><b>Sample Number:</b> 2</p>
--	--


UNCONFINED COMPRESSION TEST

**H.C. Nutting**  
A Terracon Company

Figure \_\_\_\_\_



# UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	1863379.2			
Undrained shear strength, psf	931689.6			
Failure strain, %	0.8			
Strain rate, in./min.	0.039			
Water content, %	0.7			
Wet density, pcf	N/A			
Dry density, pcf	N/A			
Saturation, %	N/A			
Void ratio	N/A			
Specimen diameter, in.	1.970			
Specimen height, in.	3.990			
Height/diameter ratio	2.03			

**Description:** LIMESTONE

LL =	PL =	PI =	Assumed GS=	Type: Limestone
------	------	------	-------------	-----------------

**Project No.:** N1105070

**Date Sampled:** 8-3-10

**Remarks:**  
Lab No. 6029

**Client:** PARSONS BRINCKERHOFF

**Project:** BRENT SPENCE BRIDGE REPLACEMENT

**Source of Sample:** L-3      **Depth:** 100.2-100.4'

**Sample Number:** 3

UNCONFINED COMPRESSION TEST


**H.C. Nutting**  
A Terracon Company

**Figure** \_\_\_\_\_

**Tested By:** SV \_\_\_\_\_

**Checked By:** GS \_\_\_\_\_

# UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	1917187.9			
Undrained shear strength, psf	958594.0			
Failure strain, %	0.7			
Strain rate, in./min.	0.038			
Water content, %	1.4			
Wet density, pcf	168.3			
Dry density, pcf	165.9			
Saturation, %	N/A			
Void ratio	N/A			
Specimen diameter, in.	1.975			
Specimen height, in.	3.830			
Height/diameter ratio	1.94			

**Description:** LIMESTONE

LL =      PL =      PI =      Assumed GS=      Type: Limestone

**Project No.:** N1105070

**Date Sampled:** 8-3-10

**Remarks:**  
Lab No. 6030

**Client:** PARSONS BRINCKERHOFF

**Project:** BRENT SPENCE BRIDGE REPLACEMENT

**Source of Sample:** L-3      **Depth:** 103.8-104.4'

**Sample Number:** 4

UNCONFINED COMPRESSION TEST



**H.C. Nutting**  
A Terracon Company

Figure \_\_\_\_\_

Tested By: SV

Checked By: GS

# UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	965311.3			
Undrained shear strength, psf	482655.6			
Failure strain, %	0.8			
Strain rate, in./min.	0.039			
Water content, %	1.3			
Wet density, pcf	165.8			
Dry density, pcf	163.6			
Saturation, %	N/A			
Void ratio	N/A			
Specimen diameter, in.	1.975			
Specimen height, in.	3.920			
Height/diameter ratio	1.98			

**Description:** LIMESTONE & SHALE

LL =	PL =	PI =	Assumed GS=	Type: Limestone & Shale
------	------	------	-------------	-------------------------

**Project No.:** N1105070  
**Date Sampled:** 8-3-10  
**Remarks:**  
 Lab No. 6033

**Client:** PARSONS BRINCKERHOFF  
**Project:** BRENT SPENCE BRIDGE REPLACEMENT  
**Source of Sample:** L-3      **Depth:** 121.2-121.8'  
**Sample Number:** 7


UNCONFINED COMPRESSION TEST

**H.C. Nutting**  
 A Terracon Company

Figure \_\_\_\_\_

**Tested By:** SV      **Checked By:** GS

# UNCONFINED COMPRESSION TEST



Sample No.	1		
Unconfined strength, psf	569305.4		
Undrained shear strength, psf	284652.7		
Failure strain, %	0.4		
Strain rate, in./min.	0.040		
Water content, %	1.2		
Wet density, pcf	166.8		
Dry density, pcf	164.7		
Saturation, %	N/A		
Void ratio	N/A		
Specimen diameter, in.	1.975		
Specimen height, in.	4.030		
Height/diameter ratio	2.04		

**Description:** LIMESTONE W/SHALE

LL =      PL =      PI =      Assumed GS=      Type: Limestone w/Shale

**Project No.:** N1105070

**Date Sampled:** 8-3-10

**Remarks:**  
Lab No. 6034

**Client:** PARSONS BRINCKERHOFF

**Project:** BRENT SPENCE BRIDGE REPLACEMENT

**Source of Sample:** L-3      **Depth:** 124.6-125.2'

**Sample Number:** 8

UNCONFINED COMPRESSION TEST


**H.C. Nutting**  
A Terracon Company

**Figure** \_\_\_\_\_

**Tested By:** SV \_\_\_\_\_

**Checked By:** GS \_\_\_\_\_

# UNCONFINED COMPRESSION TEST



Sample No.	1		
Unconfined strength, psf	1661279.5		
Undrained shear strength, psf	830639.7		
Failure strain, %	0.6		
Strain rate, in./min.	0.040		
Water content, %	0.7		
Wet density, pcf	166.7		
Dry density, pcf	165.5		
Saturation, %	N/A		
Void ratio	N/A		
Specimen diameter, in.	1.975		
Specimen height, in.	4.040		
Height/diameter ratio	2.05		

**Description:** LIMESTONE

LL =	PL =	PI =	Assumed GS=	Type: Limestone
------	------	------	-------------	-----------------

**Project No.:** N1105070  
**Date Sampled:** 8-3-10  
**Remarks:**  
 Lab No. 6038


Figure \_\_\_\_\_

**Client:** PARSONS BRINCKERHOFF  
**Project:** BRENT SPENCE BRIDGE REPLACEMENT  
**Source of Sample:** L-3      **Depth:** 145.2-146.2'  
**Sample Number:** 12

UNCONFINED COMPRESSION TEST  
**H.C. Nutting**  
 A Terracon Company

**Tested By:** SV      **Checked By:** GS

# UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	1358505.5			
Undrained shear strength, psf	679252.8			
Failure strain, %	0.5			
Strain rate, in./min.	0.040			
Water content, %	1.5			
Wet density, pcf	165.7			
Dry density, pcf	163.3			
Saturation, %	N/A			
Void ratio	N/A			
Specimen diameter, in.	1.980			
Specimen height, in.	4.060			
Height/diameter ratio	2.05			

**Description:** LIMESTONE W/SHALE

<b>LL =</b>	<b>PL =</b>	<b>PI =</b>	<b>Assumed GS=</b>	<b>Type:</b> Limestone w/Shale
-------------	-------------	-------------	--------------------	--------------------------------

**Project No.:** N1105070

**Date Sampled:** 8-3-10

**Remarks:**  
Lab No. 6037

**Client:** PARSONS BRINCKERHOFF

**Project:** BRENT SPENCE BRIDGE REPLACEMENT

**Source of Sample:** L-3      **Depth:** 145.6-146.1'

**Sample Number:** 11


UNCONFINED COMPRESSION TEST

**H.C. Nutting**  
A Terracon Company

**Figure** \_\_\_\_\_

**Tested By:** SV      **Checked By:** GS

# UNCONFINED COMPRESSION TEST




Sample No.	1			
Unconfined strength, psf	2475252.6			
Undrained shear strength, psf	1237626.3			
Failure strain, %	0.8			
Strain rate, in./min.	0.039			
Water content, %	0.4			
Wet density, pcf	165.7			
Dry density, pcf	165.0			
Saturation, %	N/A			
Void ratio	N/A			
Specimen diameter, in.	1.980			
Specimen height, in.	3.970			
Height/diameter ratio	2.01			

**Description:** LIMESTONE

<b>LL =</b>	<b>PL =</b>	<b>PI =</b>	<b>Assumed GS=</b>	<b>Type:</b> Limestone
<b>Project No.:</b> N1105070 <b>Date Sampled:</b> 8-3-10 <b>Remarks:</b> Lab No.6040			<b>Client:</b> PARSONS BRINCKERHOFF <b>Project:</b> BRENT SPENCE BRIDGE REPLACEMENT <b>Source of Sample:</b> L-3 <b>Depth:</b> 158.7-160.2' <b>Sample Number:</b> 14	
Figure _____			UNCONFINED COMPRESSION TEST <b>H.C. Nutting</b> A Terracon Company	

**Tested By:** SV      **Checked By:** GS

# UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	1744346.8			
Undrained shear strength, psf	872173.4			
Failure strain, %	1.0			
Strain rate, in./min.	0.037			
Water content, %	0.2			
Wet density, pcf	165.1			
Dry density, pcf	164.7			
Saturation, %	N/A			
Void ratio	N/A			
Specimen diameter, in.	1.980			
Specimen height, in.	3.760			
Height/diameter ratio	1.90			

**Description:** LIMESTONE

LL =      PL =      PI =      Assumed GS=      Type: Limestone

**Project No.:** N1105070

**Date Sampled:** 8-3-10

**Remarks:**  
Lab No. 6041

**Client:** PARSONS BRINCKERHOFF

**Project:** BRENT SPENCE BRIDGE REPLACEMENT

**Source of Sample:** L-3      **Depth:** 162.8-163.3'

**Sample Number:** 15

UNCONFINED COMPRESSION TEST



**H.C. Nutting**  
A Terracon Company

Figure \_\_\_\_\_

Tested By: SV      Checked By: GS



# UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	2176614.5			
Undrained shear strength, psf	1088307.3			
Failure strain, %	0.7			
Strain rate, in./min.	0.040			
Water content, %	0.8			
Wet density, pcf	164.7			
Dry density, pcf	163.5			
Saturation, %	N/A			
Void ratio	N/A			
Specimen diameter, in.	1.970			
Specimen height, in.	4.030			
Height/diameter ratio	2.05			

**Description:** LIMESTONE

LL =	PL =	PI =	Assumed GS=	Type: Limestone
------	------	------	-------------	-----------------

**Project No.:** N1105070

**Date Sampled:** 8-3-10

**Remarks:**  
Lab No. 6042

**Client:** PARSONS BRINCKERHOFF

**Project:** BRENT SPENCE BRIDGE REPLACEMENT

**Source of Sample:** L-3      **Depth:** 164.5-165.2'

**Sample Number:** 16


UNCONFINED COMPRESSION TEST

**H.C. Nutting**  
A Terracon Company

**Figure** \_\_\_\_\_

**Tested By:** SV      **Checked By:** GS

# UNCONFINED COMPRESSION TEST



Sample No.	1		
Unconfined strength, psf	82023.1		
Undrained shear strength, psf	41011.5		
Failure strain, %	2.5		
Strain rate, in./min.	0.033		
Water content, %	6.3		
Wet density, pcf	153.9		
Dry density, pcf	144.8		
Saturation, %	N/A		
Void ratio	N/A		
Specimen diameter, in.	1.960		
Specimen height, in.	3.370		
Height/diameter ratio	1.72		

**Description:** GRAY MED TOUGH SHALE

LL =	PL =	PI =	Assumed GS=	Type: Shale
------	------	------	-------------	-------------

**Project No.:** N1105070  
**Date Sampled:** 5-27-10  
**Remarks:**  
 Lab No. 4190

Figure \_\_\_\_\_


**Client:** PARSONS BRINCKERHOFF  
**Project:** BRENT SPENCE BRIDGE REPLACEMENT  
**Source of Sample:** L-3A      **Depth:** 126.5-126.75'  
**Sample Number:** 3A-1

UNCONFINED COMPRESSION TEST  
**H.C. Nutting**  
 A Terracon Company

**Tested By:** SV \_\_\_\_\_ **Checked By:** GS \_\_\_\_\_



# UNCONFINED COMPRESSION TEST



Sample No.	1		
Unconfined strength, psf	397254.7		
Undrained shear strength, psf	198627.3		
Failure strain, %	0.7		
Strain rate, in./min.	0.045		
Water content, %	0.8		
Wet density, pcf	165.2		
Dry density, pcf	163.8		
Saturation, %	N/A		
Void ratio	N/A		
Specimen diameter, in.	1.990		
Specimen height, in.	4.570		
Height/diameter ratio	2.30		

**Description:** GRAY SHALE & LIMESTONE

LL =	PL =	PI =	Assumed GS=	Type: Limestone
------	------	------	-------------	-----------------

**Project No.:** N1105070

**Date Sampled:** 5-27-10

**Remarks:**

Lab No. 4197

**Client:** PARSONS BRINCKERHOFF

**Project:** BRENT SPENCE BRIDGE REPLACEMENT

**Source of Sample:** L-3A      **Depth:** 157.7-158.0'

**Sample Number:** 3A-8


UNCONFINED COMPRESSION TEST

**H.C. Nutting**  
A Terracon Company

Figure \_\_\_\_\_

Tested By: SV      Checked By: GS

# UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	1965081.6			
Undrained shear strength, psf	982540.8			
Failure strain, %	0.8			
Strain rate, in./min.	0.038			
Water content, %	0.5			
Wet density, pcf	163.5			
Dry density, pcf	162.7			
Saturation, %	N/A			
Void ratio	N/A			
Specimen diameter, in.	2.000			
Specimen height, in.	3.840			
Height/diameter ratio	1.92			

**Description:** LIMESTONE

LL =	PL =	PI =	Assumed GS=	Type: Limestone
------	------	------	-------------	-----------------

**Project No.:** N1105070  
**Date Sampled:** 8-23-10  
**Remarks:**  
 Lab No. 5987


Figure \_\_\_\_\_

**Client:** PARSONS BRINCKERHOFF  
**Project:** BRENT SPENCE BRIDGE REPLACEMENT  
**Source of Sample:** L-4      **Depth:** 116-116.5'  
**Sample Number:** 2

UNCONFINED COMPRESSION TEST  
**H.C. Nutting**  
 A Terracon Company

**Tested By:** SV \_\_\_\_\_ **Checked By:** GS \_\_\_\_\_

# UNCONFINED COMPRESSION TEST



Sample No.	1		
Unconfined strength, psf	1829521.6		
Undrained shear strength, psf	914760.8		
Failure strain, %	1.1		
Strain rate, in./min.	0.037		
Water content, %	1.1		
Wet density, pcf	165.1		
Dry density, pcf	163.4		
Saturation, %	N/A		
Void ratio	N/A		
Specimen diameter, in.	2.000		
Specimen height, in.	3.710		
Height/diameter ratio	1.85		

**Description:** LIMESTONE

LL =      PL =      PI =      Assumed GS=      Type: Limestone

**Project No.:** N1105070

**Date Sampled:** 8-23-10

**Remarks:**  
Lab No. 5988

**Client:** PARSONS BRINCKERHOFF

**Project:** BRENT SPENCE BRIDGE REPLACEMENT

**Source of Sample:** L-4      **Depth:** 120.4-120.9'

**Sample Number:** 3

UNCONFINED COMPRESSION TEST


**H.C. Nutting**  
A Terracon Company

Figure \_\_\_\_\_

Tested By: SV \_\_\_\_\_

Checked By: GS \_\_\_\_\_

# UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	1880122.7			
Undrained shear strength, psf	940061.4			
Failure strain, %	0.9			
Strain rate, in./min.	0.037			
Water content, %	0.8			
Wet density, pcf	166.2			
Dry density, pcf	164.9			
Saturation, %	N/A			
Void ratio	N/A			
Specimen diameter, in.	2.000			
Specimen height, in.	3.760			
Height/diameter ratio	1.88			

**Description:** LIMESTONE

LL =	PL =	PI =	Assumed GS=	Type: Limestone
------	------	------	-------------	-----------------


**Project No.:** N1105070  
**Date Sampled:** 8-23-10  
**Remarks:**  
 Lab No. 5991

**Client:** PARSONS BRINCKERHOFF  
**Project:** BRENT SPENCE BRIDGE REPLACEMENT  
**Source of Sample:** L-4      **Depth:** 140.5-141'  
**Sample Number:** 6

UNCONFINED COMPRESSION TEST  
**H.C. Nutting**  
 A Terracon Company

**Tested By:** SV      **Checked By:** GS

# UNCONFINED COMPRESSION TEST



Sample No.	1		
Unconfined strength, psf	1801226.2		
Undrained shear strength, psf	900613.1		
Failure strain, %	0.9		
Strain rate, in./min.	0.034		
Water content, %	0.4		
Wet density, pcf	165.7		
Dry density, pcf	165.0		
Saturation, %	N/A		
Void ratio	N/A		
Specimen diameter, in.	1.990		
Specimen height, in.	3.490		
Height/diameter ratio	1.75		

**Description:** LIMESTONE

LL =      PL =      PI =      Assumed GS=      Type: Limestone

**Project No.:** N1105070  
**Date Sampled:** 8-23-10  
**Remarks:**  
 Lab No. 5993

**Client:** PARSONS BRINCKERHOFF  
**Project:** BRENT SPENCE BRIDGE REPLACEMENT  
**Source of Sample:** L-4      **Depth:** 143-143.5'  
**Sample Number:** 8

UNCONFINED COMPRESSION TEST

**H.C. Nutting**  
 A Terracon Company



Figure \_\_\_\_\_

Tested By: SV      Checked By: GS





# UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	1567920.4			
Undrained shear strength, psf	783960.2			
Failure strain, %	0.9			
Strain rate, in./min.	0.044			
Water content, %	0.2			
Wet density, pcf	167.4			
Dry density, pcf	167.1			
Saturation, %	N/A			
Void ratio	N/A			
Specimen diameter, in.	1.980			
Specimen height, in.	4.470			
Height/diameter ratio	2.26			

**Description:** GRAY LIMESTONE

LL =      PL =      PI =      Assumed GS=      Type: Limestone

**Project No.:** N1105070

**Date Sampled:** 7-7-10

**Remarks:**  
Lab No. 5576

**Client:** PARSONS BRINCKERHOFF

**Project:** BRENT SPENCE BRIDGE REPLACEMENT

**Source of Sample:** L-5      **Depth:** 120.2-120.6'

**Sample Number:** 4

UNCONFINED COMPRESSION TEST


**H.C. Nutting**  
A Terracon Company

Figure \_\_\_\_\_

**Tested By:** SV \_\_\_\_\_

**Checked By:** GS \_\_\_\_\_

# UNCONFINED COMPRESSION TEST



Sample No.	1		
Unconfined strength, psf	738738.4		
Undrained shear strength, psf	369369.2		
Failure strain, %	0.8		
Strain rate, in./min.	0.041		
Water content, %	0.3		
Wet density, pcf	166.2		
Dry density, pcf	165.7		
Saturation, %	N/A		
Void ratio	N/A		
Specimen diameter, in.	1.980		
Specimen height, in.	4.110		
Height/diameter ratio	2.08		


**Description:** GRAY LIMESTONE W/SHALE

LL =	PL =	PI =	Assumed GS=	Type: Limestone w/shale
------	------	------	-------------	-------------------------

<b>Project No.:</b> N1105070 <b>Date Sampled:</b> 7-7-10 <b>Remarks:</b> Lab No. 5578	<b>Client:</b> PARSONS BRINCKERHOFF  <b>Project:</b> BRENT SPENCE BRIDGE REPLACEMENT  <b>Source of Sample:</b> L-5 <b>Depth:</b> 130.3-131' <b>Sample Number:</b> 6
	UNCONFINED COMPRESSION TEST <b>H.C. Nutting</b> A Terracon Company

Tested By: SV      Checked By: GS

# UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	1217480.4			
Undrained shear strength, psf	608740.2			
Failure strain, %	0.9			
Strain rate, in./min.	0.044			
Water content, %	1.7			
Wet density, pcf	167.1			
Dry density, pcf	164.3			
Saturation, %	N/A			
Void ratio	N/A			
Specimen diameter, in.	1.980			
Specimen height, in.	4.410			
Height/diameter ratio	2.23			

**Description:** GRAY LIMESTONE W/SHALE

LL =	PL =	PI =	Assumed GS=	Type: Limestone w/shale
------	------	------	-------------	-------------------------

**Project No.:** N1105070  
**Date Sampled:** 7-7-10  
**Remarks:**  
 Lab No. 5579


**Client:** PARSONS BRINCKERHOFF  
**Project:** BRENT SPENCE BRIDGE REPLACEMENT  
**Source of Sample:** L-5      **Depth:** 133.3-133.8'  
**Sample Number:** 7

Figure \_\_\_\_\_

UNCONFINED COMPRESSION TEST  
**H.C. Nutting**  
 A Terracon Company

**Tested By:** SV      **Checked By:** GS

# UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	703969.8			
Undrained shear strength, psf	351984.9			
Failure strain, %	0.7			
Strain rate, in./min.	0.042			
Water content, %	0.3			
Wet density, pcf	167.2			
Dry density, pcf	166.8			
Saturation, %	N/A			
Void ratio	N/A			
Specimen diameter, in.	1.980			
Specimen height, in.	4.280			
Height/diameter ratio	2.16			

**Description:** GRAY LIMESTONE AND SHALE

LL =	PL =	PI =	Assumed GS=	Type: Limestone and Shale
------	------	------	-------------	---------------------------

**Project No.:** N1105070

**Date Sampled:** 7-7-10

**Remarks:**  
Lab No. 5557

**Client:** PARSONS BRINCKERHOFF

**Project:** BRENT SPENCE BRIDGE REPLACEMENT

**Source of Sample:** L-6      **Depth:** 112-112.4'

**Sample Number:** 2


UNCONFINED COMPRESSION TEST

**H.C. Nutting**  
A Terracon Company

Figure \_\_\_\_\_

**Tested By:** SV \_\_\_\_\_ **Checked By:** GS \_\_\_\_\_

# UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	2097849.1			
Undrained shear strength, psf	1048924.5			
Failure strain, %	0.7			
Strain rate, in./min.	0.041			
Water content, %	0.2			
Wet density, pcf	168.8			
Dry density, pcf	168.4			
Saturation, %	N/A			
Void ratio	N/A			
Specimen diameter, in.	1.990			
Specimen height, in.	4.180			
Height/diameter ratio	2.10			


**Description:** GRAY LIMESTONE

LL =	PL =	PI =	Assumed GS=	Type: Limestone
------	------	------	-------------	-----------------

<p><b>Project No.:</b> N1105070</p> <p><b>Date Sampled:</b> 7-7-10</p> <p><b>Remarks:</b> Lab No. 5558</p> <p><b>Figure</b> _____</p>	<p><b>Client:</b> PARSONS BRINCKERHOFF</p> <p><b>Project:</b> BRENT SPENCE BRIDGE REPLACEMENT</p> <p><b>Source of Sample:</b> L-6      <b>Depth:</b> 120.5-121'</p> <p><b>Sample Number:</b> 4</p> <p style="text-align: center;">UNCONFINED COMPRESSION TEST</p> <p style="text-align: center;"><b>H.C. Nutting</b> A Terracon Company</p>
---	---

**Tested By:** SV \_\_\_\_\_ **Checked By:** GS \_\_\_\_\_

# UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	1420383.4			
Undrained shear strength, psf	710191.7			
Failure strain, %	0.9			
Strain rate, in./min.	0.036			
Water content, %	0.2			
Wet density, pcf	164.6			
Dry density, pcf	164.3			
Saturation, %	N/A			
Void ratio	N/A			
Specimen diameter, in.	1.990			
Specimen height, in.	3.600			
Height/diameter ratio	1.81			

**Description:** GRAY LIMESTONE

LL =	PL =	PI =	Assumed GS=	Type: Limestone
------	------	------	-------------	-----------------

**Project No.:** N1105070  
**Date Sampled:** 7-7-10  
**Remarks:**  
 Lab No. 5560


Figure \_\_\_\_\_

**Client:** PARSONS BRINCKERHOFF  
**Project:** BRENT SPENCE BRIDGE REPLACEMENT  
**Source of Sample:** L-6      **Depth:** 130.5-130.9'  
**Sample Number:** 6

UNCONFINED COMPRESSION TEST  
**H.C. Nutting**  
 A Terracon Company

**Tested By:** SV \_\_\_\_\_ **Checked By:** GS \_\_\_\_\_

# UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	1544585.1			
Undrained shear strength, psf	772292.5			
Failure strain, %	0.7			
Strain rate, in./min.	0.041			
Water content, %	0.2			
Wet density, pcf	169.6			
Dry density, pcf	169.2			
Saturation, %	N/A			
Void ratio	N/A			
Specimen diameter, in.	1.990			
Specimen height, in.	4.140			
Height/diameter ratio	2.08			

**Description:** GRAY LIMESTONE

LL =      PL =      PI =      Assumed GS=      Type: Limestone

**Project No.:** N1105070  
**Date Sampled:** 7-7-10  
**Remarks:**  
 Lab No. 5562

Figure \_\_\_\_\_


**Client:** PARSONS BRINCKERHOFF  
**Project:** BRENT SPENCE BRIDGE REPLACEMENT  
**Source of Sample:** L-6      **Depth:** 147.5-148'  
**Sample Number:** 8

UNCONFINED COMPRESSION TEST  
**H.C. Nutting**  
 A Terracon Company

**Tested By:** SV      **Checked By:** GS



# UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	1183176.9			
Undrained shear strength, psf	591588.4			
Failure strain, %	0.8			
Strain rate, in./min.	0.041			
Water content, %	0.3			
Wet density, pcf	168.5			
Dry density, pcf	168.0			
Saturation, %	N/A			
Void ratio	N/A			
Specimen diameter, in.	1.980			
Specimen height, in.	4.120			
Height/diameter ratio	2.08			

**Description:** GRAY LIMESTONE

LL =      PL =      PI =      Assumed GS=      Type: Limestone

**Project No.:** N1105070  
**Date Sampled:** 7-7-10  
**Remarks:**  
 Lab No. 5564


Figure \_\_\_\_\_

**Client:** PARSONS BRINCKERHOFF  
**Project:** BRENT SPENCE BRIDGE REPLACEMENT  
**Source of Sample:** L-7      **Depth:** 101-101.5'  
**Sample Number:** 1

UNCONFINED COMPRESSION TEST  
**H.C. Nutting**  
 A Terracon Company

Tested By: SV      Checked By: GS

# UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	842027.9			
Undrained shear strength, psf	421014.0			
Failure strain, %	0.7			
Strain rate, in./min.	0.040			
Water content, %	0.3			
Wet density, pcf	166.4			
Dry density, pcf	165.9			
Saturation, %	N/A			
Void ratio	N/A			
Specimen diameter, in.	1.980			
Specimen height, in.	4.080			
Height/diameter ratio	2.06			


**Description:** GRAY LIMESTONE

**LL =**      **PL =**      **PI =**      **Assumed GS=**      **Type:** Limestone

<p><b>Project No.:</b> N1105070  <b>Date Sampled:</b> 7-7-10  <b>Remarks:</b>                  Lab No. 5567</p>	<p><b>Client:</b> PARSONS BRINCKERHOFF  <b>Project:</b> BRENT SPENCE BRIDGE REPLACEMENT  <b>Source of Sample:</b> L-7      <b>Depth:</b> 113.7-114.2'  <b>Sample Number:</b> 4</p>
UNCONFINED COMPRESSION TEST <b>H.C. Nutting</b> A Terracon Company	

**Tested By:** SV      **Checked By:** GS

# UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	689715.9			
Undrained shear strength, psf	344857.9			
Failure strain, %	0.7			
Strain rate, in./min.	0.041			
Water content, %	0.6			
Wet density, pcf	167.1			
Dry density, pcf	166.1			
Saturation, %	N/A			
Void ratio	N/A			
Specimen diameter, in.	1.980			
Specimen height, in.	4.120			
Height/diameter ratio	2.08			


**Description:** GRAY LIMESTONE W/ SHALE

LL =	PL =	PI =	Assumed GS=	Type: Limestone w/shale
------	------	------	-------------	-------------------------

<p><b>Project No.:</b> N1105070</p> <p><b>Date Sampled:</b> 7-7-10</p> <p><b>Remarks:</b> Lab No. 5571</p>	<p><b>Client:</b> PARSONS BRINCKERHOFF</p> <p><b>Project:</b> BRENT SPENCE BRIDGE REPLACEMENT</p> <p><b>Source of Sample:</b> L-7      <b>Depth:</b> 132.5-133.2'</p> <p><b>Sample Number:</b> 8</p>
<p>UNCONFINED COMPRESSION TEST</p> <p><b>H.C. Nutting</b> A Terracon Company</p>	

**Tested By:** SV      **Checked By:** GS

# UNCONFINED COMPRESSION TEST



Sample No.	1		
Unconfined strength, psf	1837107.7		
Undrained shear strength, psf	918553.9		
Failure strain, %	0.8		
Strain rate, in./min.	0.039		
Water content, %	0.4		
Wet density, pcf	167.8		
Dry density, pcf	167.1		
Saturation, %	N/A		
Void ratio	N/A		
Specimen diameter, in.	1.970		
Specimen height, in.	3.920		
Height/diameter ratio	1.99		

**Description:** LIMESTONE

LL =      PL =      PI =      Assumed GS=      Type: Limestone


**Project No.:** N1105070  
**Date Sampled:** 8-13-10  
**Remarks:**  
 Lab No. 6052

**Client:** PARSONS BRINCKERHOFF  
**Project:** BRENT SPENCE BRIDGE REPLACEMENT  
**Source of Sample:** R-1      **Depth:** 91.5-92.1'  
**Sample Number:** 1

UNCONFINED COMPRESSION TEST  
**H.C. Nutting**  
 A Terracon Company

Tested By: SV      Checked By: GS

# UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	706054.5			
Undrained shear strength, psf	353027.2			
Failure strain, %	0.8			
Strain rate, in./min.	0.039			
Water content, %	2.4			
Wet density, pcf	164.3			
Dry density, pcf	160.5			
Saturation, %	N/A			
Void ratio	N/A			
Specimen diameter, in.	1.980			
Specimen height, in.	3.970			
Height/diameter ratio	2.01			


**Description:** LIMESTONE

LL =      PL =      PI =      Assumed GS=      Type: Limestone

<p><b>Project No.:</b> NI105070  <b>Date Sampled:</b> 8-13-10  <b>Remarks:</b>                  Lab No. 6053</p>	<p><b>Client:</b> PARSONS BRINCKERHOFF  <b>Project:</b> BRENT SPENCE BRIDGE REPLACEMENT  <b>Source of Sample:</b> R-1      <b>Depth:</b> 94.3-95'  <b>Sample Number:</b> 2</p>
UNCONFINED COMPRESSION TEST <b>H.C. Nutting</b> A Terracon Company	

Tested By: SV      Checked By: GS

# UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	568922.9			
Undrained shear strength, psf	284461.5			
Failure strain, %	0.8			
Strain rate, in./min.	0.038			
Water content, %	2.4			
Wet density, pcf	164.6			
Dry density, pcf	160.7			
Saturation, %	N/A			
Void ratio	N/A			
Specimen diameter, in.	1.970			
Specimen height, in.	3.890			
Height/diameter ratio	1.97			

**Description:** LIMESTONE

LL =            PL =            PI =            Assumed GS=            Type: Limestone

**Project No.:** N1105070

**Date Sampled:** 8-13-10

**Remarks:**  
Lab No. 6055

**Client:** PARSONS BRINCKERHOFF

**Project:** BRENT SPENCE BRIDGE REPLACEMENT

**Source of Sample:** R-1            **Depth:** 104.5-105'

**Sample Number:** 4



UNCONFINED COMPRESSION TEST

**H.C. Nutting**  
A Terracon Company

**Figure** \_\_\_\_\_

**Tested By:** SV \_\_\_\_\_ **Checked By:** GS \_\_\_\_\_

# UNCONFINED COMPRESSION TEST



Sample No.	1		
Unconfined strength, psf	1443507.9		
Undrained shear strength, psf	721754.0		
Failure strain, %	0.8		
Strain rate, in./min.	0.040		
Water content, %	0.8		
Wet density, pcf	162.6		
Dry density, pcf	161.3		
Saturation, %	N/A		
Void ratio	N/A		
Specimen diameter, in.	1.980		
Specimen height, in.	4.000		
Height/diameter ratio	2.02		

**Description:** LIMESTONE

LL =      PL =      PI =      Assumed GS=      Type: Limestone

**Project No.:** N1105070  
**Date Sampled:** 8-13-10  
**Remarks:**  
 Lab No. 6058

**Client:** PARSONS BRINCKERHOFF  
**Project:** BRENT SPENCE BRIDGE REPLACEMENT  
**Source of Sample:** R-1      **Depth:** 123-123.5'  
**Sample Number:** 7


UNCONFINED COMPRESSION TEST

**H.C. Nutting**  
 A Terracon Company

Figure \_\_\_\_\_

Tested By: SV      Checked By: GS

# UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	2134074.0			
Undrained shear strength, psf	1067037.0			
Failure strain, %	0.8			
Strain rate, in./min.	0.039			
Water content, %	0.6			
Wet density, pcf	166.2			
Dry density, pcf	165.3			
Saturation, %	N/A			
Void ratio	N/A			
Specimen diameter, in.	1.970			
Specimen height, in.	3.960			
Height/diameter ratio	2.01			

**Description:** LIMESTONE

LL =	PL =	PI =	Assumed GS=	Type: Limestone
------	------	------	-------------	-----------------

**Project No.:** N1105070  
**Date Sampled:** 8-13-10  
**Remarks:**  
 Lab No. 6060

**Client:** PARSONS BRINCKERHOFF  
**Project:** BRENT SPENCE BRIDGE REPLACEMENT  
**Source of Sample:** R-1      **Depth:** 136-136.5'  
**Sample Number:** 9

UNCONFINED COMPRESSION TEST


**H.C. Nutting**  
 A Terracon Company

Figure \_\_\_\_\_

**Tested By:** SV      **Checked By:** GS



# UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	1072646.9			
Undrained shear strength, psf	536323.4			
Failure strain, %	0.8			
Strain rate, in./min.	0.038			
Water content, %	1.3			
Wet density, pcf	162.4			
Dry density, pcf	160.3			
Saturation, %	N/A			
Void ratio	N/A			
Specimen diameter, in.	1.990			
Specimen height, in.	3.830			
Height/diameter ratio	1.92			


**Description:** LIMESTONE

LL =	PL =	PI =	Assumed GS=	Type: Limestone
------	------	------	-------------	-----------------

<p><b>Project No.:</b> NI105070  <b>Date Sampled:</b> 8-23-10  <b>Remarks:</b>                  Lab No. 6062</p>	<p><b>Client:</b> PARSONS BRINCKERHOFF  <b>Project:</b> BRENT SPENCE BRIDGE REPLACEMENT  <b>Source of Sample:</b> R-1      <b>Depth:</b> 145.3-145.7'  <b>Sample Number:</b> 11</p>
UNCONFINED COMPRESSION TEST <b>H.C. Nutting</b> A Terracon Company	

**Tested By:** SV      **Checked By:** GS

# UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	1850857.7			
Undrained shear strength, psf	925428.8			
Failure strain, %	1.2			
Strain rate, in./min.	0.038			
Water content, %	0.6			
Wet density, pcf	161.9			
Dry density, pcf	160.8			
Saturation, %	N/A			
Void ratio	N/A			
Specimen diameter, in.	2.000			
Specimen height, in.	3.850			
Height/diameter ratio	1.93			

**Description:** LIMESTONE

LL =      PL =      PI =      Assumed GS=      Type: Limestone

**Project No.:** N1105070

**Date Sampled:** 8-23-10

**Remarks:**  
Lab No. 6065

**Client:** PARSONS BRINCKERHOFF

**Project:** BRENT SPENCE BRIDGE REPLACEMENT

**Source of Sample:** R-1      **Depth:** 153-153.6'

**Sample Number:** 14


UNCONFINED COMPRESSION TEST

**H.C. Nutting**  
A Terracon Company

Figure \_\_\_\_\_

**Tested By:** SV \_\_\_\_\_ **Checked By:** GS \_\_\_\_\_

# UNCONFINED COMPRESSION TEST



Sample No.	1		
Unconfined strength, psf	1592203.7		
Undrained shear strength, psf	796101.9		
Failure strain, %	1.1		
Strain rate, in./min.	0.036		
Water content, %	0.7		
Wet density, pcf	162.4		
Dry density, pcf	161.3		
Saturation, %	N/A		
Void ratio	N/A		
Specimen diameter, in.	1.990		
Specimen height, in.	3.660		
Height/diameter ratio	1.84		

**Description:** LIMESTONE

LL =	PL =	PI =	Assumed GS=	Type: Limestone
------	------	------	-------------	-----------------

**Project No.:** N1105070  
**Date Sampled:** 8-23-10  
**Remarks:**  
 Lab No. 6066

**Client:** PARSONS BRINCKERHOFF  
**Project:** BRENT SPENCE BRIDGE REPLACEMENT  
**Source of Sample:** R-1      **Depth:** 159.1-159.9'  
**Sample Number:** 15


UNCONFINED COMPRESSION TEST

**H.C. Nutting**  
 A Terracon Company

Figure \_\_\_\_\_

**Tested By:** SV      **Checked By:** GS

# UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	2046785.9			
Undrained shear strength, psf	1023392.9			
Failure strain, %	0.8			
Strain rate, in./min.	0.038			
Water content, %	1.2			
Wet density, pcf	161.3			
Dry density, pcf	159.4			
Saturation, %	N/A			
Void ratio	N/A			
Specimen diameter, in.	1.990			
Specimen height, in.	3.880			
Height/diameter ratio	1.95			



**Description:** LIMESTONE

LL =	PL =	PI =	Assumed GS=	Type: Limestone
------	------	------	-------------	-----------------

<p><b>Project No.:</b> N1105070  <b>Date Sampled:</b> 8-23-10  <b>Remarks:</b>                  Lab No. 6068</p>	<p><b>Client:</b> PARSONS BRINCKERHOFF  <b>Project:</b> BRENT SPENCE BRIDGE REPLACEMENT  <b>Source of Sample:</b> R-1      <b>Depth:</b> 163.5-164.2'  <b>Sample Number:</b> 17</p>
UNCONFINED COMPRESSION TEST <b>H.C. Nutting</b> A Terracon Company	

**Tested By:** SV      **Checked By:** GS

# UNCONFINED COMPRESSION TEST



Sample No.	1		
Unconfined strength, psf	2000122.6		
Undrained shear strength, psf	1000061.3		
Failure strain, %	1.0		
Strain rate, in./min.	0.038		
Water content, %	1.2		
Wet density, pcf	168.6		
Dry density, pcf	166.7		
Saturation, %	N/A		
Void ratio	N/A		
Specimen diameter, in.	1.990		
Specimen height, in.	3.810		
Height/diameter ratio	1.91		

**Description:** LIMESTONE

LL =      PL =      PI =      Assumed GS=      Type: Limestone

**Project No.:** N1105070

**Date Sampled:** 8-23-10

**Remarks:**  
Lab No. 6069

**Client:** PARSONS BRINCKERHOFF

**Project:** BRENT SPENCE BRIDGE REPLACEMENT

**Source of Sample:** R-1      **Depth:** 168.2-168.9'

**Sample Number:** 18


UNCONFINED COMPRESSION TEST

**H.C. Nutting**  
A Terracon Company

**Figure** \_\_\_\_\_

**Tested By:** SV \_\_\_\_\_ **Checked By:** GS \_\_\_\_\_

# UNCONFINED COMPRESSION TEST




Sample No.	1			
Unconfined strength, psf	1893232.5			
Undrained shear strength, psf	946616.2			
Failure strain, %	0.8			
Strain rate, in./min.	0.039			
Water content, %	0.2			
Wet density, pcf	167.9			
Dry density, pcf	167.7			
Saturation, %	N/A			
Void ratio	N/A			
Specimen diameter, in.	1.980			
Specimen height, in.	3.960			
Height/diameter ratio	2.00			

<b>Description: LIMESTONE</b>				
LL =	PL =	PI =	Assumed GS=	Type: Limestone
<b>Project No.:</b> N1105070 <b>Date Sampled:</b> 7-20-10 <b>Remarks:</b> Lab No. 5878			<b>Client:</b> PARSONS BRINCKERHOFF <b>Project:</b> BRENT SPENCE BRIDGE REPLACEMENT <b>Source of Sample:</b> R-2 <b>Depth:</b> 87.5-88' <b>Sample Number:</b> 1/NQ	
Figure _____			UNCONFINED COMPRESSION TEST <b>H.C. Nutting</b> A Terracon Company	

**Tested By:** SV \_\_\_\_\_ **Checked By:** GS \_\_\_\_\_

# UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	1387302.6			
Undrained shear strength, psf	693651.3			
Failure strain, %	0.8			
Strain rate, in./min.	0.044			
Water content, %	0.6			
Wet density, pcf	165.2			
Dry density, pcf	164.2			
Saturation, %	N/A			
Void ratio	N/A			
Specimen diameter, in.	1.980			
Specimen height, in.	4.490			
Height/diameter ratio	2.27			

**Description:** LIMESTONE

LL =      PL =      PI =      Assumed GS=      Type: Limestone

**Project No.:** N1105070  
**Date Sampled:** 7-20-10  
**Remarks:**  
 Lab No. 5881


Figure \_\_\_\_\_

**Client:** PARSONS BRINCKERHOFF  
**Project:** BRENT SPENCE BRIDGE REPLACEMENT  
**Source of Sample:** R-2      **Depth:** 89.3-89.7'  
**Sample Number:** 2/NQ

UNCONFINED COMPRESSION TEST  
**H.C. Nutting**  
 A Terracon Company

Tested By: SV      Checked By: GS

# UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	1848338.3			
Undrained shear strength, psf	924169.1			
Failure strain, %	0.8			
Strain rate, in./min.	0.039			
Water content, %	0.4			
Wet density, pcf	167.5			
Dry density, pcf	166.8			
Saturation, %	N/A			
Void ratio	N/A			
Specimen diameter, in.	1.980			
Specimen height, in.	3.960			
Height/diameter ratio	2.00			

**Description:** LIMESTONE

LL =      PL =      PI =      Assumed GS=      Type: Limestone

**Project No.:** N1105070  
**Date Sampled:** 7-20-10  
**Remarks:**  
 Lab No. 5882

Figure \_\_\_\_\_


**Client:** PARSONS BRINCKERHOFF  
**Project:** BRENT SPENCE BRIDGE REPLACEMENT  
**Source of Sample:** R-2      **Depth:** 90.7-91.6'  
**Sample Number:** 2/NQ

UNCONFINED COMPRESSION TEST  
**H.C. Nutting**  
 A Terracon Company

Tested By: SV      Checked By: GS



# UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	709761.6			
Undrained shear strength, psf	354880.8			
Failure strain, %	1.2			
Strain rate, in./min.	0.038			
Water content, %	2.2			
Wet density, pcf	160.9			
Dry density, pcf	157.4			
Saturation, %	N/A			
Void ratio	N/A			
Specimen diameter, in.	1.980			
Specimen height, in.	3.870			
Height/diameter ratio	1.95			


**Description:** SHALE

LL =      PL =      PI =      Assumed GS=      Type: Shale

<p><b>Project No.:</b> N1105070  <b>Date Sampled:</b> 7-20-10  <b>Remarks:</b>                  Lab No. 5883</p>	<p><b>Client:</b> PARSONS BRINCKERHOFF  <b>Project:</b> BRENT SPENCE BRIDGE REPLACEMENT  <b>Source of Sample:</b> R-2      <b>Depth:</b> 93.7-94'  <b>Sample Number:</b> 2/NQ</p>
UNCONFINED COMPRESSION TEST <b>H.C. Nutting</b> A Terracon Company	

**Tested By:** SV      **Checked By:** GS

# UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	1155667.4			
Undrained shear strength, psf	577833.7			
Failure strain, %	0.8			
Strain rate, in./min.	0.041			
Water content, %	0.8			
Wet density, pcf	165.1			
Dry density, pcf	163.8			
Saturation, %	N/A			
Void ratio	N/A			
Specimen diameter, in.	1.975			
Specimen height, in.	4.140			
Height/diameter ratio	2.10			


**Description:** LIMESTONE

LL =      PL =      PI =      Assumed GS=      Type: Limestone

<p><b>Project No.:</b> N1105070  <b>Date Sampled:</b> 7-20-10  <b>Remarks:</b>                  Lab No. 5884</p> <p>Figure _____</p>	<p><b>Client:</b> PARSONS BRINCKERHOFF  <b>Project:</b> BRENT SPENCE BRIDGE REPLACEMENT  <b>Source of Sample:</b> R-2      <b>Depth:</b> 99.8-100.1'  <b>Sample Number:</b> 3/NQ</p> <p style="text-align: center;">UNCONFINED COMPRESSION TEST  <b>H.C. Nutting</b>                  A Terracon Company</p>
--	--

Tested By: SV      Checked By: GS

# UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	2034883.4			
Undrained shear strength, psf	1017441.7			
Failure strain, %	0.7			
Strain rate, in./min.	0.039			
Water content, %	0.2			
Wet density, pcf	168.4			
Dry density, pcf	168.1			
Saturation, %	N/A			
Void ratio	N/A			
Specimen diameter, in.	1.980			
Specimen height, in.	3.970			
Height/diameter ratio	2.01			

**Description:** LIMESTONE

**LL =**      **PL =**      **PI =**      **Assumed GS=**      **Type:** Limestone

**Project No.:** N1105070  
**Date Sampled:** 7-20-10  
**Remarks:**  
 Lab No. 5887


**Figure** \_\_\_\_\_

**Client:** PARSONS BRINCKERHOFF  
**Project:** BRENT SPENCE BRIDGE REPLACEMENT  
**Source of Sample:** R-2      **Depth:** 112.9-113.9'  
**Sample Number:** 6/NQ

UNCONFINED COMPRESSION TEST  
**H.C. Nutting**  
 A Terracon Company

**Tested By:** SV      **Checked By:** GS

# UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	2005345.4			
Undrained shear strength, psf	1002672.7			
Failure strain, %	0.7			
Strain rate, in./min.	0.040			
Water content, %	0.4			
Wet density, pcf	169.1			
Dry density, pcf	168.4			
Saturation, %	N/A			
Void ratio	N/A			
Specimen diameter, in.	1.980			
Specimen height, in.	4.060			
Height/diameter ratio	2.05			

**Description:** LIMESTONE

LL =	PL =	PI =	Assumed GS=	Type: Limestone
------	------	------	-------------	-----------------

**Project No.:** N1105070  
**Date Sampled:** 7-20-10  
**Remarks:**  
 Lab No. 5888



Figure \_\_\_\_\_

**Client:** PARSONS BRINCKERHOFF  
**Project:** BRENT SPENCE BRIDGE REPLACEMENT  
**Source of Sample:** R-2      **Depth:** 119.8-120.6'  
**Sample Number:** 8/NQ

UNCONFINED COMPRESSION TEST  
**H.C. Nutting**  
 A Terracon Company

Tested By: SV      Checked By: GS

# UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	1138483.6			
Undrained shear strength, psf	569241.8			
Failure strain, %	1.0			
Strain rate, in./min.	0.040			
Water content, %	1.2			
Wet density, pcf	165.7			
Dry density, pcf	163.8			
Saturation, %	N/A			
Void ratio	N/A			
Specimen diameter, in.	1.970			
Specimen height, in.	4.030			
Height/diameter ratio	2.05			

**Description:** LIMESTONE

**LL =**      **PL =**      **PI =**      **Assumed GS=**      **Type:** Limestone

**Project No.:** N1105070  
**Date Sampled:** 7-20-10  
**Remarks:**  
 Lab No. 5891


Figure \_\_\_\_\_

**Client:** PARSONS BRINCKERHOFF  
**Project:** BRENT SPENCE BRIDGE REPLACEMENT  
**Source of Sample:** R-2      **Depth:** 139-139.5'  
**Sample Number:** 12/NQ

UNCONFINED COMPRESSION TEST  
**H.C. Nutting**  
 A Terracon Company

**Tested By:** SV \_\_\_\_\_ **Checked By:** GS \_\_\_\_\_

# UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	2075031.3			
Undrained shear strength, psf	1037515.7			
Failure strain, %	1.3			
Strain rate, in./min.	0.045			
Water content, %	0.6			
Wet density, pcf	167.6			
Dry density, pcf	166.5			
Saturation, %	N/A			
Void ratio	N/A			
Specimen diameter, in.	2.380			
Specimen height, in.	4.530			
Height/diameter ratio	1.90			

**Description:** LIMESTONE

LL =      PL =      PI =      Assumed GS=      Type: Limestone

**Project No.:** N1105070

**Date Sampled:** 10-5-10

**Remarks:**

Lab No. 9697

**Client:** PARSONS BRINCKERHOFF

**Project:** BRENT SPENCE BRIDGE REPLACEMENT

**Source of Sample:** R-2A

**Depth:** 99.5-100.1'

**Sample Number:** 1

UNCONFINED COMPRESSION TEST


**H.C. Nutting**  
A Terracon Company

Figure \_\_\_\_\_

Tested By: MRE

Checked By: GS

# UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	1773180.9			
Undrained shear strength, psf	886590.5			
Failure strain, %	1.1			
Strain rate, in./min.	0.039			
Water content, %	1.1			
Wet density, pcf	169.3			
Dry density, pcf	167.4			
Saturation, %	N/A			
Void ratio	N/A			
Specimen diameter, in.	2.375			
Specimen height, in.	3.970			
Height/diameter ratio	1.67			

**Description:** LIMESTONE


LL =	PL =	PI =	Assumed GS=	Type: Limestone
------	------	------	-------------	-----------------

<p><b>Project No.:</b> N1105070  <b>Date Sampled:</b> 10-5-10  <b>Remarks:</b>                  Lab No. 9699</p> <p>Figure _____</p>	<p><b>Client:</b> PARSONS BRINCKERHOFF</p> <p><b>Project:</b> BRENT SPENCE BRIDGE REPLACEMENT</p> <p><b>Source of Sample:</b> R-2A      <b>Depth:</b> 111.8-112.2'</p> <p><b>Sample Number:</b> 3</p> <p style="text-align: center;">UNCONFINED COMPRESSION TEST</p> <p style="text-align: center;"><b>H.C. Nutting</b> A Terracon Company</p>
--	--

**Tested By:** MRE

**Checked By:** GS

# UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	872331.3			
Undrained shear strength, psf	436165.7			
Failure strain, %	0.7			
Strain rate, in./min.	0.033			
Water content, %	1.9			
Wet density, pcf	161.1			
Dry density, pcf	158.1			
Saturation, %	N/A			
Void ratio	N/A			
Specimen diameter, in.	2.380			
Specimen height, in.	3.360			
Height/diameter ratio	1.41			

**Description:** LIMESTONE

LL =      PL =      PI =      Assumed GS=      Type: Limestone

**Project No.:** N1105070  
**Date Sampled:** 10-5-10  
**Remarks:**  
 Lab No. 9701

**Client:** PARSONS BRINCKERHOFF  
**Project:** BRENT SPENCE BRIDGE REPLACEMENT  
**Source of Sample:** R-2A      **Depth:** 117.8-118.2'  
**Sample Number:** 5

UNCONFINED COMPRESSION TEST


**H.C. Nutting**  
 A Terracon Company

Figure \_\_\_\_\_

**Tested By:** MRE      **Checked By:** GS



# UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	1331115.6			
Undrained shear strength, psf	665557.8			
Failure strain, %	0.6			
Strain rate, in./min.	0.037			
Water content, %	0.7			
Wet density, pcf	164.3			
Dry density, pcf	163.2			
Saturation, %	N/A			
Void ratio	N/A			
Specimen diameter, in.	1.970			
Specimen height, in.	3.700			
Height/diameter ratio	1.88			


**Description:** LIMESTONE

LL =      PL =      PI =      Assumed GS=      Type: Limestone

<p><b>Project No.:</b> N1105070  <b>Date Sampled:</b> 8-3-10  <b>Remarks:</b>                  Lab No. 6014</p> <p>Figure _____</p>	<p><b>Client:</b> PARSONS BRINCKERHOFF  <b>Project:</b> BRENT SPENCE BRIDGE REPLACEMENT  <b>Source of Sample:</b> R-3      <b>Depth:</b> 92.3-92.7'  <b>Sample Number:</b> 1</p> <p style="text-align: center;">UNCONFINED COMPRESSION TEST  <b>H.C. Nutting</b>                  A Terracon Company</p>
---	--

Tested By: SV      Checked By: GS

# UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	1474639.5			
Undrained shear strength, psf	737319.7			
Failure strain, %	0.6			
Strain rate, in./min.	0.039			
Water content, %	0.2			
Wet density, pcf	170.4			
Dry density, pcf	170.0			
Saturation, %	N/A			
Void ratio	N/A			
Specimen diameter, in.	1.970			
Specimen height, in.	3.940			
Height/diameter ratio	2.00			

**Description:** LIMESTONE

LL =      PL =      PI =      Assumed GS=      Type: Limestone

**Project No.:** N1105070

**Date Sampled:** 8-3-10

**Remarks:**  
Lab No. 6015

**Client:** PARSONS BRINCKERHOFF

**Project:** BRENT SPENCE BRIDGE REPLACEMENT

**Source of Sample:** R-3      **Depth:** 93.8-94.5'

**Sample Number:** 2

UNCONFINED COMPRESSION TEST



**H.C. Nutting**  
A Terracon Company

Figure \_\_\_\_\_

**Tested By:** SV \_\_\_\_\_

**Checked By:** GS \_\_\_\_\_

# UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	1041933.4			
Undrained shear strength, psf	520966.7			
Failure strain, %	0.6			
Strain rate, in./min.	0.035			
Water content, %	1.7			
Wet density, pcf	165.2			
Dry density, pcf	162.4			
Saturation, %	N/A			
Void ratio	N/A			
Specimen diameter, in.	1.970			
Specimen height, in.	3.580			
Height/diameter ratio	1.82			

**Description:** LIMESTONE & SHALE

LL =      PL =      PI =      Assumed GS=      Type: Limestone and Shale

**Project No.:** N1105070

**Date Sampled:** 7-30-10

**Remarks:**  
Lab No. 6017

**Client:** PARSONS BRINCKERHOFF

**Project:** BRENT SPENCE BRIDGE REPLACEMENT

**Source of Sample:** R-3      **Depth:** 102.7

**Sample Number:** 4

UNCONFINED COMPRESSION TEST



**H.C. Nutting**  
A Terracon Company

Figure \_\_\_\_\_

**Tested By:** SV \_\_\_\_\_ **Checked By:** GS \_\_\_\_\_



# UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	983924.2			
Undrained shear strength, psf	491962.1			
Failure strain, %	0.4			
Strain rate, in./min.	0.039			
Water content, %	0.9			
Wet density, pcf	165.8			
Dry density, pcf	164.4			
Saturation, %	N/A			
Void ratio	N/A			
Specimen diameter, in.	1.970			
Specimen height, in.	3.940			
Height/diameter ratio	2.00			

**Description:** LIMESTONE & SHALE

LL =      PL =      PI =      Assumed GS=      Type: Limestone & Shale

**Project No.:** N1105070  
**Date Sampled:** 8-3-10  
**Remarks:**  
 Lab No. 6022


Figure \_\_\_\_\_

**Client:** PARSONS BRINCKERHOFF  
**Project:** BRENT SPENCE BRIDGE REPLACEMENT  
**Source of Sample:** R-3      **Depth:** 123.8-124.7'  
**Sample Number:** 9

UNCONFINED COMPRESSION TEST  
**H.C. Nutting**  
 A Terracon Company

**Tested By:** SV      **Checked By:** GS

# UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	1310334.6			
Undrained shear strength, psf	655167.3			
Failure strain, %	0.6			
Strain rate, in./min.	0.039			
Water content, %	0.5			
Wet density, pcf	166.3			
Dry density, pcf	165.5			
Saturation, %	N/A			
Void ratio	N/A			
Specimen diameter, in.	1.970			
Specimen height, in.	3.940			
Height/diameter ratio	2.00			

**Description:** LIMESTONE

**LL =**      **PL =**      **PI =**      **Assumed GS=**      **Type:** Limestone

**Project No.:** N1105070

**Date Sampled:** 8-3-10

**Remarks:**

Lab No. 6024

**Client:** PARSONS BRINCKERHOFF

**Project:** BRENT SPENCE BRIDGE REPLACEMENT

**Source of Sample:** R-3

**Depth:** 140-140.5'

**Sample Number:** 11


UNCONFINED COMPRESSION TEST

**H.C. Nutting**  
A Terracon Company

**Figure** \_\_\_\_\_

**Tested By:** SV \_\_\_\_\_ **Checked By:** GS \_\_\_\_\_

# UNCONFINED COMPRESSION TEST



Sample No.	1		
Unconfined strength, psf	1694430.2		
Undrained shear strength, psf	847215.1		
Failure strain, %	0.9		
Strain rate, in./min.	0.039		
Water content, %	1.1		
Wet density, pcf	167.8		
Dry density, pcf	165.9		
Saturation, %	N/A		
Void ratio	N/A		
Specimen diameter, in.	1.970		
Specimen height, in.	3.910		
Height/diameter ratio	1.98		

**Description:** LIMESTONE

LL =	PL =	PI =	Assumed GS=	Type: Limestone
------	------	------	-------------	-----------------

**Project No.:** N1105070

**Date Sampled:** 8-3-10

**Remarks:**  
Lab No. 6025

**Client:** PARSONS BRINCKERHOFF

**Project:** BRENT SPENCE BRIDGE REPLACEMENT

**Source of Sample:** R-3      **Depth:** 145.5-146'

**Sample Number:** 12


UNCONFINED COMPRESSION TEST

**H.C. Nutting**  
A Terracon Company

Figure \_\_\_\_\_

**Tested By:** SV      **Checked By:** GS

# UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	2048572.8			
Undrained shear strength, psf	1024286.4			
Failure strain, %	0.9			
Strain rate, in./min.	0.040			
Water content, %	0.5			
Wet density, pcf	168.3			
Dry density, pcf	167.5			
Saturation, %	N/A			
Void ratio	N/A			
Specimen diameter, in.	1.970			
Specimen height, in.	4.010			
Height/diameter ratio	2.04			

**Description:** LIMESTONE

LL =      PL =      PI =      Assumed GS=      Type: Limestone

**Project No.:** N1105070

**Date Sampled:** 8-3-10

**Remarks:**  
Lab No. 6026

**Client:** PARSONS BRINCKERHOFF

**Project:** BRENT SPENCE BRIDGE REPLACEMENT

**Source of Sample:** R-3      **Depth:** 157.3-158'

**Sample Number:** 13

UNCONFINED COMPRESSION TEST

**H.C. Nutting**  
A Terracon Company


Figure \_\_\_\_\_

Tested By: SV

Checked By: GS



# UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	1198015.0			
Undrained shear strength, psf	599007.5			
Failure strain, %	1.0			
Strain rate, in./min.	0.040			
Water content, %	4.2			
Wet density, pcf	162.0			
Dry density, pcf	155.5			
Saturation, %	N/A			
Void ratio	N/A			
Specimen diameter, in.	2.000			
Specimen height, in.	4.040			
Height/diameter ratio	2.02			

**Description:** LIMESTONE

LL =	PL =	PI =	Assumed GS=	Type: Limestone
------	------	------	-------------	-----------------

**Project No.:** N1105070  
**Date Sampled:** 8-23-10  
**Remarks:**  
 Lab No. 6070

**Client:** PARSONS BRINCKERHOFF  
**Project:** BRENT SPENCE BRIDGE REPLACEMENT  
**Source of Sample:** R-4      **Depth:** 90.5-91.0'  
**Sample Number:** 1


UNCONFINED COMPRESSION TEST

**H.C. Nutting**  
 A Terracon Company

Figure \_\_\_\_\_

**Tested By:** SV \_\_\_\_\_ **Checked By:** GS \_\_\_\_\_

# UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	832099.0			
Undrained shear strength, psf	416049.5			
Failure strain, %	0.9			
Strain rate, in./min.	0.039			
Water content, %	4.2			
Wet density, pcf	159.3			
Dry density, pcf	152.8			
Saturation, %	N/A			
Void ratio	N/A			
Specimen diameter, in.	1.990			
Specimen height, in.	3.930			
Height/diameter ratio	1.97			


**Description:** LIMESTONE

LL =      PL =      PI =      Assumed GS=      Type: Limestone

<p><b>Project No.:</b> N1105070  <b>Date Sampled:</b> 8-23-10  <b>Remarks:</b>                  Lab No. 6072</p>	<p><b>Client:</b> PARSONS BRINCKERHOFF  <b>Project:</b> BRENT SPENCE BRIDGE REPLACEMENT  <b>Source of Sample:</b> R-4      <b>Depth:</b> 95.5-96'  <b>Sample Number:</b> 3</p>
UNCONFINED COMPRESSION TEST <b>H.C. Nutting</b> A Terracon Company	

Tested By: SV      Checked By: GS

# UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	380693.0			
Undrained shear strength, psf	190346.5			
Failure strain, %	0.8			
Strain rate, in./min.	0.039			
Water content, %	1.9			
Wet density, pcf	161.3			
Dry density, pcf	158.3			
Saturation, %	N/A			
Void ratio	N/A			
Specimen diameter, in.	1.990			
Specimen height, in.	3.920			
Height/diameter ratio	1.97			

**Description:** LIMESTONE AND SHALE

LL =      PL =      PI =      Assumed GS=      Type: Limestone and Shale

**Project No.:** N1105070  
**Date Sampled:** 8-23-10  
**Remarks:**  
 Lab No. 6074


Figure \_\_\_\_\_

**Client:** PARSONS BRINCKERHOFF  
**Project:** BRENT SPENCE BRIDGE REPLACEMENT  
**Source of Sample:** R-4      **Depth:** 102.8-103.3'  
**Sample Number:** 5

UNCONFINED COMPRESSION TEST  
**H.C. Nutting**  
 A Terracon Company

Tested By: SV      Checked By: GS

# UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	857943.7			
Undrained shear strength, psf	428971.8			
Failure strain, %	0.8			
Strain rate, in./min.	0.039			
Water content, %	1.5			
Wet density, pcf	161.9			
Dry density, pcf	159.5			
Saturation, %	N/A			
Void ratio	N/A			
Specimen diameter, in.	1.990			
Specimen height, in.	3.910			
Height/diameter ratio	1.96			

**Description:** LIMESTONE

LL =	PL =	PI =	Assumed GS=	Type: Limestone
------	------	------	-------------	-----------------

**Project No.:** N1105070  
**Date Sampled:** 8-23-10  
**Remarks:**  
 Lab No. 6075

**Client:** PARSONS BRINCKERHOFF  
**Project:** BRENT SPENCE BRIDGE REPLACEMENT  
**Source of Sample:** R-4      **Depth:** 111.3-111.9'  
**Sample Number:** 6


UNCONFINED COMPRESSION TEST

**H.C. Nutting**  
 A Terracon Company

Figure \_\_\_\_\_

**Tested By:** SV \_\_\_\_\_ **Checked By:** GS \_\_\_\_\_

# UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	2216031.5			
Undrained shear strength, psf	1108015.8			
Failure strain, %	0.8			
Strain rate, in./min.	0.038			
Water content, %	1.1			
Wet density, pcf	161.2			
Dry density, pcf	159.5			
Saturation, %	N/A			
Void ratio	N/A			
Specimen diameter, in.	2.000			
Specimen height, in.	3.860			
Height/diameter ratio	1.93			

**Description:** LIMESTONE

LL =	PL =	PI =	Assumed GS=	Type: Limestone
------	------	------	-------------	-----------------

**Project No.:** N1105070

**Date Sampled:** 8-23-10

**Remarks:**  
Lab No. 6077

**Client:** PARSONS BRINCKERHOFF

**Project:** BRENT SPENCE BRIDGE REPLACEMENT

**Source of Sample:** R-4      **Depth:** 121.9-122.3'

**Sample Number:** 8


UNCONFINED COMPRESSION TEST

**H.C. Nutting**  
A Terracon Company

**Figure** \_\_\_\_\_

**Tested By:** SV      **Checked By:** GS

# UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	828577.7			
Undrained shear strength, psf	414288.9			
Failure strain, %	0.8			
Strain rate, in./min.	0.037			
Water content, %	1.5			
Wet density, pcf	160.7			
Dry density, pcf	158.3			
Saturation, %	N/A			
Void ratio	N/A			
Specimen diameter, in.	1.990			
Specimen height, in.	3.770			
Height/diameter ratio	1.89			



**Description:** LIMESTONE

LL =      PL =      PI =      Assumed GS=      Type: Limestone

<p><b>Project No.:</b> N1105070  <b>Date Sampled:</b> 8-23-10  <b>Remarks:</b>                  Lab No. 6078</p>	<p><b>Client:</b> PARSONS BRINCKERHOFF  <b>Project:</b> BRENT SPENCE BRIDGE REPLACEMENT  <b>Source of Sample:</b> R-4      <b>Depth:</b> 129.6-130'  <b>Sample Number:</b> 9</p>
UNCONFINED COMPRESSION TEST <b>H.C. Nutting</b> A Terracon Company	

Tested By: SV      Checked By: GS

# UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	1956363.0			
Undrained shear strength, psf	978181.5			
Failure strain, %	1.1			
Strain rate, in./min.	0.038			
Water content, %	0.4			
Wet density, pcf	165.8			
Dry density, pcf	165.2			
Saturation, %	N/A			
Void ratio	N/A			
Specimen diameter, in.	1.990			
Specimen height, in.	3.800			
Height/diameter ratio	1.91			

**Description:** LIMESTONE

LL =      PL =      PI =      Assumed GS=      Type: Limestone

**Project No.:** N1105070  
**Date Sampled:** 8-23-10  
**Remarks:**  
 Lab No. 6080



Figure \_\_\_\_\_

**Client:** PARSONS BRINCKERHOFF  
**Project:** BRENT SPENCE BRIDGE REPLACEMENT  
**Source of Sample:** R-4      **Depth:** 140.6-141.1'  
**Sample Number:** 11

UNCONFINED COMPRESSION TEST  
**H.C. Nutting**  
 A Terracon Company

**Tested By:** SV      **Checked By:** GS

# UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	1534100.3			
Undrained shear strength, psf	767050.1			
Failure strain, %	0.8			
Strain rate, in./min.	0.038			
Water content, %	1.1			
Wet density, pcf	162.0			
Dry density, pcf	160.3			
Saturation, %	N/A			
Void ratio	N/A			
Specimen diameter, in.	1.990			
Specimen height, in.	3.810			
Height/diameter ratio	1.91			

**Description:** LIMESTONE

LL =	PL =	PI =	Assumed GS=	Type: Limestone
------	------	------	-------------	-----------------

**Project No.:** N1105070

**Date Sampled:** 8-23-10

**Remarks:**  
Lab No. 6082

**Client:** PARSONS BRINCKERHOFF

**Project:** BRENT SPENCE BRIDGE REPLACEMENT

**Source of Sample:** R-4      **Depth:** 152.8-153.6'

**Sample Number:** 13

UNCONFINED COMPRESSION TEST

**H.C. Nutting**  
A Terracon Company


**Figure** \_\_\_\_\_

**Tested By:** SV \_\_\_\_\_ **Checked By:** GS \_\_\_\_\_





# UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	1022251.4			
Undrained shear strength, psf	511125.7			
Failure strain, %	0.8			
Strain rate, in./min.	0.042			
Water content, %	2.9			
Wet density, pcf	165.0			
Dry density, pcf	160.4			
Saturation, %	N/A			
Void ratio	N/A			
Specimen diameter, in.	1.964			
Specimen height, in.	4.250			
Height/diameter ratio	2.16			

**Description:** LIMESTONE

LL =      PL =      PI =      Assumed GS=      Type: Limestone

**Project No.:** N1105070  
**Date Sampled:** 7-16-10  
**Remarks:**  
 Lab No. 5840

**Client:** PARSONS BRINCKERHOFF  
**Project:** BRENT SPENCE BRIDGE REPLACEMENT  
**Source of Sample:** R-5      **Depth:** 85.2-85.7'  
**Sample Number:** 1/NQ

UNCONFINED COMPRESSION TEST


**H.C. Nutting**  
 A Terracon Company

Figure \_\_\_\_\_

**Tested By:** SV

**Checked By:** GS

# UNCONFINED COMPRESSION TEST



Sample No.	1		
Unconfined strength, psf	1556479.7		
Undrained shear strength, psf	778239.9		
Failure strain, %	0.8		
Strain rate, in./min.	0.039		
Water content, %	0.3		
Wet density, pcf	167.1		
Dry density, pcf	166.7		
Saturation, %	N/A		
Void ratio	N/A		
Specimen diameter, in.	1.973		
Specimen height, in.	3.970		
Height/diameter ratio	2.01		

**Description:** LIMESTONE

**LL =**      **PL =**      **PI =**      **Assumed GS=**      **Type:** Limestone

**Project No.:** N1105070

**Date Sampled:** 7-16-10

**Remarks:**  
Lab No. 5841

**Client:** PARSONS BRINCKERHOFF

**Project:** BRENT SPENCE BRIDGE REPLACEMENT

**Source of Sample:** R-5      **Depth:** 86.4-86.8'

**Sample Number:** 1/NQ

UNCONFINED COMPRESSION TEST


**H.C. Nutting**  
A Terracon Company

**Figure** \_\_\_\_\_

**Tested By:** SV \_\_\_\_\_

**Checked By:** GS \_\_\_\_\_

# UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	1011411.0			
Undrained shear strength, psf	505705.5			
Failure strain, %	0.8			
Strain rate, in./min.	0.040			
Water content, %	0.5			
Wet density, pcf	166.3			
Dry density, pcf	165.5			
Saturation, %	N/A			
Void ratio	N/A			
Specimen diameter, in.	1.970			
Specimen height, in.	4.060			
Height/diameter ratio	2.06			

**Description:** LIMESTONE

LL =	PL =	PI =	Assumed GS=	Type: Limestone
------	------	------	-------------	-----------------

**Project No.:** N1105070  
**Date Sampled:** 7-16-10  
**Remarks:**  
 Lab No. 5842

**Client:** PARSONS BRINCKERHOFF  
**Project:** BRENT SPENCE BRIDGE REPLACEMENT  
**Source of Sample:** R-5      **Depth:** 90.1-90.8'  
**Sample Number:** 2/NQ


UNCONFINED COMPRESSION TEST

**H.C. Nutting**  
 A Terracon Company

Figure \_\_\_\_\_

**Tested By:** SV      **Checked By:** GS

# UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	16945.6			
Undrained shear strength, psf	8472.8			
Failure strain, %	4.2			
Strain rate, in./min.	0.040			
Water content, %	8.6			
Wet density, pcf	150.0			
Dry density, pcf	138.1			
Saturation, %	N/A			
Void ratio	N/A			
Specimen diameter, in.	1.950			
Specimen height, in.	4.010			
Height/diameter ratio	2.06			

**Description:** SHALE

LL =      PL =      PI =      Assumed GS=      Type: Shale

**Project No.:** N1105070  
**Date Sampled:** 7-16-10  
**Remarks:**  
 Lab No. 5843

**Client:** PARSONS BRINCKERHOFF  
**Project:** BRENT SPENCE BRIDGE REPLACEMENT  
**Source of Sample:** R-5      **Depth:** 92.2-92.8'  
**Sample Number:** 2/NQ


UNCONFINED COMPRESSION TEST

**H.C. Nutting**  
 A Terracon Company

Figure \_\_\_\_\_

**Tested By:** SV      **Checked By:** GS

# UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	2062678.8			
Undrained shear strength, psf	1031339.4			
Failure strain, %	0.9			
Strain rate, in./min.	0.039			
Water content, %	0.6			
Wet density, pcf	167.4			
Dry density, pcf	166.5			
Saturation, %	N/A			
Void ratio	N/A			
Specimen diameter, in.	1.975			
Specimen height, in.	3.940			
Height/diameter ratio	1.99			

**Description:** LIMESTONE

LL =      PL =      PI =      Assumed GS=      Type: Limestone

**Project No.:** N1105070

**Date Sampled:** 7-16-10

**Remarks:**  
Lab No. 5844

**Client:** PARSONS BRINCKERHOFF

**Project:** BRENT SPENCE BRIDGE REPLACEMENT

**Source of Sample:** R-5      **Depth:** 93-93.8'

**Sample Number:** 2/NQ

UNCONFINED COMPRESSION TEST


**H.C. Nutting**  
A Terracon Company

**Figure** \_\_\_\_\_

**Tested By:** SV

**Checked By:** GS

# UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	1179728.7			
Undrained shear strength, psf	589864.4			
Failure strain, %	0.9			
Strain rate, in./min.	0.040			
Water content, %	0.5			
Wet density, pcf	166.9			
Dry density, pcf	166.1			
Saturation, %	N/A			
Void ratio	N/A			
Specimen diameter, in.	1.968			
Specimen height, in.	4.030			
Height/diameter ratio	2.05			

**Description:** LIMESTONE

LL =      PL =      PI =      Assumed GS=      Type: Limestone

**Project No.:** N1105070

**Date Sampled:** 7-16-10

**Remarks:**  
Lab No. 5845

**Client:** PARSONS BRINCKERHOFF

**Project:** BRENT SPENCE BRIDGE REPLACEMENT

**Source of Sample:** R-5      **Depth:** 95-95.3'

**Sample Number:** 3/NQ

UNCONFINED COMPRESSION TEST


**H.C. Nutting**  
A Terracon Company

Figure \_\_\_\_\_

**Tested By:** SV

**Checked By:** GS

# UNCONFINED COMPRESSION TEST



Sample No.	1		
Unconfined strength, psf	692912.3		
Undrained shear strength, psf	346456.2		
Failure strain, %	0.7		
Strain rate, in./min.	0.040		
Water content, %	1.5		
Wet density, pcf	167.8		
Dry density, pcf	165.2		
Saturation, %	N/A		
Void ratio	N/A		
Specimen diameter, in.	1.975		
Specimen height, in.	4.030		
Height/diameter ratio	2.04		

**Description:** LIMESTONE

LL =      PL =      PI =      Assumed GS=      Type: Limestone

**Project No.:** N1105070

**Date Sampled:** 7-16-10

**Remarks:**  
Lab No. 5848

**Client:** PARSONS BRINCKERHOFF

**Project:** BRENT SPENCE BRIDGE REPLACEMENT

**Source of Sample:** R-5      **Depth:** 103-103.5'

**Sample Number:** 3/NQ

UNCONFINED COMPRESSION TEST

**H.C. Nutting**  
A Terracon Company


Figure \_\_\_\_\_

Tested By: SV

Checked By: GS



# UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	1753704.3			
Undrained shear strength, psf	876852.2			
Failure strain, %	0.8			
Strain rate, in./min.	0.042			
Water content, %	0.5			
Wet density, pcf	165.1			
Dry density, pcf	164.3			
Saturation, %	N/A			
Void ratio	N/A			
Specimen diameter, in.	1.977			
Specimen height, in.	4.200			
Height/diameter ratio	2.12			

**Description:** LIMESTONE

LL =      PL =      PI =      Assumed GS=      Type: Limestone

**Project No.:** N1105070  
**Date Sampled:** 7-16-10  
**Remarks:**  
 Lab No. 5853

**Client:** PARSONS BRINCKERHOFF  
**Project:** BRENT SPENCE BRIDGE REPLACEMENT  
**Source of Sample:** R-5      **Depth:** 146.2-147'  
**Sample Number:** 13/NQ



UNCONFINED COMPRESSION TEST

**H.C. Nutting**  
 A Terracon Company

Figure \_\_\_\_\_

**Tested By:** SV      **Checked By:** GS

# UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	851152.9			
Undrained shear strength, psf	425576.4			
Failure strain, %	0.4			
Strain rate, in./min.	0.041			
Water content, %	0.6			
Wet density, pcf	165.5			
Dry density, pcf	164.5			
Saturation, %	N/A			
Void ratio	N/A			
Specimen diameter, in.	1.980			
Specimen height, in.	4.100			
Height/diameter ratio	2.07			

**Description:** LIMESTONE

LL =      PL =      PI =      Assumed GS=      Type: Limestone

**Project No.:** N1105070

**Date Sampled:** 7-27-10

**Remarks:**  
Lab No. 5897

**Client:** PARSONS BRINCKERHOFF

**Project:** BRENT SPENCE BRIDGE REPLACEMENT

**Source of Sample:** R-6      **Depth:** 84.1-84.5'

**Sample Number:** 1/NQ


UNCONFINED COMPRESSION TEST

**H.C. Nutting**  
A Terracon Company

**Figure** \_\_\_\_\_

**Tested By:** SV \_\_\_\_\_ **Checked By:** GS \_\_\_\_\_

# UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	1150291.5			
Undrained shear strength, psf	575145.7			
Failure strain, %	0.7			
Strain rate, in./min.	0.040			
Water content, %	0.7			
Wet density, pcf	167.9			
Dry density, pcf	166.7			
Saturation, %	N/A			
Void ratio	N/A			
Specimen diameter, in.	1.980			
Specimen height, in.	4.020			
Height/diameter ratio	2.03			

**Description:** LIMESTONE

**LL =**      **PL =**      **PI =**      **Assumed GS=**      **Type:** Limestone

**Project No.:** N1105070

**Date Sampled:** 7-27-10

**Remarks:**  
Lab No. 5898

**Client:** PARSONS BRINCKERHOFF

**Project:** BRENT SPENCE BRIDGE REPLACEMENT

**Source of Sample:** R-6      **Depth:** 88.5-89'

**Sample Number:** 2/NQ

UNCONFINED COMPRESSION TEST


**H.C. Nutting**  
A Terracon Company

**Figure** \_\_\_\_\_

**Tested By:** SV \_\_\_\_\_

**Checked By:** GS \_\_\_\_\_

# UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	1403296.0			
Undrained shear strength, psf	701648.0			
Failure strain, %	0.6			
Strain rate, in./min.	0.044			
Water content, %	0.1			
Wet density, pcf	168.6			
Dry density, pcf	168.4			
Saturation, %	N/A			
Void ratio	N/A			
Specimen diameter, in.	1.980			
Specimen height, in.	4.410			
Height/diameter ratio	2.23			

**Description:** LIMESTONE

LL =	PL =	PI =	Assumed GS=	Type: Limestone
------	------	------	-------------	-----------------

**Project No.:** N1105070

**Date Sampled:** 7-27-10

**Remarks:**  
Lab No. 5901

**Client:** PARSONS BRINCKERHOFF

**Project:** BRENT SPENCE BRIDGE REPLACEMENT

**Source of Sample:** R-6      **Depth:** 94.5-94.9'

**Sample Number:** 3/NQ


UNCONFINED COMPRESSION TEST

**H.C. Nutting**  
A Terracon Company

**Figure** \_\_\_\_\_

**Tested By:** SV      **Checked By:** GS

# UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	1828127.1			
Undrained shear strength, psf	914063.6			
Failure strain, %	0.8			
Strain rate, in./min.	0.039			
Water content, %	0.1			
Wet density, pcf	167.8			
Dry density, pcf	167.6			
Saturation, %	N/A			
Void ratio	N/A			
Specimen diameter, in.	1.980			
Specimen height, in.	3.990			
Height/diameter ratio	2.02			

**Description:** LIMESTONE

LL =      PL =      PI =      Assumed GS=      Type: Limestone

**Project No.:** N1105070

**Date Sampled:** 7-27-10

**Remarks:**  
Lab No. 5903

**Client:** PARSONS BRINCKERHOFF

**Project:** BRENT SPENCE BRIDGE REPLACEMENT

**Source of Sample:** R-6      **Depth:** 100.1-100.5'

**Sample Number:** 4/NQ


UNCONFINED COMPRESSION TEST

**H.C. Nutting**  
A Terracon Company

Figure \_\_\_\_\_

**Tested By:** SV      **Checked By:** GS

# UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	1259226.7			
Undrained shear strength, psf	629613.3			
Failure strain, %	0.7			
Strain rate, in./min.	0.039			
Water content, %	0.5			
Wet density, pcf	168.0			
Dry density, pcf	167.2			
Saturation, %	N/A			
Void ratio	N/A			
Specimen diameter, in.	1.980			
Specimen height, in.	3.980			
Height/diameter ratio	2.01			

**Description:** LIMESTONE

LL =	PL =	PI =	Assumed GS=	Type: Limestone
------	------	------	-------------	-----------------

**Project No.:** N1105070

**Date Sampled:** 7-27-10

**Remarks:**  
Lab No. 5906

**Client:** PARSONS BRINCKERHOFF

**Project:** BRENT SPENCE BRIDGE REPLACEMENT

**Source of Sample:** R-6      **Depth:** 107.1-107.5'

**Sample Number:** 6/NQ


UNCONFINED COMPRESSION TEST

**H.C. Nutting**  
A Terracon Company

**Figure** \_\_\_\_\_

**Tested By:** SV \_\_\_\_\_ **Checked By:** GS \_\_\_\_\_

# UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	1466508.1			
Undrained shear strength, psf	733254.1			
Failure strain, %	0.6			
Strain rate, in./min.	0.040			
Water content, %	0.2			
Wet density, pcf	169.2			
Dry density, pcf	168.9			
Saturation, %	N/A			
Void ratio	N/A			
Specimen diameter, in.	1.980			
Specimen height, in.	4.020			
Height/diameter ratio	2.03			

**Description:** LIMESTONE

LL =	PL =	PI =	Assumed GS=	Type: Limestone
------	------	------	-------------	-----------------

**Project No.:** N1105070  
**Date Sampled:** 7-27-10  
**Remarks:**  
 Lab No. 5907

**Client:** PARSONS BRINCKERHOFF  
**Project:** BRENT SPENCE BRIDGE REPLACEMENT  
**Source of Sample:** R-6      **Depth:** 114.5-115'  
**Sample Number:** 7/NQ


UNCONFINED COMPRESSION TEST

**H.C. Nutting**  
 A Terracon Company

Figure \_\_\_\_\_

**Tested By:** SV \_\_\_\_\_ **Checked By:** GS \_\_\_\_\_

# UNCONFINED COMPRESSION TEST



Sample No.	1		
Unconfined strength, psf	1649615.1		
Undrained shear strength, psf	824807.5		
Failure strain, %	0.8		
Strain rate, in./min.	0.039		
Water content, %	0.3		
Wet density, pcf	167.3		
Dry density, pcf	166.7		
Saturation, %	N/A		
Void ratio	N/A		
Specimen diameter, in.	1.980		
Specimen height, in.	3.990		
Height/diameter ratio	2.02		

**Description:** LIMESTONE

LL =      PL =      PI =      Assumed GS=      Type: Limestone

**Project No.:** N1105070

**Date Sampled:** 7-27-10

**Remarks:**  
Lab No. 5909

**Client:** PARSONS BRINCKERHOFF

**Project:** BRENT SPENCE BRIDGE REPLACEMENT

**Source of Sample:** R-6      **Depth:** 136.5-137.3'

**Sample Number:** 12/NQ

UNCONFINED COMPRESSION TEST

**H.C. Nutting**  
A Terracon Company


Figure \_\_\_\_\_

Tested By: SV \_\_\_\_\_

Checked By: GS \_\_\_\_\_



# UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	1273413.0			
Undrained shear strength, psf	636706.5			
Failure strain, %	0.6			
Strain rate, in./min.	0.039			
Water content, %	0.8			
Wet density, pcf	167.0			
Dry density, pcf	165.6			
Saturation, %	N/A			
Void ratio	N/A			
Specimen diameter, in.	1.980			
Specimen height, in.	3.930			
Height/diameter ratio	1.98			

**Description:** LIMESTONE

LL =      PL =      PI =      Assumed GS=      Type: Limestone

**Project No.:** N1105070

**Date Sampled:** 7-27-10

**Remarks:**  
Lab No. 5912

**Client:** PARSONS BRINCKERHOFF

**Project:** BRENT SPENCE BRIDGE REPLACEMENT

**Source of Sample:** R-6      **Depth:** 159.8-160.2'

**Sample Number:** 16/NQ

UNCONFINED COMPRESSION TEST


**H.C. Nutting**  
A Terracon Company

Figure \_\_\_\_\_

Tested By: SV

Checked By: GS

# UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	1277541.7			
Undrained shear strength, psf	638770.9			
Failure strain, %	1.0			
Strain rate, in./min.	0.041			
Water content, %	0.3			
Wet density, pcf	168.1			
Dry density, pcf	167.6			
Saturation, %	N/A			
Void ratio	N/A			
Specimen diameter, in.	1.972			
Specimen height, in.	4.110			
Height/diameter ratio	2.08			

**Description:** LIMESTONE

LL =	PL =	PI =	Assumed GS=	Type: Limestone
------	------	------	-------------	-----------------

**Project No.:** N1105070

**Date Sampled:** 7-19-10

**Remarks:**  
Lab No. 5857

**Client:** PARSONS BRINCKERHOFF

**Project:** BRENT SPENCE BRIDGE REPLACEMENT

**Source of Sample:** R-7      **Depth:** 83.5-83.9'

**Sample Number:** 1/NQ


UNCONFINED COMPRESSION TEST

**H.C. Nutting**  
A Terracon Company

**Figure** \_\_\_\_\_

**Tested By:** SV      **Checked By:** GS

# UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	1748783.3			
Undrained shear strength, psf	874391.7			
Failure strain, %	0.8			
Strain rate, in./min.	0.039			
Water content, %	0.3			
Wet density, pcf	168.9			
Dry density, pcf	168.4			
Saturation, %	N/A			
Void ratio	N/A			
Specimen diameter, in.	1.970			
Specimen height, in.	3.930			
Height/diameter ratio	1.99			

**Description:** LIMESTONE

LL =	PL =	PI =	Assumed GS=	Type: Limestone
------	------	------	-------------	-----------------

**Project No.:** N1105070  
**Date Sampled:** 7-19-10  
**Remarks:**  
 Lab No. 5858


**Client:** PARSONS BRINCKERHOFF  
**Project:** BRENT SPENCE BRIDGE REPLACEMENT  
**Source of Sample:** R-7      **Depth:** 88.4-89'  
**Sample Number:** 2/NQ

Figure \_\_\_\_\_

UNCONFINED COMPRESSION TEST  
**H.C. Nutting**  
 A Terracon Company

**Tested By:** SV      **Checked By:** GS

# UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	979514.7			
Undrained shear strength, psf	489757.3			
Failure strain, %	0.8			
Strain rate, in./min.	0.039			
Water content, %	1.0			
Wet density, pcf	170.6			
Dry density, pcf	168.9			
Saturation, %	N/A			
Void ratio	N/A			
Specimen diameter, in.	1.970			
Specimen height, in.	3.960			
Height/diameter ratio	2.01			

**Description:** LIMESTONE

LL =	PL =	PI =	Assumed GS=	Type: Limestone
------	------	------	-------------	-----------------

**Project No.:** N1105070

**Date Sampled:** 7-19-10

**Remarks:**  
Lab No. 5862

**Client:** PARSONS BRINCKERHOFF

**Project:** BRENT SPENCE BRIDGE REPLACEMENT

**Source of Sample:** R-7      **Depth:** 98-98.5'

**Sample Number:** 5/NQ


UNCONFINED COMPRESSION TEST

**H.C. Nutting**  
A Terracon Company

Figure \_\_\_\_\_

**Tested By:** SV      **Checked By:** GS

# UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	263952.1			
Undrained shear strength, psf	131976.0			
Failure strain, %	1.4			
Strain rate, in./min.	0.039			
Water content, %	3.5			
Wet density, pcf	161.0			
Dry density, pcf	155.6			
Saturation, %	N/A			
Void ratio	N/A			
Specimen diameter, in.	1.970			
Specimen height, in.	3.900			
Height/diameter ratio	1.98			

**Description:** SHALE

**LL =**      **PL =**      **PI =**      **Assumed GS=**      **Type:** Shale

**Project No.:** N1105070

**Date Sampled:** 7-19-10

**Remarks:**  
Lab No. 5866

**Client:** PARSONS BRINCKERHOFF

**Project:** BRENT SPENCE BRIDGE REPLACEMENT

**Source of Sample:** R-7      **Depth:** 121.1-121.4'

**Sample Number:** 9/NQ

UNCONFINED COMPRESSION TEST


**H.C. Nutting**  
A Terracon Company

**Figure** \_\_\_\_\_

**Tested By:** SV \_\_\_\_\_

**Checked By:** GS \_\_\_\_\_

# UNCONFINED COMPRESSION TEST



Sample No.	1		
Unconfined strength, psf	1227670.6		
Undrained shear strength, psf	613835.3		
Failure strain, %	0.7		
Strain rate, in./min.	0.042		
Water content, %	0.5		
Wet density, pcf	165.0		
Dry density, pcf	164.2		
Saturation, %	N/A		
Void ratio	N/A		
Specimen diameter, in.	1.970		
Specimen height, in.	4.270		
Height/diameter ratio	2.17		

**Description:** LIMESTONE

LL =	PL =	PI =	Assumed GS=	Type: Limestone
------	------	------	-------------	-----------------

**Project No.:** N1105070  
**Date Sampled:** 7-19-10  
**Remarks:**  
 Lab No. 5868

**Client:** PARSONS BRINCKERHOFF  
**Project:** BRENT SPENCE BRIDGE REPLACEMENT  
**Source of Sample:** R-7      **Depth:** 128.7-129.5'  
**Sample Number:** 10/NQ


UNCONFINED COMPRESSION TEST

**H.C. Nutting**  
 A Terracon Company

Figure \_\_\_\_\_

**Tested By:** SV \_\_\_\_\_ **Checked By:** GS \_\_\_\_\_

# UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	1724247.7			
Undrained shear strength, psf	862123.8			
Failure strain, %	0.8			
Strain rate, in./min.	0.040			
Water content, %	0.4			
Wet density, pcf	168.4			
Dry density, pcf	167.8			
Saturation, %	N/A			
Void ratio	N/A			
Specimen diameter, in.	1.970			
Specimen height, in.	4.090			
Height/diameter ratio	2.08			

**Description:** LIMESTONE

LL =      PL =      PI =      Assumed GS=      Type: Limestone

**Project No.:** N1105070  
**Date Sampled:** 7-19-10  
**Remarks:**  
 Lab No. 5869

**Client:** PARSONS BRINCKERHOFF  
**Project:** BRENT SPENCE BRIDGE REPLACEMENT  
**Source of Sample:** R-7      **Depth:** 136.6-137.6'  
**Sample Number:** 12/NQ


UNCONFINED COMPRESSION TEST

**H.C. Nutting**  
 A Terracon Company

Figure \_\_\_\_\_

**Tested By:** SV \_\_\_\_\_ **Checked By:** GS \_\_\_\_\_

# UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	1812415.1			
Undrained shear strength, psf	906207.5			
Failure strain, %	0.8			
Strain rate, in./min.	0.039			
Water content, %	0.5			
Wet density, pcf	165.8			
Dry density, pcf	165.0			
Saturation, %	N/A			
Void ratio	N/A			
Specimen diameter, in.	1.970			
Specimen height, in.	3.970			
Height/diameter ratio	2.02			

**Description:** LIMESTONE

LL =	PL =	PI =	Assumed GS=	Type: Limestone
------	------	------	-------------	-----------------

**Project No.:** N1105070

**Date Sampled:** 7-19-10

**Remarks:**  
Lab No. 5871

**Client:** PARSONS BRINCKERHOFF

**Project:** BRENT SPENCE BRIDGE REPLACEMENT

**Source of Sample:** R-7      **Depth:** 154.5-155.1

**Sample Number:** 16/NQ

UNCONFINED COMPRESSION TEST


**H.C. Nutting**  
A Terracon Company

**Figure** \_\_\_\_\_

**Tested By:** SV \_\_\_\_\_ **Checked By:** GS \_\_\_\_\_



# UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	1263171.1			
Undrained shear strength, psf	631585.6			
Failure strain, %	1.0			
Strain rate, in./min.	0.041			
Water content, %	0.4			
Wet density, pcf	165.4			
Dry density, pcf	164.6			
Saturation, %	N/A			
Void ratio	N/A			
Specimen diameter, in.	1.970			
Specimen height, in.	4.100			
Height/diameter ratio	2.08			



**Description:** LIMESTONE

LL =	PL =	PI =	Assumed GS=	Type: Limestone
------	------	------	-------------	-----------------

<p><b>Project No.:</b> N1105070  <b>Date Sampled:</b> 7-19-10  <b>Remarks:</b>                  Lab No. 5872</p>	<p><b>Client:</b> PARSONS BRINCKERHOFF  <b>Project:</b> BRENT SPENCE BRIDGE REPLACEMENT  <b>Source of Sample:</b> R-7      <b>Depth:</b> 163.7-164.5'  <b>Sample Number:</b> 17/NQ</p>
UNCONFINED COMPRESSION TEST <b>H.C. Nutting</b> A Terracon Company	

**Tested By:** SV \_\_\_\_\_ **Checked By:** GS \_\_\_\_\_

# UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	1388903.4			
Undrained shear strength, psf	694451.7			
Failure strain, %	1.2			
Strain rate, in./min.	0.037			
Water content, %	0.1			
Wet density, pcf	166.9			
Dry density, pcf	166.8			
Saturation, %	N/A			
Void ratio	N/A			
Specimen diameter, in.	1.980			
Specimen height, in.	3.750			
Height/diameter ratio	1.89			

**Description:** LIMESTONE

LL =      PL =      PI =      Assumed GS=      Type: Limestone

**Project No.:** N1105070  
**Date Sampled:** 10-5-10  
**Remarks:**  
 Lab No. 9682



Figure \_\_\_\_\_

**Client:** PARSONS BRINCKERHOFF  
**Project:** BRENT SPENCE BRIDGE REPLACEMENT  
**Source of Sample:** R-8      **Depth:** 87.8-88.2'  
**Sample Number:** 1

UNCONFINED COMPRESSION TEST  
**H.C. Nutting**  
 A Terracon Company

**Tested By:** MRE      **Checked By:** GS

# UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	1618490.2			
Undrained shear strength, psf	809245.1			
Failure strain, %	1.0			
Strain rate, in./min.	0.036			
Water content, %	0.6			
Wet density, pcf	167.4			
Dry density, pcf	166.4			
Saturation, %	N/A			
Void ratio	N/A			
Specimen diameter, in.	1.980			
Specimen height, in.	3.640			
Height/diameter ratio	1.84			

**Description:** LIMESTONE



LL =      PL =      PI =      Assumed GS=      Type: Limestone

<p><b>Project No.:</b> N1105070  <b>Date Sampled:</b> 10-5-10  <b>Remarks:</b>                  Lab No. 9685</p>	<p><b>Client:</b> PARSONS BRINCKERHOFF  <b>Project:</b> BRENT SPENCE BRIDGE REPLACEMENT  <b>Source of Sample:</b> R-8      <b>Depth:</b> 100.5-101'  <b>Sample Number:</b> 4</p>
UNCONFINED COMPRESSION TEST <b>H.C. Nutting</b> A Terracon Company	

Figure \_\_\_\_\_

**Tested By:** MRE      **Checked By:** GS

# UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	711870.3			
Undrained shear strength, psf	355935.1			
Failure strain, %	1.4			
Strain rate, in./min.	0.037			
Water content, %	1.0			
Wet density, pcf	164.3			
Dry density, pcf	162.7			
Saturation, %	N/A			
Void ratio	N/A			
Specimen diameter, in.	1.980			
Specimen height, in.	3.780			
Height/diameter ratio	1.91			

**Description:** LIMESTONE

LL =      PL =      PI =      Assumed GS=      Type: Limestone

**Project No.:** NI105070  
**Date Sampled:** 10-5-10  
**Remarks:**  
 Lab No. 9687


Figure \_\_\_\_\_

**Client:** PARSONS BRINCKERHOFF  
**Project:** BRENT SPENCE BRIDGE REPLACEMENT  
**Source of Sample:** R-8      **Depth:** 101.8-102.3'  
**Sample Number:** 6

UNCONFINED COMPRESSION TEST  
**H.C. Nutting**  
 A Terracon Company

**Tested By:** MRE      **Checked By:** GS

# UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	1674834.1			
Undrained shear strength, psf	837417.0			
Failure strain, %	1.1			
Strain rate, in./min.	0.039			
Water content, %	0.7			
Wet density, pcf	166.4			
Dry density, pcf	165.3			
Saturation, %	N/A			
Void ratio	N/A			
Specimen diameter, in.	1.980			
Specimen height, in.	3.970			
Height/diameter ratio	2.01			

**Description:** LIMESTONE

<b>LL =</b>	<b>PL =</b>	<b>PI =</b>	<b>Assumed GS=</b>	<b>Type:</b> Limestone
-------------	-------------	-------------	--------------------	------------------------

**Project No.:** N1105070  
**Date Sampled:** 10-5-10  
**Remarks:**  
 Lab No. 9690



Figure \_\_\_\_\_

**Client:** PARSONS BRINCKERHOFF  
**Project:** BRENT SPENCE BRIDGE REPLACEMENT  
**Source of Sample:** R-8      **Depth:** 126.3-126.7'  
**Sample Number:** 9

UNCONFINED COMPRESSION TEST  
**H.C. Nutting**  
 A Terracon Company

**Tested By:** MRE      **Checked By:** GS

# UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	1537026.1			
Undrained shear strength, psf	768513.1			
Failure strain, %	1.1			
Strain rate, in./min.	0.038			
Water content, %	0.3			
Wet density, pcf	166.6			
Dry density, pcf	166.1			
Saturation, %	N/A			
Void ratio	N/A			
Specimen diameter, in.	1.980			
Specimen height, in.	3.870			
Height/diameter ratio	1.95			

**Description:** LIMESTONE

LL =      PL =      PI =      Assumed GS=      Type: Limestone

**Project No.:** N1105070  
**Date Sampled:** 10-5-10  
**Remarks:**  
 Lab No. 9691


Figure \_\_\_\_\_

**Client:** PARSONS BRINCKERHOFF  
**Project:** BRENT SPENCE BRIDGE REPLACEMENT  
**Source of Sample:** R-8      **Depth:** 127.8-128.3'  
**Sample Number:** 10

UNCONFINED COMPRESSION TEST  
**H.C. Nutting**  
 A Terracon Company

**Tested By:** MRE      **Checked By:** GS

# UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	1511267.5			
Undrained shear strength, psf	755633.8			
Failure strain, %	1.0			
Strain rate, in./min.	0.038			
Water content, %	0.5			
Wet density, pcf	162.5			
Dry density, pcf	161.7			
Saturation, %	N/A			
Void ratio	N/A			
Specimen diameter, in.	1.970			
Specimen height, in.	3.890			
Height/diameter ratio	1.97			

**Description:** LIMESTONE

LL =	PL =	PI =	Assumed GS=	Type: Limestone
------	------	------	-------------	-----------------

**Project No.:** NI105070

**Date Sampled:** 10-5-10

**Remarks:**  
Lab No. 9692

**Client:** PARSONS BRINCKERHOFF

**Project:** BRENT SPENCE BRIDGE REPLACEMENT

**Source of Sample:** R-8      **Depth:** 135.5-136'

**Sample Number:** 11

UNCONFINED COMPRESSION TEST


**H.C. Nutting**  
A Terracon Company

Figure \_\_\_\_\_

**Tested By:** MRE

**Checked By:** GS

# UNCONFINED COMPRESSION TEST



Sample No.	1		
Unconfined strength, psf	1831836.4		
Undrained shear strength, psf	915918.2		
Failure strain, %	1.1		
Strain rate, in./min.	0.038		
Water content, %	0.3		
Wet density, pcf	162.5		
Dry density, pcf	162.0		
Saturation, %	N/A		
Void ratio	N/A		
Specimen diameter, in.	1.980		
Specimen height, in.	3.850		
Height/diameter ratio	1.94		

**Description:** LIMESTONE


LL =      PL =      PI =      Assumed GS=      Type: Limestone

<p><b>Project No.:</b> N1105070  <b>Date Sampled:</b> 10-5-10  <b>Remarks:</b>                  Lab No. 9693</p>	<p><b>Client:</b> PARSONS BRINCKERHOFF  <b>Project:</b> BRENT SPENCE BRIDGE REPLACEMENT  <b>Source of Sample:</b> R-8      <b>Depth:</b> 141-141.5'  <b>Sample Number:</b> 12</p>
UNCONFINED COMPRESSION TEST <b>H.C. Nutting</b> A Terracon Company	

**Tested By:** MRE      **Checked By:** GS



# UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	1817085.1			
Undrained shear strength, psf	908542.5			
Failure strain, %	1.1			
Strain rate, in./min.	0.040			
Water content, %	0.3			
Wet density, pcf	160.0			
Dry density, pcf	159.6			
Saturation, %	N/A			
Void ratio	N/A			
Specimen diameter, in.	1.980			
Specimen height, in.	4.090			
Height/diameter ratio	2.07			

**Description:** LIMESTONE

<b>LL =</b>	<b>PL =</b>	<b>PI =</b>	<b>Assumed GS=</b>	<b>Type:</b> Limestone
-------------	-------------	-------------	--------------------	------------------------

**Project No.:** N1105070  
**Date Sampled:** 10-5-10  
**Remarks:**  
 Lab No. 9694

**Figure** \_\_\_\_\_


**Client:** PARSONS BRINCKERHOFF  
**Project:** BRENT SPENCE BRIDGE REPLACEMENT  
**Source of Sample:** R-8      **Depth:** 149-149.5'  
**Sample Number:** 13

UNCONFINED COMPRESSION TEST  
**H.C. Nutting**  
 A Terracon Company

**Tested By:** MRE

**Checked By:** GS

# UNCONFINED COMPRESSION TEST



Sample No.	1		
Unconfined strength, psf	1475126.5		
Undrained shear strength, psf	737563.2		
Failure strain, %	1.1		
Strain rate, in./min.	0.037		
Water content, %	0.2		
Wet density, pcf	164.4		
Dry density, pcf	164.2		
Saturation, %	N/A		
Void ratio	N/A		
Specimen diameter, in.	1.980		
Specimen height, in.	3.760		
Height/diameter ratio	1.90		



**Description:** LIMESTONE

LL =	PL =	PI =	Assumed GS=	Type: Limestone
------	------	------	-------------	-----------------

<p><b>Project No.:</b> N1105070  <b>Date Sampled:</b> 10-5-10  <b>Remarks:</b>                  Lab No. 9695</p>	<p><b>Client:</b> PARSONS BRINCKERHOFF  <b>Project:</b> BRENT SPENCE BRIDGE REPLACEMENT  <b>Source of Sample:</b> R-8      <b>Depth:</b> 151.8-152.1'  <b>Sample Number:</b> 14</p>
UNCONFINED COMPRESSION TEST <b>H.C. Nutting</b> A Terracon Company	

**Tested By:** MRE \_\_\_\_\_ **Checked By:** GS \_\_\_\_\_

# UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	1729572.6			
Undrained shear strength, psf	864786.3			
Failure strain, %	1.1			
Strain rate, in./min.	0.039			
Water content, %	0.2			
Wet density, pcf	164.9			
Dry density, pcf	164.4			
Saturation, %	N/A			
Void ratio	N/A			
Specimen diameter, in.	1.980			
Specimen height, in.	3.920			
Height/diameter ratio	1.98			

**Description:** LIMESTONE

LL =      PL =      PI =      Assumed GS=      Type: Limestone

**Project No.:** N1105070  
**Date Sampled:** 10-5-10  
**Remarks:**  
 Lab No. 9696


Figure \_\_\_\_\_

**Client:** PARSONS BRINCKERHOFF  
**Project:** BRENT SPENCE BRIDGE REPLACEMENT  
**Source of Sample:** R-8      **Depth:** 158.7-159.2'  
**Sample Number:** 15

UNCONFINED COMPRESSION TEST  
**H.C. Nutting**  
 A Terracon Company

Tested By: MRE      Checked By: GS

# UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	607979.7			
Undrained shear strength, psf	303989.9			
Failure strain, %	1.5			
Strain rate, in./min.	0.038			
Water content, %	1.7			
Wet density, pcf	162.3			
Dry density, pcf	159.6			
Saturation, %	N/A			
Void ratio	N/A			
Specimen diameter, in.	2.380			
Specimen height, in.	3.830			
Height/diameter ratio	1.61			

**Description:** LIMESTONE W/SHALE

LL =      PL =      PI =      Assumed GS=      Type: Limestone w/Shale

**Project No.:** N1105070

**Date Sampled:** 10-7-10

**Remarks:**  
Lab No. 9702

**Client:** PARSONS BRINCKERHOFF

**Project:** BRENT SPENCE BRIDGE REPLACEMENT

**Source of Sample:** R-2A      **Depth:** 120.51-121'

**Sample Number:** 6

UNCONFINED COMPRESSION TEST


**H.C. Nutting**  
A Terracon Company

Figure \_\_\_\_\_

**Tested By:** MRE

**Checked By:** GS

# UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	1089495.1			
Undrained shear strength, psf	544747.5			
Failure strain, %	1.0			
Strain rate, in./min.	0.043			
Water content, %	1.2			
Wet density, pcf	162.6			
Dry density, pcf	160.7			
Saturation, %	N/A			
Void ratio	N/A			
Specimen diameter, in.	2.375			
Specimen height, in.	4.360			
Height/diameter ratio	1.84			



**Description:** LIMESTONE

LL =	PL =	PI =	Assumed GS=	Type: Limestone
------	------	------	-------------	-----------------

<p><b>Project No.:</b> N1105070  <b>Date Sampled:</b> 10-7-10  <b>Remarks:</b>                  Lab No. 9705</p>	<p><b>Client:</b> PARSONS BRINCKERHOFF  <b>Project:</b> BRENT SPENCE BRIDGE REPLACEMENT  <b>Source of Sample:</b> R-2A      <b>Depth:</b> 134.4-134.9'  <b>Sample Number:</b> 9</p>
UNCONFINED COMPRESSION TEST <b>H.C. Nutting</b> A Terracon Company	

**Tested By:** MRE \_\_\_\_\_ **Checked By:** GS \_\_\_\_\_

# UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	1117004.0			
Undrained shear strength, psf	558502.0			
Failure strain, %	1.5			
Strain rate, in./min.	0.043			
Water content, %	0.7			
Wet density, pcf	162.0			
Dry density, pcf	160.9			
Saturation, %	N/A			
Void ratio	N/A			
Specimen diameter, in.	2.380			
Specimen height, in.	4.320			
Height/diameter ratio	1.82			

**Description:** LIMESTONE



LL =                      PL =                      PI =                      Assumed GS=                      Type: Limestone

<p><b>Project No.:</b> N1105070  <b>Date Sampled:</b> 10-7-10  <b>Remarks:</b>                  Lab No. 9706</p>	<p><b>Client:</b> PARSONS BRINCKERHOFF  <b>Project:</b> BRENT SPENCE BRIDGE REPLACEMENT  <b>Source of Sample:</b> R-2A                      <b>Depth:</b> 140-140.5'  <b>Sample Number:</b> 10</p>
UNCONFINED COMPRESSION TEST <b>H.C. Nutting</b> A Terracon Company	

Figure \_\_\_\_\_

**Tested By:** MRE                      **Checked By:** GS

# UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	2192551.5			
Undrained shear strength, psf	1096275.7			
Failure strain, %	1.2			
Strain rate, in./min.	0.048			
Water content, %	0.2			
Wet density, pcf	168.3			
Dry density, pcf	167.9			
Saturation, %	N/A			
Void ratio	N/A			
Specimen diameter, in.	2.370			
Specimen height, in.	4.800			
Height/diameter ratio	2.03			

**Description:** LIMESTONE

LL =	PL =	PI =	Assumed GS=	Type: Limestone
------	------	------	-------------	-----------------

**Project No.:** N1105070  
**Date Sampled:** 10-7-10  
**Remarks:**  
 Lab No. 9708


Figure \_\_\_\_\_

**Client:** PARSONS BRINCKERHOFF  
**Project:** BRENT SPENCE BRIDGE REPLACEMENT  
**Source of Sample:** R-2A      **Depth:** 148-148.5'  
**Sample Number:** 12

UNCONFINED COMPRESSION TEST  
**H.C. Nutting**  
 A Terracon Company

**Tested By:** MRE \_\_\_\_\_ **Checked By:** GS \_\_\_\_\_

# UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	1550817.3			
Undrained shear strength, psf	775408.7			
Failure strain, %	1.4			
Strain rate, in./min.	0.048			
Water content, %	0.6			
Wet density, pcf	162.0			
Dry density, pcf	161.1			
Saturation, %	N/A			
Void ratio	N/A			
Specimen diameter, in.	2.380			
Specimen height, in.	4.880			
Height/diameter ratio	2.05			

**Description:** LIMESTONE

LL =      PL =      PI =      Assumed GS=      Type: Limestone

**Project No.:** N1105070  
**Date Sampled:** 10-7-10  
**Remarks:**  
 Lab No. 9709

Figure \_\_\_\_\_


**Client:** PARSONS BRINCKERHOFF  
**Project:** BRENT SPENCE BRIDGE REPLACEMENT  
**Source of Sample:** R-2A      **Depth:** 160-160.5'  
**Sample Number:** 13

UNCONFINED COMPRESSION TEST  
**H.C. Nutting**  
 A Terracon Company

**Tested By:** MRE \_\_\_\_\_ **Checked By:** GS \_\_\_\_\_



# UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	1495031.6			
Undrained shear strength, psf	747515.8			
Failure strain, %	1.0			
Strain rate, in./min.	0.049			
Water content, %	0.8			
Wet density, pcf	162.8			
Dry density, pcf	161.6			
Saturation, %	N/A			
Void ratio	N/A			
Specimen diameter, in.	2.390			
Specimen height, in.	4.900			
Height/diameter ratio	2.05			


**Description:** LIMESTONE

<b>LL =</b>	<b>PL =</b>	<b>PI =</b>	<b>Assumed GS=</b>	<b>Type:</b> Limestone
-------------	-------------	-------------	--------------------	------------------------

<p><b>Project No.:</b> N1105070  <b>Date Sampled:</b> 10-7-10  <b>Remarks:</b>                  Lab No. 9711</p>	<p><b>Client:</b> PARSONS BRINCKERHOFF  <b>Project:</b> BRENT SPENCE BRIDGE REPLACEMENT  <b>Source of Sample:</b> R-2A      <b>Depth:</b> 175.8-176.3'  <b>Sample Number:</b> 15</p>
UNCONFINED COMPRESSION TEST <b>H.C. Nutting</b> A Terracon Company	

**Tested By:** MRE      **Checked By:** GS

# UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, psf	1902575.1			
Undrained shear strength, psf	951287.5			
Failure strain, %	1.2			
Strain rate, in./min.	0.047			
Water content, %	0.1			
Wet density, pcf	165.6			
Dry density, pcf	165.4			
Saturation, %	N/A			
Void ratio	N/A			
Specimen diameter, in.	2.390			
Specimen height, in.	4.760			
Height/diameter ratio	1.99			


**Description:** LIMESTONE

LL =	PL =	PI =	Assumed GS=	Type: Limestone
------	------	------	-------------	-----------------

<p><b>Project No.:</b> N1105070  <b>Date Sampled:</b> 10-7-10  <b>Remarks:</b>                  Lab No. 9712</p>	<p><b>Client:</b> PARSONS BRINCKERHOFF  <b>Project:</b> BRENT SPENCE BRIDGE REPLACEMENT  <b>Source of Sample:</b> R-2A      <b>Depth:</b> 179.8-180.3'  <b>Sample Number:</b> 16</p>
UNCONFINED COMPRESSION TEST <b>H.C. Nutting</b> A Terracon Company	

**Tested By:** MRE      **Checked By:** GS

# UNCONFINED COMPRESSION TEST



Sample No.	1		
Unconfined strength, psf	1400566.4		
Undrained shear strength, psf	700283.2		
Failure strain, %	1.2		
Strain rate, in./min.	0.046		
Water content, %	0.1		
Wet density, pcf	168.8		
Dry density, pcf	168.7		
Saturation, %	N/A		
Void ratio	N/A		
Specimen diameter, in.	2.380		
Specimen height, in.	4.670		
Height/diameter ratio	1.96		

**Description:** LIMESTONE

LL =      PL =      PI =      Assumed GS=      Type: Limestone

**Project No.:** N1105070

**Date Sampled:** 10-7-10

**Remarks:**

Lab No. 9713

**Client:** PARSONS BRINCKERHOFF

**Project:** BRENT SPENCE BRIDGE REPLACEMENT

**Source of Sample:** R-2A

**Depth:** 183.5-184'

**Sample Number:** 17

UNCONFINED COMPRESSION TEST

**H.C. Nutting**  
A Terracon Company

Figure \_\_\_\_\_

**Tested By:** MRE

**Checked By:** GS

**Geotechnical Engineering Report**

Brent Spence Bridge Replacement ■ Cincinnati, Ohio-Covington, Kentucky  
March 11, 2011 ■ HCN/Terracon Project No. N1105070



## **POINT LOAD TESTING RESULTS**

**Point Load Test Results**

Parsons Brinckerhoff ■ Brent Spence Bridge Replacement ■ Cincinnati, Ohio  
 March 11, 2011 ■ HCN/Terracon Project No. N1105070

**POINT LOAD TEST RESULTS**

<b>Boring</b>	<b>Top Depth (ft.)</b>	<b>Top Elevation (ft.)</b>	<b>Bottom Depth (ft.)</b>	<b>Bottom Elevation (ft.)</b>	<b>Is (psi)</b>	<b>UCS (psi)</b>
L-1	139.5	353.96	140	353.46	733	14651
L-1	145	348.46	145.5	347.96	795	15893
L-1A	140.1	351.35	140.7	350.75	458	9157
L-1A	152.6	338.85	153	338.45	617	12346
L-1A	154.5	336.95	155.3	336.15	597	11932
L-2A	142.5	352.00	142.9	351.60	607	12131
L-2A	165.2	329.30	165.7	328.80	677	13547
L-3	93.1	365.56	93.6	365.06	460	9195
L-3	117.6	341.06	118.4	340.26	589	11786
L-3	137.2	321.46	138	320.66	522	10439
L-3	147.8	310.86	148.3	310.36	522	10434
L-3A	134.6	361.45	135	361.05	742	14846
L-3A	152.75	343.30	153.5	342.55	649	12976
L-4	132.4	347.57	132.9	347.07	585	11696
L-4	141.4	338.57	141.8	338.17	593	11853
L-5	122.7	363.63	123.3	363.03	736	14712
L-5	143.5	342.83	144	342.33	523	10455
L-6	114	371.69	115	370.69	586	11720
L-6	126.3	359.39	126.8	358.89	604	12087
L-7	116	368.41	116.5	367.91	544	10879
L-7	139.7	344.71	140.2	344.21	576	11517
R-1	101	357.04	101.5	356.54	523	10455
R-1	110.2	347.84	110.9	347.14	64	1282
R-1	129.4	328.64	129.8	328.24	555	11103
R-1	145.7	312.34	146.5	311.54	655	13095
R-1	161.8	296.24	162.5	295.54	731	14614
R-2	107.7	350.40	108.5	349.60	289	5783
R-2	130.7	327.40	131.1	327.00	529	10575
R-2	148.5	309.60	149	309.10	644	12884
R-2	159.5	298.60	160.1	298.00	648	12962
R-2A	105.1	352.54	105.5	352.14	451	9027
R-2A	131.5	326.14	132	325.64	407	8142
R-2A	141.2	316.44	141.5	316.14	551	11014
R-2A	166.9	290.74	167.5	290.14	499	9985

**Point Load Test Results**

Parsons Brinckerhoff ■ Brent Spence Bridge Replacement ■ Cincinnati, Ohio  
 March 11, 2011 ■ HCN/Terracon Project No. N1105070



Boring	Top Depth (ft.)	Top Elevation (ft.)	Bottom Depth (ft.)	Bottom Elevation (ft.)	Is (psi)	UCS (psi)
R-3	98	360.01	98.7	359.31	664	13271
R-3	113.3	344.71	113.8	344.21	652	13042
R-3	117.2	340.81	117.9	340.11	528	10568
R-4	95	362.98	95.5	362.48	596	11920
R-4	101	356.98	101.6	356.38	664	13271
R-4	147	310.98	147.4	310.58	624	12473
R-4	155.5	302.48	155.9	302.08	652	13035
R-5	100.8	357.79	101.5	357.09	551	11011
R-5	108	350.59	108.5	350.09	810	16192
R-5	118.2	340.39	118.8	339.79	553	11057
R-5	156.4	302.19	157	301.59	720	14406
R-6	91.5	365.54	92	365.04	582	11637
R-6	105	352.04	106	351.04	630	12607
R-6	124.7	332.34	125.1	331.94	580	11607
R-6	153.1	303.94	153.9	303.14	655	13102
R-7	89.7	368.76	90.1	368.36	649	12982
R-7	100.8	357.66	101.6	356.86	599	11981
R-7	125.9	332.56	126.7	331.76	746	14914
R-7	145.5	312.96	146.1	312.36	657	13149
R-8	96	359.70	96.5	359.20	533	10656
R-8	118.6	337.10	119	336.70	533	10656

**Geotechnical Engineering Report**

Brent Spence Bridge Replacement ■ Cincinnati, Ohio-Covington, Kentucky  
March 11, 2011 ■ HCN/Terracon Project No. N1105070



## **ELASTIC MODULUS TESTING RESULTS**

**Elastic Modulus Test Results**

Parsons Brinckerhoff ■ Brent Spence Bridge Replacement ■ Cincinnati, Ohio  
 March 11, 2011 ■ HCN/Terracon Project No. N1105070

**ELASTIC MODULUS TEST RESULTS**

Boring	Top Depth (ft.)	Top Elevation (ft.)	Bottom Depth (ft)	Bottom Elevation (ft)	Unconfined Compressive Strength (psi)	Young's Modulus (ksi)	Rock Type
L-1	150.7	342.76	151.3	342.16	21926	9302	Limestone
L-1A	150	341.45	150.4	341.05	21828	9750	Limestone
L-2A	150.9	343.60	151.4	343.10	16544	8863	Limestone
L-3	113.2	345.46	114.2	344.46	21169	9808	Limestone
L-3	121.8	336.86	122.8	335.86	13540	6323	Limestone
L-3A	155	341.05	155.5	340.55	16975	7601	Limestone
L-4	127.5	352.47	128	351.97	17130	8666	Limestone
L-5	137.3	349.03	138	348.33	20794	9086	Limestone
L-6	138	347.69	138.3	347.39	25530	9219	Limestone
L-7	125.7	358.71	126.2	358.21	23281	9443	Limestone
R-1	115	343.04	115.9	342.14	12584	8636	Limestone
R-1	137.7	320.34	138.2	319.84	15380	6475	Limestone
R-1	146.5	311.54	147	311.04	20779	10022	Limestone
R-2	143.5	314.60	144	314.10	13836	8461	Limestone
R-2	155.3	302.80	155.6	302.50	26538	7518	Limestone
R-2A	112.7	344.94	113.2	344.44	10771	8474	Limestone
R-2A	125.5	332.14	126	331.64	10193	7020	Limestone
R-3	106	352.01	106.5	351.51	14729	6789	Limestone
R-3	136.5	321.51	137	321.01	24544	6685	Limestone
R-4	120.6	337.38	121.3	336.68	19133	10417	Limestone
R-4	139.6	318.38	140.5	317.48	16884	8452	Limestone
R-5	103.5	355.09	104	354.59	14991	5369	Limestone
R-5	128.1	330.49	128.8	329.79	19640	8454	Limestone
R-6	99.6	357.44	100.1	356.94	14253	6276	Limestone
R-6	158.4	298.64	158.9	298.14	22557	9098	Limestone
R-7	106.2	352.26	106.7	351.76	16419	8899	Limestone
R-8	101.5	354.20	102.2	353.50	10883	7995	Limestone
R-8	122.9	332.80	123.3	332.40	14846	8419	Limestone



**Geotechnical Engineering Report**

Brent Spence Bridge Replacement ■ Cincinnati, Ohio-Covington, Kentucky

March 11, 2011 ■ HCN/Terracon Project No. N1105070



## **SLAKE DURABILITY TESTING RESULTS**

**Slake Durability Index Test Results**

Parsons Brinckerhoff ■ Brent Spence Bridge Replacement ■ Cincinnati, Ohio

March 11, 2011 ■ HCN/Terracon Project No. N1105070

**SLAKE DURABILITY INDEX TEST RESULTS**

Boring	Top Depth (ft.)	Top Elevation (ft.)	Bottom Depth (ft.)	Bottom Elevation (ft.)	SDI
L-1	137.1	356.36	137.8	355.66	68
L-1	147.7	345.76	149.2	344.26	67.3
L-1	157	336.46	157.8	335.66	67.8
L-2	133	363.26	133.5	362.76	89.9
L-2	143.5	352.76	144	352.26	91.4
L-2	148.2	348.06	145.5	350.76	88.2
L-2A	138.1	356.40	138.9	355.60	75.3
L-2A	147.3	347.20	147.9	346.60	40.1
L-3A	134.25	361.80	134.5	361.55	85.3
L-3A	150.5	345.55	150.7	345.35	97.7
L-4	108.5	371.47	109.5	370.47	59.2
L-5	109	377.33	109.4	376.93	50.9
L-5	118.5	367.83	118.8	367.53	48.1
L-6	110	375.69	110.4	375.29	56.9
L-6	117.7	367.99	118	367.69	55.1
L-7	105.5	378.91	105.8	378.61	65.9
L-7	107.5	376.91	107.8	376.61	93.3
L-7	118.6	365.81	11.8	472.61	77
R-2	88.2	369.90	88.5	369.60	67.9
R-2	89	369.10	89.3	368.80	82.5
R-2	93.7	364.40	94	364.10	93.6
R-2	100.4	357.70	101.3	356.80	94.1
R-2	134	324.10	134.3	323.80	91.7
R-5	92.2	366.39	92.8	365.79	57.9
R-5	95.7	362.89	95.9	362.69	52.5
R-5	153	305.59	153.5	305.09	98.8
R-6	85.1	371.94	85.6	371.44	36.9
R-6	91.5	365.54	92	365.04	53.6
R-6	100.5	356.54	101	356.04	91
R-7	93.4	365.06	93.6	364.86	79.5
R-7	95.7	362.76	96	362.46	72.8
R-7	102	356.46	102.2	356.26	92.6
R-7	121.1	337.36	121.4	337.06	80.4
R-8	88.4	367.30	88.9	366.80	66.8

**Geotechnical Engineering Report**

Brent Spence Bridge Replacement ■ Cincinnati, Ohio-Covington, Kentucky  
March 11, 2011 ■ HCN/Terracon Project No. N1105070



**APPENDIX C**  
**SUPPORTING DOCUMENTS**

**Geotechnical Engineering Report**

Brent Spence Bridge Replacement ■ Cincinnati, Ohio-Covington, Kentucky  
March 11, 2011 ■ HCN/Terracon Project No. N1105070



**EXHIBIT C-1**  
**ODOT CLASSIFICATION**



# SOIL AND ROCK SYMBOLOGY

Ohio Department of Transportation

## SOIL

SYMBOL	DESCRIPTION	Classification	
		AASHTO	OHIO
	Gravel and/or Stone Fragments	A-1-a	
	Gravel and/or Stone Fragments with Sand	A-1-b	
	Fine Sand	A-3	
	Coarse and Fine Sand	--	A-3a
	Gravel and/or Stone Fragments with Sand and Silt	A-2-4	
		A-2-5	
	Gravel and/or Stone Fragments with Sand, Silt and Clay	A-2-6	
		A-2-7	
	Sandy Silt	A-4	A-4a
	Silt	A-4	A-4b
	Elastic Silt and Clay	A-5	
	Silt and Clay	A-6	A-6a
	Silty Clay	A-6	A-6b
	Elastic Clay	A-7-5	
	Clay	A-7-6	
	Organic Silt	A-8	A-8a
	Organic Clay	A-8	A-8b

## VISUALLY CLASSIFIED MATERIALS

	Uncontrolled Fill (Describe)		Sod and Topsoil
	Bouldery Zone		Pavement or Base
	Peat, S-Sedimentary W-Woody F-Fibrous L-Loamy & etc		

## ROCK

	Anhydrite		Limestone
	Breccia		Mudstone
	Chert		Sandstone
	Claystone		Shale
	Coal		Siltstone
	Conglomerate		Underclay
	Dolomite		Use for highly or severely weathered descriptions. Not applicable to coal, fireclay or underclay
	Fireclay		
	Flint		
	Gypsum		
	Halite		
	Interbedded Shale and Limestone		
	Ironstone		

**Geotechnical Engineering Report**

Brent Spence Bridge Replacement ■ Cincinnati, Ohio-Covington, Kentucky

March 11, 2011 ■ HCN/Terracon Project No. N1105070



**EXHIBIT C-2**  
**DRILLED SHAFT BASE & SHAFT RESISTANCE**  
**CALCULATIONS**



**Drilled Shaft Side Resistance Calculations**

Location	Avg. RQD (%)	Design Unconfined Compressive Strength ( $q_u$ , psi) <sup>5</sup>	Design Elastic Modulus ( $E_i$ , ksi)	Rock Mass Rating (RMR) <sup>1</sup>		Rock Mass Modulus ( $E_M$ , ksi) <sup>2</sup>	Rock Mass Modulus/ Intact Rock Modulus ( $E_M/E_i$ )	Jointed Rock Reduction Factor ( $\alpha_E$ ) <sup>3</sup>	Nominal Shaft Resistance ( $q_s$ , ksf) <sup>4</sup>		
									Rock	<	Concrete <sup>6</sup>
Ohio-Land	38%	4000	6043	47	III (Fair Rock)	1220	0.20	0.63	14.3		22.7
Ohio-River	67%	4800	5311	52	III (Fair Rock)	1627	0.31	0.71	17.7		22.7
Kentucky-River	59%	4800	4757	52	III (Fair Rock)	1627	0.34	0.72	17.9		22.7
Kentucky-Land	49%	4000	6073	47	III (Fair Rock)	1220	0.20	0.63	14.3		22.7

Notes

- 1 Per AASHTO LRFD Bridge Design Specifications Tables 10.4.6.4-1, 10.4.6.4-2, 10.4.6.4-3
- 2 Per AASHTO LRFD Bridge Design Specifications Equation 10.4.6.5-1
- 3 Interpolated From AASHTO LRFD Bridge Design Specifications Table 10.8.3.5.4b-1
- 4 Per AASHTO LRFD Bridge Design Specifications Equation 10.8.3.5.4b-1, Lower value is selected
- 5 This is the value used in design computation considering all the variable factors
- \* Average RQD and elastic modulus values from upper 30 ft. of bedrock
- \* Example calculation and copies of AASHTO tables provided on following pages



**EXAMPLE CALCULATION**  
 (Ohio-River Portion)

Step 1: Obtain average RQD, unconfined compressive strength ( $q_u$ ), and elastic modulus ( $E_M$ ) data from field/lab testing

Avg. RQD (%)= 67  
 Design  $q_u$  (psi)= 4800  
 Design  $E_M$  (ksi)= 5311

Step 2: Determine Rock Mass Rating (RMR) using Tables 10.4.6.4-1, 10.4.6.4-2, 10.4.6.4-3 in the AASHTO Manual

Criteria	Rating
1) Strength of Rock	2
2) RQD	13
3) Joint Spacing	10
4) Joint Condition	20
5) Groundwater	7
Joint Orientation Adjustment	0
Total (RMR)=	52
Rock Mass Class=	III (Fair Rock)

Step 3: Determine Rock Mass Modulus using Equation 10.4.6.5-1

$$E_M = 145 \left( 10^{\frac{RMR-10}{40}} \right)$$

$$E_M = 145 \left( 10^{\frac{52-10}{40}} \right) = 1627 \text{ksi}$$

Step 4: Determine Ratio of Rock Mass Modulus ( $E_M$ ) to Intact Rock Modulus ( $E_I$ )

$$\frac{E_M}{E_I} = \frac{1627 \text{ksi}}{5311 \text{ksi}} = 0.31$$

Step 5: Interpolate Jointed Rock Reduction Factor from Table 10.8.3.5.4b-1

$$\frac{0.3 - 0.1}{0.7 - 0.55} = \frac{0.3 - 0.31}{0.7 - \alpha_E}$$

$$\alpha_E = 0.71$$

Step 6: Calculate Shaft Resistance using Equation 10.8.3.5.4b-1. Select lower of two values calculated

$$q_s = 0.65 \cdot \alpha_E \cdot p_a \left( \frac{q_u}{p_a} \right)^{0.5} < 7.8 \cdot p_a \left( \frac{f'c}{p_a} \right)^{0.5}$$

$p_a = 2.12$  ksf (Atmospheric Pressure)  
 $f'c = 4$  ksi (Concrete Compressive Strength)

$$q_s = 0.65 \cdot 0.71 \cdot 2.12 \cdot \left( \frac{4800 \cdot \frac{144}{1000}}{2.12} \right)^{0.5} < 7.8 \cdot 2.12 \cdot \left( \frac{4}{2.12} \right)^{0.5}$$

$$q_s = 17.7 \text{ksf} < 22.7 \text{ksf}$$

Shaft Resistance ( $q_s$ )= 17.7 ksf

Step 7: Calculate Base Resistance using Equation 10.8.3.5.4c-1

$$q_p = 2.5 \cdot q_u$$

$$q_p = 2.5 \cdot (4800 \text{ psi} * \frac{144}{1000})$$

$$q_p = 1728 \text{ksf}$$

A value of 350 ksf has been recommended for use in the design. See report text.




**Geotechnical Engineering Report**

Brent Spence Bridge Replacement ■ Cincinnati, Ohio-Covington, Kentucky  
March 11, 2011 ■ HCN/Terracon Project No. N1105070



**EXHIBIT C-3**  
**DRIVEN PILE CALCULATIONS**  
**(DRIVEN & GRLWEAP)**

### Ohio-Land 14" Diameter CIP Pile Ultimate Capacity



**DRIVEN 1.2**  
**GENERAL PROJECT INFORMATION**

Filename: N:\PROJECTS\2010\N1105070\DRIVENL2A\_14.DVN  
Project Name: BSB Project Date: 12/07/2010  
Project Client: PB  
Computed By: DWW  
Project Manager: AJM

**PILE INFORMATION**

Pile Type: Pipe Pile - Closed End  
Top of Pile: 0.00 ft  
Diameter of Pile: 14.00 in

**ULTIMATE CONSIDERATIONS**

Water Table Depth At Time Of:	- Drilling:	0.00 ft
	- Driving/Restrike	0.00 ft
	- Ultimate:	0.00 ft
Ultimate Considerations:	- Local Scour:	0.00 ft
	- Long Term Scour:	0.00 ft
	- Soft Soil:	0.00 ft

**ULTIMATE PROFILE**

Layer	Type	Thickness	Driving Loss	Unit Weight	Strength	Ultimate Curve
1	Cohesionless	12.50 ft	0.00%	125.00 pcf	30.0/30.0	Nordlund
2	Cohesionless	17.50 ft	0.00%	120.00 pcf	24.0/24.0	Nordlund
3	Cohesionless	30.00 ft	0.00%	125.00 pcf	30.0/30.0	Nordlund
4	Cohesionless	15.00 ft	0.00%	120.00 pcf	30.0/30.0	Nordlund
5	Cohesionless	30.00 ft	0.00%	125.00 pcf	32.0/32.0	Nordlund
6	Cohesionless	23.50 ft	0.00%	125.00 pcf	34.0/34.0	Nordlund

## ULTIMATE - SKIN FRICTION


Depth	Soil Type	Effective Stress At Midpoint	Sliding Friction Angle	Adhesion	Skin Friction
0.01 ft	Cohesionless	0.31 psf	19.99	N/A	0.00 Kips
9.01 ft	Cohesionless	282.01 psf	19.99	N/A	3.17 Kips
12.49 ft	Cohesionless	390.94 psf	19.99	N/A	6.10 Kips
12.51 ft	Cohesionless	782.79 psf	16.00	N/A	6.11 Kips
21.51 ft	Cohesionless	1041.99 psf	16.00	N/A	13.40 Kips
29.99 ft	Cohesionless	1286.21 psf	16.00	N/A	23.58 Kips
30.01 ft	Cohesionless	1790.81 psf	19.99	N/A	23.61 Kips
39.01 ft	Cohesionless	2072.51 psf	19.99	N/A	46.91 Kips
48.01 ft	Cohesionless	2354.21 psf	19.99	N/A	76.53 Kips
57.01 ft	Cohesionless	2635.91 psf	19.99	N/A	112.49 Kips
59.99 ft	Cohesionless	2729.19 psf	19.99	N/A	125.79 Kips
60.01 ft	Cohesionless	3668.79 psf	19.99	N/A	125.88 Kips
69.01 ft	Cohesionless	3927.99 psf	19.99	N/A	170.03 Kips
74.99 ft	Cohesionless	4100.21 psf	19.99	N/A	202.59 Kips
75.01 ft	Cohesionless	4532.81 psf	21.33	N/A	202.71 Kips
84.01 ft	Cohesionless	4814.51 psf	21.33	N/A	270.74 Kips
93.01 ft	Cohesionless	5096.21 psf	21.33	N/A	346.73 Kips
102.01 ft	Cohesionless	5377.91 psf	21.33	N/A	430.68 Kips
104.99 ft	Cohesionless	5471.19 psf	21.33	N/A	460.23 Kips
105.01 ft	Cohesionless	6410.81 psf	22.66	N/A	460.45 Kips
114.01 ft	Cohesionless	6692.51 psf	22.66	N/A	575.21 Kips
123.01 ft	Cohesionless	6974.21 psf	22.66	N/A	699.64 Kips
128.49 ft	Cohesionless	7145.74 psf	22.66	N/A	780.13 Kips

## ULTIMATE - END BEARING

Depth	Soil Type	Effective Stress At Tip	Bearing Cap. Factor	Limiting End Bearing	End Bearing
0.01 ft	Cohesionless	0.63 psf	30.00	14.24 Kips	0.01 Kips
9.01 ft	Cohesionless	564.03 psf	30.00	14.24 Kips	10.49 Kips
12.49 ft	Cohesionless	781.87 psf	30.00	14.24 Kips	14.24 Kips
12.51 ft	Cohesionless	783.08 psf	13.80	14.24 Kips	5.18 Kips
21.51 ft	Cohesionless	1301.48 psf	13.80	14.24 Kips	8.61 Kips
29.99 ft	Cohesionless	1789.92 psf	13.80	14.24 Kips	10.52 Kips
30.01 ft	Cohesionless	1791.13 psf	30.00	14.24 Kips	14.24 Kips
39.01 ft	Cohesionless	2354.53 psf	30.00	14.24 Kips	14.24 Kips
48.01 ft	Cohesionless	2917.93 psf	30.00	14.24 Kips	14.24 Kips
57.01 ft	Cohesionless	3481.33 psf	30.00	14.24 Kips	14.24 Kips
59.99 ft	Cohesionless	3667.87 psf	30.00	14.24 Kips	14.24 Kips
60.01 ft	Cohesionless	3669.08 psf	30.00	14.24 Kips	14.24 Kips
69.01 ft	Cohesionless	4187.48 psf	30.00	14.24 Kips	14.24 Kips
74.99 ft	Cohesionless	4531.92 psf	30.00	14.24 Kips	14.24 Kips
75.01 ft	Cohesionless	4533.13 psf	40.40	35.28 Kips	35.28 Kips
84.01 ft	Cohesionless	5096.53 psf	40.40	35.28 Kips	35.28 Kips
93.01 ft	Cohesionless	5659.93 psf	40.40	35.28 Kips	35.28 Kips
102.01 ft	Cohesionless	6223.33 psf	40.40	35.28 Kips	35.28 Kips
104.99 ft	Cohesionless	6409.87 psf	40.40	35.28 Kips	35.28 Kips
105.01 ft	Cohesionless	6411.13 psf	55.60	78.59 Kips	78.59 Kips
114.01 ft	Cohesionless	6974.53 psf	55.60	78.59 Kips	78.59 Kips
123.01 ft	Cohesionless	7537.93 psf	55.60	78.59 Kips	78.59 Kips
128.49 ft	Cohesionless	7880.97 psf	55.60	78.59 Kips	78.59 Kips

## ULTIMATE - SUMMARY OF CAPACITIES

Depth	Skin Friction	End Bearing	Total Capacity
0.01 ft	0.00 Kips	0.01 Kips	0.01 Kips
9.01 ft	3.17 Kips	10.49 Kips	13.66 Kips
12.49 ft	6.10 Kips	14.24 Kips	20.34 Kips
12.51 ft	6.11 Kips	5.18 Kips	11.29 Kips
21.51 ft	13.40 Kips	8.61 Kips	22.01 Kips
29.99 ft	23.58 Kips	10.52 Kips	34.10 Kips
30.01 ft	23.61 Kips	14.24 Kips	37.85 Kips
39.01 ft	46.91 Kips	14.24 Kips	61.15 Kips
48.01 ft	76.53 Kips	14.24 Kips	90.77 Kips
57.01 ft	112.49 Kips	14.24 Kips	126.73 Kips
59.99 ft	125.79 Kips	14.24 Kips	140.03 Kips
60.01 ft	125.88 Kips	14.24 Kips	140.12 Kips
69.01 ft	170.03 Kips	14.24 Kips	184.27 Kips
74.99 ft	202.59 Kips	14.24 Kips	216.82 Kips
75.01 ft	202.71 Kips	35.28 Kips	237.99 Kips
84.01 ft	270.74 Kips	35.28 Kips	306.02 Kips
93.01 ft	346.73 Kips	35.28 Kips	382.01 Kips
102.01 ft	430.68 Kips	35.28 Kips	465.95 Kips
104.99 ft	460.23 Kips	35.28 Kips	495.50 Kips
105.01 ft	460.45 Kips	78.59 Kips	539.04 Kips
114.01 ft	575.21 Kips	78.59 Kips	653.81 Kips
123.01 ft	699.64 Kips	78.59 Kips	778.23 Kips
128.49 ft	780.13 Kips	78.59 Kips	858.72 Kips




HC Nutting Company  
BSB : 12/07/2010 : DWW

15-Dec-2010  
GRLWEAP(TM) Version 1998-1

Ultimate Capacity kips	Maximum Compression Stress ksi	Maximum Tension Stress ksi	Blow Count bl/ft	Stroke feet	Energy kips-ft
100.0	20.136	0.410	5.4	5.47	33.14
150.0	22.006	0.876	9.0	5.99	29.75
200.0	23.564	1.922	13.9	6.49	28.02
250.0	24.484	0.000	18.2	6.74	26.27
300.0	25.544	0.000	23.8	7.14	26.77
350.0	26.142	0.000	32.7	7.34	26.70
400.0	26.985	0.696	45.3	7.70	27.50
450.0	27.470	0.993	69.5	7.88	27.71
500.0	28.112	1.060	117.1	8.16	28.32
550.0	28.483	1.087	306.8	8.30	28.46



### Ohio-Land 16" Diameter CIP Pile Ultimate Capacity



**DRIVEN 1.2**  
**GENERAL PROJECT INFORMATION**

Filename: N:\PROJECTS\2010\N1105070\DRIVEN\L2A\_16.DVN  
Project Name: BSB Project Date: 12/07/2010  
Project Client: PB  
Computed By: DWW  
Project Manager: AJM

**PILE INFORMATION**

Pile Type: Pipe Pile - Closed End  
Top of Pile: 0.00 ft  
Diameter of Pile: 16.00 in

**ULTIMATE CONSIDERATIONS**

Water Table Depth At Time Of:	- Drilling:	0.00 ft
	- Driving/Restrike	0.00 ft
	- Ultimate:	0.00 ft
Ultimate Considerations:	- Local Scour:	0.00 ft
	- Long Term Scour:	0.00 ft
	- Soft Soil:	0.00 ft

**ULTIMATE PROFILE**

Layer	Type	Thickness	Driving Loss	Unit Weight	Strength	Ultimate Curve
1	Cohesionless	12.50 ft	0.00%	125.00 pcf	30.0/30.0	Nordlund
2	Cohesionless	17.50 ft	0.00%	120.00 pcf	24.0/24.0	Nordlund
3	Cohesionless	30.00 ft	0.00%	125.00 pcf	30.0/30.0	Nordlund
4	Cohesionless	15.00 ft	0.00%	120.00 pcf	30.0/30.0	Nordlund
5	Cohesionless	30.00 ft	0.00%	125.00 pcf	32.0/32.0	Nordlund
6	Cohesionless	23.50 ft	0.00%	125.00 pcf	34.0/34.0	Nordlund

## ULTIMATE - SKIN FRICTION


Depth	Soil Type	Effective Stress At Midpoint	Sliding Friction Angle	Adhesion	Skin Friction
0.01 ft	Cohesionless	0.31 psf	21.97	N/A	0.00 Kips
9.01 ft	Cohesionless	282.01 psf	21.97	N/A	4.27 Kips
12.49 ft	Cohesionless	390.94 psf	21.97	N/A	8.21 Kips
12.51 ft	Cohesionless	782.79 psf	17.58	N/A	8.24 Kips
21.51 ft	Cohesionless	1041.99 psf	17.58	N/A	17.85 Kips
29.99 ft	Cohesionless	1286.21 psf	17.58	N/A	31.29 Kips
30.01 ft	Cohesionless	1790.81 psf	21.97	N/A	31.34 Kips
39.01 ft	Cohesionless	2072.51 psf	21.97	N/A	62.72 Kips
48.01 ft	Cohesionless	2354.21 psf	21.97	N/A	102.64 Kips
57.01 ft	Cohesionless	2635.91 psf	21.97	N/A	151.09 Kips
59.99 ft	Cohesionless	2729.19 psf	21.97	N/A	169.01 Kips
60.01 ft	Cohesionless	3668.79 psf	21.97	N/A	169.13 Kips
69.01 ft	Cohesionless	3927.99 psf	21.97	N/A	228.61 Kips
74.99 ft	Cohesionless	4100.21 psf	21.97	N/A	272.47 Kips
75.01 ft	Cohesionless	4532.81 psf	23.44	N/A	272.65 Kips
84.01 ft	Cohesionless	4814.51 psf	23.44	N/A	365.28 Kips
93.01 ft	Cohesionless	5096.21 psf	23.44	N/A	468.76 Kips
102.01 ft	Cohesionless	5377.91 psf	23.44	N/A	583.07 Kips
104.99 ft	Cohesionless	5471.19 psf	23.44	N/A	623.31 Kips
105.01 ft	Cohesionless	6410.81 psf	24.90	N/A	623.62 Kips
114.01 ft	Cohesionless	6692.51 psf	24.90	N/A	781.38 Kips
123.01 ft	Cohesionless	6974.21 psf	24.90	N/A	952.43 Kips
128.49 ft	Cohesionless	7145.74 psf	24.90	N/A	1063.09 Kips

## ULTIMATE - END BEARING

Depth	Soil Type	Effective Stress At Tip	Bearing Cap. Factor	Limiting End Bearing	End Bearing
0.01 ft	Cohesionless	0.63 psf	30.00	18.60 Kips	0.02 Kips
9.01 ft	Cohesionless	564.03 psf	30.00	18.60 Kips	13.70 Kips
12.49 ft	Cohesionless	781.87 psf	30.00	18.60 Kips	18.60 Kips
12.51 ft	Cohesionless	783.08 psf	13.80	18.60 Kips	6.77 Kips
21.51 ft	Cohesionless	1301.48 psf	13.80	18.60 Kips	11.24 Kips
29.99 ft	Cohesionless	1789.92 psf	13.80	18.60 Kips	14.71 Kips
30.01 ft	Cohesionless	1791.13 psf	30.00	18.60 Kips	18.60 Kips
39.01 ft	Cohesionless	2354.53 psf	30.00	18.60 Kips	18.60 Kips
48.01 ft	Cohesionless	2917.93 psf	30.00	18.60 Kips	18.60 Kips
57.01 ft	Cohesionless	3481.33 psf	30.00	18.60 Kips	18.60 Kips
59.99 ft	Cohesionless	3667.87 psf	30.00	18.60 Kips	18.60 Kips
60.01 ft	Cohesionless	3669.08 psf	30.00	18.60 Kips	18.60 Kips
69.01 ft	Cohesionless	4187.48 psf	30.00	18.60 Kips	18.60 Kips
74.99 ft	Cohesionless	4531.92 psf	30.00	18.60 Kips	18.60 Kips
75.01 ft	Cohesionless	4533.13 psf	40.40	46.08 Kips	46.08 Kips
84.01 ft	Cohesionless	5096.53 psf	40.40	46.08 Kips	46.08 Kips
93.01 ft	Cohesionless	5659.93 psf	40.40	46.08 Kips	46.08 Kips
102.01 ft	Cohesionless	6223.33 psf	40.40	46.08 Kips	46.08 Kips
104.99 ft	Cohesionless	6409.87 psf	40.40	46.08 Kips	46.08 Kips
105.01 ft	Cohesionless	6411.13 psf	55.60	102.65 Kips	102.65 Kips
114.01 ft	Cohesionless	6974.53 psf	55.60	102.65 Kips	102.65 Kips
123.01 ft	Cohesionless	7537.93 psf	55.60	102.65 Kips	102.65 Kips
128.49 ft	Cohesionless	7880.97 psf	55.60	102.65 Kips	102.65 Kips

## ULTIMATE - SUMMARY OF CAPACITIES

Depth	Skin Friction	End Bearing	Total Capacity
0.01 ft	0.00 Kips	0.02 Kips	0.02 Kips
9.01 ft	4.27 Kips	13.70 Kips	17.98 Kips
12.49 ft	8.21 Kips	18.60 Kips	26.81 Kips
12.51 ft	8.24 Kips	6.77 Kips	15.00 Kips
21.51 ft	17.85 Kips	11.24 Kips	29.10 Kips
29.99 ft	31.29 Kips	14.71 Kips	46.00 Kips
30.01 ft	31.34 Kips	18.60 Kips	49.94 Kips
39.01 ft	62.72 Kips	18.60 Kips	81.32 Kips
48.01 ft	102.64 Kips	18.60 Kips	121.24 Kips
57.01 ft	151.09 Kips	18.60 Kips	169.69 Kips
59.99 ft	169.01 Kips	18.60 Kips	187.61 Kips
60.01 ft	169.13 Kips	18.60 Kips	187.73 Kips
69.01 ft	228.61 Kips	18.60 Kips	247.21 Kips
74.99 ft	272.47 Kips	18.60 Kips	291.07 Kips
75.01 ft	272.65 Kips	46.08 Kips	318.72 Kips
84.01 ft	365.28 Kips	46.08 Kips	411.36 Kips
93.01 ft	468.76 Kips	46.08 Kips	514.83 Kips
102.01 ft	583.07 Kips	46.08 Kips	629.15 Kips
104.99 ft	623.31 Kips	46.08 Kips	669.39 Kips
105.01 ft	623.62 Kips	102.65 Kips	726.27 Kips
114.01 ft	781.38 Kips	102.65 Kips	884.04 Kips
123.01 ft	952.43 Kips	102.65 Kips	1055.09 Kips
128.49 ft	1063.09 Kips	102.65 Kips	1165.74 Kips




HC Nutting Company  
BSB : 12/07/2010 : DWW

15-Dec-2010  
GRLWEAP(TM) Version 1998-1

Ultimate Capacity kips	Maximum Compression Stress ksi	Maximum Tension Stress ksi	Blow Count bl/ft	Stroke feet	Energy kips-ft
100.0	18.971	2.373	5.4	5.60	31.98
150.0	20.757	1.547	9.0	6.13	28.44
200.0	22.149	2.042	13.8	6.59	26.85
250.0	22.914	2.081	19.7	6.82	24.83
300.0	24.034	0.274	24.5	7.26	24.30
350.0	24.628	0.000	31.5	7.48	24.19
400.0	24.980	0.414	41.9	7.59	24.09
450.0	25.712	0.637	54.7	7.91	24.79
500.0	26.105	0.834	76.7	8.08	25.01
550.0	26.330	0.835	116.4	8.16	25.02

### Ohio-Land HP 14x73 Pile Ultimate Capacity





**DRIVEN 1.2**  
**GENERAL PROJECT INFORMATION**

Filename: N:\PROJECTS\2010\N1105070\DRIVEN\HPILES\L214X73.DVN  
Project Name: BSB Project Date: 12/07/2010  
Project Client: PB  
Computed By: DWW  
Project Manager: AJM

**PILE INFORMATION**

Pile Type: H Pile - HP14X73  
Top of Pile: 0.00 ft  
Perimeter Analysis: Box  
Tip Analysis: Pile Area

**ULTIMATE CONSIDERATIONS**

Water Table Depth At Time Of:	- Drilling:	0.00 ft
	- Driving/Restrike	0.00 ft
	- Ultimate:	0.00 ft
Ultimate Considerations:	- Local Scour:	0.00 ft
	- Long Term Scour:	0.00 ft
	- Soft Soil:	0.00 ft

**ULTIMATE PROFILE**

Layer	Type	Thickness	Driving Loss	Unit Weight	Strength	Ultimate Curve
1	Cohesionless	12.50 ft	0.00%	125.00 pcf	30.0/30.0	Nordlund
2	Cohesionless	17.50 ft	0.00%	120.00 pcf	24.0/24.0	Nordlund
3	Cohesionless	30.00 ft	0.00%	125.00 pcf	30.0/30.0	Nordlund
4	Cohesionless	15.00 ft	0.00%	120.00 pcf	30.0/30.0	Nordlund
5	Cohesionless	30.00 ft	0.00%	125.00 pcf	32.0/32.0	Nordlund
6	Cohesionless	23.50 ft	0.00%	125.00 pcf	34.0/34.0	Nordlund

## ULTIMATE - SKIN FRICTION



Depth	Soil Type	Effective Stress At Midpoint	Sliding Friction Angle	Adhesion	Skin Friction
0.01 ft	Cohesionless	0.31 psf	23.58	N/A	0.00 Kips
9.01 ft	Cohesionless	282.01 psf	23.58	N/A	4.01 Kips
12.49 ft	Cohesionless	390.94 psf	23.58	N/A	7.71 Kips
12.51 ft	Cohesionless	782.79 psf	18.86	N/A	7.73 Kips
21.51 ft	Cohesionless	1041.99 psf	18.86	N/A	17.59 Kips
29.99 ft	Cohesionless	1286.21 psf	18.86	N/A	31.37 Kips
30.01 ft	Cohesionless	1790.81 psf	23.58	N/A	31.42 Kips
39.01 ft	Cohesionless	2072.51 psf	23.58	N/A	60.87 Kips
48.01 ft	Cohesionless	2354.21 psf	23.58	N/A	98.33 Kips
57.01 ft	Cohesionless	2635.91 psf	23.58	N/A	143.78 Kips
59.99 ft	Cohesionless	2729.19 psf	23.58	N/A	160.60 Kips
60.01 ft	Cohesionless	3668.79 psf	23.58	N/A	160.72 Kips
69.01 ft	Cohesionless	3927.99 psf	23.58	N/A	216.53 Kips
74.99 ft	Cohesionless	4100.21 psf	23.58	N/A	257.68 Kips
75.01 ft	Cohesionless	4532.81 psf	25.15	N/A	257.84 Kips
84.01 ft	Cohesionless	4814.51 psf	25.15	N/A	340.86 Kips
93.01 ft	Cohesionless	5096.21 psf	25.15	N/A	433.60 Kips
102.01 ft	Cohesionless	5377.91 psf	25.15	N/A	536.05 Kips
104.99 ft	Cohesionless	5471.19 psf	25.15	N/A	572.11 Kips
105.01 ft	Cohesionless	6410.81 psf	26.72	N/A	572.38 Kips
114.01 ft	Cohesionless	6692.51 psf	26.72	N/A	709.29 Kips
123.01 ft	Cohesionless	6974.21 psf	26.72	N/A	857.73 Kips
128.49 ft	Cohesionless	7145.74 psf	26.72	N/A	953.76 Kips

## ULTIMATE - END BEARING

Depth	Soil Type	Effective Stress At Tip	Bearing Cap. Factor	Limiting End Bearing	End Bearing
0.01 ft	Cohesionless	0.63 psf	30.00	1.98 Kips	0.00 Kips
9.01 ft	Cohesionless	564.03 psf	30.00	1.98 Kips	1.46 Kips
12.49 ft	Cohesionless	781.87 psf	30.00	1.98 Kips	1.98 Kips
12.51 ft	Cohesionless	783.08 psf	13.80	1.98 Kips	0.72 Kips
21.51 ft	Cohesionless	1301.48 psf	13.80	1.98 Kips	1.20 Kips
29.99 ft	Cohesionless	1789.92 psf	13.80	1.98 Kips	1.50 Kips
30.01 ft	Cohesionless	1791.13 psf	30.00	1.98 Kips	1.98 Kips
39.01 ft	Cohesionless	2354.53 psf	30.00	1.98 Kips	1.98 Kips
48.01 ft	Cohesionless	2917.93 psf	30.00	1.98 Kips	1.98 Kips
57.01 ft	Cohesionless	3481.33 psf	30.00	1.98 Kips	1.98 Kips
59.99 ft	Cohesionless	3667.87 psf	30.00	1.98 Kips	1.98 Kips
60.01 ft	Cohesionless	3669.08 psf	30.00	1.98 Kips	1.98 Kips
69.01 ft	Cohesionless	4187.48 psf	30.00	1.98 Kips	1.98 Kips
74.99 ft	Cohesionless	4531.92 psf	30.00	1.98 Kips	1.98 Kips
75.01 ft	Cohesionless	4533.13 psf	40.40	4.90 Kips	4.90 Kips
84.01 ft	Cohesionless	5096.53 psf	40.40	4.90 Kips	4.90 Kips
93.01 ft	Cohesionless	5659.93 psf	40.40	4.90 Kips	4.90 Kips
102.01 ft	Cohesionless	6223.33 psf	40.40	4.90 Kips	4.90 Kips
104.99 ft	Cohesionless	6409.87 psf	40.40	4.90 Kips	4.90 Kips
105.01 ft	Cohesionless	6411.13 psf	55.60	10.93 Kips	10.93 Kips
114.01 ft	Cohesionless	6974.53 psf	55.60	10.93 Kips	10.93 Kips
123.01 ft	Cohesionless	7537.93 psf	55.60	10.93 Kips	10.93 Kips
128.49 ft	Cohesionless	7880.97 psf	55.60	10.93 Kips	10.93 Kips

## ULTIMATE - SUMMARY OF CAPACITIES

Depth	Skin Friction	End Bearing	Total Capacity
0.01 ft	0.00 Kips	0.00 Kips	0.00 Kips
9.01 ft	4.01 Kips	1.46 Kips	5.47 Kips
12.49 ft	7.71 Kips	1.98 Kips	9.69 Kips
12.51 ft	7.73 Kips	0.72 Kips	8.45 Kips
21.51 ft	17.59 Kips	1.20 Kips	18.79 Kips
29.99 ft	31.37 Kips	1.50 Kips	32.87 Kips
30.01 ft	31.42 Kips	1.98 Kips	33.40 Kips
39.01 ft	60.87 Kips	1.98 Kips	62.85 Kips
48.01 ft	98.33 Kips	1.98 Kips	100.30 Kips
57.01 ft	143.78 Kips	1.98 Kips	145.76 Kips
59.99 ft	160.60 Kips	1.98 Kips	162.58 Kips
60.01 ft	160.72 Kips	1.98 Kips	162.70 Kips
69.01 ft	216.53 Kips	1.98 Kips	218.51 Kips
74.99 ft	257.68 Kips	1.98 Kips	259.66 Kips
75.01 ft	257.84 Kips	4.90 Kips	262.74 Kips
84.01 ft	340.86 Kips	4.90 Kips	345.77 Kips
93.01 ft	433.60 Kips	4.90 Kips	438.50 Kips
102.01 ft	536.05 Kips	4.90 Kips	540.95 Kips
104.99 ft	572.11 Kips	4.90 Kips	577.01 Kips
105.01 ft	572.38 Kips	10.93 Kips	583.30 Kips
114.01 ft	709.29 Kips	10.93 Kips	720.22 Kips
123.01 ft	857.73 Kips	10.93 Kips	868.66 Kips
128.49 ft	953.76 Kips	10.93 Kips	964.68 Kips



DELMAG D 30-32

Efficiency 0.800

Helmet 2.70 kips

Hammer Cushion 109975 kips/in

Skin Quake 0.100 in

Toe Quake 0.100 in


Skin Damping 0.100 sec/ft

Toe Damping 0.100 sec/ft


Pile Length 94.00 ft

Pile Top Area 21.40 in<sup>2</sup>

Pile Model



Skin Friction Distribution




Res. Shaft = 95 % (Proportional)

1st Pile  
2nd Pile

Ultimate Capacity kips	Maximum Compression Stress ksi	Maximum Tension Stress ksi	Blow Count bl/ft	Stroke feet	Energy kips-ft
200.0	25.972	2.839	12.6	6.48	31.75
250.0	26.994	1.716	16.5	6.75	30.34
300.0	28.318	0.000	20.2	7.17	30.80
350.0	29.040	0.741	25.5	7.39	31.28
400.0	29.842	1.606	32.0	7.66	32.27
450.0	30.250	1.739	42.0	7.79	32.48
500.0	31.039	1.481	54.1	8.08	33.71
550.0	31.468	1.185	75.2	8.22	34.10
600.0	31.727	1.306	114.7	8.29	34.21
650.0	32.421	1.308	183.7	8.58	35.22

### Kentucky-Land 14" Diameter CIP Pile Ultimate Capacity



**DRIVEN 1.2**  
**GENERAL PROJECT INFORMATION**

Filename: N:\PROJECTS\2010\N1105070\DRIVEN\5\_14.DVN  
Project Name: BSB Project Date: 12/09/2010  
Project Client: PB  
Computed By: DWW  
Project Manager: AJM

**PILE INFORMATION**

Pile Type: Pipe Pile - Closed End  
Top of Pile: 0.00 ft  
Diameter of Pile: 14.00 in

**ULTIMATE CONSIDERATIONS**

Water Table Depth At Time Of:	- Drilling:	0.00 ft
	- Driving/Restrike	0.00 ft
	- Ultimate:	0.00 ft
Ultimate Considerations:	- Local Scour:	0.00 ft
	- Long Term Scour:	0.00 ft
	- Soft Soil:	0.00 ft

**ULTIMATE PROFILE**

Layer	Type	Thickness	Driving Loss	Unit Weight	Strength	Ultimate Curve
1	Cohesive	35.00 ft	0.00%	120.00 pcf	1500.00 psf	T-80 Clay
2	Cohesive	10.00 ft	0.00%	120.00 pcf	2000.00 psf	T-80 Clay
3	Cohesionless	30.00 ft	0.00%	125.00 pcf	30.0/30.0	Nordlund
4	Cohesionless	32.00 ft	0.00%	125.00 pcf	34.0/34.0	Nordlund



### ULTIMATE - SKIN FRICTION


Depth	Soil Type	Effective Stress At Midpoint	Sliding Friction Angle	Adhesion	Skin Friction
0.01 ft	Cohesive	N/A	N/A	500.59 psf	0.02 Kips
9.01 ft	Cohesive	N/A	N/A	500.59 psf	16.53 Kips
18.01 ft	Cohesive	N/A	N/A	794.62 psf	52.45 Kips
27.01 ft	Cohesive	N/A	N/A	1041.36 psf	103.09 Kips
34.99 ft	Cohesive	N/A	N/A	1041.36 psf	133.55 Kips
35.01 ft	Cohesive	N/A	N/A	595.08 psf	133.61 Kips
44.01 ft	Cohesive	N/A	N/A	595.08 psf	153.24 Kips
44.99 ft	Cohesive	N/A	N/A	595.08 psf	155.38 Kips
45.01 ft	Cohesionless	2592.31 psf	19.99	N/A	155.43 Kips
54.01 ft	Cohesionless	2874.01 psf	19.99	N/A	187.73 Kips
63.01 ft	Cohesionless	3155.71 psf	19.99	N/A	226.37 Kips
72.01 ft	Cohesionless	3437.41 psf	19.99	N/A	271.33 Kips
74.99 ft	Cohesionless	3530.69 psf	19.99	N/A	287.62 Kips
75.01 ft	Cohesionless	4470.31 psf	22.66	N/A	287.76 Kips
84.01 ft	Cohesionless	4752.01 psf	22.66	N/A	369.25 Kips
93.01 ft	Cohesionless	5033.71 psf	22.66	N/A	460.40 Kips
102.01 ft	Cohesionless	5315.41 psf	22.66	N/A	561.21 Kips
106.99 ft	Cohesionless	5471.29 psf	22.66	N/A	621.14 Kips

### ULTIMATE - END BEARING

Depth	Soil Type	Effective Stress At Tip	Bearing Cap. Factor	Limiting End Bearing	End Bearing
0.01 ft	Cohesive	N/A	N/A	N/A	14.43 Kips
9.01 ft	Cohesive	N/A	N/A	N/A	14.43 Kips
18.01 ft	Cohesive	N/A	N/A	N/A	14.43 Kips
27.01 ft	Cohesive	N/A	N/A	N/A	14.43 Kips
34.99 ft	Cohesive	N/A	N/A	N/A	14.43 Kips
35.01 ft	Cohesive	N/A	N/A	N/A	19.24 Kips
44.01 ft	Cohesive	N/A	N/A	N/A	19.24 Kips
44.99 ft	Cohesive	N/A	N/A	N/A	19.24 Kips
45.01 ft	Cohesionless	2592.63 psf	30.00	14.24 Kips	14.24 Kips
54.01 ft	Cohesionless	3156.03 psf	30.00	14.24 Kips	14.24 Kips
63.01 ft	Cohesionless	3719.43 psf	30.00	14.24 Kips	14.24 Kips
72.01 ft	Cohesionless	4282.83 psf	30.00	14.24 Kips	14.24 Kips
74.99 ft	Cohesionless	4469.37 psf	30.00	14.24 Kips	14.24 Kips
75.01 ft	Cohesionless	4470.63 psf	55.60	78.59 Kips	78.59 Kips
84.01 ft	Cohesionless	5034.03 psf	55.60	78.59 Kips	78.59 Kips
93.01 ft	Cohesionless	5597.43 psf	55.60	78.59 Kips	78.59 Kips
102.01 ft	Cohesionless	6160.83 psf	55.60	78.59 Kips	78.59 Kips
106.99 ft	Cohesionless	6472.57 psf	55.60	78.59 Kips	78.59 Kips

## ULTIMATE - SUMMARY OF CAPACITIES

Depth	Skin Friction	End Bearing	Total Capacity
0.01 ft	0.02 Kips	14.43 Kips	14.45 Kips
9.01 ft	16.53 Kips	14.43 Kips	30.96 Kips
18.01 ft	52.45 Kips	14.43 Kips	66.88 Kips
27.01 ft	103.09 Kips	14.43 Kips	117.52 Kips
34.99 ft	133.55 Kips	14.43 Kips	147.98 Kips
35.01 ft	133.61 Kips	19.24 Kips	152.85 Kips
44.01 ft	153.24 Kips	19.24 Kips	172.48 Kips
44.99 ft	155.38 Kips	19.24 Kips	174.62 Kips
45.01 ft	155.43 Kips	14.24 Kips	169.67 Kips
54.01 ft	187.73 Kips	14.24 Kips	201.97 Kips
63.01 ft	226.37 Kips	14.24 Kips	240.61 Kips
72.01 ft	271.33 Kips	14.24 Kips	285.57 Kips
74.99 ft	287.62 Kips	14.24 Kips	301.86 Kips
75.01 ft	287.76 Kips	78.59 Kips	366.35 Kips
84.01 ft	369.25 Kips	78.59 Kips	447.84 Kips
93.01 ft	460.40 Kips	78.59 Kips	538.99 Kips
102.01 ft	561.21 Kips	78.59 Kips	639.80 Kips
106.99 ft	621.14 Kips	78.59 Kips	699.73 Kips




HC Nutting Company  
BSB : 12/09/2010 : DWW

15-Dec-2010  
GRLWEAP(TM) Version 1998-1

Ultimate Capacity kips	Maximum Compression Stress ksi	Maximum Tension Stress ksi	Blow Count bl/ft	Stroke feet	Energy kips-ft
100.0	23.235	1.202	5.1	5.49	35.71
150.0	25.375	1.069	8.5	5.86	31.89
200.0	27.872	0.690	12.8	6.55	31.69
250.0	29.104	0.012	16.8	6.90	30.45
300.0	29.711	0.000	21.4	7.07	29.48
350.0	30.999	0.000	26.8	7.44	30.21
400.0	31.714	0.000	34.9	7.63	30.41
450.0	32.650	0.000	45.8	7.88	31.11
500.0	33.182	0.000	63.4	8.01	31.30
550.0	33.458	0.000	97.4	8.07	30.98

### Kentucky-Land 16" Diameter CIP Pile Ultimate Capacity



**DRIVEN 1.2**  
**GENERAL PROJECT INFORMATION**

Filename: N:\PROJECTS\2010\N1105070\DRIVENL5\_16.DVN  
Project Name: BSB Project Date: 12/09/2010  
Project Client: PB  
Computed By: DWW  
Project Manager: AJM

**PILE INFORMATION**

Pile Type: Pipe Pile - Closed End  
Top of Pile: 0.00 ft  
Diameter of Pile: 16.00 in

**ULTIMATE CONSIDERATIONS**

Water Table Depth At Time Of:	- Drilling:	0.00 ft
	- Driving/Restrike	0.00 ft
	- Ultimate:	0.00 ft
Ultimate Considerations:	- Local Scour:	0.00 ft
	- Long Term Scour:	0.00 ft
	- Soft Soil:	0.00 ft

**ULTIMATE PROFILE**

Layer	Type	Thickness	Driving Loss	Unit Weight	Strength	Ultimate Curve
1	Cohesive	35.00 ft	0.00%	120.00 pcf	1500.00 psf	T-80 Clay
2	Cohesive	10.00 ft	0.00%	120.00 pcf	2000.00 psf	T-80 Clay
3	Cohesionless	30.00 ft	0.00%	125.00 pcf	30.0/30.0	Nordlund
4	Cohesionless	32.00 ft	0.00%	125.00 pcf	34.0/34.0	Nordlund

### ULTIMATE - SKIN FRICTION

Depth	Soil Type	Effective Stress At Midpoint	Sliding Friction Angle	Adhesion	Skin Friction
0.01 ft	Cohesive	N/A	N/A	500.59 psf	0.02 Kips
9.01 ft	Cohesive	N/A	N/A	500.59 psf	18.89 Kips
18.01 ft	Cohesive	N/A	N/A	690.27 psf	52.07 Kips
27.01 ft	Cohesive	N/A	N/A	1041.36 psf	117.82 Kips
34.99 ft	Cohesive	N/A	N/A	1041.36 psf	152.63 Kips
35.01 ft	Cohesive	N/A	N/A	595.08 psf	152.70 Kips
44.01 ft	Cohesive	N/A	N/A	595.08 psf	175.13 Kips
44.99 ft	Cohesive	N/A	N/A	595.08 psf	177.57 Kips
45.01 ft	Cohesionless	2592.31 psf	21.97	N/A	177.64 Kips
54.01 ft	Cohesionless	2874.01 psf	21.97	N/A	221.16 Kips
63.01 ft	Cohesionless	3155.71 psf	21.97	N/A	273.22 Kips
72.01 ft	Cohesionless	3437.41 psf	21.97	N/A	333.80 Kips
74.99 ft	Cohesionless	3530.69 psf	21.97	N/A	355.74 Kips
75.01 ft	Cohesionless	4470.31 psf	24.90	N/A	355.93 Kips
84.01 ft	Cohesionless	4752.01 psf	24.90	N/A	467.96 Kips
93.01 ft	Cohesionless	5033.71 psf	24.90	N/A	593.26 Kips
102.01 ft	Cohesionless	5315.41 psf	24.90	N/A	731.85 Kips
106.99 ft	Cohesionless	5471.29 psf	24.90	N/A	814.24 Kips

### ULTIMATE - END BEARING

Depth	Soil Type	Effective Stress At Tip	Bearing Cap. Factor	Limiting End Bearing	End Bearing
0.01 ft	Cohesive	N/A	N/A	N/A	18.85 Kips
9.01 ft	Cohesive	N/A	N/A	N/A	18.85 Kips
18.01 ft	Cohesive	N/A	N/A	N/A	18.85 Kips
27.01 ft	Cohesive	N/A	N/A	N/A	18.85 Kips
34.99 ft	Cohesive	N/A	N/A	N/A	18.85 Kips
35.01 ft	Cohesive	N/A	N/A	N/A	25.13 Kips
44.01 ft	Cohesive	N/A	N/A	N/A	25.13 Kips
44.99 ft	Cohesive	N/A	N/A	N/A	25.13 Kips
45.01 ft	Cohesionless	2592.63 psf	30.00	18.60 Kips	18.60 Kips
54.01 ft	Cohesionless	3156.03 psf	30.00	18.60 Kips	18.60 Kips
63.01 ft	Cohesionless	3719.43 psf	30.00	18.60 Kips	18.60 Kips
72.01 ft	Cohesionless	4282.83 psf	30.00	18.60 Kips	18.60 Kips
74.99 ft	Cohesionless	4469.37 psf	30.00	18.60 Kips	18.60 Kips
75.01 ft	Cohesionless	4470.63 psf	55.60	102.65 Kips	102.65 Kips
84.01 ft	Cohesionless	5034.03 psf	55.60	102.65 Kips	102.65 Kips
93.01 ft	Cohesionless	5597.43 psf	55.60	102.65 Kips	102.65 Kips
102.01 ft	Cohesionless	6160.83 psf	55.60	102.65 Kips	102.65 Kips
106.99 ft	Cohesionless	6472.57 psf	55.60	102.65 Kips	102.65 Kips



## ULTIMATE - SUMMARY OF CAPACITIES

Depth	Skin Friction	End Bearing	Total Capacity
0.01 ft	0.02 Kips	18.85 Kips	18.87 Kips
9.01 ft	18.89 Kips	18.85 Kips	37.74 Kips
18.01 ft	52.07 Kips	18.85 Kips	70.92 Kips
27.01 ft	117.82 Kips	18.85 Kips	136.67 Kips
34.99 ft	152.63 Kips	18.85 Kips	171.48 Kips
35.01 ft	152.70 Kips	25.13 Kips	177.83 Kips
44.01 ft	175.13 Kips	25.13 Kips	200.26 Kips
44.99 ft	177.57 Kips	25.13 Kips	202.71 Kips
45.01 ft	177.64 Kips	18.60 Kips	196.24 Kips
54.01 ft	221.16 Kips	18.60 Kips	239.76 Kips
63.01 ft	273.22 Kips	18.60 Kips	291.81 Kips
72.01 ft	333.80 Kips	18.60 Kips	352.40 Kips
74.99 ft	355.74 Kips	18.60 Kips	374.34 Kips
75.01 ft	355.93 Kips	102.65 Kips	458.59 Kips
84.01 ft	467.96 Kips	102.65 Kips	570.61 Kips
93.01 ft	593.26 Kips	102.65 Kips	695.92 Kips
102.01 ft	731.85 Kips	102.65 Kips	834.50 Kips
106.99 ft	814.24 Kips	102.65 Kips	916.89 Kips




DELMAG D 30-32

Efficiency 0.800  
 Helmet 2.70 kips  
 Hammer Cushion 10998 kips/in  
 Skin Quake 0.100 in  
 Toe Quake 0.100 in  
 Skin Damping 0.100 sec/ft  
 Toe Damping 0.150 sec/ft  
 Pile Length 75.00 ft  
 Pile Top Area 24.35 in<sup>2</sup>



Skin Friction Distribution



Res. Shaft = 95 %  
(Proportional)


--- 1st Pile  
 - - - - 2nd Pile

HC Nutting Company  
BSB : 12/09/2010 : DWW

15-Dec-2010  
GRLWEAP(TM) Version 1998-1

Ultimate Capacity kips	Maximum Compression Stress ksi	Maximum Tension Stress ksi	Blow Count bl/ft	Stroke feet	Energy kips-ft
100.0	19.231	1.880	5.1	5.69	33.88
150.0	21.000	1.265	8.6	6.15	30.06
200.0	22.845	1.102	12.3	6.81	29.25
250.0	23.751	0.632	17.9	7.14	27.80
300.0	24.887	0.000	22.2	7.59	27.20
350.0	25.401	0.000	27.4	7.82	26.29
400.0	25.708	0.000	34.3	7.93	25.98
450.0	26.531	0.000	42.2	8.26	26.76
500.0	26.947	0.000	54.0	8.43	26.96
550.0	27.261	0.000	71.9	8.51	26.93

### Kentucky-Land HP 14x73 Pile Ultimate Capacity



**DRIVEN 1.2**  
**GENERAL PROJECT INFORMATION**

Filename: N:\PROJECTS\2010\N1105070\DRIVEN\HPILES\L514X73.DVN  
Project Name: BSB Project Date: 12/09/2010  
Project Client: PB  
Computed By: DWW  
Project Manager: AJM

**PILE INFORMATION**

Pile Type: H Pile - HP14X73  
Top of Pile: 0.00 ft  
Perimeter Analysis: Box  
Tip Analysis: Pile Area

**ULTIMATE CONSIDERATIONS**

Water Table Depth At Time Of:	- Drilling:	0.00 ft
	- Driving/Restrike	0.00 ft
	- Ultimate:	0.00 ft
Ultimate Considerations:	- Local Scour:	0.00 ft
	- Long Term Scour:	0.00 ft
	- Soft Soil:	0.00 ft

**ULTIMATE PROFILE**

Layer	Type	Thickness	Driving Loss	Unit Weight	Strength	Ultimate Curve
1	Cohesive	35.00 ft	0.00%	120.00 pcf	1500.00 psf	T-80 Clay
2	Cohesive	10.00 ft	0.00%	120.00 pcf	2000.00 psf	T-80 Clay
3	Cohesionless	30.00 ft	0.00%	125.00 pcf	30.0/30.0	Nordlund
4	Cohesionless	32.00 ft	0.00%	125.00 pcf	34.0/34.0	Nordlund

## ULTIMATE - SKIN FRICTION


Depth	Soil Type	Effective Stress At Midpoint	Sliding Friction Angle	Adhesion	Skin Friction
0.01 ft	Cohesive	N/A	N/A	500.59 psf	0.02 Kips
9.01 ft	Cohesive	N/A	N/A	500.59 psf	21.19 Kips
18.01 ft	Cohesive	N/A	N/A	761.13 psf	64.42 Kips
27.01 ft	Cohesive	N/A	N/A	1041.36 psf	132.17 Kips
34.99 ft	Cohesive	N/A	N/A	1041.36 psf	171.22 Kips
35.01 ft	Cohesive	N/A	N/A	595.08 psf	171.30 Kips
44.01 ft	Cohesive	N/A	N/A	595.08 psf	196.47 Kips
44.99 ft	Cohesive	N/A	N/A	595.08 psf	199.21 Kips
45.01 ft	Cohesionless	2592.31 psf	23.58	N/A	199.28 Kips
54.01 ft	Cohesionless	2874.01 psf	23.58	N/A	240.12 Kips
63.01 ft	Cohesionless	3155.71 psf	23.58	N/A	288.96 Kips
72.01 ft	Cohesionless	3437.41 psf	23.58	N/A	345.80 Kips
74.99 ft	Cohesionless	3530.69 psf	23.58	N/A	366.39 Kips
75.01 ft	Cohesionless	4470.31 psf	26.72	N/A	366.56 Kips
84.01 ft	Cohesionless	4752.01 psf	26.72	N/A	463.78 Kips
93.01 ft	Cohesionless	5033.71 psf	26.72	N/A	572.52 Kips
102.01 ft	Cohesionless	5315.41 psf	26.72	N/A	692.79 Kips
106.99 ft	Cohesionless	5471.29 psf	26.72	N/A	764.29 Kips

## ULTIMATE - END BEARING

Depth	Soil Type	Effective Stress At Tip	Bearing Cap. Factor	Limiting End Bearing	End Bearing
0.01 ft	Cohesive	N/A	N/A	N/A	2.01 Kips
9.01 ft	Cohesive	N/A	N/A	N/A	2.01 Kips
18.01 ft	Cohesive	N/A	N/A	N/A	2.01 Kips
27.01 ft	Cohesive	N/A	N/A	N/A	2.01 Kips
34.99 ft	Cohesive	N/A	N/A	N/A	2.01 Kips
35.01 ft	Cohesive	N/A	N/A	N/A	2.67 Kips
44.01 ft	Cohesive	N/A	N/A	N/A	2.67 Kips
44.99 ft	Cohesive	N/A	N/A	N/A	2.67 Kips
45.01 ft	Cohesionless	2592.63 psf	30.00	1.98 Kips	1.98 Kips
54.01 ft	Cohesionless	3156.03 psf	30.00	1.98 Kips	1.98 Kips
63.01 ft	Cohesionless	3719.43 psf	30.00	1.98 Kips	1.98 Kips
72.01 ft	Cohesionless	4282.83 psf	30.00	1.98 Kips	1.98 Kips
74.99 ft	Cohesionless	4469.37 psf	30.00	1.98 Kips	1.98 Kips
75.01 ft	Cohesionless	4470.63 psf	55.60	10.93 Kips	10.93 Kips
84.01 ft	Cohesionless	5034.03 psf	55.60	10.93 Kips	10.93 Kips
93.01 ft	Cohesionless	5597.43 psf	55.60	10.93 Kips	10.93 Kips
102.01 ft	Cohesionless	6160.83 psf	55.60	10.93 Kips	10.93 Kips
106.99 ft	Cohesionless	6472.57 psf	55.60	10.93 Kips	10.93 Kips

## ULTIMATE - SUMMARY OF CAPACITIES

Depth	Skin Friction	End Bearing	Total Capacity
0.01 ft	0.02 Kips	2.01 Kips	2.03 Kips
9.01 ft	21.19 Kips	2.01 Kips	23.20 Kips
18.01 ft	64.42 Kips	2.01 Kips	66.42 Kips
27.01 ft	132.17 Kips	2.01 Kips	134.18 Kips
34.99 ft	171.22 Kips	2.01 Kips	173.23 Kips
35.01 ft	171.30 Kips	2.67 Kips	173.98 Kips
44.01 ft	196.47 Kips	2.67 Kips	199.14 Kips
44.99 ft	199.21 Kips	2.67 Kips	201.88 Kips
45.01 ft	199.28 Kips	1.98 Kips	201.26 Kips
54.01 ft	240.12 Kips	1.98 Kips	242.09 Kips
63.01 ft	288.96 Kips	1.98 Kips	290.94 Kips
72.01 ft	345.80 Kips	1.98 Kips	347.78 Kips
74.99 ft	366.39 Kips	1.98 Kips	368.37 Kips
75.01 ft	366.56 Kips	10.93 Kips	377.49 Kips
84.01 ft	463.78 Kips	10.93 Kips	474.70 Kips
93.01 ft	572.52 Kips	10.93 Kips	583.45 Kips
102.01 ft	692.79 Kips	10.93 Kips	703.71 Kips
106.99 ft	764.29 Kips	10.93 Kips	775.22 Kips



Compressive Stress (ksi) —  
Tension Stress (ksi) - - -

DEL MAG D 30-32

Efficiency 0.800

Helmet 2.70 kips

Hammer Cushion 109975 kips/in

Skin Quake 0.100 in



Toe Quake 0.100 in

Skin Damping 0.100 sec/ft

Toe Damping 0.150 sec/ft


Pile Length 81.00 ft

Pile Top Area 21.40 in<sup>2</sup>



Res. Shaft = 95 %  
(Proportional)

1st Pile  
2nd Pile



Ultimate Capacity (kips) —  
Stroke (feet) - - -


HC Nutting Company  
BSB : 12/09/2010 : DWW

28-Feb-2011  
GRLWEAP(TM) Version 1998-1


Ultimate Capacity kips	Maximum Compression Stress ksi	Maximum Tension Stress ksi	Blow Count bl/ft	Stroke feet	Energy kips-ft
200.0	26.492	0.629	12.7	6.52	31.00
250.0	27.794	1.298	17.3	6.89	30.19
300.0	28.999	0.000	21.2	7.26	29.64
350.0	29.559	0.000	26.6	7.44	29.34
400.0	29.865	0.000	33.9	7.54	29.43
450.0	30.931	0.000	42.1	7.88	30.44
500.0	31.484	0.000	54.6	8.05	30.74
550.0	31.825	0.000	74.9	8.14	30.74
600.0	32.044	0.000	110.6	8.18	30.73
650.0	32.834	0.000	170.3	8.41	31.47



Ohio River - HP 14 x 73 to rock



Compressive Stress (ksi) ———



Tension Stress (ksi) - - - - -

DELIMAG D 30

Efficiency 0.800

Helmet 2.70 kips

Hammer Cushion 109975 kips/in

Skin Quake 0.100 in



Toe Quake 0.100 in

Skin Damping 0.100 sec/ft

Toe Damping 0.150 sec/ft


Pile Length 57.98 ft

Pile Top Area 21.40 in<sup>2</sup>



Res. Shaft = 5 %  
 (Proportional)

1st Pile  
 2nd Pile



Ultimate Capacity (kips) ———

Stroke (feet) - - - - -

Ohio River  
 HP 14 x 73 to rock

HC Nutting Company  
 BSB : 12/09/2010 : DWW  
 Ohio River HP 14x73 to rock

28-Feb-2011  
 GRLWEAP(TM) Version 1998-1

Ultimate Capacity kips	Maximum Compression Stress ksi	Maximum Tension Stress ksi	Blow Count bl/ft	Stroke feet	Energy kips-ft
200.0	25.032	0.215	17.7	5.22	24.51
250.0	28.832	0.344	22.9	5.52	24.55
300.0	32.532	1.001	27.8	5.90	25.71
350.0	35.052	1.543	34.6	6.09	26.05
400.0	38.483	2.929	40.9	6.58	27.81
450.0	40.642	3.482	50.9	6.83	28.55
500.0	43.390	4.238	61.3	7.29	30.25
550.0	44.975	4.779	78.5	7.52	30.93
600.0	47.248	5.149	97.4	7.93	32.37
650.0	48.492	5.524	128.2	8.14	33.25

$R_p \text{ max} = 530 \text{ kips}$

$Comp_{\text{max}} = 44.3 \text{ ksi}$

$Ten_{\text{max}} = 4.56 \text{ ksi}$

Blow Count = 71.6  $\frac{\text{bl}}{\text{ft}}$