Project: US 42 NoBuild
Scenario: AM Peak
Run(s): Batch (10 runs)
Simulated: Various
Time: 08:15:00 - 09:15:00
Interval: Summary
Selection: --

Intersection LOS - Overview

471 SB ON-RAMP, E LIBERTY ST & US 42 -- SIGNALIZED — NODE: 22

Run	Number of Vehicles	Total Control Delay (hr)	Avg Control Delay (sec/veh)	Level of Service
1	3,073.0	15.50	18.2	B
2	3,081.0	16.40	19.1	B
3	3,068.0	15.80	18.5	B
4	3,081.0	15.70	18.3	B
5	3,050.0	16.10	19.0	B
6	3,073.0	15.60	18.2	B
7	3,075.0	15.40	18.0	B
8	3,076.0	15.50	18.1	B
9	3,080.0	15.10	17.7	B
10	3,085.0	15.90	18.5	B
Average:	**3,074.2**	**15.70**	**18.4**	**B**

71 ON-RAMP, US 42, EDEN PARK DR & DORCHESTER AVENUE -- SIGNALIZED — NODE: 10

Run	Number of Vehicles	Total Control Delay (hr)	Avg Control Delay (sec/veh)	Level of Service
1	2,482.0	13.20	19.2	B
2	2,508.0	13.00	18.6	B
3	2,475.0	12.30	17.9	B
4	2,442.0	13.30	19.6	B
5	2,479.0	12.10	17.6	B
6	2,425.0	12.80	19.1	B
7	2,443.0	12.80	18.9	B
8	2,464.0	12.30	18.0	B
9	2,464.0	13.10	19.1	B
10	2,478.0	12.30	17.9	B
Average:	**2,466.0**	**12.72**	**18.6**	**B**

ELSINORE PL & US 42 -- SIGNALIZED — NODE: 18

Run	Number of Vehicles	Total Control Delay (hr)	Avg Control Delay (sec/veh)	Level of Service
1	2,590.0	5.60	7.8	A
2	2,586.0	5.30	7.4	A
3	2,592.0	5.50	7.6	A
4	2,589.0	5.40	7.6	A
5	2,585.0	5.40	7.6	A
6	2,578.0	5.10	7.1	A
7	2,579.0	5.50	7.7	A
8	2,587.0	5.40	7.5	A

9	2,584.0	5.20	7.2	A
10	2,579.0	5.20	7.3	A
Average:	**2,584.9**	**5.36**	**7.5**	**A**

Project: US 42 NoBuild
Scenario: AM Peak
Run(s): Batch (10 runs)
Simulated: Various
Time: 08:15:00 - 09:15:00
Interval: Summary
Selection: --

Intersection LOS - Total Control Delay

Node ID	Intersection	Control Type	Average	Std Dev	Minimum	Maximum	# Samples
22	471 SB On-Ramp, E Liberty St & US 42	Actuated	15.7	0.4	15.1	16.4	10
10	71 On-Ramp, US 42, Eden Park Dr & Dorchester Avenue	Actuated	12.7	0.4	12.1	13.3	10
18	Elsinore Pl & US 42	Actuated	5.4	0.2	5.1	5.6	10

Project: US 42 NoBuild
Scenario: AM Peak
Run(s): Batch (10 runs)
Simulated: Various
Time: 08:15:00 - 09:15:00
Interval: Summary
Selection: --

Intersection LOS - Avg Control Delay

Node ID	Intersection	Control Type	Average	Std Dev	Minimum	Maximum	# Samples
22	471 SB On-Ramp, E Liberty St & US 42	Actuated	18.4	0.4	17.7	19.1	10
10	71 On-Ramp, US 42, Eden Park Dr & Dorchester Avenue	Actuated	18.6	0.7	17.6	19.6	10
18	Elsinore Pl & US 42	Actuated	7.5	0.2	7.1	7.8	10