

J:\20110903\ODOT\HAM\77889\structures\WALL_00B\sheets\77889_00BE0001.dgn 5/22/2026 10:21:17 AM hbrendinger

ESTIMATED QUANTITIES (02/IMS/03)															SEE STRUCTURE SHEET NO.
WALL B	WALL C	WALL F	WALL G	WALL H	WALL HI	WALL I	WALL II			ITEM	ITEM EXT	TOTAL	UNIT	DESCRIPTION	
						LUMP	LUMP			202	11200		LUMP	PORTIONS OF STRUCTURE REMOVED	
5	1187	815	608		442		820			203	20000	3877	CU YD	EMBANKMENT	
	4791	1614	1384							203	35110	7789	CU YD	GRANULAR MATERIAL, TYPE B	
290					830		1348			203	35111	2468	CU YD	GRANULAR MATERIAL, TYPE B, AS PER PLAN	1/43
1	4	4	4	3	3	9	3			SPECIAL	20365000	31	EACH	SPECIAL - SETTLEMENT PLATFORM	2/43
LUMP	LUMP	LUMP	LUMP	LUMP	LUMP	LUMP	LUMP			503	11101		LUMP	COFFERDAMS AND EXCAVATION BRACING, AS PER PLAN	1/43
215	409	388	296	1045	246	4667	253			512	10101	7519	SQ YD	SEALING OF CONCRETE SURFACES (EPOXY-URETHANE), AS PER PLAN	1/43
34	274				204		240			516	13200	752	SQ FT	1/2" PREFORMED EXPANSION JOINT FILLER	
		247	225							516	13600	472	SQ FT	1" PREFORMED EXPANSION JOINT FILLER	
				12		12				516	13900	24	SQ FT	2" PREFORMED EXPANSION JOINT FILLER	
55				51						517	76300	106	FT	RAILING, MISC.: TRAFFIC BARRIER ON MSE WALL	1/43
				227		1128				517	80010	1355	FT	RAILING (COMBINATION NOISE AND TRAFFIC BARRIER ON MSE WALL WITH FLEXIBLE PAVEMENT)	1/43
7	56	37	33		52		51			601	21000	236	SQ YD	CONCRETE SLOPE PROTECTION	
	23									601	37500	23	FT	PAVED GUTTER, TYPE 1-2	
LUMP										SPECIAL	69098400		LUMP	SPECIAL - TEMPORARY SURCHARGE WALL B	1/43
	LUMP									SPECIAL	69098400		LUMP	SPECIAL - TEMPORARY SURCHARGE WALL C	1/43
		LUMP								SPECIAL	69098400		LUMP	SPECIAL - TEMPORARY SURCHARGE WALL F	1/43
			LUMP							SPECIAL	69098400		LUMP	SPECIAL - TEMPORARY SURCHARGE WALL G	1/43
					LUMP					SPECIAL	69098400		LUMP	SPECIAL - TEMPORARY SURCHARGE WALL HI	1/43
							LUMP			SPECIAL	69098400		LUMP	SPECIAL - TEMPORARY SURCHARGE WALL II	1/43
2082	4556	4235	3398	6300	4076	26,607	4172			840	20001	55,426	SQ FT	MECHANICALLY STABILIZED EARTH WALL, AS PER PLAN	1/43
835	10190	1387	1043	2104	2907	7463	2889			840	21000	28,818	CU YD	WALL EXCAVATION	
219		793	696	667		2778				840	22000	5153	SQ YD	FOUNDATION PREPARATION	
	1227				656		700			840	22001	2583	SQ YD	FOUNDATION PREPARATION, AS PER PLAN	1/43
796	9084	3276	2412	3744	3500	17,578	3800			840	23000	44,190	CU YD	SELECT GRANULAR BACKFILL	
	163	37	35		11		11			840	23050	257	CU YD	NATURAL SOIL	
230	792	625	575	848	472	2670	480			840	25010	6692	FT	6" DRAINAGE PIPE, PERFORATED	
3	85	10	11		240	20				840	25020	369	FT	6" DRAINAGE PIPE, NON-PERFORATED	
139	285	299	278	322	236	1173	237			840	26000	2969	FT	CONCRETE COPING	1/43
1805	3990	3647	2841	5671	3605	24,223	3703			840	26050	49,485	SQ FT	AESTHETIC SURFACE TREATMENT	1/43
1	1	1	1	1	1	3	3			840	27000	12	DAY	ON-SITE ASSISTANCE	
	LUMP									867	00100		LUMP	TEMPORARY WIRE FACED MECHANICALLY STABILIZED EARTH WALL (WALL C-1)	
	LUMP									867	00100		LUMP	TEMPORARY WIRE FACED MECHANICALLY STABILIZED EARTH WALL (WALL C-2)	
		LUMP								867	00100		LUMP	TEMPORARY WIRE FACED MECHANICALLY STABILIZED EARTH WALL (WALL F1)	
		LUMP								867	00100		LUMP	TEMPORARY WIRE FACED MECHANICALLY STABILIZED EARTH WALL (WALL F2)	
			LUMP							867	00100		LUMP	TEMPORARY WIRE FACED MECHANICALLY STABILIZED EARTH WALL (WALL G1)	
			LUMP							867	00100		LUMP	TEMPORARY WIRE FACED MECHANICALLY STABILIZED EARTH WALL (WALL G2)	
				LUMP						867	00100		LUMP	TEMPORARY WIRE FACED MECHANICALLY STABILIZED EARTH WALL (WALL HI-1)	
				LUMP						867	00100		LUMP	TEMPORARY WIRE FACED MECHANICALLY STABILIZED EARTH WALL (WALL HI-2)	
						LUMP				867	00100		LUMP	TEMPORARY WIRE FACED MECHANICALLY STABILIZED EARTH WALL (WALL II-1)	
						LUMP				867	00100		LUMP	TEMPORARY WIRE FACED MECHANICALLY STABILIZED EARTH WALL (WALL II-2)	

NOTE

1. SEE SHEET 2/43 FOR ABBREVIATION LEGEND.

HAM - 75 - 7.85
PID No. 121447

ESTIMATED QUANTITIES - MSE WALLS
MSE RETAINING WALL NUMBERS B, C, F, G, H, AND I

DESIGNED
RUE
CHECKED
RWW/TDA
DRAWN
GB
REVISED
-
REVIEWED
CAS
DATE
5-22-26
STRUCTURE FILE NUMBER

DESIGN AGENCY
EMH-T
Engineering, Mapping & Technology, Inc.
10000 Highway 100, Suite 100
Houston, Texas 77036
713.462.1100
www.emh-t.com

3 / 43

624
1047