

BRIDGE INSPECTION REPORT

2801388
Structure File Number

BRIDGE NUMBER **GEA 00322 0863**

YEAR BUILT **1961**

DIST **12** Bridge Type **395** TYPE SERVICE **1 5** **BEAVER CRK 1.77 MI. W 44**

DECK out/out 0 Deck Area 1,076 sqft			N NOT APPLICABLE (CULVERT UNDER FILL ETC)	
1. FLOOR	N NONE		2. WEARING SURFACE	Thk 0
Left N NONE / Right N NONE				
3. CURBS, SIDEWALKS AND WALKWAYS			4. MEDIAN	Lanes on 2
5. RAILING	N NONE		6. DRAINAGE	N NONE
7. EXPANSION JOINTS			8. SUMMARY	
SUPERSTRUCTURE			3 N/A (CULVERTS, TRUSSES, ETC.)	
9. ALIGNMENT	Max Spans 6		10. BEAMS/GIRDERS/SLAB	
11. DIAPHRAGMS or CROSSFRAMES			12. JOISTS/STRINGERS	
13. FLOOR BEAMS			14. FLOOR BEAM CONNECTIONS	
15. VERTICALS			16. DIAGONALS	
17. END POSTS			18. TOP CHORD	
19. LOWER CHORD			20. LOWER LATERAL BRACING	
21. TOP LATERAL BRACING			22. SWAY BRACING	
23. PORTALS			24. BEARING DEVICES N NONE	
25. ARCH			26. ARCH COLUMNS or HANGERS	
27. SPANDREL WALLS			28. PROTECTIVE COATING SYSTEM	
29. PINS/HANGERS/HINGES			30. FATIGUE PRONE CONNECTIONS	
31. LIVE LOAD RESPONSE			32. SUMMARY	
SUBSTRUCTURE			N NONE	
33. ABUTMENTS	N NONE		34. ABUTMENT SEATS Abutment: NOT ON PILING	
35. PIERS			36. PIER SEATS Piers: NOT ON PILING	
37. BACKWALLS			38. WINGWALLS	
39. FENDERS and DOLPHINS Piers = NN NN NN Spans = 3			40. SCOUR	
41. SLOPE PROTECTION N NONE-NATURAL PROTECTION(GRA			42. SUMMARY Dive Date 9/24/2007	
CULVERTS				
43. GENERAL	5 PIPE-ARCH	2	44. ALIGNMENT	
45. SHAPE		2	46. SEAMS	
47. HEADWALLS or ENDWALLS Culvert Length 18		2	48. SCOUR Culvert Fill Depth 0	
49.			50. SUMMARY	
CHANNEL				
51. ALIGNMENT		2	52. PROTECTION 0 OTHER-GRASS, BUSHES & TREES	
53. WATERWAY ADEQUACY 8 SLIGHT CHANCE OVERTOPPING		2	54. SUMMARY	
APPROACHES				
55. PAVEMENT	2 BITUMINOUS	2	56. APPROACH SLABS	
57. GUARDRAIL	1 STEEL BEAM	1	58. RELIEF JOINTS	
59. EMBANKMENT		2	60. SUMMARY Percent Legal = 150	
GENERAL				
61. NAVIGATION LIGHTS			62. WARNING SIGNS Maint Resp 1 OHIO TRAN DEPT	
63. SIGN SUPPORTS Signs on = N MVC on = 9999.9 Under C = 0			64. UTILITIES	
65. VERTICAL CLEARANCE Under NC = 0		N	66. GENERAL APPRAISAL & OPERATIONAL STATUS	
67. INSPECTED BY			68. REVIEWED BY	

70223 AWH
SIGNED PE Number INITIALS SIGNED PE Number INITIALS

DATE 11/8/2010

NN1N1NNN
SURVEY

DATE

5 A

CULVERTS

GENERAL: RUSTING SECTION LOSS TO AREAS OF THE INVERT AND
OTHER AREAS BELOW WATER LINE.

SHAPE: WEST CELL APPROX 10' IN FROM INLET THERE IS A 8"
DIAMETER BULGE AT 10 O'CLOCK. BULGE IS NOT UNDER
TRAFFIC. EAST CELL APPROX 12' IN FROM INLET THERE IS
A 4" DIAMETER BULGE AT 10 O'CLOCK.

SEAMS: WATER INFILTRATION. SOME RUSTING SECTION LOSS. A FEW
AREAS OF CUSPING AS MUCH AS 1/8".

HEADWALLS: CRACKS AND SPALLS.

CHANNEL

ALIGNMENT: STREAM LINES UP WITH WESTERN 2 PIPES. LITTLE OR
NO FLOW.

WATERWAY ADEQUACY: 1.5' CLEARANCE BETWEEN WATER AND TOP OF
PIPE. 2" OF SEDIMENT ON AVERAGE IN ALL PIPES.

APPROACHES

PAVEMENT: TRANSVERSE CRACKS AT LIMITS OF EACH PIPE.
DIP IN PAVEMENT 10' WEST OF PIPES.

EMBANKMENT: MINOR EROSION AROUND INLET AND OUTLET. SLIGHT
EROSION HOLE AT OUTLET BETWEEN WEST CELL AND MIDDLE CELL.

GENERAL


LAST DIVE INSPECTION IN 2007. (REPORT IS ATTACHED TO THIS
FILE).

LOOK THROUGH INSPECTION WITH KB.



2011 LOCATION

UPDATED 2011 AWH



Hydrographic reference – Water surface 1.8' below top of pipe 3 to the water surface.

Legend

- Depth 8.0' below water
- ▣ Tree Debris



MSI MARINE SOLUTIONS, INC.
ENGINEERING & COMMERCIAL DIVING SERVICES

GRAPHIC SCALE: Not to Scale	
INSPECTION DATE: October 24, 2007	
DRAWN BY: DW	CKD. BY: ANW
FMSM JOB NO.: MSI2007008	
FILE NAME: GEA-00322-0863	

PROJECT: ODOT District 12 2007 Underwater Bridge Inspections	
SHEET: GEA-00322-0863 US 322 (Mayfield Rd) over Beaver Creek Geauga County	
Substructure Plan View	
PAGE NO.:	B-2
FIG. NO.:	2

2801388

Structural File Number

GEA-00322-0863

Bridge Number

September 24, 2007

Inspection Date

Underwater Inspection Report for:

US 322 (Mayfield Road) over Beaver Creek
Geauga County, Ohio
(Three cell culvert)



General Elevation View

Personnel on site during inspection:

ODOT

Ms. Andrea Persanyi

Contractor

Mr. Don W. Wilkins (Primary Diver/ Supervisor)

Mr. James A. Ritchie (Backup Diver/ Inspector)

Mr. Brian B. Butler (Tender)

Prepared for:

ODOT District 12

5500 Transportation Blvd

Garfield Heights, Ohio 44125

Prepared by:



Marine Solutions, Inc.

250 Gold Rush Drive, Suite 4

Lexington, Kentucky 40503

Phone: (859) 260-1055

awilkins@MSIdiving.com

2801388

Structural File Number

GEA-00322-0863

Bridge Number

September 24, 2007

Inspection Date

Table of Contents

Section	Page No.
1. Introduction.....	1
2. Description of Structure	1
3. Inspection Procedure.....	1
4. Observed Conditions	1
5. Conclusions.....	2

List of Appendixes

Appendix

Appendix A Photographs

Appendix B Figures

1. Introduction

Marine Solutions, Inc (MSI) conducted a routine underwater inspection of the GEA-00322-0863 culvert over Beaver Creek in Claridon Township, Ohio. The inspection was completed on September 24, 2007. Details of the inspection, along with observed conditions and conclusions, are provided within this report. Supplemental drawings, pictures and a location map are provided within the Appendixes.

2. Description of Structure

Culvert Number GEA-00322-0863 (SFN 2801388) carries U.S. Route 322 (Mayfield Road) over Beaver Creek in Geauga County, Ohio. The culvert has an overall length of approximately 72 feet. The structure consists of three cell corrugated metal pipe arch culvert measuring approximately 6 feet wide by 4 feet 9 inches tall.

3. Inspection Procedure

The culvert inspection was performed on 9/24/07. A visual/tactile inspection was performed on the portions of the culvert located below the water surface. Original plans were not available for review.

Inspection Mode: *Wading*

Flow Direction / Velocity: *North/ < 1 knot*

Channel Bottom: *Corrugated steel pipe with silt and light debris*

Scour Checked By: *N/A*

Equipment Used: *Wet suit, digital camera, survey rod, lights*

Hazards Encountered: *< 2 ft of visibility*

Hydrographic Reference: *Top of footing, 5.1 ft below the water surface*

4. Observed Conditions

- There is light to moderate corrosion of the culvert pipes with no holes or section loss.
- The bottom material consists of the steel pipe with silt and light debris.
- There is an indentation in the top of barrel 1 measuring approximately 8 inches tall by 3 inches deep located 8.5 feet north of the south entrance of the barrel.
- There is an indentation in the top of barrel 3 measuring approximately 8 inches tall by 3 inches deep located 13.5 feet north of the south entrance of the barrel.
- There is light tree debris at the south entrance of barrel 2.
- There is a boulder measuring 2 feet in diameter located 2 feet south of the entrance to barrel 1.
- There is minor surface corrosion on the culvert joint bolt heads located throughout the three culvert pipes.

2801388

Structural File Number

GEA-00322-0863

Bridge Number

September 24, 2007

Inspection Date

- There is an area of tree debris located on the northwest face of the pier.
- There is minor surface corrosion on the sides of the steel pipe from 1 foot below the surface to 1 foot above the water surface.
- There is minor surface corrosion of the steel culvert roof. There are isolated water seepage through the top of the culvert pipe.

5. Conclusions

The condition of the culvert during the 2007 inspection was consistent with the findings of the 2006 inspection.

2801388
Structural File Number

GEA-00322-0863
Bridge Number

September 24, 2007
Inspection Date



Photo by B. Butler 09/24/07

Photo 1. Elevation view looking North to South.



Photo by B. Butler 09/24/07

Photo 2. Elevation view looking South to North.



Photo by B. Butler 09/24/07

Photo 3. Indention in pipe number 1.



Photo by B. Butler 09/24/07

Photo 4. Indention in pipe number 3.





Photo by B. Butler 09/24/07

Photo 5. Typical surface corrosion from water surface to 1 ft above.



Photo by B. Butler 09/24/07

Photo 6. Typical surface corrosion on roof of culvert.



Legend

- Depth 8.0' below water
- ▣ Tree Debris



MSI MARINE SOLUTIONS, INC.
ENGINEERING & COMMERCIAL DIVING SERVICES

GRAPHIC SCALE: Not to Scale	
INSPECTION DATE: October 24, 2007	
DRAWN BY: DW	CKD. BY: ANW
FMSM JOB NO.: MSI2007008	
FILE NAME: GEA-00322-0863	

PROJECT: ODOT District 12 2007 Underwater Bridge Inspections	
SHEET: GEA-00322-0863 US 322 (Mayfield Rd) over Beaver Creek Geauga County	
PAGE NO.: B-2	
FIG. NO.: 2	
Substructure Plan View	