DRAINAGE

** 707.41 Non-Perforated ASTM D3034, SDR 35, 707.42 or 707.33

REF. NO.	STATION FROM	STATION TO	SIDE	603 6" Conduit, Type F **	603 15" Conduit, Type C	604 Catch Basin, No. 4 With E-Grate, A.P.P.	604 6" Shallow Pipe U.D. w/Fabric Wrap (18" Deep)	605 6" Shallow Pipe U.D. (30" Deep)	605 6" Shallow Pipe U.D. w/Fabric Wrap (30" Deep)	605 6" Unclassified Underdrain w/Fabric Wrap	605 6" Unclassified Underdrain	670 Ditch Erosion Protection	604 Precast Reinforced Concrete Outlet
				Lin.Ft.	Lin.Ft.	Each	Lin.Ft.	Lin.Ft.	Lin.Ft.	Lin.Ft.	Lin.Ft.	Sq.Yd.	Each
U-1	500+00	515+00	Lt.	60					1500	44			4
U-2	500+00	515+00	Lt.	30				1500			26		
U-3	500+00	515+00	Lt.				1500						
U-4	500+00	515+00	Rt.				1500						
U-5	500+00	515+00	Rt.	30				1500			26		
U-6	500+00	515+00	Rt.	60					1500	44			4
D-1	496+50	500+98	℄		448	1						125	
D-2	500+98	500+98	℄			1						125	
		TOTALS		180	448	2	3000	3000	3000	88	52	250	8

ROADWAY

REF. NO.	STATION FROM	STATION TO	SIDE	202 Guardrail Removed	202 Fence Removed	203 Ditch Cleanout	Special Pipe Cleanout
				Lin.Ft.	Lin.Ft.	Lin.Ft.	Lin.Ft.
R-1	500+00	515+00	Rt.		1505		
R-2	500+00	515+00	Lt.		1539		
R-4	503+00	505+56	Rt.	256			
D-3	501+29	505+07	Lt.			380	
D-4	500+45	505+13	Rt.			465	
D-5	505+20	505+20	Rt./Lt.				213
D-6	513+99	514+98	Rt.			100	
	TOTALS			256	3044	945	213

FENCE

REF. NO.	STATION FROM	STATION TO	SIDE	607 Fence, Type CLT
				Lin.Ft.
F-1	500+00	515+00	Rt.	1505
F-2	500+00	515+00	Lt.	1539
	TOTALS			3044

PLAN & PROFILE QUANTITIES STA. 500+00 TO STA. 515+00

PLOT SUBMITTED:31-JUL-1998 08:00
307qu02.dgn
PLOTTED BY:fkonopka
PLOTTED:FROM: Defaultsbrb$pid08459$dgn:[]307qu02.dgn