DRAINAGE

** 707.41 Non-Perforated ASTM D3034, SDR 35, 707.42 or 707.33

REF. NO.	STATION FROM	STATION TO	SIDE	603 6" Conduit, Type F **	603	603	603	604 Catch Basin, No. 4 with E-Grate, As Per Plan	604	605 6" Shallow Pipe U.D. w/Fabric Wrap (18" Deep)	605 6" Shallow Pipe U.D. (30" Deep)	605 6" Shallow Pipe U.D. w/Fabric Wrap (30" Deep)	605 6" Unclassified Underdrain w/Fabric Wrap	605 6" Unclassified Underdrain	670 Ditch Erosion Protection	604 Precast Reinforced Concrete Outlet
				Lin.Ft.				Each		Lin.Ft.	Lin.Ft.	Lin.Ft.	Lin.Ft.	Lin.Ft.	Sq.Yd.	Each
U-1	545+00	560+00	Lt.	75								1491	33			3
U-2	545+00	560+00	Lt.	15							1491			13		
U-3	545+00	560+00	Lt.							1491						
U-4	545+00	560+00	Rt.							1491						
U-5	545+00	560+00	Rt.	15							1491			13		
U-6	545+00	560+00	Rt.	85								1491	33			3
D-4	552+45	553+00	℄					1							125	
D-7	548+00	552+45	℄												371	
TOTALS				190				1		2982	2982	2982	66	26	496	6

ROADWAY

REF. NO.	STATION FROM	STATION TO	SIDE	202 Guardrail Removed	202 Fence Removed	202	202	203 Ditch Cleanout	Special Pipe Cleanout
				Lin.Ft.	Lin.Ft.			Lin.Ft.	Lin.Ft.
R-1	545+00	545+19.45Bk.	Rt.	19.5					
R-2	545+00	545+19.45Bk.	Lt.	19.5					
R-3	545+00	545+19.45Bk.	Rt.		20				
R-4	545+00	545+19.45Bk.	Lt.		20				
R-5	545+28.30Ah.	560+00	Rt.	1471.7					
R-6	545+28.30Ah.	560+00	Lt.	1471.7					
R-7	545+28.30Ah.	560+00	Rt.		1472				
R-8	545+28.30Ah.	560+00	Lt.		1473				
D-1	545+00	548+00	Lt.					291	
D-2	546+11	547+23	Lt./Rt.						268
D-3	546+93	553+43	Rt.					650	
D-5	556+72	556+72	Lt./Rt.						216
D-6	556+72	556+72	Rt.					53	
TOTALS				2983	2985			994	484

GUARDRAIL

REF. NO.	STATION FROM	STATION TO	SIDE	606 Guardrail, Type 5	448 3" Asphalt Conc. Intermediate Course Type 1, PG 64-22
				Lin.Ft.	Cu.Yd.
GR-1	545+00	560+00	Lt.	1500	55.56
GR-2	545+00	560+00	Rt.	1500	55.56
TOTALS				3000	111.1

NOTE: Station Equation - Sta. 545+19.45 Back = Sta. 545+28.30 Ahead

FENCE

REF. NO.	STATION FROM	STATION TO	SIDE	607 Fence, Type CLT
				Lin.Ft.
F-1	545+00	545+19.45Bk.	Rt.	20
F-2	545+00	545+19.45Bk.	Lt.	20
F-3	545+28.30Ah.	560+00	Rt.	1472
F-4	545+28.30Ah.	560+00	Lt.	1473
TOTALS				2985

PLOT SUBMITTED:07-AUG-1998 09:08
307qu05.dgn
PLOTTED BY:fkonopka
PLOTTED:Fri Mar 06 Reformersberg Bpid08459 Bdgn 307qu05.dgn