

** 707.41 Non-Perforated ASTM D3034,
SDR 35, 707.42 or 707.33

DRAINAGE														
REF. NO.	STATION		SIDE	603		604		605				670	604	
				6" Conduit, Type F ##		Catch Basin, No. 4 with E-Grate, As Per Plan		6" Shallow Pipe U.D. w/Fabric Wrap (18" Deep)	6" Shallow Pipe U.D. (30" Deep)	6" Shallow Pipe U.D. w/Fabric Wrap (30" Deep)	6" Unclassified Underdrain w/Fabric Wrap	6" Unclassified Underdrain	Ditch Erosion Protection	Precast Reinforced Concrete Outlet
	FROM	TO		Lin.Ft.	Each		Lin.Ft.	Lin.Ft.	Lin.Ft.	Lin.Ft.	Sq.Yd.	Each		
U-1	560+00	575+00	Lt.	40								3		
U-2	560+00	575+00	Lt.	15				1500			13			
U-3	560+00	575+00	Rt.					1500						
U-4	560+00	575+00	Rt.					1500						
U-5	560+00	575+00	Lt.	15						13				
U-6	560+00	575+00	Rt.	50					1500	33		3		
TOTALS				120		1		3000	3000	3000	66	26	580	6
D-1	565+45	567+00	℄			1					125			
D-3	560+00	565+45	℄								455			

ROADWAY							
REF. NO.	STATION		SIDE	202			203
				Guardrail Removed	Fence Removed		Ditch Cleanout
	FROM	TO	Lin.Ft.	Lin.Ft.			Lin.Ft.
R-1	560+00	568+18.5	Rt.	818.5			
R-2	560+00	566+27	Lt.	627			
R-3	560+00	575+00	Rt.		1543		
R-4	560+00	575+00	Lt.		1567		
TOTALS				1445.5	3110		200

GUARDRAIL							
REF. NO.	STATION		SIDE	606			448
				Guardrail, Type 5	Anchor Assembly, Type E-98	Anchor Assembly, Type T	3" Asphalt Concrete Intermed Course, Type 1, PG 64-22
	FROM	TO	Lin.Ft.	Each	Each	Cu.Yd.	
GR-1	560+00	567+50.55	Rt.	738.05		1	27.80
GR-2	560+00	568+25.85	Lt.	775.85	1		31.28
TOTALS				1513.9	1	1	59.1

FENCE				
REF. NO.	STATION		SIDE	607
				Fence, Type CLT
	FROM	TO		Lin.Ft.
F-1	560+00	575+00	Rt.	1543
F-2	560+00	575+00	Lt.	1567
TOTALS				3110

PLOTTED BY: jmincek
 PLOTTED IN: 08/19/98
 PLOT SUBMITTED: 05-AUG-1998 11:43
 307qu06.dgn