CUY-71-0.00	OHIO
	FHWA REGION 5
	FEDERAL PROJECT

93
361

707.41 Non-Perforated ASTM D3034, SDR 35, 707.42 or 707.33

DRAINAGE

REF. NO.	STATION FROM	STATION TO	SIDE	603 6" Conduit, Type F ## Lin.Ft.	603	603	604 Catch Basin, No. 4 with E-Grate, As Per Plan Each	604	605 6" Shallow Pipe U.D. w/Fabric Wrap (18" Deep) Lin.Ft.	605 6" Shallow Pipe U.D. (30" Deep) Lin.Ft.	605 6" Shallow Pipe U.D. w/Fabric Wrap (30" Deep) Lin.Ft.	605 6" Unclassified Underdrain w/Fabric Wrap Lin.Ft.	605 6" Unclassified Underdrain Lin.Ft.	670 Ditch Erosion Protection Sq.Yd.	604 Precast Reinforced Concrete Outlet Each
U-1	575+00	590+00	Lt.	30							1500	33			3
U-2	575+00	590+00	Lt.	15						1500			13		
U-3	575+00	590+00	Lt.						1500						
U-4	575+00	590+00	Rt.						1500						
U-5	575+00	590+00	Rt.	15						1500			13		
U-6	575+00	590+00	Rt.	30							1500	33			3
D-1	574+00	580+45	℄											538	
D-2	580+45	582+00	℄				1							125	
TOTALS				90			1		3000	3000	3000	66	26	663	6

ROADWAY

REF. NO.	STATION FROM	STATION TO	SIDE	202 Guardrail Removed Lin.Ft.	202 Fence Removed Lin.Ft.	202 Catch Basin or Inlet Removed Each	203 Ditch Cleanout Lin.Ft.	Special Pipe Cleanout Lin.Ft.
R-1	575+00	590+00	Rt.		1518			
R-2	575+00	590+00	Lt.		1484			
R-3	579+74	583+86	Rt.	412				
R-4	582+00	582+00	℄			1		
R-5	587+48	590+00	Rt.	252				
D-3	581+68	582+18	Rt.				50	
D-4	589+00	590+00	Rt.				100	
D-5	588+15	589+92	Lt./Rt.					284
TOTALS				664	3002	1	150	284

GUARDRAIL

REF. NO.	STATION FROM	STATION TO	SIDE	606 Guardrail, Type 5 Lin.Ft.	606 Anchor Assembly, Type E-98 Each	448 3" Asphalt Conc. Intermediate Course Type 1, PG 64-22 Cu.Yd
GR-1	579+34	590+00	Rt.	1016	1	40.18
TOTALS				1016	1	40.2

FENCE

REF. NO.	STATION FROM	STATION TO	SIDE	607 Fence, Type CLT Lin.Ft.
F-1	575+00	590+00	Rt.	1518
F-2	575+00	590+00	Lt.	1484
TOTALS				3002

PLAN & PROFILE QUANTITIES STA. 575+00 TO STA. 590+00

PLOT SUBMITTED:05-AUG-1998 11:45
307qu07.dgn
PLOTTED BY: lmincek
PLOTTED FROM: c:\projects\reforsberg\pid08459\dgn\307qu07.dgn