

## 707.41 Non-Perforated ASTM D3034,  
SDR 35, 707.42 or 707.33

REF. NO.	STATION		SIDE	DRAINAGE									
				603		604		605				670	604
				6" Conduit, Type F ##		Catch Basin, No. 4 With E-Grate, As Per Plan	6" Shallow Pipe U.D. w/Fabric Wrap (18" Deep)	6" Shallow Pipe U.D. (30" Deep)	6" Shallow Pipe U.D. w/Fabric Wrap (30" Deep)	6" Unclassified Underdrain w/Fabric Wrap	6" Unclassified Underdrain	Ditch Erosion Protection	Precast Reinforced Concrete Outlet
FROM	TO	Lin.Ft.	Each	Lin.Ft.	Lin.Ft.	Lin.Ft.	Lin.Ft.	Lin.Ft.	Sq.Yd.	Each			
U-1	590+00	605+00	Lt.	55									
U-2	590+00	605+00	Lt.	15			1500				13		
U-3	590+00	605+00	Lt.			1500							
U-4	590+00	605+00	Rt.			1500							
U-5	590+00	605+00	Rt.	15			1500				13		
U-6	590+00	605+00	Rt.	95				1500	33			3	
TOTALS				180	1	3000	3000	3000	66	26	661	6	
D-2	589+00	595+43	℄								536		
D-3	595+43	596+98	℄		1						125		

REF. NO.	STATION		SIDE	ROADWAY				
				202		203		
				Guardrail Removed	Fence Removed			Ditch Cleanout
FROM	TO	Lin.Ft.	Lin.Ft.			Lin.Ft.		
R-1	590+00	605+00	Rt.	1510				
R-2	590+00	605+00	Rt.		1529			
R-3	590+00	605+00	Lt.		1484			
R-5	595+99	605+00	Lt.	895				
D-1	590+00	590+35	Rt.					35
D-4	597+05	599+55	Rt.					250
TOTALS				2405	3013			285

REF. NO.	STATION		SIDE	GUARDRAIL				
				606		448	203	
				Guardrail, Type 5	Anchor Assembly, Type E-98	Anchor Assembly, Type T	3" Asphalt Conc. Intermediate Course, Type I, PG 64-22	Linear Grading, As Per Plan
FROM	TO	Lin.Ft.	Each	Each	Cu.Yd.	Lin.Ft.		
GR-1	590+00	605+00	Rt.	1500			55.56	
GR-2	596+50	605+00	Lt.	837.5	1	1	31.02	
GR-3	597+40	598+65	Rt.	62.5	1	1	5.32	125
GR-4	601+90	603+15	Rt.	62.5	1	1	5.32	125
TOTALS				2462.5	2	3	97.2	250 2.5 Stas.

REF. NO.	STATION		SIDE	607
				Fence, Type CLT
				Lin.Ft.
F-1	590+00	605+00	Rt.	1529
F-2	590+00	605+00	Lt.	1484
TOTALS				3013

PLOTTED BY: lmi ncek  
 PLOTTED IN: 08/08/2008 10:44:44  
 PLOT SUBMITTED: 05-AUG-1998 11:48  
 307qu08.dgn  
 307qu08.dgn  
 pi d08459ddgn307qu08.dgn