

** 707.41 Non-Perforated ASTM D3034,
SDR 35, 707.42 or 707.33

DRAINAGE														
REF. NO.	STATION		SIDE	603		604		605					670	604
				6" Conduit, Type F ##		Catch Basin, No. 4 with E-Grate As Per Plan		6" Shallow Pipe U.D. w/Fabric Wrap (18" Deep)	6" Shallow Pipe U.D. (30" Deep)	6" Shallow Pipe U.D. w/Fabric Wrap (30" Deep)	6" Unclassified Underdrain w/Fabric Wrap	6" Unclassified Underdrain	Ditch Erosion Protection	Precast Reinforced Concrete Outlet
	FROM	TO	Lin.Ft.	Each	Lin.Ft.	Lin.Ft.	Lin.Ft.	Lin.Ft.	Lin.Ft.	Lin.Ft.	Sq.Yd.	Each		
U-1	605+00	610+00	Lt.	25								1		
U-2	605+00	620+00	Lt.	15			1500							
U-3	605+00	620+00	Lt.			1500								
U-4	605+00	620+00	Rt.			1500								
U-5	607+02	620+00	Rt.	15			1500					13		
U-6	605+00	611+00	Rt.	50				600	22			2		
U-7	609+47	620+00	Lt.	10				1053	11			1		
U-8	608+45	620+00	Rt.	20				1155	11					
TOTALS				135	1	3000	3000	3308	55	26	938	4		
D-1	610+44	611+99	ℓ		1						125			
D-3	600+50	610+25	ℓ								813			

ROADWAY							
REF. NO.	STATION		SIDE	202			
				Guardrail Removed	Fence Removed	Pipe Removed, 24" And Under	Catch Basin or Inlet Removed
	FROM	TO	Rt.	Lin.Ft.	Lin.Ft.	Lin.Ft.	Each
R-1	605+00	614+64	Rt.	992			
R-2	605+00	612+05	Lt.	700			
R-3	605+00	608+94	Rt.		457		
R-4	611+99	611+99	ℓ			8	1
R-5	605+00	615+00	Lt.		1123		
TOTALS				1692	1580	8	1

GUARDRAIL									
REF. NO.	STATION		SIDE	606		448	203		
				Guardrail, Type 5	Anchor Assembly, Type E-98	Anchor Assembly, Type T	3" Asphalt Conc. Intermediate Course Type I, PG 64-22	Linear Grading, As Per Plan	
	FROM	TO	Lin.Ft.	Each	Each	Cu.Yd.	Lin.Ft.		
GR-1	605+00	614+64	Rt.	975	1	36.11			
GR-2	605+00	613+25	Lt.	775	1	31.24			
GR-3	606+40	612+40	Rt.	537.5	1	22.92	600		
TOTALS				2287.5	2	90.3	600		

FENCE				
REF. NO.	STATION		SIDE	607
				Fence, Type CLT
	FROM	TO	Rt.	Lin.Ft.
F-1	605+00	608+94	Rt.	457
F-2	605+00	615+00	Lt.	1123
TOTALS				1580

PLOTTED BY: lmincek
 PLOTTED IN: 307qu09.dgn
 PLOT SUBMITTED: 05-AUG-1998 11:49
 307qu09.dgn