

** 707.41 Non-Perforated ASTM D3034,
SDR 35, 707.42 or 707.33

REF. NO.	STATION		SIDE	DRAINAGE														
				603			604			605					670	604		
				6" Conduit, Type F #	15" Conduit, Type C	21" Conduit, Type B	Catch Basin, No. 2-2B, A.P.P.	Catch Basin, No. 4 with F. Grate, As Per Plan	Catch Basin, No. 6	Junction Chamber, Type 1, As Per Plan	Catch Basin Reconstructed To Grade	6" Shallow Pipe U.D. w/Fabric Wrap (18" Deep)	6" Shallow Pipe U.D. (30" Deep)	6" Shallow Pipe U.D. w/Fabric Wrap (30" Deep)	6" Unclassified Underdrain w/Fabric Wrap	6" Unclassified Underdrain	Ditch Erosion Protection	Precast Reinforced Concrete Outlet
FROM	TO	LT.	Each	Each	Each	Each	Each	Lin.Ft.	Lin.Ft.	Lin.Ft.	Lin.Ft.	Lin.Ft.	S.Y.	Each				
U-1	620+00	622+10	Lt.	10														
U-2	620+00	635+00	Lt.	30								1500			26			
U-3	620+00	635+00	Lt.									1500						
U-4	620+00	635+00	Rt.									1500						
U-5	620+00	635+00	Rt.	30								1500			26			
U-6	620+00	622+70	Rt.	10									270					
U-7	620+00	635+00	Rt.	20									1500	22		1		
U-8	621+00	626+00	Rt.									500						
U-10	622+09	624+50	Lt.											241				
U-11	622+00	635+00	Lt.	10										1300	11	1		
U-12	632+00	635+00	Rt.											300				
D-1	620+60	622+15	℄			55	1								125			
D-2	622+08.83	622+08.83	78' Lt.												1			
D-3	622+74.24	622+74.24	74' Rt.					1										
D-4	622+68.19	622+68.19	10' Rt.						1									
D-5	625+42	626+97	℄				1								162			
D-6	622+68	622+99	3' Rt.		30													
D-7	626+97	626+97	Rt.												75			
D-8	611+99	620+60	℄												733			
TOTALS				110	30	55	1	2	1	1	1	3500	3000	3821	33	52	1095	2

REF. NO.	STATION		SIDE	ROADWAY			
				202			
				Guardrail Removed	Fence Removed	Catch Basin or Inlet Removed	Pipe Removed, 24" And Under
FROM	TO	LT.	Lin.Ft.	Lin.Ft.	Each	Lin.Ft.	
R-1	621+00	622+68	℄				
R-2	621+50	623+96.5	Rt.	246.5			165
R-3	622+45	624+40	Lt./Rt.	390			
R-4	623+05	625+95.5	Lt.	290.5			
R-6	631+00	635+00	Rt.		506		
R-7	128+02	129+83	Rt.	181			
TOTALS				1108	506	1	165

REF. NO.	STATION		SIDE	FENCE
				607
				Fence, Type CLT
FROM	TO	LT.	Lin.Ft.	
F-1	631+00	635+00	Rt.	506
TOTALS				506

REF. NO.	STATION		SIDE	GUARDRAIL										
				606										
				Guardrail, Type 5	Anchor Assembly, Type E-98	Anchor Assembly, Type T	Bridge Terminal Assembly, Type I	Guardrail, Type 5A	Guardrail, Barrier Design, Type 5	Impact Attenuator, Type I-98	Concrete Barrier, Type D, As Per Plan A	3" Asphalt Conc. Intermediate Course Type 1, P6 64-22	203	
FROM	TO	LT.	Lin.Ft.	Each	Each	Each	Lin.Ft.	Lin.Ft.	Each	Lin.Ft.	Cu.Yd.	Lin. Ft.		
GR-1	620+20	623+95	Rt.	312.5	1	1						14.58	375	
GR-2	621+52.75	623+71	Rt.	56.25	1		1					4.63		
GR-3	622+93.5	624+43.5	Lt.			1		87.5	50	1		7.5	181.5	
GR-4	623+17.34	626+35.49	Lt.	156.25	1		1					8.33		
GR-5	126+87.5	130+00	Rt.	250	1	1						12.27		
TOTALS				775	4	3	2	87.5	50	1	228	47.3	556.5	5.6 Stds.

PLOTTED BY: fkonopka
 PLOTTED IN: 08/19/98
 PLOT SUBMITTED: 07-AUG-1998 09:11
 307QU10.DGN
 307QU10.dgn