

** 707.41 Non-Perforated ASTM D3034,
SDR 35, 707.42 or 707.33

CUY-71-0.00

OHIO
FHWA REGION 5
FEDERAL PROJECT

103
361

PLOT SUBMITTED:05 -AUG- 1998 11:53

307QU12.DGN

PLOTTED BY: lmi ncek
PLOTTED: 08/05/98 10:59 AM

REF. NO.	STATION		SIDE	DRAINAGE														
				603			604		605				660	670	838	604		
				6" Conduit, Type F #	15" Conduit, Type B	15" Conduit, Type C	Catch Basin, No. 4 with E-Grate, As Per Plan	Manhole, No. 3	6" Shallow Pipe U.D. w/Fabric Wrap (18" Deep)	6" Shallow Pipe U.D. (30" Deep)	6" Shallow Pipe U.D. w/Fabric Wrap (30" Deep)	6" Unclassified Underdrain w/Fabric Wrap	6" Unclassified Underdrain	Reinforced Sodding	Ditch Erosion Protection	Gabions with Additional Coating	Precast Reinforced Concrete Outlet	
FROM	TO	LT.	Lin.Ft.	Lin.Ft.	Lin.Ft.	Each	Each	Lin.Ft.	Lin.Ft.	Lin.Ft.	Lin.Ft.	Sq.Yd.	Sq.Yd.	Cu.Yd.	Each			
U-1	650+00	658+37	Lt.	20														
U-2	650+00	658+37	Lt.	30						837								
U-3	650+00	658+37	Lt.							837								
U-4	650+00	658+37	Rt.							837								
U-5	650+00	658+37	Rt.	30						837								
U-6	650+00	658+37	Rt.	25							837	22					2	
U-7	658+37	662+57	Lt.							420								
U-8	658+37	662+76	Lt.								439							
U-9	658+37	662+61	Lt.	15							424			13				
U-10	658+37	662+34	Lt.							397								
U-11	658+37	662+18	Rt.							381								
U-12	658+37	662+39	Rt.	15							402			13				
U-13	658+37	662+23	Rt.								386							
U-14	658+37	661+96	Rt.							359								
D-2	651+95	653+50	℄				1										125	
D-3	653+50	654+50	℄		100			1									250	
D-4	654+50	659+92	℄			387	1										79	
D-5	651+00	651+95	℄															
D-6	662+30	662+30	Lt.										53.3			3.3		
D-7	661+70	661+70	Rt.										37.2			3.3		
TOTALS				135	100	387	2	1	3231	2500	2499	44	78	90.5	454	7	4	

REF. NO.	STATION		SIDE	ROADWAY				
				202			203	
				Guardrail Removed	Fence Removed	Catch Basin or Inlet Removed	Pipe Removed, 24" And Under	Ditch Cleanout
FROM	TO	LT.	Lin.Ft.	Lin.Ft.	Each	Lin.Ft.	Lin.Ft.	
R-1	650+00	662+28	Rt.		1390			
R-2	650+00	662+88	Lt.		1478			
R-3	657+38	657+38	3' Lt.			1	96	
R-4	658+37	658+37	3' Rt.			1		
R-5	657+91	662+09	Rt.	418				
R-6	658+36	662+73	Lt.	437				
R-7	659+97	662+29	Rt.	237				
R-8	662+58	662+58	Lt./Rt.		76			
D-1	650+20	650+50	Lt.					35
TOTALS				1092	2944	2	96	35

REF. NO.	STATION		SIDE	607	
				Fence, Type CLT	Gate, Type CL, As Per Plan
				Lin.Ft.	Each
FROM	TO	LT.	Lin.Ft.	Each	
F-1	650+00	662+28	Rt.	1383	
F-2	650+00	662+88	Lt.	1469	
F-3	662+58	662+58	Lt./Rt.	22	1
TOTALS				2874	1

REF. NO.	STATION		SIDE	GUARDRAIL							
				606					448	203	
				Guardrail, Type 5	Anchor Assembly, Type E-98	Anchor Assembly, Type T	Bridge Terminal, Assembly, Type 1	Bridge Terminal, Assembly, Type 2	3" Asphalt Conc. Intermediate Course Type 1, PG 64-22	Linear Grading, As Per Plan	
FROM	TO	LT.	Lin.Ft.	Each	Each	Each	Each	Cu.Yd.	Lin. Ft.		
GR-1	650+25	651+50	Rt.	62.5	1	1			5.32	125	
GR-2	655+25	656+50	Rt.	62.5	1	1			5.32	125	
GR-3	655+56.21	661+99.96	Rt.	593.75	1		1		24.54		
GR-4	658+23.77	662+61.27	Lt.	425	1	1	1		16.20		
GR-5	659+56.26	662+25.01	Rt.	218.75	1		1		10.73	268.75	
TOTALS				1325	4	3	2	1	62.1	518.75	5.2 Stas.