

707.41 Non-Perforated ASTM D3034,
SDR 35, 707.42 or 707.33

DRAINAGE																
REF. NO.	STATION	SIDE	603		604		605				660	670	838	604		
			6" Conduit, Type F ##		Catch Basin, No. 44 with E-Grade, As Per Plan	Catch Basin Reconstructed to Grade	6" Shallow Pipe U.D. w/Fabric Wrap (18" Deep)	6" Shallow Pipe U.D. (30" Deep)	6" Shallow Pipe U.D. w/Fabric Wrap (30" Deep)	6" Unclassified Underdrain w/Fabric Wrap	6" Unclassified Underdrain	Reinforced Sodding	Ditch Erosion Protection	Gabions with Additional Coatings	Precast Reinforced Concrete Outlet	
	FROM	TO	Lin.Ft.		Each	Each	Lin.Ft.	Lin.Ft.	Lin.Ft.	Lin.Ft.	Sq. Yd.	Sq.Yd.	Cu. Yd.	Each		
U-1	764+00	775+97	Lt.	85										2		
U-2	764+00	777+00	Lt.	15				1300	1197	22		13				
U-3	764+00	777+00	Lt.				1300									
U-4	764+00	777+00	Rt.				1300									
U-5	764+00	777+00	Rt.	15				1300			13					
U-6	764+00	768+85	Rt.					485								
U-7	768+85	777+00	Rt.	20				815	25					1		
U-8	775+97	777+00	Lt.	15				103						1		
U-9	768+85	771+00	Lt.	10				215	11					1		
TOTALS				160		1	2	2600	2600	2815	58	26	36.2	125	3.3	5
D-1	766+35	766+35	℄			1							125			
D-3	771+09	771+09	79.4' Rt.			1										
D-4	776+02	776+02	76.3' Lt.			1										
D-5	776+84.2	776+84.2	Lt.								36.2		3.3			

ROADWAY									
REF. NO.	STATION	SIDE	202				Special		
			Guardrail Removed	Fence Removed	Gate Removed	Catch Basin or Inlet Removed	Pipe Cleanout		
	FROM	TO	Lin.Ft.	Lin.Ft.	Each	Each	Lin.Ft.		
R-1	764+00	777+00	Lt.	1294					
R-2	764+00	765+80	Lt.	182					
R-3	764+00	771+61	Rt.		816				
R-4	764+00	768+45	Lt.		444				
R-5	766+35	766+35	℄				1		
R-6	768+01	769+81	Rt.	181					
R-7	768+45	768+59	Lt.			1			
R-8	768+59	770+32	Lt.		190				
R-9	776+13	777+00	Rt.	88					
TOTALS				1745	1450	1	1	352	
D-2	770+68	771+88	Lt.					352	

FENCE						
REF. NO.	STATION	SIDE	607		625	
			Fence, Type CLT	Gate, Type CL, As Per Plan	Ground Rod	
	FROM	TO	Lin.Ft.	Each	Each	Each
F-1	764+00	771+61	Rt.	816		
F-2	764+00	768+45	Lt.	444		
F-3	767+82	767+82	Rt.			1
F-4	768+27	768+27	Lt.			1
F-5	768+45	768+59	Lt.		1	
F-6	768+59	770+32	Lt.	190		
F-7	768+60	768+60	Rt.			1
F-8	769+05	769+05	Lt.			1
TOTALS				1450	1	4

GUARDRAIL								
REF. NO.	STATION	SIDE	606	606	606	203	448	
			Guardrail, Type 5	Anchor Assembly, Type E-98	Anchor Assembly, Type T	Linear Grading, As Per Plan	3" Asphalt Concrete Intermediate Course Type 1, PG 64-22	
	FROM	TO	Lin.Ft.	Each	Each	Lin. Ft.	Cu.Yd.	
GR-1	764+00	777+00	Lt.	1300				48.15
GR-2	764+00	766+44.87	Lt.	194.87	1		249.87	9.85
GR-3	768+02.5	769+65	Rt.	100	1	1	167.5	6.80
GR-4	772+73.85	777+00	Rt.	376.15	1		431.15	16.56
TOTALS				1971	3	1	849	81.4
							8.5 Stas.	

PLOTTED BY: lmincek
 PLOTTED: 08/05/98
 PLOT SUBMITTED: 05-AUG-1998 12:01
 3070U20.DGN