

707.41 Non-Perforated ASTM D3034,
SDR 35, 707.42 or 707.33

DRAINAGE																
REF. NO.	STATION		SIDE	603		604		605				670	604			
	FROM	TO		6" Conduit, Type F **		Inlet, No. 3850	Catch Basin, No. E-2B	Catch Basin, No. 5, As Per Plan	Catch Basin, No. 6	6" Shallow Pipe U.D. w/Fabric Wrap (18" Deep)	6" Shallow Pipe U.D. (30" Deep)	6" Shallow Pipe U.D. w/Fabric Wrap (30" Deep)	6" Unclassified Underdrain w/Fabric Wrap	6" Unclassified Underdrain	Ditch Erosion Protection	Precast Reinforced Concrete Outlet
			Lin.Ft.		Each	Each	Each	Each	Lin.Ft.	Lin.Ft.	Lin.Ft.	Lin.Ft.	Lin.Ft.		Each	
U-1	777+00	777+14	Lt.								14					
U-2	777+00	778+20	Lt.							120						
U-3	777+00	778+13	Lt.							113						
U-4	777+00	778+60	Rt.							160						
U-5	777+00	778+90	Rt.							190						
U-6	777+00	779+22	Rt.							222						
U-7	780+49	789+00	Lt.	40						791	82				2	
U-8	781+00	789+00	Lt.	15						740		73				
U-9	781+10	789+00	Lt.						735			55				
U-10	781+55	789+00	Rt.						720			25				
U-11	781+67	789+00	Rt.	15						720		26				
U-12	782+53	789+00	Rt.	60							627	42			2	
U-17	74+55	74+55	Rt.									23				
U-18	85+13	85+13	Lt.									25				
TOTALS																
			130		1	1	1	1	1728	1770	1654	252	99		1263.2	4
D-1	777+80	778+60	Ø												71.7	
D-3	781+74.14	781+74.14	9.47' Lt.													
D-4	781+80	781+80	5' Rt.													
D-5	782+30.33	782+30.33	75' Rt.													
D-6	784+15	784+15	Ø													
D-7	781+89	789+00	Lt.												591.5	
D-8	781+80	789+00	Rt.												600	
TOTALS																
			130		1	1	1	1	1728	1770	1654	252	99		1263.2	4

ROADWAY							
REF. NO.	STATION		SIDE	202			
	FROM	TO		Guardrail Removed	Fence Removed	Catch Basin or Inlet Removed	Pipe Removed, 24" And Under
			Lin.Ft.	Lin.Ft.	Each	Lin Ft.	
R-1	777+00	777+24	Lt.	24			
R-2	777+80	777+80	Ø			1	5
R-3	777+00	778+92	Rt.	198			
R-4	778+65	778+65	Lt./Rt.		114		
R-5	779+86.6	781+92	Lt.	266			
R-6	780+70	783+36	Lt./Rt.	273			
R-7	781+00	781+00	Lt./Rt.		114		
R-8	781+80	781+80	5' Rt.			1	23
R-9	784+14	784+14	Ø			1	4
R-10	784+43	789+00	Lt.	486			
R-11	786+41	789+00	Rt.	258			
TOTALS							
			1505	228	3	32	

QUANTITIES FOR PRESSURE RELIEF JOINTS						
REF. NO.	STATION		SIDE	202	305	SPECIAL
	FROM	TO		PAVEMENT REMOVED*	9" CONCRETE BASE, A.P.P.	Pressure Relief Joint, Type A
			SQ. YD.	SQ. YD.	Lin.Ft.	
PRJ-5	74+55	74+55	Rt.	89	89	22
PRJ-6	85+13	85+13	Lt.	89	89	22
TOTALS						
			178	178	44	

* 16' x 50' ±

FENCE				
REF. NO.	STATION		SIDE	
	FROM	TO		
			607 Fence, Type CLT Lin.Ft.	
F-1	778+65	778+65	Lt./Rt.	41
F-2	781+00	781+00	Lt./Rt.	41
TOTALS				
			82	

GUARDRAIL											
REF. NO.	STATION		SIDE	606					203	448	
	FROM	TO		Guardrail, Type 5	Anchor Assembly, Type E-98	Anchor Assembly, Type T	Bridge Terminal Assembly, Type 1	Bridge Terminal Assembly, Type 2	Linear Grading, As Per Plan	3" Asphalt Concrete Intermed Course, Type 1, PG 64-22	
			Lin.Ft.	Each	Each	Each	Each	Lin. Ft.	Cu. Yd.		
GR-1	777+00	777+15	Lt.	15			1		1.00		
GR-2	779+90.54	780+95	Lt.	56.25	1		1		4.71		
GR-3	777+00	778+55.10	Rt.	155.1			1	155.1	5.74		
GR-4	87+00	89+00	Lt.	187.5		1			8.19		
GR-5	786+50	789+00	Rt.	200	1				10.04		
TOTALS											
			614	2	1	2	1	155.1	29.7		
										1.6 Stas.	

PLOTTED BY: lmincek
 PLOTTED DATE: 08/19/98
 PLOT SUBMITTED: 05-AUG-1998 12:02
 3070U21.DGN
 3070U21.DGN