

SUMMARY OF QUANTITIES

STORM SEWERS

From Sta.	To Sta.	10"	12"	"Y's	"T's
1+00	2+86	186			
17+55	15+69	114			
16+64	17+54	90			
23+29	27+09	292		112"	10
45+30	46+18	88			
48+60	57+40	1074		110" 105" 10"	3-10" 10
47+95	56+15	814			3-10" 10
Totals		2,180	478	1	9

From Station	To Station	Cubic Yards			
		Exc.	Emb.	Emb+%	%Added Borrow
0+00	10+00	316.8	431.7	495.8	15
10+00	20+00	405.6	485.1	557.9	15
20+00	30+00	406.3	396.4	455.8	15
30+00	40+00	538.2	563.4	647.9	15
40+00	50+00	564.0	556.8	640.3	15
50+00	57+25	160.0	292.6	336.5	15
Excav.		2,390.9	2,725.4	3,134.2	
Old pavement removed		32.0			
Borrow		711.3			
Totals		3,134.2		3,134.2	711.3

Station	10"	12"
3+42 Lt.		16
4+57 Rt.		16
6+57 Lt.		16
8+73 Lt.		16
8+73 Rt.		16
16+56 Rt.		16
16+84 Lt.		16
18+17 Lt.		16
21+45 Lt.		16
22+56 Lt.		16
23+51 Lt.		16
26+08 Lt.		16
33+72 Lt.		16
35+47 Rt.		16
36+86 Rt.		16
42+38 Lt.		16
46+34 Lt.		16
Totals	64	208

Station	Side
25+98	Lt.
47+42	Rt.
50+05	Rt.
50+50	Lt.
52+78	Lt.
52+95	Rt.
54+25	Lt.
54+55	Rt.
56+44	Rt.
Total	9

From Station	To Station	Side of Road	Lin. Ft.
0+8	0+88	Lt.	96
7+94	8+18	Rt. & Lt.	48
23+28	23+52	Rt. & Lt.	48
28+32	29+68	Rt. & Lt.	272
34+34	34+78	Rt. & Lt.	48
Total			512

- R-1 Excavation 2,390.9 cu. yds.
- R-1 Borrow (furnished by Contractor) 711.3 cu. yds.
- R-3 Finishing Berms Slopes & Ditches. 5,725.0 Lin. Ft.
- R-1 Removing old concrete pavement. 124.4 Sq. Yds.
- T-7 Reinforced 6" concrete pavement. 11,290.0 Sq. Yds.
- T-7 Reinforced 9" concrete pavement. 160.0 Sq. Yds.
- T-6 Plain 6" concrete pavement. 100.0 Sq. Yds.