

SLM 11.13, 48"
SEE SHEET 303

SLM 11.32, 21"
SEE SHEET 304

SLM 11.12, 48"
SEE SHEET 303

SLM 11.24, 36"
SEE SHEET 304

old CFN 180711124
 new CFN 1864311
 SLM 11:24, 36"
 SEE SHEET 304

CFN 1972385
 SLM 11.12, 15"
 SEE SHEET 303

old CFN 180711123
 new CFN 1844597
 SLM 11.23, 36"
 SEE SHEET 304

CFN 1972387
 SLM 11.34, 15"
 SEE SHEET 304

REF. STATION TO STATION SIDE		ESTIMATED QUANTITIES								
		I-1 PIPE			I-5 PIPE SPL					
		6" Sec. M-64K	6" SHALLOW	6"	6" CI:1	6" CI:1	6" CI:1			
1-UD	660+00 to 662+36	LT.	10	226						
2-UD	660+00 to 662+46	E.		246						
3-UD	662+50 to 662+74	E.	10	14						
4-UD	660+00 to 663+10	RT.		510						
5-UD	663+75	LT.	10	13						
6-UD	664+10	LT.			61					
7-UD	663+49 to 669+70	LT.		621						
8-UD	663+86 to 663+36	E.		450						
9-UD	664+23 to 673+46	RT.	10	938						
10-UD	665+50 to 673+46	E.	10	486						
11-UD	673+50 to 675+00	E.		140						
12-UD	673+54 to 675+00	RT.	10	157						
SUB-TOTAL			30	30	3601	61				
TOTALS			30	30	3601	61				

REF. STATION TO STATION SIDE		ESTIMATED QUANTITIES								
		E-12 PIPE REMOVE 15" & OVER	I-14 PAVED GUTTER TYPE-1	I-10 DUMPED ROCK CHANNEL PROTECT.	I-16 MANHOLE EACH	L-10 SODDING	L-120 JUTE MATTING			
		540	540	CUYD	EACH	SQ. YD.	SQ. YD.			
1-D	663+45 to 663+93	LT.								
2-D	664+85 to 665+03	RT.								
3-D	665+17 to 666+67	RT.								
4-D	667+00 to 670+50	RT.						234		
5-D	669+00 to 673+50	LT.						75		
6-D	672+64 to 673+14	LT.								125
7-D	673+50 to 675+00	RT.						156		
8-D	673+12	RT.				2.2				
1-DR	672+57 to 672+67	E.	200							
2-DR	671+42 to 672+72	E.					4			
3-DR	671+67 to 672+85	RT.	140							
TOTALS			540	540	2.2	4	653	267		

NOTE:
 FOR DRAINAGE PROFILES
 SEE SHEET NO. 303 & 304.
 FOR PURITAS ROAD DRAINAGE
 PLANS - SEE SHEET NOS. 213 to 218.