

Detail Specifications

Table of Contents

D-1	SCOPE OF WORK.....	1
D-2	GENERAL CONDITIONS, SUPPLEMENTAL GENERAL CONDITIONS, AND PLANS	2
D-3	CONSTRUCTION AND MATERIAL SPECIFICATIONS.....	2
D-4	SEASONAL SUSPENSION OF WORK	3
D-5	CONTRACTOR HOURS	3
D-6	WORK HOURS-NOISE CONTROL	3
D-7	ELEVATIONS AND DIMENSION	4
D-8	NEW MATERIALS SPECIFIED	4
D-9	RESTORING ROADWAYS, DRIVEWAYS, SIDEWALKS, CURBING, AND TREELAWNS	4
D-10	INCONVENIENCE TO THE PUBLIC	4
D-11	WORK PERMITS	5
D-12	WATER SUPPLY	5
D-13	FORCE ACCOUNT	5
D-14	REDUCTION/ELIMINATION OF WORK AND/OR INCREASE IN WORK	5
D-15	PAVMENT AND/ OR BASE REMOVED (ITEM 202).....	6
D-16	UNDERCUTTING SUBGRADE AND SUBBASE (ITEM SPECIAL)	6
D-17	REMOVAL MISC. TRACK REMOVED (ITEM 202)	6
D-18	POLE REMOVED (WOOD OR METAL/CONCRETE (ITEM 202)	7
D-19	POLE FOUNDATION AND/OR VAULT REMOVED (ITEM 202)	7
D-20	LINEAR GRADING (ITEM 209).....	7
D-21	MATERIAL DISPOSAL (ITEM 203).....	8
D-22	EROSION CONTROL (ITEM 207).....	8
D-23	CONSTRUCTION OF CONCRETE BASE, PAVEMENT, SIDEWALKS, DRIVEWAYS AND CURB (ITEMS 305, 451, 452, 608, 609, SPECIAL).....	9
D-24	CONCRETE DESIGN MIX (ITEM SPECIAL).....	17
D-25	CONCRETE MIX DESIGN FOR CLASS MS CONCRETE (ITEM SPECIAL)...	18
D-26	CONCRETE MIX DESIGN FOR CLASS FS CONCRETE (ITEM SPECIAL).....	19
D-27	ADA CURB RAMP LAYOUT, AS PER PLAN, ITEM 608.....	20
D-28	PORTLAND CEMENT CONCRETE SEALING - ITEM SPECIAL.....	21

D-29	ASPHALT CONCRETE ITEM 301, 446 AND 448.....	24
D-30	BACKFILL MATERIAL (ITEM 603, SPECIAL).....	25
D-31	BACKFILL MATERIAL - FLOWABLE FILL SPECIFICATION FOR UTILITY TRENCHES (INSIDE OF PAVEMENT AREA) (ITEM 603, SPECIAL).....	25
D-32	PIPE CULVERTS, SEWERS, AND CONNECTIONS (ITEM 603).....	27
D-33	CROSSING AND CONNECTIONS TO EXISTING PIPE AND UTILITIES.....	27
D-34	CATCH BASINS (ITEM 604).....	28
D-35	CLEAN CATCH BASINS AND CONNECTIONS (ITEM 604, SPECIAL).....	28
D-36	PRE-CONSTRUCTION VIDEO TAPING OF RIGHT OF WAY.....	28
D-37	CLEAN AND TELEWISE CONDUIT (SEWER).....	29
D-38	CATCH BASIN RECONSTRUCTED TO GRADE (ITEM 604).....	29
D-39	ADJUSTING STREET CASTINGS (ITEM 604).....	30
D-40	MONUMENT ASSEMBLIES (ITEM 604).....	31
D-41	MONUMENT BOX, ADJUSTED TO GRADE OR REPLACED (ITEM 604).....	32
D-42	4" UNCLASSIFIED PIPE UNDERDRAIN (ITEM 605)	32
D-43	UNDERDRAIN, MISC.: EDGEDRAIN (ITEM SPECIAL).....	33
D-44	DRIVEWAY ACCESS (ITEM 614).....	33
D-45	FIELD OFFICE (ITEM 619).....	34
D-46	COMPUTER EQUIPMENT (ITEM 619, SPECIAL).....	35
D-47	CONSTRUCTION LAYOUT STAKES (ITEM 623).....	36
D-48	SIGNAL SUPPORT FOUNDATION, AS PER PLAN (ITEM 632).....	36
D-49	MAINTENANCE OF TRAFFIC SIGNAL/FLASHER INSTALLATIONS.....	37
D-50	POWER SERVICE (Traffic Control).....	38
D-51	CONDUIT 2", 3" OR 4" (ITEM 625).....	38
D-52	SIGNALIZATION MISC.: FOUNDATION TEST HOLES.....	39
D-53	SIGN LIGHTING MISC.: SIGN LIGHTING CABLE (ITEM 631).....	39
D-54	LIGHTING MISC.: LUMINAIRE LIGHTING CABLE (ITEM 625).....	39
D-55	POWER CABLE MISC.: POWER FOR SIGN LIGHTING (ITEM 632)	39
D-56	POWER CABLE MISC.: POWER FOR LUMINAIRE LIGHTING (ITEM 632)	39
D-57	POWER CABLE MISC.: PUSHBUTTON CABLE (ITEM 632)	39
D-58	GROUND ROD (ITEM 625).....	40
D-59	TEMPORARY FACILITIES & CONSTRUCTION IN THE PEDESTRIAN ACCESS ROUTE.....	40

D-60	CONTROLLER ACTUATED, 8 PHASE SOLID STATE DIGITAL MICROPROCESSOR (ITEM 633).....	40
D-61	PLASTIC CAUTION TAPE (ITEM 625 SPECIAL).....	47
D-62	REMOVAL OF TRAFFIC SIGNAL INSTALLATION (ITEM 632).....	47
D-63	SIGN HANGER ASSEMBLY, MAST ARM, AS PER PLAN (ITEM 630)	47
D-64	COMBINATION SIGNAL SUPPORT (BY TYPE AND DESIGN) & SIGNALIZATION MISC.: SIGNAL, OVERHEAD SIGN AND LIGHT POLE SUPPORT, AS PER PLAN (ITEM 632)	48
D-65	WATER WORK DETAILS	50
D-66	SEEDING AND MULCHING (ITEM 659)	53
D-67	WATER FOR SEEDING (ITEM 659)	53
D-68	COMMERCIAL FERTILIZER (ITEM 659)	53
D-69	TREE PRUNING (ITEM 666)	54
D-70	TREE REMOVAL	55
D-71	ROOT PRUNING	55
D-72	MISCELLANEOUS METAL (ITEM SPECIAL)	59
D-73	TESTING OF CONSTRUCTION MATERIAL, (ITEM SPECIAL)	59
D-74	ASPHALT REJUVENATING AGENT (ITEM SPECIAL)	63